


PERIYANAICKENPALAYAM TOWN PANCHAYAT

Bio remediation Techniques Phytoremediation, Constructed with Wetlands in Periya Pallam at Periyanaickenpalayam Town Panchayat.

SIGN HE



அனுப்புநர்

திரு.கு.வீரபாண்டியன் B.A.,
செயல் அலுவலர்(பொ),
பெரியநாயக்கன்பாளையம் பேரூராட்சி,
கோவை-20

பெறுநர்

உதவி செயற்பொறியாளர் அவர்கள்,
பேரூராட்சிகளின்
உதவி இயக்குனர் அலுவலகம்,
கோவை மண்டலம்
கோவை- 18.

ந.க.எண் :525/2021 நாள் : .08.2021.

அப்பா,

பொருள் : பொதுநிதி திட்டம் 2021-2022 - பெரியநாயக்கன்பாளையம் பேரூராட்சி
- பணிகள் தேர்வு செய்தது - மதிப்பீடுகளுக்கு நிர்வாக அனுமதி
பெறப்பட்டது - தொழிற்நுட்ப அனுமதி வேண்டல் - தொடர்பாக.

பார்வை : 1.தனி அலுவலர் பெரியநாயக்கன்பாளையம் பேரூராட்சி
அவர்களின் முன் அனுமதி நாள்.16.08.2021
2. கோயம்புத்தூர் மண்டல பேரூராட்சிகளின் உதவி இயக்குநர்
அவர்களின் செயல்முறை ஆணை மூ.மு.எண்.1048/2021/பே1
நாள்.17.08.2021

பெரியநாயக்கன்பாளையம் பேரூராட்சியில் 2021-2022ம் ஆண்டு பொது நிதியின் கீழ்
மேற்கொள்ளப்படும் வேலைக்கு மதிப்பீடுகள் தயார் செய்யப்பட்டது. கீழ்க்காணும் வேலைக்கு
பார்வை-1ல் காணும் மன்ற முன் அனுமதியின்படியும், பார்வை-2ல் காணும் பேரூராட்சிகளின் உதவி
இயக்குநர் அவர்களின் செயல்முறை ஆணையில் கீழ்க்கண்ட பணியினை மேற்கொள்ள நிர்வாக
அங்கீகாரம் வழங்கி உத்தரவிடப்பட்டுள்ளது.

வ. எண்.	வேலையின் பெயர்	மதிப்பீடு இலட்சத்தில்
1	Bio-remediation Techniques Phytoremediation, Constructed with Wellands in Periyapallam at Periyanaickenpalayam Town Panchayat	6.70

மேற்படி மதிப்பீடுக்கு உரிய தொழில் நுட்ப அனுமதி அளிக்க வேண்டுகொள்
பணிவுடன் கேட்டுக் கொள்கிறேன்.

இணைப்பு - 1. நிர்வாக அனுமதி நகல் -1
2. மதிப்பீடு -1

செயல் அலுவலர்(பொ)
பெரியநாயக்கன்பாளையம் பேரூராட்சி,
கோயம்புத்தூர்-641020.

17.8.2021

**பெரியநாயக்கன்பாளையம்(சிறப்புநிலை) பேரூராட்சி அலுவலகம்
கூட்ட நடவடிக்கைகளின் நகல்**

2021-ம் ஆண்டு ஆகஸ்ட் மாதம் 24-ம் நாள் செவ்வாய்கிழமை பிற்பகல் 3.00 பெரியநாயக்கன்பாளையம் (சிறப்புநிலை) பேரூராட்சி அலுவலகத்தில் நடைபெற்ற தனி அலுவலக சாதாரணக் கூட்ட நடவடிக்கை நகல்

முன்னிலை: திரு.கோ.துவாரநாத் சிங், தனி அலுவலர் மற்றும் பேரூராட்சிகளின் உதவி இயக்குநர்

பொருள் - 12		தீர்மானம்					
<p>பெரியநாயக்கன்பாளையம் பேரூராட்சிக்குட்பட்ட பெரிபள்ளம் ஓடையில் செல்லும் கழிவுநீரால் அப்பகுதியில் துர்நாற்றம் வீசுவதோடு, நோய்தொற்று ஏற்படும் அபாயம் உள்ளதாக தெரிவித்து 14.02.2021 ஆம் தேதிய கூடைஅநள டிக ஐனையை நாளிதழ் “Stench from check dam make life miserable” என்ற செய்தி வெளியானதின் அடிப்படையில் தேசிய பசுமை தீர்பாயம் தானாக முன்வந்து அசல் விண்ணப்பம் எண்.80/2021(SZ) நாள்.14.02.2021, 19.05.2021 07.08.2021-ன்படியான தேசிய பசுமை தீர்பாயத்தின் அசல் மனுவில் கட்டிக்காட்டியுள்ளவாறு மேற்படி பகுதியில் உள்ள தடுப்பணையில் சேகரம் ஆகும் கழிவுநீரை சுத்திகரிப்பு செய்ய “நடந்தாய்வாழி காவேரி” திட்டத்தில் பணிமேற்கொள்ளப்படும் காலம்வரை பேரூராட்சியின் மூலம் சுத்திகரிப்பு செய்ய நடவடிக்கை மேற்கொள்ள தெரிவிக்கப்பட்டுள்ளதன் அடிப்படையில் தற்காலிக தீர்வாக வார்டு எண்.4 கஸ்தூரிபாளையம் மயானம் அருகில் உள்ள பள்ளத்தில் உயிரியல் மேம்பாட்டு கட்டமைப்பு ஏற்படுத்த பணிகள் தேர்வு செய்ய தனி அலுவலர் அவர்களின் முன் அனுமதி பெறப்பட்டது மன்றத்தின் அனுமதிக்கு வைக்கப்படுகிறது.</p>		<p align="center">தீர்மானம் எண்.71 நாள் 24.08.2021</p> <p align="center">அனுமதிக்கப்பட்டது</p> <p>(ஓம்) திரு. கோ.துவாரநாத் தனி அலுவலர் மற்றும் பேரூராட்சிகளின் உதவி இயக்குநர் பெரியநாயக்கன்பாளையம் பேரூராட்சி பெரியநாயக்கன்பாளையம்</p>					
<table border="1"> <thead> <tr> <th>வரிசை எண்.</th> <th>வேலையின் பெயர்</th> <th>மதிப்பீடு (ரூ.)</th> </tr> </thead> <tbody> <tr> <td align="center">1</td> <td>Bio-remediation Techniques Phytoremediation, Constructed with Wellands in Periyapallam at Periyanaickenpalayam Panchayat Town</td> <td align="center">ரூ.6,70,000/-</td> </tr> </tbody> </table>	வரிசை எண்.	வேலையின் பெயர்	மதிப்பீடு (ரூ.)	1	Bio-remediation Techniques Phytoremediation, Constructed with Wellands in Periyapallam at Periyanaickenpalayam Panchayat Town	ரூ.6,70,000/-	
வரிசை எண்.	வேலையின் பெயர்	மதிப்பீடு (ரூ.)					
1	Bio-remediation Techniques Phytoremediation, Constructed with Wellands in Periyapallam at Periyanaickenpalayam Panchayat Town	ரூ.6,70,000/-					

(உண்மை நகல்)


 செயல் அலுவலர்(பொ),
 பெரியநாயக்கன்பாளையம் பேரூராட்சி
 கோயம்புத்தூர் -20

20.9.2021

கோயம்புத்தூர் மண்டல பேரூராட்சிகளின் உதவி இயக்குநர் அவர்களின் செயல்முறைகள்
பிறப்பிப்பவர் : திரு.கோ.சுவாரசநாத்சிங்

மூ.மு.எண்.1048/2021/பே1

நாள். 17.08.2021

பொருள் : பொதுநிதி 2021-2022 – பேரூராட்சிகள் நிர்வாகம் – கோயம்புத்தூர் மண்டலம் – பெரியநாயக்கன்பாளையம் பேரூராட்சி – அடிப்படை வசதி பணிகள் மேற்கொள்ளுதல் – நிர்வாக அனுமதி அளித்து ஆணை பிறப்பித்தல் தொடர்பாக

பார்வை : 1. தனி அலுவலர், பெரியநாயக்கன்பாளையம் பேரூராட்சி அவர்களின் முன் அனுமதி நாள்.16.08.2021
2. பெரியநாயக்கன்பாளையம் பேரூராட்சி செயல் அலுவலரது கடிதம் ந.க.எண்.525/2021/அ, நாள்.16.08.2021
3. அரசாணை (ப) எண்.166 நகராட்சிகள் நிர்வாகம் மற்றும் குடிநீர் வழங்கல் துறை, நாள். 12.04.2008

உத்திரவு :

கோயம்புத்தூர் மாவட்டம், பெரியநாயக்கன்பாளையம் பேரூராட்சியின் பார்வை-1-ல் காணும் விவரப்படி தனி அலுவலர், பெரியநாயக்கன்பாளையம் பேரூராட்சி அவர்களின் முன் அனுமதி மற்றும் பார்வை 2-ல் காணும் செயல் அலுவலரது முன்மொழிவு ஆகியவற்றின் பேரில், 2021-2022 ஆம் ஆண்டு பொது நிதி திட்டத்தில் பின்வரும் பணியினை மேற்கொள்வதற்கு, பார்வை 3-ல் காணும் அரசாணையில் வழங்கப்பட்டுள்ள அதிகார வரம்பிற்குட்பட்டும், கீழ்க்காணும் நிபந்தனைகளுக்குட்பட்டும் நிர்வாக அனுமதி அளித்து இதன் மூலம் ஆணை பிறப்பிக்கப்படுகிறது.

வ. எண்.	பணியின் விபரம்	மதிப்பீடு (ரூ.இலட்சத்தில்)
1	Bio-remediation Techniques Phytoremediation, Constructed with Wellands in Periyapallam at Periyanaickenpalayam Town Panchayat	ரூ.6.70

நிபந்தனைகள் :

- 1 இப்பணிக்கு தயாரிக்கப்பட்டுள்ள மதிப்பீட்டிற்கு உதவி செயற்பொறியாளரிடம் தொழில்நுட்ப அங்கீகாரம் பெறப்பட வேண்டும்.
- 2 இப்பணி விபரங்களை பேரூராட்சியின் மதிப்பீடு மற்றும் ஒதுக்கீடு பதிவேடு மற்றும் திட்டப் பேரேடு ஆகியவற்றில் பதிவு செய்யப்பட வேண்டும்
- 3 1998 ஆம் வருடத்திய தமிழ்நாடு ஒழிவுமறைவற்ற ஒப்பந்தப்புள்ளிகள் சட்டம் மற்றும் 2000ம் வருடத்திய தமிழ்நாடு ஒழிவு மறைவற்ற ஒப்பந்த விதிகள் ஆகியவற்றின் தொகுத்தளிக்கப்பட்ட நடைமுறைகளை தவறாமல் பின்பற்றி, இப்பணியினை செயலாக்க ஒப்பந்தப்புள்ளிகள் பெற்று தீர்வு செய்யப்பட வேண்டும்.
- 4 ஒரு ஒப்பந்தப்புள்ளி பெற்று முடிவு செய்யப்படுவதை முற்றிலுமாக தவிர்க்க வேண்டும்.

5. பேரூராட்சி மன்ற நிர்வாகிகளின் உறவினர்களுக்கு (தாய், தந்தை, சகோதரன், மனைவி, சகோதரி முதலானவர்கள்) பணிகள் ஒப்படைப்பதை தவிர்க்க வேண்டும்.
6. ஒப்பந்தப்புள்ளிகள் பேரூராட்சியின் மன்றத்தின் அங்கீகராத்திற்குட்பட்டது.
7. இப்பணியானது சம்மந்தப்பட்ட பேரூராட்சிக்கு சொந்தமான அல்லது மேலியுள்ள புறம்போக்கு நிலத்தில் மட்டுமே நடைபெறுவதை செயல் அலுவலர் மற்றும் பொறியாளர் உறுதி செய்ய வேண்டும்.
8. இப்பணிகளுக்கான செலவினம் மேற்கொள்வதற்கு இப்பேரூராட்சியின் நடப்பாண்டு வரவு செலவு திட்டத்தில் க.கு.எண்.2040-ல் உரிய ஒதுக்கீடு செய்யப்பட்டுள்ளதை செயல் அலுவலர் உறுதி செய்ய வேண்டும்.
9. இந்த அனுமதியின் மூலம் உருவாக்கப்படும் மூலதன சொத்துக்களை முறையாக சொத்தாக்கம் செய்யப்பட வேண்டும்.
10. இப்பணியின் பொருட்டு எதிர்காலத்தில் தணிக்கையில் தடைகள் ஏதேனும் எழுப்பப்பட்டின், அத்தகைய தடைகளுக்கு தமிழ்நாடு உள்ளாட்சி நிதித் தணிக்கை நடைமுறைநூல் தொகுதி 2-ல் குறித்துரைக்கப்பட்ட விகிதாச்சாரப்படி சம்மந்தப்பட்ட செயல் அலுவலர் மற்றும் பொறியாளர் ஆகியோர்களே பொறுப்பாவார்கள்.
11. இப்பணி மேற்கொள்வதினால் சட்ட ரீதியான சிக்கல்கள் எழும்பச்சத்திலும், நீதி மன்ற உத்தரவு நடவடிக்கைகளுக்கு குந்தகம் ஏற்படுத்தும் பட்சத்திலும் அல்லது இன்னபிற காரணங்களுக்காகவும் இந்த ஆணையினை ரத்து செய்வதற்கு பேரூராட்சிகளின் உதவி இயக்குநருக்கு முழு அதிகாரம் உண்டு.
12. இப்பணி துவங்கும் முன்னர், நடைபெறும் போது மற்றும் முடிவுற்ற பின்னர் ஆகிய மூன்று நிலைகளில் வண்ணப் புகைப்படம் எடுத்து ஆவணப்படுத்தப்படவேண்டும்.
13. எந்தவொரு வேலைக்கும் முன்பணம் கட்டாயம் வழங்கக் கூடாது
14. இவ்வாணையின் விவரங்கள் இவ்வலுவலகத்தில் பராமரிக்கப்படும் நிர்வாக அனுமதி வழங்கும் பதிவேடு பக்கம் எண். 136 முதல் 155-ல் பதியப்பட்டுள்ளது.
15. இதில் முரண்படும் செயல் அலுவலர்கள் மீது ஒழுங்கு நடவடிக்கை எடுக்க நேரிடும்.

பேரூராட்சிகளின் உதவி இயக்குநர்
கோயம்புத்தூர் மண்டலம்.

பெறுநர் :
செயல் அலுவலர்,
பெரியநாயக்கன்பாளையம் பேரூராட்சி

நகல் : உதவி செயிற் பொறியாளர், (பேரூராட்சிகள்), கோயம்புத்தூர் மண்டலம்.
நகல் : இளம்/உதவி பொறியாளர், பெரியநாயக்கன்பாளையம் பேரூராட்சி



COIMBATORE DISTRICT

PERIYANAICKENPALAYAM TOWN PANCHAYAT

GENERAL FUND 2021-2022

Name of the Work	Bio remediation Techniques Phytoremediation, Constructed with Wetlands in Periya Pallam at Periyanaickenpalayam Town Panchayat.
Estimate Amount	Rs.670,000

Specification Report

Specification Report to accompany the Estimate for the work of Bio remediation Techniques Phytoremediation, Constructed with Wetlands in Periya Pallam at Periyanaickenpalayam Town Panchayat.


Estimate Amount : Rs670,000


Name of the Town Panchayat : PERIYANAICKENPALAYAM TOWN PANCHAYAT

Name of the Scheme : GENERAL FUND 2021-2022

- 1 Earth work excavation for foundation and depositing on bank with in the initial lead of 10m and a lift of 2m in hard stiff clay, stiff block cotton, hard red earth, shales, murram, gravel, stoney earth and earth mixed with small size boulders etc. complete. complying with std. specifications. SS 20 B
- 2 Cement concrete 1:4:8 mix (One cement, four sand and Eight aggregate) using 40mm gauge hard broken stone jelly for foundation and flooring including dewatering if found necessary and laid in layers of not more than 15cm thick and compacting including all charges etc., complete as per standard specification.
- 3 Random Rubble masonry in Cement Mortar 1:5 Mix (one cement, five sand) using new best rough and bond stones from approved quarry including cost and conveyance of all materials to site. Loading and unloading charges and labour charges for mixing. laying and curing etc. complete. complying with std. specifications.
- 4 Supplying and erecting centering for sides and soffits including supports and strutting up to 3.29m height for plane surfaces in all floors with cross bracings using mild steel sheets of size 30cm x 55cm and 10 gauge stiffened welded with mild steel sheets of size 25mm x 25mm x 3mm for boarding and laid over silver oak (country wood). Joists of size 10cm x 6.5 cm dia spaced at about 90cm centre to centre and supported by casurina props of 10cm to 13cm dia spaced at 75cm centre to centre etc complete complying with standard specification
- 5 Cement concrete 1:3:6 mix (One cement, Three sand and six aggregate) using 20mm gauge hard broken stone jelly for foundation and flooring including dewatering if found necessary and laid in layers of not more than 15cm thick and compacting including all charges etc., complete as per standard specification.
- 6 Supply and filling of 40 mm metal Filling including cost and conveyance of all cost of material charges and labour charges for all other etc.,
- 7 Provision for G S T 12%
- 8 Provision for Labour Well Fund 1%
- 9 Contingencies and L.S. provisions

The estimate is prepared with current schedule of rates for the year 2020-2021. On sanction, this work will be carried out as per MORTH and other circular instructions issued from time to time.


Junior Engineer,
Periyanaickenpalayam Group
Coimbatore District


ASSISTANT EXECUTIVE ENGINEER
TOWN PANCHAYATS
COIMBATORE ZONE

PERIYANAICKENPALAYAM TOWN PANCHAYAT

GENERAL FUND 2021-2022

Name of work : Bio remediation Techniques Phytoremediation, Constructed with Wetlands in Periya Pallam at Periyanaickenpalayam Town Panchayat.

ABSTRACT ESTIIMATE

Sl. No	Contents	Description of work etc.,	Rate	Per	Amount
1	53.00 M ³	Earth work excavation excavating and depositing on Bank with Initial lead of 10 Metres and Initial lift of 2 Metres in Hard stiff clay, stiff black cotton soils, hard red earth, shales, murram, gravel, stoney earth and earth mixed with small size boulders SS 20 .A for Sectioning and Levelling.	Rs126.00	1M ³	Rs6,678
2	4.00 M ³	Cement concrete 1:4:8mix (One cement, four sand and Eight aggregate) using 40mm gauge hard broken stone jelly for foundation and flooring including dewatering if found necessary and laid in layers of not more than 15cm thick and compacting including all charges etc., complete as per standard specification.	Rs4,220.90	1M ³	Rs16,884
3	50.00 M ³	Random Rubble masonry in Cement Mortor 1:5 Mix (one cement, five sand) using new best rough and bond stones from approved quarry including cost and conveyance of all materials to site. Loading and unloading charges and labour charges for mixing. laying and curing etc. complete. complying with std. specifications.	Rs4,355.48	1M ³	Rs217,774
4	70.00 M ²	Supplying and erecting centering for sides and soffits including supports and strutting up to 3.29mm height for plane surfaces in all floors with cross bracings using mild steel sheets of size 30cm x 55cm and 10 gauge stiffened welded with mild steel sheets of size 25mm x 25mm x 3mm for boarding and laid over silver oak (country wood). Joists of size 10cm x 6.5 cm dia spaced at about 90cm centre to centre and supported by casurina props of 10cm to 13cm dia spaced at 75cm centre to centre etc complete complying with standard specification	Rs273.85	1M ²	Rs19,170

Sl. No.	Contents	Description of work etc.,	Rate	Per	Amount
5	58.00 M ³	Cement concrete 1:3:6 mix (One cement, Three sand and six aggregate) using 20mm gauge hard broken stone jelly for foundation and flooring including dewatering if found necessary and laid in layers of not more than 15cm thick and compacting including all charges etc., complete as per standard specification.	Rs4,941.10	1M ³	Rs286,584
6	23.00 M ³	Supply and filling of 40 mm metal Filling including cost and conveyence of all cost of material charges and labour charges for all other etc.,	Rs1,204.90	1M ³	Rs27,713
7	L.S.	Provision for G S T 12%	L.S.		Rs68,976
8	L.S.	Provision for Labour Well Fund 1%	L.S.		Rs6,700
9	L.S.	Contingencies and L.S. provisions	L.S.		Rs19,521

TOTAL Rs670,000

[Signature]
17/8/21
Junior Engineer,
Periyanaickenpalayam Group
Coimbatore District

Technically Sanctioned For Rs. 6,70,000/-
Rupees Six lakh and seventy thousand

Only and entered in T.S. Register

No. 54/2021-22 Dt. 24/8/2021

for the Year 2021... 2022... A.S. in

Proceeding ROC No : 1045/2021/64, Dt. 17/8/21

Asst- Director of Town Panchayat, Coimbatore

[Signature]
24/8/21
ASSISTANT EXECUTIVE ENGINEER
TOWN PANCHAYATS
COIMBATORE ZONE

PERIYANAICKENPALAYAM TOWN PANCHAYAT
GENERAL FUND 2021-2022

Name of work :


Bio remediation Techniques Phytoremediation, Constructed with Wetlands in Periya Pallam at Periyanaickenpalayam Town Panchayat.

DETAILED ESTIMATE

Sl. No.	Description of work etc.,	Numbers	Length	Breadth	Depth	Contents
1	Earth work excavation for foundation and depositing on bank with in the initial lead of 10m and a lift of 2m in hard stiff clay, stiff block cotton, hard red earth, shales, murrum, gravel, stoney earth and earth mixed with small size boulders etc. complete. complying with std. specifications.SS 20 B					
	West side wall	1 x 1	6.00	2.00	2.00	24.00 M ³
	Esat side wall	1 x 1	5.00	2.00	2.00	20.00 M ³
	Side wall	1 x 1	5.90	1.15	0.90	6.11 M ³
		1 x 1	2.00	1.20	0.90	2.16 M ³
						Total = 52.27 M ³
					Say= 53.00 M ³	
2	Cement concrete 1:4:8mix (One cement, four sand and Eight aggregate) using 40mm gauge hard broken stone jelly for foundation and flooring including dewatering if found necessary and laid in layers of not more than 15cm thick and compacting including all charges etc., complete as per standard specification.					
	West side wall	1 x 1	6.00	2.00	0.10	1.20 M ³
	Esat side wall	1 x 1	5.00	2.00	0.10	1.00 M ³
	Side wall	1 x 1	5.90	1.15	0.10	0.68 M ³
		1 x 1	2.00	1.20	0.10	0.24 M ³
						Total = 3.12 M ³
					Say= 4.00 M ³	
3	Random Rubble masonry in Cement Mortar 1:5 Mix (one cement, five sand) using new best rough and bond stones from approved quarry including cost and conveyance of all materials to site. Loading and unloading charges and labour charges for mixing, laying and curing etc. complete. complying with std. specifications.					
	West side wall	1 x 1	6.00	2.00	1.90	22.80 M ³
	Esat side wall	1 x 1	5.00	2.00	1.90	19.00 M ³
	Side wall	1 x 1	5.90	1.15	0.80	5.43 M ³
		1 x 1	2.00	1.20	0.80	1.92 M ³
						Total = 49.15 M ³
					Say= 50.00 M ³	

Sl. No.	Description of work etc.,	Numbers	Length	Breadth	Depth	Contents		
4	Supplying and erecting centering for sides and soffits including supports and strutting up to 3.29m height for plane surfaces in all floors with cross bracings using mild steel sheets of size 30cm x 55cm and 10 gauge stiffened welded with mild steel sheets of size 25mm x 25mm x 3mm for boarding and laid over silver oak (country wood). Joists of size 10cm x 6.5 cm dia spaced at about 90cm centre to centre and supported by casurina props of 10cm to 13cm dia spaced at 75cm centre to centre etc complete complying with standard							
	West side wall	1	x	2	6.00	1.75	21.00 M ²	
	rising above GL	1	x	2	3.30	0.30	1.98 M ²	
	east side wall	1	x	2	5.00	1.75	17.50 M ²	
	rising above GL	1	x	2	2.30	0.45	2.07 M ²	
	side wall	1	x	2	5.90	1.50	17.70 M ²	
		1	x	2	2.00	1.50	6.00 M ²	
	Nea west side wall	1	x	1	5.00	0.75	3.75 M ²	
						Total =	70.00 M ²	
						Say=	70.00 M ²	
5	Cement concrete 1:3:6 mix (One cement, Three sand and six aggregate) using 20mm gauge hard broken stone jelly for foundation and flooring including dewatering if found necessary and laid in layers of not more than 15cm thick and compacting including all charges etc., complete as per standard specification.							
	West side wall	1	x	1	6.00	2.00	1.75	21.00 M ³
	rising above GL	1	x	1	3.30	1.70	0.30	1.68 M ³
	east side wall	1	x	1	5.00	2.00	1.75	17.50 M ³
	rising above GL	1	x	1	2.30	1.70	0.45	1.76 M ³
	side wall	1	x	1	5.90	1.15	1.50	10.18 M ³
		1	x	1	2.00	1.20	1.50	3.60 M ³
	Nea west side wall	1	x	1	5.00	0.45	0.75	1.69 M ³
						Total =	57.41 M ³	
						Say=	58.00 M ³	
6	Supply and filling of 40 mm metal Filling including cost and conveyence of all cost of material charges and labour charges for all other etc.,							
		1	x	1	6.00	5.00	0.75	22.50 M ³
							22.50 M ³	
						Say=	23.00 M ³	
7	Provision for G S T 12%							
8	Provision for Labour Well Fund 1%						L.S.	
9	Contingencies and L.S. provisions						L.S.	


 Junior Engineer,
 Periyanaickenpalayam Group
 Coimbatore District


 ASSISTANT EXECUTIVE ENGINEER
 TOWN PANCHAYATS
 COIMBATORE ZONE

PERIYANAICKENPALAYAM TOWN PANCHAYAT

GENERAL FUND 2021-2022

TENDER SCHEDULE

Town Panchayat.

Name of work : Bio remediation Techniques Phytoremediation, Constructed with Wetlands in Periya Pallam at Periyanaickenpalayam Town Panchayat.

Date -

Schedule Cost remitted vide Challan no-

issued to Thiru.

Estimate Amount: Rs. 670,000

EMT Rs. 6,700

Sl. No.	Probable quantity.	Description of work etc.,	MOT SSRB	Rate in	
				Figures	Words
1	53.00 M ³	Earth work excavation excavating and depositing on Bank with initial lead of 10 Metres and initial lift of 2 Metres in Hard stiff clay, stiff black cotton soils, hard red earth, shales, murrum, gravel, stoney earth and earth mixed with small size boulders SS 20 .A for Sectioning and Levelling.			1m ³ (One Cubic Metre)
2	4.00 M ³	Cement concrete 1:4:8mix (One cement, four sand and Eight aggregate) using 40mm gauge hard broken stone jelly for foundation and flooring including dewatering if found necessary and laid in layers of not more than 15cm thick and compacting including all charges etc., complete as per standard specification.			1m ³ (One Cubic Metre)
3	50.00 M ³	Random Rubble masonry in Cement Mortar 1:5 Mix (one cement, five sand) using new best rough and bond stones from approved quarry including cost and conveyance of all materials to site. Loading and unloading charges and labour charges for mixing, laying and curing etc. complete. complying with std. specifications.			1m ³ (One Cubic Metre)

Sl. No.	Probable quantity.	Description of work etc.,	MOT SSRB	Rate in	
				Figures	Words
4	70.00 M ²	Supplying and erecting centering for sides and soffits including supports and strutting up to 3.29mm height for plane surfaces in all floors with cross bracings using mild steel sheets of size 30cm x 55cm and 10 gauge stiffened welded with mild steel sheets of size 25mm x 25mm x 3mm for boarding and laid over silver oak (country wood). Joists of size 10cm x 6.5 cm dia spaced at about 90cm centre to centre and supported by casurina props of 10cm to 13cm dia spaced at 75cm centre to centre etc complete complying with standard specification			1 m ² (One Square Metre)
5	58.00 M ³	Cement concrete 1:3:6 mix (One cement, Three sand and six aggregate) using 20mm gauge hard broken stone jelly for foundation and flooring including dewatering if found necessary and laid in layers of not more than 15cm thick and compacting including all charges etc., complete as per standard specification.			1m ³ (One Cubic Metre)
6	23.00 M ³	Supply and filling of 40 mm metal Filling including cost and conveyance of all cost of material charges and labour charges for all other etc.,			1m ³ (One Cubic Metre)

Tender Schedule Approved

for Sl. No: From TO
(From Saturday one to
six only)

ANNEXURE
Junior Engineer,
Pariyanaickenpalayam Group,
Coimbatore District

24/12/21
ASSISTANT EXECUTIVE ENGINEER
TOWN PANCHAYATS
COIMBATORE ZONE

பெரியநாயக்கன்பாளையம் (சிறப்புநிலை) பேரூராட்சி

டெண்டர் விளம்பரம்

ந.க.எண். 525 /2021/அ

நாள்:- 23.08.2021

பெரியநாயக்கன்பாளையம் பேரூராட்சியில் 2021-2022-ம் ஆண்டு உயிரியல் மேம்பாட்டு கட்டமைப்பு திட்டத்தின்(பொதுநிதிவேலை) கீழ், கீழ்க்காணும் பணியினை செய்ய மூடி முத்திரையிட்ட டெண்டர்கள் 09.09.2021ம் தேதி பிற்பகல் 2.30 மணி வரை வரவேற்கப்படுகிறது. டெண்டர்கள் செயல் அலுவலர் அல்லது அவரது அதிகாரம் பெற்றவரால் பெற்றுக்கொள்ளப்படும் 09.09.2021ம் தேதி பிற்பகல் 2.30 மணிக்கு பிறகு வரும் டெண்டர்கள் எக்காரணம் கொண்டும் ஏற்றுக்கொள்ளப்படமாட்டாது. டெண்டர்கள் கொடுப்பவர்கள் சம்மந்தப்பட்ட வேலைக்குரிய, செட்யூல் படிவத்திற்குரிய தொகையினை 08.09.2021ம் தேதி பிற்பகல் 3.00 மணி வரை ரொக்கமாக செலுத்தியும், டேவணித் தொகை செலுத்திய அசல் இரசீதை டெண்டருடன் இணைத்து அனுப்ப வேண்டும். வரப்பெற்ற டெண்டர்கள் 09.09.2021ம் தேதி பிற்பகல் 3.00 மணிக்கு ஆஜராகியுள்ள டெண்டர்தாரர்கள் முன்னிலையில் செயல் அலுவலர் அல்லது அவரது அதிகாரம் பெற்றவரால் திறந்து பரிசீலிக்கப்படும். டெண்டர்கள் கொடுப்பவர்கள் பேரூராட்சியில் பதிவு பெற்ற ஒப்பந்ததாரர்களாக இருக்கவேண்டும். மறு அறிவிப்பு இன்றியோ அல்லது எவ்வித காரணமும் தெரிவிக்காமலேயே டெண்டர்களை நிறுத்திவைக்க செயல் அலுவலருக்கு அதிகாரம் உண்டு. இதர விபரங்களை பேரூராட்சியின் அலுவலக நாட்களில் அலுவலக நேரத்தில் கேட்டுத்தொரிந்து கொள்ளலாம் டெண்டர் படிவம் (செட்யூல்) 10,000/- வரையாலான மதிப்புடைய வேலைகளுக்கு ரூ.150 + மதிப்பிட்டுகூட்டு வரி (5%), 10,000/- மேல் மற்றும் ரூ.2/- இலட்சம் வரையாலான மதிப்புடைய வேலைகளுக்கு ரூ.300 + மதிப்பிட்டுகூட்டு வரி (5%), ரூ.2/- இலட்சத்திற்கு மேல் மற்றும் ரூ.5 இலட்சம் வரையாலான மதிப்புடைய வேலைகளுக்கு ரூ.750 + மதிப்பிட்டுகூட்டு வரி (5%) ரூ.5/- இலட்சத்திற்கு மேல் மற்றும் ரூ.10/- இலட்சம் வரையாலான மதிப்புடைய வேலைகளுக்கு ரூ.1500 + மதிப்பிட்டுகூட்டு வரி (5%) ரூ.10/- இலட்சத்திற்கு மேல் மற்றும் ரூ.25/- இலட்சம் வரையாலான மதிப்புடைய வேலைகளுக்கு ரூ.6000 + மதிப்பிட்டுகூட்டு வரி (5%) ரூ.25/- இலட்சத்திற்கு மேல் மற்றும் ரூ.50/- இலட்சம் வரையாலான மதிப்புடைய வேலைகளுக்கு ரூ.9000 + மதிப்பிட்டுகூட்டு வரி (5%) ரூ.50/- இலட்சத்திற்கு மேல் மதிப்புடைய வேலைகளுக்கு ரூ.15000 + மதிப்பிட்டு கூட்டுவரி (5%) செலுத்தி இரசீது பெற்றுக்கொள்ள வேண்டும்

உயிரியல் மேம்பாட்டு கட்டமைப்பு திட்டம் -2021-2022(பொதுநிதி வேலை)

வ.எண்.	வேலையின் பெயர்	மதிப்பீடு இலட்சத்தில்	டேவணி தொகை (1%)	செட்டியூல் கட்டணம்+ GST 18%
1	Bio-remediation Techniques Phytoremediation, Constructed with Wellands in Periyapallam at Periyanaickenpalayam Town Panchayat	6.70	6700	1770

(ஒப்பம்) XXXXX

தனி அலுவலர்

பெரியநாயக்கன்பாளையம் பேரூராட்சி மற்றும் பேரூராட்சிகளின் உதவி இயக்குநர் கோயம்புத்தூர்

(ஒப்பம்) XXXXX

செயல் அலுவலர்

பெரியநாயக்கன்பாளையம் பேரூராட்சி கோயம்புத்தூர்-20

(Handwritten Signature)
செயல் அலுவலர்

பெரியநாயக்கன்பாளையம் பேரூராட்சி கோயம்புத்தூர்-20

23.08.2021

பெரியநாயக்கன்பாளையம் (சிறப்புநிலை) பேரூராட்சி

மறுடெண்டர்(இரண்டாம் அழைப்பு) விளம்பரம்

ந.க.எண். 525 /2021/அ


நாள்:- 13.09.2021

பெரியநாயக்கன்பாளையம் பேரூராட்சியில் 2021-2022-ம் ஆண்டு உயிரியல் மேம்பாட்டு கட்டமைப்பு திட்டத்தின்(பொதுநிதிவேலை) கீழ், கீழ்க்காணும் பணியினை செய்ய மூடி முத்திரையிட்ட டெண்டர்கள் 28.09.2021ம் தேதி பிற்பகல் 2.30 மணி வரை வரவேற்கப்படுகிறது. டெண்டர்கள் செயல் அலுவலர் அல்லது அவரது அதிகாரம் பெற்றவரால் பெற்றுக்கொள்ளப்படும் 28.09.2021ம் தேதி பிற்பகல் 2.30 மணிக்கு பிறகு வரும் டெண்டர்கள் எக்காரணம் கொண்டும் ஏற்றுக்கொள்ளப்படமாட்டாது. டெண்டர்கள் கொடுப்பவர்கள் சம்மந்தப்பட்ட வேலைக்குரிய, செட்யூல் படிவத்திற்குரிய தொகையினை 27.09.2021ம் தேதி பிற்பகல் 3.00 மணி வரை ரொக்கமாக செலுத்தியும், டேவணித் தொகை செலுத்திய அசல் இரசீதை டெண்டருடன் இணைத்து அனுப்ப வேண்டும். வரப்பெற்ற டெண்டர்கள் 28.09.2021ம் தேதி பிற்பகல் 3.00 மணிக்கு ஆஜராகியுள்ள டெண்டர்தாரர்கள் முன்னிலையில் செயல் அலுவலர் அல்லது அவரது அதிகாரம் பெற்றவரால் திறந்து பரிசீலிக்கப்படும். டெண்டர்கள் கொடுப்பவர்கள் பேரூராட்சியில் பதிவு பெற்ற ஒப்பந்ததாரர்களாக இருக்கவேண்டும். மறு அறிவிப்பு இன்றியோ அல்லது எவ்வித காரணமும் தெரிவிக்காமலேயே டெண்டர்களை நிறுத்திவைக்க செயல் அலுவலருக்கு அதிகாரம் உண்டு. இதர விபரங்களை பேரூராட்சியின் அலுவலக நாட்களில் அலுவலக நேரத்தில் கேட்டுத்தெரிந்து கொள்ளலாம் டெண்டர் படிவம் (செட்யூல்) 10,000/- வரையாலான மதிப்புடைய வேலைகளுக்கு ரூ.150 + மதிப்பிட்டுகூட்டு வரி (5%), 10,000/- மேல் மற்றும் ரூ.2/- இலட்சம் வரையாலான மதிப்புடைய வேலைகளுக்கு ரூ.300 + மதிப்பிட்டுகூட்டு வரி (5%), ரூ.2/- இலட்சத்திற்கு மேல் மற்றும் ரூ.5 இலட்சம் வரையாலான மதிப்புடைய வேலைகளுக்கு ரூ.750 + மதிப்பிட்டுகூட்டு வரி (5%) ரூ.5/- இலட்சத்திற்கு மேல் மற்றும் ரூ.10/- இலட்சம் வரையாலான மதிப்புடைய வேலைகளுக்கு ரூ.1500 + மதிப்பிட்டுகூட்டு வரி (5%) ரூ.10/- இலட்சத்திற்கு மேல் மற்றும் ரூ.25/- இலட்சம் வரையாலான மதிப்புடைய வேலைகளுக்கு ரூ.6000 + மதிப்பிட்டுகூட்டு வரி (5%) ரூ.25/- இலட்சத்திற்கு மேல் மற்றும் ரூ.50/- இலட்சம் வரையாலான மதிப்புடைய வேலைகளுக்கு ரூ.9000 + மதிப்பிட்டுகூட்டு வரி (5%) ரூ.50/- இலட்சத்திற்கு மேல் மதிப்புடைய வேலைகளுக்கு ரூ.15000 + மதிப்பிட்டு கூட்டுவரி (5%) செலுத்தி இரசீது பெற்றுக்கொள்ள வேண்டும்

உயிரியல் மேம்பாட்டு கட்டமைப்பு திட்டம்.-2021-2022(பொதுநிதி வேலை)

வ.எண்.	வேலையின் பெயர்	மதிப்பீடு இலட்சத்தில்	டேவணி தொகை (1%)	செட்யூல் கட்டணம். GST 18%
1	Bio-remediation Techniques Phytoremediation, Constructed with Wellands in Periyapallam at Periyanaickenpalayam Town Panchayat	6.70	6700	1770


 செயல் அலுவலர்
 பெரியநாயக்கன்பாளையம் பேரூராட்சி
 கோயம்புத்தூர்-20


 13-9-2021

பெறுநர்:
 பதிவு செய்யப்பட்ட ஒப்பந்ததாரர்கள்,
 பெரியநாயக்கன்பாளையம் பேரூராட்சி,

நகல் : அலுவலக விளம்பர பலகைக்கு

பெரியநாயக்கன்பாளையம் (சிறப்புநிலை) பேரூராட்சி

மறுடெண்டர்(இரண்டாம் அழைப்பு) விளம்பரம்

ந.க.எண். 525 /2021/அ

நாள்:- 13.09.2021

பெரியநாயக்கன்பாளையம் பேரூராட்சியில் 2021-2022-ம் ஆண்டு உயிரியல் மேம்பாட்டு கட்டமைப்பு திட்டத்தின்(பொதுநிதிவேலை) கீழ், கீழ்க்காணும் பணியினை செய்ய மூடி முத்திரையிட்ட டெண்டர்கள் 28.09.2021ம் தேதி பிற்பகல் 2.30 மணி வரை வரவேற்கப்படுகிறது. டெண்டர்கள் செயல் அலுவலர் அல்லது அவரது அதிகாரம் பெற்றவரால் பெற்றுக்கொள்ளப்படும் 28.09.2021ம் தேதி பிற்பகல் 2.30 மணிக்கு பிறகு வரும் டெண்டர்கள் எக்காரணம் கொண்டும் ஏற்றுக்கொள்ளப்படமாட்டாது. டெண்டர்கள் கொடுப்பவர்கள் சம்மந்தப்பட்ட வேலைக்குரிய, செட்யூல் படிவத்திற்குரிய தொகையினை 27.09.2021ம் தேதி பிற்பகல் 3.00 மணி வரை ரொக்கமாக செலுத்தியும், டேவணித் தொகை செலுத்திய அசல் இரசீதை டெண்டருடன் இணைத்து அனுப்ப வேண்டும். வரப்பெற்ற டெண்டர்கள் 28.09.2021ம் தேதி பிற்பகல் 3.00 மணிக்கு ஆஜராகியுள்ள டெண்டர்தாரர்கள் முன்னிலையில் செயல் அலுவலர் அல்லது அவரது அதிகாரம் பெற்றவரால் திறந்து பரிசீலிக்கப்படும். டெண்டர்கள் கொடுப்பவர்கள் பேரூராட்சியில் பதிவு பெற்ற ஒப்பந்ததாரர்களாக இருக்கவேண்டும். மறு அறிவிப்பு இன்றியோ அல்லது எவ்வித காரணமும் தெரிவிக்காமலேயே டெண்டர்களை நிறுத்திவைக்க செயல் அலுவலருக்கு அதிகாரம் உண்டு. இதர விபரங்களை பேரூராட்சியின் அலுவலக நாட்களில் அலுவலக நேரத்தில் கேட்டுத்தெரிந்து கொள்ளலாம் டெண்டர் படிவம் (செட்யூல்) 10,000/- வரையாலான மதிப்புடைய வேலைகளுக்கு ரூ.150 + மதிப்பிட்டுகூட்டு வரி (5%), 10,000/- மேல் மற்றும் ரூ.2/- இலட்சம் வரையாலான மதிப்புடைய வேலைகளுக்கு ரூ.300 + மதிப்பிட்டுகூட்டு வரி (5%), ரூ.2/- இலட்சத்திற்கு மேல் மற்றும் ரூ.5 இலட்சம் வரையாலான மதிப்புடைய வேலைகளுக்கு ரூ.750 + மதிப்பிட்டுகூட்டு வரி (5%) ரூ.5/- இலட்சத்திற்கு மேல் மற்றும் ரூ.10/- இலட்சம் வரையாலான மதிப்புடைய வேலைகளுக்கு ரூ.1500 + மதிப்பிட்டுகூட்டு வரி (5%) ரூ.10/- இலட்சத்திற்கு மேல் மற்றும் ரூ.25/- இலட்சம் வரையாலான மதிப்புடைய வேலைகளுக்கு ரூ.6000 + மதிப்பிட்டுகூட்டு வரி (5%) ரூ.25/- இலட்சத்திற்கு மேல் மற்றும் ரூ.50/- இலட்சம் வரையாலான மதிப்புடைய வேலைகளுக்கு ரூ.9000 + மதிப்பிட்டுகூட்டு வரி (5%) ரூ.50/- இலட்சத்திற்கு மேல் மதிப்புடைய வேலைகளுக்கு ரூ.15000 + மதிப்பிட்டு கூட்டுவரி (5%) செலுத்தி இரசீது பெற்றுக்கொள்ள வேண்டும்

உயிரியல் மேம்பாட்டு கட்டமைப்பு திட்டம்.-2021-2022(பொதுநிதி வேலை)

வ.எண்.	வேலையின் பெயர்	மதிப்பீடு இலட்சத்தில்	டேவணி தொகை (1%)	செட்டியூல் கட்டணம். GST 18%
1	Bio-remediation Techniques Phytoremediation, Constructed with Wellands in Periyapallam at Periyanaickenpalayam Town Panchayat	6.70	6700	1770

(ஒப்பம்) XXXXX
தனி அலுவலர்
பெரியநாயக்கன்பாளையம் பேரூராட்சி
மற்றும் பேரூராட்சிகளின் உதவி இயக்குநர்
கோயம்புத்தூர்

(ஒப்பம்) XXXXX
செயல் அலுவலர்
பெரியநாயக்கன்பாளையம் பேரூராட்சி
கோயம்புத்தூர்-20


செயல் அலுவலர்
பெரியநாயக்கன்பாளையம் பேரூராட்சி
கோயம்புத்தூர்-20

13.9.2021

பெரியநாயக்கன்பாளையம் (சிறப்புநிலை) பேரூராட்சி

மறுடெண்டர்(மூன்றாம் அழைப்பு) விளம்பரம்


ந.க.எண். 525 /2021/அ

நாள்:- 01.11.2021

பெரியநாயக்கன்பாளையம் பேரூராட்சியில் 2021-2022-ம் ஆண்டு உயிரியல் மேம்பாட்டு கட்டமைப்பு திட்டத்தின்(பொதுநிதிவேலை) கீழ், கீழ்க்காணும் பணியினை செய்ய மூடி முத்திரையிட்ட டெண்டர்கள் 16.11.2021ம் தேதி பிற்பகல் 2.30 மணி வரை வரவேற்கப்படுகிறது. டெண்டர்கள் செயல் அலுவலர் அல்லது அவரது அதிகாரம், பெற்றவரால் பெற்றுக்கொள்ளப்படும் 16.11.2021ம் தேதி பிற்பகல் 2.30 மணிக்கு பிறகு வரும் டெண்டர்கள் எக்காரணம் கொண்டும் ஏற்றுக்கொள்ளப்படமாட்டாது. டெண்டர்கள் கொடுப்பவர்கள் சம்மந்தப்பட்ட வேலைக்குரிய, செட்யூல் படிவத்திற்குரிய தொகையினை 15.11.2021ம் தேதி பிற்பகல் 3.00 மணி வரை ரொக்கமாக செலுத்தியும், டேவணித் தொகை செலுத்திய அசல் இரசீதை டெண்டருடன் இணைத்து அனுப்ப வேண்டும். வரப்பெற்ற டெண்டர்கள் 16.11.2021ம் தேதி பிற்பகல் 3.00 மணிக்கு ஆஜராகியுள்ள டெண்டர்தாரர்கள் முன்னிலையில் செயல் அலுவலர் அல்லது அவரது அதிகாரம் பெற்றவரால் திறந்து பரிசீலிக்கப்படும். டெண்டர்கள் கொடுப்பவர்கள் பேரூராட்சியில் பதிவு பெற்ற ஒப்பந்ததாரர்களாக இருக்கவேண்டும். மறு அறிவிப்பு இன்றியோ அல்லது எவ்வித காரணமும் தெரிவிக்காமலேயே டெண்டர்களை நிறுத்திவைக்க செயல் அலுவலருக்கு அதிகாரம் உண்டு. இதர விபரங்களை பேரூராட்சியின் அலுவலக நாட்களில் அலுவலக நேரத்தில் கேட்டுத்தெரிந்து கொள்ளலாம் டெண்டர் படிவம் (செட்யூல்) 10,000/- வரையாலான மதிப்புடைய வேலைகளுக்கு ரூ.150 + மதிப்பிட்டுகூட்டு வரி (5%), 10,000/- மேல் மற்றும் ரூ.2/- இலட்சம் வரையாலான மதிப்புடைய வேலைகளுக்கு ரூ.300 + மதிப்பிட்டுகூட்டு வரி (5%), ரூ.2/- இலட்சத்திற்கு மேல் மற்றும் ரூ.5 இலட்சம் வரையாலான மதிப்புடைய வேலைகளுக்கு ரூ.750 + மதிப்பிட்டுகூட்டு வரி (5%) ரூ.5/- இலட்சத்திற்கு மேல் மற்றும் ரூ.10/- இலட்சம் வரையாலான மதிப்புடைய வேலைகளுக்கு ரூ.1500 + மதிப்பிட்டுகூட்டு வரி (5%) ரூ.10/- இலட்சத்திற்கு மேல் மற்றும் ரூ.25/- இலட்சம் வரையாலான மதிப்புடைய வேலைகளுக்கு ரூ.6000 + மதிப்பிட்டுகூட்டு வரி (5%) ரூ.25/- இலட்சத்திற்கு மேல் மற்றும் ரூ.50/- இலட்சம் வரையாலான மதிப்புடைய வேலைகளுக்கு ரூ.9000 + மதிப்பிட்டுகூட்டு வரி (5%) ரூ.50/- இலட்சத்திற்கு மேல் மதிப்புடைய வேலைகளுக்கு ரூ.15000 + மதிப்பிட்டு கூட்டுவரி (5%) செலுத்தி இரசீது பெற்றுக்கொள்ள வேண்டும்

உயிரியல் மேம்பாட்டு கட்டமைப்பு திட்டம்.-2021-2022(பொதுநிதி வேலை)

வ.எண்.	வேலையின் பெயர்	மதிப்பீடு இலட்சத்தில்	டேவணி தொகை (1%)	செட்யூல் கட்டணம்+ GST 18%
1	Bio-remediation Techniques Phytoremediation, Constructed with Wellands in Periyapallam at Periyanaickenpalayam Town Panchayat	6.70	6700	1770


 செயல் அலுவலர்
 பெரியநாயக்கன்பாளையம் பேரூராட்சி
 கோயம்புத்தூர்-20

பெறுநர்:
 பதிவு செய்யப்பட்ட ஒப்பந்ததாரர்கள்,
 பெரியநாயக்கன்பாளையம் பேரூராட்சி,

நகல் : அலுவலக விளம்பர பலகைக்கு

SCHEDULE -- A
PERIYANAICKENPALAYAM TOWN PANCHAYAT

Est. No.: /AEE/2020-21
Estimate Amount: 670,000
EMD Amount:
Tender Date & Time:

Issued to: Thiru. V. Susikumar

Executive officer
Periyanaickenpalayam Town panchayat

Name of Work:

Bio remediation Techniques Phytoremediation, Constructed with Wetlands in Periya Pallam at Periyanaickenpalayam Town Panchayat.

Chalan No: Dated:

Schedule of Rates and approximate quantities

- a) The quantities have given are those upon which the lump-sum tender cost at the work is caused but they are subject to alterations, omissions, deductions or additions as provided for in the conditions of the contract and do not necessarily show the actual quantities of the work to be done. The unit of rates noted below are those governing payment for extras or deductions for omission according to the conditions of the contract as set forth in the conditions and specification for the contract.
- b) It is to be expressly understood that the measured work it is to be taken out (Not withstanding any customarily practice to the contrary according to the actual quantities when the place and finished accordingly to the Drawings or as may be ordered time to time by the Special Village Panchayat Engineer and the cost calculated by works connected there with. The rate quoted is for the works in site and complete in every respect.
- c) The material required for the works must be supplied by the contractor and of the approved quality



PERIYANAICKENPALAYAM TOWN PANCHAYAT

GENERAL FUND 2021-2022

TENDER SCHEDULE

Name of work : Bio remediation Techniques Phytoremediation, Constructed with Wetlands in Periya Pallam at Periyanaickenpalayam Town Panchayat.

Estimate Amount: Rs. 670,000

Schedule Cost remitted vide Challan no- Date -
Issued to Thiru.

EMT Rs. 6,700

Sl. No.	Probable quantity.	Description of work etc.,	MOT SSRB	Rate in		
				Figures	Words	
1	53.00 M ³	Earth work excavation excavating and depositing on Bank with initial lead of 10 Metres and initial lift of 2 Metres in Hard stiff clay, stiff black cotton soils, hard red earth, shales, murram, gravel, stoney earth and earth mixed with small size boulders SS 20 .A for Sectioning and Levelling.		133	hundred and thirty three	1m ³ (One Cubic Metre)
2	4.00 M ³	Cement concrete 1:4:8mix (One cement, four sand and Eight aggregate) using 40mm gauge hard broken stone jelly for foundation and flooring including dewatering if found necessary and laid in layers of not more than 15cm thick and compacting including all charges etc., complete as per standard specification.		4132	four thousand four hundred and thirty two	1m ³ (One Cubic Metre)
3	50.00 M ³	Random Rubble masonry in Cement Mortar 1:5 Mix (one cement, five sand) using new best rough and bond stones from approved quarry including cost and conveyance of all materials to site. Loading and unloading charges and labour charges for mixing, laying and curing etc. complete. complying with std. specifications.		4574	four thousand five hundred and seventy four	1m ³ (One Cubic Metre)

V. Jay

Sl. No.	Probable quantity.	Description of work etc.,	MOT SSRB	Rate in	
				Figures	Words
4	70.00 M ²	Supplying and erecting centering for sides and soffits including supports and strutting up to 3.29mm height for plane surfaces in all floors with cross bracings using mild steel sheets of size 30cm x 55cm and 10 gauge stiffened welded with mild steel sheets of size 25mm x 25mm x 3mm for boarding and laid over silver oak (country wood). Joists of size 10cm x 6.5 cm dia spaced at about 90cm centre to centre and supported by casurina props of 10cm to 13cm dia spaced at 75cm centre to centre etc complete complying with standard specification		288	two hundred and eighty eight 1 m ² (One Square Metre)
5	58.00 M ³	Cement concrete 1:3:6 mix (One cement, Three sand and six aggregate) using 20mm gauge hard broken stone jelly for foundation and flooring including dewatering if found necessary and laid in layers of not more than 15cm thick and compacting including all charges etc., complete as per standard specification.		589	five hundred and eighty nine 1m ³ (One Cubic Metre)
6	23.00 M ³	Supply and filling of 40 mm metal Filling including cost and conveyance of all cost of material charges and labour charges for all other etc.,		1266	two thousand two hundred and sixty six 1m ³ (One Cubic Metre)

11/10/17

TENDER

opened by me -

name of work: Bio remediation techniques phyto remediation, introduced with methods in puzos pallam at periyarickenpalayam town perthay

16/11/22
Estimate Amount: 6,70,000

Name of scheme: General fund 2021-2022

From: V. Sathikumar
periyarickenpalayam
to: The executive officer,
Town perthayal,
periyarickenpalayam
Coimbatore - 20

SCHEDULE - A

PERIYANAICKENPALAYAM TOWN PANCHAYAT

/AEE/2020-21

Issued to : Thiru. D. Radh Kumar

670,000

Est. No.:

Estimate Amount:

EMD Amount:

Tender Date & Time:

Executive officer

Periyanaickenpalayam Town panchayat

Chalan No: Dated:

Name of Work:

Bio remediation Techniques Phytoremediation. Constructed with Wetlands in Periya Pallam at Periyanaickenpalayam Town Panchayat.

Schedule of Rates and approximate quantities

- a) The quantities have given are those upon which the lump-sum tender cost at the work is caused but they are subject to alterations, omissions, deductions or additions as provided for in the conditions of the contract and do not necessarily show the actual quantities of the work to be done. The unit of rates noted below are those governing payment for extras or deductions for omission according to the conditions of the contract as set forth in the conditions and specification for the contract.
- b) It is to be expressly understood that the measured work it is to be taken out (Not withstanding any customarily practice to the contrary according to the actual quantities when the place and finished accordingly to the Drawings or as may be ordered time to time by the Special Village Panchayat Engineer and the cost calculated by works connected there with. The rate quoted is for the works in site and complete in every respect.
- c) The material required for the works must be supplied by the contractor and of the approved quality



PERIYANAICKENPALAYAM TOWN PANCHAYAT

GENERAL FUND 2021-2022

TENDER SCHEDULE

Name of work : Bio remediation Techniques Phytoremediation, Constructed with Wetlands in Periya Pallam at Periyanaickenpalayam Town Panchayat.

Estimate Amount: Rs. 670,000

EMT Rs. 6,700

Schedule Cost remitted vide Challan no. _____ Date _____
Issued to Thiruv.

Sl. No.	Probable quantity.	Description of work etc.,	MOT SSRB	Rate in		
				Figures	Words	
1	53.00 M ³	Earth work excavation excavating and depositing on Bank with initial lead of 10 Metres and Initial lift of 2 Metres in Hard stiff clay, stiff black cotton soils, hard red earth, shales, murrum, gravel, stoney earth and earth mixed with small size boulders SS 20 .A for Sectioning and Levelling.		133	One hundred and thirty three only	1m ³ (One Cubic Metre)
2	4.00 M ³	Cement concrete 1:4:8mix (One cement, four sand and Eight aggregate) using 40mm gauge hard broken stone jelly for foundation and flooring including dewatering if found necessary and laid in layers of not more than 15cm thick and compacting including all charges etc., complete as per standard specification.		4429	Four thousand four hundred and twenty nine only	1m ³ (One Cubic Metre)
3	50.00 M ³	Random Rubble masonry in Cement Mortar 1:5 Mix (one cement, five sand) using new best rough and bond stones from approved quarry including cost and conveyance of all materials to site. Loading and unloading charges and labour charges for mixing. laying and curing etc. complete. complying with std. specifications.		4571	Four thousand five hundred and seventy one only	1m ³ (One Cubic Metre)

[Handwritten Signature]

Sl. No.	Probable quantity.	Description of work etc.,	MOT SSRB	Rate in	
				Figures	Words
4	70.00 M ²	Supplying and erecting centering for sides and soffits including supports and strutting up to 3.29mm height for plane surfaces in all floors with cross bracings using mild steel sheets of size 30cm x 55cm and 10 gauge stiffened welded with mild steel sheets of size 25mm x 25mm x 3mm for boarding and laid over silver oak (country wood). Joists of size 10cm x 6.5 cm dia spaced at about 90cm centre to centre and supported by casurina props of 10cm to 13cm dia spaced at 75cm centre to centre etc complete complying with standard specification		288	two hundred and eighty eight only 1 m ² (One Square Metre)
5	58.00 M ³	Cement concrete 1:3:6 mix (One cement, Three sand and six aggregate) using 20mm gauge hard broken stone jelly for foundation and flooring including dewatering if found necessary and laid in layers of not more than 15cm thick and compacting including all charges etc., complete as per standard specification.		5185	five thousand one hundred and eighty five only. 1m ³ (One Cubic Metre)
6	23.00 M ³	Supply and filling of 40 mm metal Filling including cost and conveyance of all cost of material charges and labour charges for all other etc.,		1265	one thousand two hundred and sixty five only 1m ³ (One Cubic Metre)

Handwritten signature

TENDER

Name of work - Bio remediation techniques phytoremediation, constructed with wetlands in Periyar Palaiam at Periyaraickenpalayam Thuvu Panichay.

Estimated amount - Rs. 6,70,000/- ^{16/11/22} _{16/11/22}

Name of scheme - GENERAL FUND 2021-2022

Signature

To - The Executive off
Town Panichayal,
Periyaraickenpalayam
Coimbatore - 20.

Name -

D. RADHUMAR,
Periyaraickenpalayam,
Coimbatore - 20.

COMPARATIVE STATEMENT

Name of work **Bio remediation Techniques Phytoremediation, Constructed with Wetlands in Periya Pallam at Periyanaickenpalayam Town Panchayat.**

Name of Scheme **GENERAL FUND 2021-2022**

Estimate amount **670,000**

Sl. No.	Probable Quantity	Description of Work	Estimate Rate			Thiru.D.Rajkumar			Thiru. V.Sasikumar		
			Rate	Per	Amount	Rate	Per	Amount	Rate	Per	Amount
1	53.00 M ³	Earth work excavation and depositing on Bank with Initial lead of 10 Metres and Initial lift of 2 Metres in Hard stiff clay, stiff black cotton soils, hard red earth, shales, murrum, gravel, stoney earth and earth mixed with small size boulders SS 20 .A for Sectioning and Levelling.	126.00	M ³	6678.00	133.00	M ³	7049.00	133.00	M ³	7049.00
2	4.00 M ³	Cement concrete 1:4:8mix (One cement, four sand and Eight aggregate) using 40mm gauge hard broken stone jelly for foundation and flooring including dewatering if found necessary and laid in layers of not more than 15cm thick and compacting including all charges etc., complete as per standard specification.	4220.90	M ³	16883.60	4429.00	M ³	17716.00	4432.00	M ³	17728.00
3	50.00 M ³	Random Rubble masonry in Cement Mortar 1:5 Mix (one cement, five sand) using new best rough and bond stones from approved quarry including cost and conveyance of all materials to site. Loading and unloading charges and labour charges for mixing, laying and curing etc. complete. complying with std. specifications.	4355.48	M ³	21774.00	4571.00	M ³	228550.00	4574.00	M ³	228700.00
4	70.00 M ³	Supplying and erecting centering for sides and soffits including supports and strutting up to 3.29mm height for plane surfaces in all floors with cross bracings using mild steel sheets of size 30cm x 55cm and 10 gauge stiffened welded with mild steel sheets of size 25mm x 25mm x 3mm for boarding and laid over silver oak (country wood). Joists of size 10cm x 6.5 cm dia spaced at about 90cm centre to centre and supported by casurina props of 10cm to 13cm dia spaced at 75cm centre to centre etc complete complying with standard specification	273.85	M ³	19169.50	288.00	M ³	20160.00	288.00	M ³	20160.00

5	58.00 M ³	Cement concrete 1:3:6 mix (One cement. Three sand and six aggregate) using 20mm gauge hard broken stone jelly for foundation and flooring including dewatering if found necessary and laid in layers of not more than 15cm thick and compacting including all charges etc., complete as per standard specification.	4941.10 M ³	286583.80	5185.00 M ³	300730.00	5189.00 M ³	300962.00
6	22.00 M ³	Supply and filling of 40 mm metal Filling including cost and conveyence of all cost of material charges and labour charges for all other etc.,	1204.90 M ³	27712.70	1265.00 M ³	29095.00	1266.00 M ³	29118.00
			574801.60		603300.00		603717.00	

Submitted

Two Tenders were received in the First call as follows on

- 1 by Thiru.D.Rajkumar
- 2 by Thiru . V.Sasikumar

.2021 and both two tenders qualified

4.96% Above (EMD Paid)
5.03% Above

4.96%
5.03%

Comparing the two tenders, the lowest above rate quoted Thiru.D.Rajkumar 4.96% is above than the Estimate rate and another tender Thiru V.Sasikumar ~~quoted~~ quoted 5.03% above than the estimate rates.

Hence the Lowest tender Thiru D.Rajkumar tender may be approved subject placed before the council for approval.

(Signature)
Junior Engineer,
Perivanaickenpalayam Group
Coimbatore District

பெரியநாயக்கன்பாளையம்(சிறப்புநிலை) பேரூராட்சி அலுவலகம்
கூட்ட நடவடிக்கைகளின் நகல்

2021-ம் ஆண்டு நவம்பர் மாதம் 17-ம் நாள் புதன்கிழமை பிற்பகல் 2.00 மணிக்கு பெரியநாயக்கன்பாளையம் (சிறப்புநிலை) பேரூராட்சி அலுவலகத்தில் நடைபெற்ற தனி அலுவலரின் சாதாரணக் கூட்ட நடவடிக்கை நகல்

முன்னிலை: திரு.கோ.துவாரநாத் சிங், தனி அலுவலர் மற்றும் பேரூராட்சிகளின் உதவி இயக்குநர்

பொருள் - 5					தீர்மானம்
<p>பெரியநாயக்கன்பாளையம் பேரூராட்சியில் 2021-2022-ம் ஆண்டு பொதுநிதியின் கீழ் கீழ்க்கண்டுகள்ள பணியினை செய்ய 16.11.2021-ம் தேதியில் டெண்டர் கோரப்பட்டதில், ஒப்பந்தப்புள்ளிகள் பெறப்பட்டது. மேற்படி பெறப்பட்ட ஒப்பந்தப்புள்ளிகளில் குறைந்த ஒப்பந்தவிலைப்புள்ளி அளித்துள்ள ஒப்பந்ததாரருக்கு பணி உத்தரவு வழங்க இவ்வலுவலக ந.க.எண்.525/2021/அ நாள்.16.11.2021-ன்படி தனி அலுவலர் மற்றும் பேரூராட்சிகளின் உதவி இயக்குநர் அவர்களின் முன் அனுமதி பெற்று உத்தரவு வழங்கப்பட்டது. மன்றத்தின் அனுமதிக்கும், அங்கீகாரத்திற்கும் வைக்கப்படுகிறது.</p>					<p>தீர்மானம் எண்.93 நாள் 17.11.2021</p>
வ. எண்.	வேலையின் பெயர்	மதிப்பீடு இலட்சத்தில்	ஒப்பந்ததாரர் பெயர்	டெண்டர் சதவீதம்	<p>குறைந்த ஒப்பந்தப்புள்ளி அங்கீகரிக்கப்படுகிறது</p>
1	Bio-remediation Techniques Phytoremediation Constructed with Wellands in Periyapallam in Periyanaickenpalayam Town Panchayat	6.70	திரு.டி.ராஜ்குமார்	மதிப்பீட்டு தொகைக்கு 4.99சதவீதம் அதிகம்	
			திரு.வெ.சசிக்குமார்	மதிப்பீட்டு தொகைக்கு 5.20 சதவீதம் அதிகம்	<p>(ஓம்) திரு. கோ.துவாரநாத்சிங் தனி அலுவலர் மற்றும் பேரூராட்சிகளின் உதவி இயக்குநர் பெரியநாயக்கன்பாளையம் பேரூராட்சி பெரியநாயக்கன்பாளையம்</p>

(உண்மை நகல்)


 செயல் அலுவலர்,
 பெரியநாயக்கன்பாளையம் பேரூராட்சி
 கோயம்புத்தூர் -20

17.11.2021

பெரியநாயக்கன்பாளையம் பேரூராட்சி செயல் அலுவலர் அவர்களின் நடவடிக்கைகள்

முன்னிலை:- திருமதி.டி.ஏ.ஜெசிமாடானு

ந.க.எண். 525 /2021

நாள். 17.11.2021

பொருள்: வேலைகள் – பெரியநாயக்கன்பாளையம் பேரூராட்சி-2020-2021-ம் ஆண்டு பொது நிதி வேலை – Bio-remediation Techniques Phytoremediation, Constructed with Wellands in Periyapallam- வேலை செய்ய உத்தரவிடப்படுகிறது.

பார்வை:

1. பெரியநாயக்கன்பாளையம் பேரூராட்சியின் முன் அனுமதி நாள். 16.08.2021
2. கோயம்புத்தூர் மாவட்ட ஆட்சித் தலைவர் அவர்களின் செயல்முறை ஆணை மூ.மு.எண்.1048/2021/பே1 நாள்.17.08.2021
3. பெரியநாயக்கன்பாளையம் பேரூராட்சி மன்ற தீர்மான எண்.71 நாள்.24.08.2021
4. கோயம்புத்தூர் மண்டல பேரூராட்சிகளின் செயற்பொறியாளர் அவர்களின் தொழில்நுட்ப அனுமதி எண்.54/2021-22 நாள்.24.08.2021
4. பெரியநாயக்கன்பாளையம் பேரூராட்சியின் ஒப்பந்தப்புள்ளி நாள்.16.11.2021
5. பேரூராட்சிகளின் உதவி இயக்குநர் அவர்களின் முன் அனுமதி நாள்.16.11.2021

உத்தரவு:

பெரியநாயக்கன்பாளையம் பேரூராட்சி 2021-2022-ம் ஆண்டு பொதுநிதி வேலை – Bio-remediation Techniques Phytoremediation, Constructed with Wellands in Periyapallam வேலையை (மதிப்பீடு ரூ.6.70 இலட்சம்) ஒப்பந்ததாரர் டி.ராஜ்குமார் என்பவருக்கு மதிப்பீட்டுத் தொகையில் 4.99% அதிகமாக செய்து கொடுக்க கீழ்க்கண்ட நிபந்தனைகளுக்குட்பட்டு வேலை உத்தரவு வழங்கப்படுகிறது.

நிபந்தனைகள்

1. ஒப்பந்ததாரர் ரூ.20.00 மதிப்புள்ள சபா காகிதத்தில் காண்ட்ராக்ட் சம்பந்தமான முழுவிபரங்கள் அடங்கிய ஓர் உடன்படிக்கை இவ்வலுவலகத்தில் எழுதிக் கொடுக்க வேண்டும்.
2. ஒப்பந்ததாரர் வேலை ஆரம்பிப்பதற்கு முன்பு தொகுதி பொறியாளர் மற்றும் செயல் அலுவலர் ஆகியோர்களுக்கு தெரிவித்தும், வேலை ஆரம்பிக்கும் முன்பும், வேலைச் செய்யும் போதும் மற்றும் வேலை செய்து முடிக்கும் போதும் புகைப்படங்கள் எடுத்து பேரூராட்சிக்கு ஒப்படைக்க வேண்டும்.
3. உத்தரவு கிடைக்கப்பெற்ற 120 தினத்திற்குள் வேலையை முடிக்க வேண்டும். குறிப்பிட்ட காலத்திற்குள் வேலையை முடிக்காவிட்டால் வேலைக்கான மேற்படியாரின் டெண்டரை ரத்து செய்து டெண்டர் டேவணித் தொகையை பறிமுதல் செய்தும் மறு டெண்டர் கோர நடவடிக்கைகள் மேற்கொள்ளப்படும். இதனால் ஏற்படும் சகல நஷ்டங்களுக்கும் மேற்படி டெண்டர்தாரரே பொறுப்பாவார்.
4. டெண்டர் சம்பந்தமான விவரங்களுக்கு நீதிமன்றத்தில் வழக்கு தொடர ஒப்பந்ததாரருக்கு எவ்வித உரிமையும் கிடையாது.
5. வேலை முடித்த பின்பு அரசு நிதி கிடைக்கப்பெற்றவுடன் தொகை வழங்கப்படும்.
6. ஒப்பந்ததாரர் மதிப்பீட்டில் குறிப்பிட்டுள்ள அளவுகளில் மட்டுமே வேலைபைச் செய்ய வேண்டும்.
7. செயல் அலுவலர் ஆய்வு செய்யும் போது வேலைகள் தரம் குறைந்தால் உரிய நடவடிக்கை எடுக்கப்படும்.
8. ஒப்பந்ததாரர் வேலைபைச் செய்யும் போது சரியான லெவலிலும், நல்லமுறையிலும், சுத்தமாகவும் செய்யப்பட வேண்டும்.
9. ஒப்பந்ததாரர் வேலைச் செய்யும் போது வேலையின் ஒவ்வொரு நிலையிலும் செயல் அலுவலரிடம் தெரியப்படுத்த வேண்டும்.

செயல் அலுவலர்


பெரியநாயக்கன்பாளையம்(சிறப்புநிலை) பேரூராட்சி

பெறுதல்

திரு.டி.ராஜ்குமார், ஒப்பந்ததாரர்
பெரியநாயக்கன்பாளையம், கோயம்புத்தூர்.

நகல்: தொகுதி பொறியாளர், பெரியநாயக்கன்பாளையம் பேரூராட்சி

**COIMBATORE DISTRICT, PERIYANAICKENPALAYAM TOWN PANCHAYAT
GENERAL FUND 2021 - 2022**




Name of work : Bio Remediation Techniques Phytoremediation,Constructed with Wetlands in Periya Pallam at Periyanaickenpalayam Town Panchayat. Est Amount : Rs.6,70,000.

**COIMBATORE DISTRICT, PERIYANAICKENPALAYAM TOWN PANCHAYAT
GENERAL FUND 2021 - 2022**



Name of work : Bio Remediation Techniques Phytoremediation,Constructed with Wetlands in Periya Pallam at Periyanaickenpalayam Town Panchayat. Est Amount : Rs.6,70,000.

**COIMBATORE DISTRICT, PERIYANAICKENPALAYAM TOWN PANCHAYAT
GENERAL FUND 2021 - 2022**



Name of work : Bio Remediation Techniques Phytoremediation,Constructed with Wetlands in
Periya Pallam at Periyanaickenpalayam Town Panchayat. Est Amount : Rs.6,70,000.

**COIMBATORE DISTRICT, PERIYANAICKENPALAYAM TOWN PANCHAYAT
GENERAL FUND 2021 - 2022**



Name of work : Bio Remediation Techniques Phytoremediation,Constructed with Wetlands in
Periya Pallam at Periyanaickenpalayam Town Panchayat. Est Amount : Rs.6,70,000.

**COIMBATORE DISTRICT, PERIYANAICKENPALAYAM TOWN PANCHAYAT
GENERAL FUND 2021 - 2022**




Name of work : Bio Remediation Techniques Phytoremediation,Constructed with Wetlands in
Periya Pallam at Periyanaickenpalayam Town Panchayat. Est Amount : Rs.6,70,000.

**COIMBATORE DISTRICT, PERIYANAICKENPALAYAM TOWN PANCHAYAT
GENERAL FUND 2021 - 2022**



Name of work : Bio Remediation Techniques Phytoremediation,Constructed with Wetlands in
Periya Pallam at Periyanaickenpalayam Town Panchayat. Est Amount : Rs.6,70,000.

**COIMBATORE DISTRICT, PERIYANAICKENPALAYAM TOWN PANCHAYAT
GENERAL FUND 2021 - 2022**



Name of work : Bio Remediation Techniques Phytoremediation,Constructed with Wetlands in
Periya Pallam at Periyanaickenpalayam Town Panchayat. Est Amount : Rs.6,70,000.

**COIMBATORE DISTRICT, PERIYANAICKENPALAYAM TOWN PANCHAYAT
GENERAL FUND 2021 - 2022**




Name of work : Bio Remediation Techniques Phytoremediation,Constructed with Wetlands in
Periya Pallam at Periyanaickenpalayam Town Panchayat Est Amount : Rs.6,70,000

**COIMBATORE DISTRICT, PERIYANAICKENPALAYAM TOWN PANCHAYAT
GENERAL FUND 2021 - 2022**



Name of work : Bio Remediation Techniques Phytoremediation,Constructed with Wetlands in
Periya Pallam at Periyanaickenpalayam Town Panchayat. Est Amount : Rs.6,70,000.

**COIMBATORE DISTRICT, PERIYANAICKENPALAYAM TOWN PANCHAYAT
GENERAL FUND 2021 - 2022**




Name of work : Bio Remediation Techniques Phytoremediation,Constructed with Wetlands in
Periya Pallam at Periyanaickenpalayam Town Panchayat. Est Amount : Rs.6,70,000.

**COIMBATORE DISTRICT, PERIYANAICKENPALAYAM TOWN PANCHAYAT
GENERAL FUND 2021 - 2022**




Name of work : Bio Remediation Techniques Phytoremediation,Constructed with Wetlands in
Periya Pallam at Periyanaickenpalayam Town Panchayat. Est Amount : Rs.6,70,000.

**COIMBATORE DISTRICT, PERIYANAICKENPALAYAM TOWN PANCHAYAT
GENERAL FUND 2021 - 2022**




Name of work : Bio Remediation Techniques Phytoremediation,Constructed with Wetlands in
Periya Pallam at Periyanaickenpalayam Town Panchayat. Est Amount : Rs.6,70,000.

**COIMBATORE DISTRICT, PERIYANAICKENPALAYAM TOWN PANCHAYAT
GENERAL FUND 2021 - 2022**



Name of work : Bio Remediation Techniques Phytoremediation,Constructed with Wetlands in
Periya Pallam at Periyanaickenpalayam Town Panchayat. Est Amount : Rs.6,70,000.

**COIMBATORE DISTRICT, PERIYANAICKENPALAYAM TOWN PANCHAYAT
GENERAL FUND 2021 - 2022**



Name of work : Bio Remediation Techniques Phytoremediation,Constructed with Wetlands in
Periya Pallam at Periyanaickenpalayam Town Panchayat. Est Amount : Rs.6,70,000.

**COIMBATORE DISTRICT, PERIYANAICKENPALAYAM TOWN PANCHAYAT
GENERAL FUND 2021 - 2022**



Name of work : Bio Remediation Techniques Phytoremediation,Constructed with Wetlands in
Periya Pallam at Periyanaickenpalayam Town Panchayat. Est Amount : Rs.6,70,000.

**COIMBATORE DISTRICT, PERIYANAICKENPALAYAM TOWN PANCHAYAT
GENERAL FUND 2021 - 2022**



Name of work : Bio Remediation Techniques Phytoremediation,Constructed with Wetlands in
Periya Pallam at Periyanaickenpalayam Town Panchayat. Est Amount : Rs.6,70,000.

PERIYANAICKENPALAYAM TOWN PANCHAYAT

GENERAL FUND - 2021-2022

FINAL CONTRACT CERTIFICATE

NAME OF WORK : Bio remediation Techniques Phytoremediation, Constructed with Wetlands in Periya Pallam at Periyanaickenpalayam Town Panchayat..

Estimate Amount : 6,70,000 /-

AEE T.P TS NO : 54/2021-22 DT 24.08.2021

Name of Contractor :Thiru.D. Rajkumar

Quantity executed or supplied				Items	Rate	Per	Amount	
Up to Date		Since last Certificate					Up to Date	Since last Certificate
1		2					6	7
				3	4	5	Rs	Rs
					Rs.P			
118.46	M ³	118.46	M ³	Earth work excavation for foundation and depositing on bank with in the initial lead of 10m and a lift of 2m in hard stiff clay, stiff block cotton, hard red earth, shales, murrum, gravel, stoney earth and earth mixed with small size boulders etc. complete. complying with std. specifications	133.00	M ³	15,755.18	15,755.18
25.44	M ³	25.44	M ³	Cement concrete 1:4:8mix (One cement, four sand and Eight aggregate) using 40mm gauge hard broken stone jelly for foundation and flooring including dewatering if found necessary and laid in layers of not more than 15cm thick and compacting including all charges etc., complete as per standard specification.	4429.00	M ³	112,673.76	112,673.76
184.08	M ²	184.08	M ²	Supplying and erecting centering for sides and soffits including supports and strutting up to 3.29mm height for plane surfaces in all floors with cross bracings using mild steel sheets of size 30cm x 55cm and 10 gauge stiffened welded with mild steel sheets of size 25mm x 25mm x 3mm for boarding and laid over silver oak (country wood). Joists of size 10cm x 6.5 cm dia spaced at about 90cm centre to centre and supported by casurina props of 10cm to 13cm dia spaced at 75cm centre to centre etc complete complying with standard specification	288.00	M ²	53,015.04	53,015.04
68.54	M ³	68.54	M ³	Cement concrete 1:3:6 mix (One cement, Three sand and six aggregate) using 20mm gauge hard broken stone jelly for foundation and flooring including dewatering if found necessary and laid in layers of not more than 15cm thick and compacting including all charges etc., complete as per standard specification.	5185.00	M ³	355,379.90	355,379.90

Quantity executed or supplied			Items	Rate	Per	Amount	
Up to Date		Since last Certificate				Up to Date	Since last Certificate
1		2	3	4	5	6	7
				Rs.P		Rs	Rs
						675094.47	675094.47
Total						675094.47	675094.47
Add in col.7 total up to date as in last Certificate Voucher No						675094.00	
Total Value of workdone up to date agreeing with total of col 6						Restricted to = Rs.670000.00	
Deduct :							
Fines and other Deductions up to date						<i>Rs. 6,70,000/-</i>	
Amount of Previous payments as per last certificate							
Voucher No							
Payments Now made Rs.							
						Balance Due	

Signature of Contractor.....Dated 2020

Certified that the preceding claim is correct, that the necessary measurements have been made by me on2020 and that the work has been satisfactorily performed - vide page 01 to 11 of Measurement Book No. /2020-2021 ,

Dated.....2020

Counter Signed for Rs: *6,70,000/-*

only subject to the condition that the Executive Officer

own Panchayat is responsible for all **CHECK MEASUREMENT CERTIFICATE** standard deductions from this bill measured by me on (dates).....

[Signature]
 JUNIOR ENGINEER
 Town Panchayat
 H.Q : PERIYANAICKENPALAYAM T.P
 Coimbatore

[Signature]
 Chairman
 Commissioner

DEDUCTION
COMPLETION CERTIFICATE
TOWN PANCHAYATS
COIMBATORE ZONE

Certified that the Work has been completed in accordance with the plan and estimate in a substantial and satisfactory manner.

bill amount no: *6,70,000.00*
 Deductions *33500.00*
 Net amount *6,36,500.00*

Allocation for the year *675000.00*
 Expenditure including this bill *14300.00*
 Balance available *33500.00*

[Signature]
 ASSISTANT EXECUTIVE ENGINEER
 TOWN PANCHAYATS
 COIMBATORE ZONE

Pay Rupees (*6,36,500.00*)

Station : *THIRY SIKK THOOSAR THOOSAR FILE HANDLED ONLY*
 Date :

Received Rs.(
 only , as a final payment in *N.C.* all demands.



[Signature]
 EXECUTIVE OFFICER
 Periyanaickenpalayam Town Panchayat
 Periyanaickenpalayam (Po)
 Coimbatore (Dt) - 20,

Chairman
 Commissioner

24.2.2022

COMPLETION REPORT

PERIYANAICKENPALAYAM TOWN PANCHAYAT

COIMBATORE ZONE

NAME OF WORK : Bio remediation Techniques Phytoremediation, Constructed with Wetlands in Periya Pallam at Periyanaickenpalayam Town Panchayat..

GENERAL FUND - 2021-2022

ESTIMATE AMOUNT : 6,70,000 /-

Periyanaickenpalayam

S. NO	DESCRIPTION	AS PER ESTIMATE			AS PER EXECUTION			DIFFERENCE		REMARKS
		Qty	Rate	Amount	Qty	Rate	Amount	Increase	decrease	
1	Earth work excavation for foundation and depositing on bank with in the initial lead of 10m and a lift of 2m in hard stiff clay, stiff block cotton, hard red earth, shales, murram, gravel, stoney earth and earth mixed with small size boulders etc. complete. complying with std. specifications	119.00	133.00	15,827.00	118.46	133.00	15,755.18	0	71.82	As per Actual
2	Cement concrete 1:4:8mix (One cement, four sand and Eight aggregate) using 40mm gauge hard broken stone jelly for foundation and flooring including dewatering if found necessary and laid in layers of not more than 15cm thick and compacting including all charges etc., complete as per standard specification.	26.00	4429.00	115,154.00	25.44	4429.00	112,673.76	0	2480.24	As per Actual
3	Supplying and erecting centering for sides and soffits including supports and strutting up to 3.29mm height for plane surfaces in all floors with cross bracings using mild steel sheets of size 30cm x 55cm and 10 gauge stiffened welded with mild steel sheets of size 25mm x 2.5mm x 3mm for boarding and laid over silver oak (country wood). Joists of size 10cm x 6.5 cm dia spaced at about 90cm centre to centre and supported by casurina props of 10cm to 13cm dia spaced at 75cm centre to centre etc complete complying with standard specification	185.00	288.00	53,280.00	184.06	288.00	53,015.04	0	264.96	As per Actual
4	Cement concrete 1:3:6 mix (One cement, Three sand and six aggregate) using 20mm gauge hard broken stone jelly for foundation and flooring including dewatering if found necessary and laid in layers of not more than 15cm thick and compacting including all charges etc., complete as per standard specification.	69.00	5185.00	357,765.00	68.54	5185.00	355,379.90	0	2385.10	As per Actual

S. NO.	DESCRIPTION	AS PER ESTIMATE			AS PER EXECUTION			DIFFERENCE		REMARKS
		Qty	Rate	Amount	Qty	Rate	Amount	Increase	decrease	
5	Rough stone Dry packing for apron and revetment including cost and conveyance of all materials to site, loading and unloading charges and labour charges for mixing, laying and curing etc. complete . complying with std. specifications	36.00	m3 1359.90	48,956.00	44.10	1359.90	59,971.59	11015.59	0	Due to site condition and Contractor quoted rate 4.96% above
6	Providing GST 12%	LS	L.S	70,918.00			71,615.00	697.00	0	As per Actual
7	Provision for Labour welfare Fund 1%	LS	L.S	6,700.00			6,684.00	0	16.00	As per Actual
8	Lumpsum provision for Contingencies and other unforeseen items	LS		1,400.00			0.00	0	1400.00	As per Actual
	Total			67000.00			675094.47	11742.59	6618.12	
							5094.47	5094.47		

Total Value Of Workdone =Rs. 675094.00

Resticted To = Rs.670000.00

[Signature]
 Junior Engineer
 Town Panchayat
 Periyanaickenpalayam Townpanchayat
 Coimbatore

67000/-

Completion Report Approved
 for Rs. 6,70,000/- (Six Lakh's Seventy thousand only)

[Signature]
 29/3/2022

ASSISTANT EXECUTIVE ENGINEER
 TOWN PANCHAYATS
 COIMBATORE ZONE



COIMBATORE DISTRICT – PERIYANAICKENPALAYAM TOWN PANCHAYAT
GENERAL FUND -2021 -2022

Name of work : Bio-remediation Techniques Phytoremediation,Constructed with Wellands in Periyapallan at periyanaickenpalayam Town Panchayat
Estimate Amt :6.70 Lakhs
Stage of Work : Completed

தேவகிருபை நர்சரி கார்டன்

பெரியகோட்டை காலனி தெரு. ம.மு. கோவிலூர் (வழி), திண்டுக்கல்.

ப்ராஞ்சு : பல்லைம் ரோடு, கோட்டாம்பட்டி, பொள்ளாச்சி.

J.ரபேல்

8778371500

26.12.2021

பிள்ளை :-

செயலி சிவசுந்தர் சிவாச்சரி
பெரியகோட்டை காலனி தெரு. ம.மு. கோவிலூர் (வழி), திண்டுக்கல்.

பட்டியல்

SIGN HERE

சமீப :-

பெரியகோட்டை காலனி தெரு. ம.மு. கோவிலூர் (வழி), திண்டுக்கல்.

உட்பட 3 வார்டு உட்பட சிவசுந்தர் சிவாச்சரி

475 2500 வார்டு சிவசுந்தர் 100 சிவசுந்தர் சிவாச்சரி

மேலும் சிவசுந்தர் சிவசுந்தர் சிவசுந்தர் சிவசுந்தர்

சுடர் சிவசுந்தர் சிவசுந்தர் சிவசுந்தர் 9900 %

மேலும் சிவசுந்தர் சிவசுந்தர் சிவசுந்தர் சிவசுந்தர்

சிவசுந்தர்

J. Rajeev

தேவகிருபை நப்சரி கார்டன்

வெரியகோட்டை காலனி தெரு, ம.மு. கோவிலூர் (வழி), திண்டுக்கல்.
 ப்ராஞ்ச் : பல்லடம் ரோடு, கோட்டாம்பட்டி, பொள்ளாச்சி.

J.ரபேல்

8778371500

27.12.2021

பெறுகிறது :-

பெறுகிறது அல்லது அல்லது

பெறுகிறது அல்லது அல்லது அல்லது

அல்லது

பெறுகிறது

பெறுகிறது அல்லது அல்லது அல்லது

அல்லது 3 அல்லது அல்லது அல்லது அல்லது அல்லது

அல்லது அல்லது அல்லது 100 அல்லது அல்லது அல்லது

அல்லது அல்லது அல்லது அல்லது அல்லது

அல்லது அல்லது அல்லது 9900 % அல்லது அல்லது

அல்லது அல்லது அல்லது அல்லது

அல்லது

J. Rabeel


தேவகிருபை நர்சரி கார்டன்

பெரியகோட்டை காலனி தெரு, ம.மு. கோவிலூர் (வழி), திண்டுக்கல்.

புராஞ்சு : பல்லைம் ரோடு, கோட்டாம்பட்டி, பொள்ளாச்சி.

J.ரபேல்

8778371500



பெரியகோட்டை

செல் அலுவலர் அலுவலர்
பெரியகிருபை நர்சரி கார்டன் கோட்டாம்பட்டி

பல்லைம்

அலுவலர்

பெரியகிருபை நர்சரி கார்டன் கோட்டாம்பட்டி உபநாயகர்

3 மார்ச் 2018 இன்று பிள்ளைகளை பிள்ளைகளை பிள்ளைகளை

காணொலி 100 ரூபாய் செலவு செய்து

அதன் மூலம் 100 ரூபாய் செலவு செய்து

ரூ. 10000 மட்டும் வசூலித்து அதன் மூலம்

J. Rabeel

J. Rabeel

தேவகிருபை நர்சரி கார்டன்

பெரியகோட்டை காலனி தெரு. ம.மு. கோவிலூர் (வழி), திண்டுக்கல்.

ப்ராஞ்ச் : பல்லடம் ரோடு, கோட்டாம்பட்டி, பொள்ளாச்சி.

J.ரபேல்

8778371500

3.1.2022



செயல் துணை துணை
பெரியகோட்டை காலனி தெரு. ம.மு. கோவிலூர் (வழி), திண்டுக்கல்.

பட்டினம்

செயல் துணை

பெரியகோட்டை காலனி தெரு. ம.மு. கோவிலூர் (வழி), திண்டுக்கல்.

உபயுக்த 3 வார்டு காலனி தெரு. ம.மு. கோவிலூர் (வழி), திண்டுக்கல்.

2000 வார்டுகளில் 100 கிராமங்கள் சேர்ந்து சேர்ந்து

சேர்ந்து சேர்ந்து சேர்ந்து சேர்ந்து சேர்ந்து

சேர்ந்து சேர்ந்து சேர்ந்து சேர்ந்து சேர்ந்து

சேர்ந்து சேர்ந்து சேர்ந்து சேர்ந்து சேர்ந்து

சேர்ந்து சேர்ந்து

J. Rajeev

தேவகிருபை நர்சரி கார்

பெரியகோட்டை காலனி தெரு, ம.மு. கோவிலூர் (வழி), திசை
 ப்ராஞ்ச் : பல்லடம் ரோடு, கோட்டாம்பட்டி, பொள்ளாச்சி

J.ரபேல்

8778371500



S-01-2022

பெணர் :-

செயல் அலுவலர் அகாடமி

பெரியகோட்டை காலனி பள்ளையல் கட்டுரை

பலகையல்

அரசா :-

பெரியகோட்டை காலனி பள்ளையல் கட்டுரை

கட்டிடம் 3 மாளிக் கூடகையல் கட்டிடம் அணி 475

உள்ளி அமரணலி 100 கட்டிடம் செய் கட்டிடம்

அட்டை அகாடமி 100 கட்டிடம் செய் கட்டிடம்

கட்டிடம் அகாடமி கட்டிடம் 99.00 %

கட்டிடம் அகாடமி கட்டிடம் கட்டிடம் கட்டிடம்

அகாடமி

J. A. Jeyal

தேவகிருபை நர்சரி கார்டன்

பெரியகோட்டை காலனி தெரு, ம.மு. கோவிலூர் (வழி), திண்டுக்கல்.


ப்ராஞ்ச் : பல்லடம் ரோடு, கோட்டாம்பட்டி, பொள்ளாச்சி.

J.ரபேல்

8778371500

6.1.2022

6/1/22



பெரிய

தெயல் அலுவலர் அலுவலர்

பெரியநாயக்கன் பாளையம் கோபுரமடக்கு

பல்கலை

அமே

பெரியநாயக்கன் பாளையம் கோபுரமடக்கு

2 மாட்டு உயல்பணி களவில் பின் புறம் தெயல்

வாசலில் 100 சிலி வாசலில் தெயல் மட்டில் ஆபதன்

பெரியநாயக்கன் பாளையம் கோபுரமடக்கு தெயல் மட்டில்

தெயல் மட்டில் தெயல் மட்டில் 6.9900% மட்டில்

தெயல் மட்டில் தெயல் மட்டில் தெயல் மட்டில்

தெயல் மட்டில்

J. Rabeal

தேவகிருபை நர்சரி கார்டன்

பெரியகோட்டை காலனி தெரு, ம.மு. கோவிலூர் (வழி), திண்டுக்கல்.

ப்ராஞ்ச் : பல்லடம் ரோடு, கோட்டாம்பட்டி, பொள்ளாச்சி.

J.ரபேல்
8778371500

14.2.2022



செயல் அலுவலர் அலுவலர்
பெரியகோட்டை காலனி பள்ளையம் சிவம் நினைவு கிளாஸ்டர்

சின்

அம்மா

பெரியகோட்டை காலனி பள்ளையம் கிளாஸ்டர் உபயல்

3 ஆண்டு கட்டாயம் காலத்தில் சின் 44ம்

செயல் அலுவலர் 100 செயல் அலுவலர் 100ம்

செயல் அலுவலர்

J. Raveel



COIMBATORE DISTRICT – PERIYANAICKENPALAYAM TOWN PANCHAYAT

GENERAL FUND -2021 -2022

**Name of work : Bio-remediation Techniques Phytoremediation, Constructed with Wellands
in Periyapallan at periyanaickenpalayam Town Panchayat**

Estimate Amt :6.70 Lakhs

Stage of Work : Completed

