

**BEFORE THE HON'BLE NATIONAL GREEN TRIBUNAL
PRINCIPAL BENCH, NEW DELHI**

Original Application No. 200/2014

In the matter of:

M. C. Mehta

...Applicant

Versus

Union of India & Ors

...Respondents

Index

Sr. No.	Particulars	Page No.
1.	Compliance report in pursuance to Hon'ble NGT order dated 13.09.2024 in OA 200/2014 titled MC Mehta VS Union of India & Ors.	
2.	Annexure-I A copy of the Hon'ble NGT order dated 13.09.2024 in OA 200/2014 titled MC Mehta VS Union of India & Ors.	
3.	Annexure -II The district-wise names and details of drains located in the state of Uttar Pradesh which have potential to discharge waste water in the main stream of River Ganga	
4.	Annexure -III A copy of document containing photographs of drains along with location	
5.	Annexure-IV The detailed status of STPs in the state of Uttar Pradesh	
6.	Annexure-V The water quality data of River Ganga at 41 locations in Uttar Pradesh during January- October, 2024	

Rajkumar

**Filed by: Adv. Rajkumar
On behalf of Central Pollution Control Board**

Place: Delhi

Date: 14.02.2025

Compliance Report on behalf of CPCB in compliance to Hon'ble NGT order dated 13.09.2024 in the matter of M.C. Mehta vs Union of India & Ors., O.A. No. 200/2014

This report is submitted in compliance to Hon'ble NGT order dated 13.09.2024 (**Annexure-I**) in OA No. 200/2014 titled M.C. Mehta vs Union of India & Ors. The concerned matter is related to remedying of pollution in River Ganga. The verbatim of the order is as follows:

“6. Learned Counsel for the CPCB submits that he will obtain instructions and place the complete record of drains in respect of all the districts of Jharkhand through which the river Ganga and its tributaries are flowing along with the details of outfall points and the quantity of untreated sewage flowing in river Ganga and its tributaries. He is directed to provide such details in respect of other States and also district-wise one week in advance whenever those matters are taken up.”

In compliance to the above mentioned NGT order, the district wise status of drains, sewage treatment plants (STPs) and water quality of River Ganga located in the state of Uttar Pradesh was filed before the Hon'ble NGT on 22.10.2024. In compliance of the above mentioned order, the updated status including 307 drains monitored during pre- monsoon 2023, 326 drains monitored during post- monsoon, 2023, 41 STPs monitored during April - July, 2024 and water quality of River Ganga at 41 locations in Uttar Pradesh during January - October, 2024 has been provided hereunder for kind consideration please.

1. Status of Drains located in the state of Uttar Pradesh

A. Pre-Monsoon, 2023

CPCB along with UPPCB conducted monitoring of 307 drains discharging directly into river Ganga (179) and its tributaries (Ramganga & its tributaries-24, Kali East-29, Pandu-09, Yamuna-21, Varuna & Moorwa-22, Jargo & Ojhla-10, Duar & Mansahaita-13) in Uttar Pradesh during 2023 in pre-monsoon season. These drains carry wastewater which comprises sewage, industrial effluent, and surface run-off. Out of 307 monitored drains, 95 were found tapped to various STPs. Monitoring was carried out to the nearest possible confluence point.

Significant Flow and BOD load were observed in drains discharging from following cities:

- Bareilly: 3 drains discharging into river Ramganga having flow 153.02 MLD and BOD Load 11.28 TPD.
- Bulandsahar: 11 drains discharging into river Kali East having flow 61.64 MLD and BOD Load 3.01 TPD.
- Kanpur: 17 drains discharging into river Ganga having flow 175.76 MLD and BOD Load 5.14 TPD and 9 drains discharging into river Pandu having flow 78.64 MLD and BOD Load 5.28 TPD.
- Meerut: 4 drains discharging into river Kali East having flow 1153.79 MLD and BOD Load 301.79 TPD.
- Moradabad: 19 drains discharging into river Ramganga & Gagan having flow 220.90 MLD and BOD Load 17.37 TPD.

The brief status of monitored drains in Uttar Pradesh is given in Table-1 and district wise status is given in Table-2

Table-1: Status of drains of river Ganga and its tributaries of Uttar Pradesh state during Pre monsoon 2023

River	Pre-Monsoon 2023						
	Monitored Drains	Flow (MLD)	BOD Load (TPD)	Tapped Drains	Interim measure adopted	Domestic	Mixed
Ganga	179	673.92	34.2	62	80	164	15
Ramganga-Kosi & Gagan	24	443.4	36.16	-	1	15	9
Kali East	29	1393.3	321.66	4	3	19	10
Pandu	9	78.6	5.28	5	2	2	7
Yamuna	21	14.2	0.33	8	4	20	1
Varuna & Moorwa	22	224.9	11.46	10	3	19	3
Jargo & Ojhala	10	4.34	0.05	-	2	9	1
Duar & Mansahaita	13	26.7	1.10	6	6	13	-
Total	307	2859.4	410.23	95	101	261	46

Table-2: District wise status of drains discharging into river Ganga and its tributaries in Uttar Pradesh

River	Monitored Drains	Flow (MLD)	BOD Load (TPD)	Tapped Drains	Interim measure adopted	Domestic	Mixed
1. Amroha							
Ganga	1	Dry	-	-	-	-	1
2. Balia							
Ganga	1	9.3	0.26	-	-	1	-
3. Bareilly							
Ramganga	3	153.02	11.28	-	-	1	2
4. Bhadohi							
Varuna & Moorwa	5	41.68	1.90	-	3	2	3
5. Bijnor							
Ramganga	1	FCM	-	-	-	-	1
6. Bulandshahar							
Kali East	12	84.86	7.19	-	3	8	4
7. Chandauli							
Ganga	2	52.65	1.19	-	2	-	2
8. Farrukhabad							
Ganga	5	38.63	0.96	2	2	3	2
9. Fatehpur							
Yamuna	1	10.53	0.073	-	-	1	-
10. Ghazipur							
Ganga	31	88.33	3.40	-	28	31	-
11. Hapur							
Ganga	2	FCM	-	-	1	2	-
Kali East	5	131.19	12.45	-	-	4	1
Total	7	131.19	12.45	-	-	6	1
12. Kannauj							
Kali East	3	11.88	0.13	2	-	3	-
13. Kanpur							
Ganga	23	175.76	5.14	13	10	18	5

Pandu	9	78.64	5.28	5	2	2	7
Total	32	254.4	10.42	18	12	20	12
14.Kasganj							
Kali East	4	FCM	-	2	-	4	-
15.Meerut							
Ganga	1	21.6	0.22	-	-	1	-
Kali East	4	1153.79	301.8	-	-	-	4
Total	5	1175.39	302.02	-	-	1	4
16.Mirzapur							
Ganga	37	58.58	4.23	8	14	36	1
Jargo-Ojhala	10	4.34	0.05	-	2	9	1
Total	47	62.92	4.28	8	16	45	3
17.Moradabad							
Ramganga & Gagan	19	220.90	17.37	-	-	14	5
18.Muzaffarnagar							
Kali East	1	11.6	0.09	-	-	-	1
19.Pratapgarh							
Ganga	5	0.86	0.01	-	3	5	-
Duar	1	Dry	-	-	-	1	-
20.Prayagraj							
Ganga	27	130.01	6.74	12	11	27	-
Yamuna	20	3.67	0.25	8	4	19	1
Manashita	12	26.7	1.10	6	6	12	-
Total	59	160.38	8.1	26	21	59	1
21.Raebareli							
Ganga	8	1.23	0.03	-	4	7	1
22.Rampur							
Kosi (tributary of river Ramganga)	1	69.49	7.50	-	-	-	1
23.Unnao							
Ganga	6	38	4.30	-	4	4	2

24. Varanasi							
Ganga	30	58.98	7.71	27	1	29	1
Varuna	17	183.18	9.56	10	-	17	-
Total	47	242.16	17.27	37	1	46	1

FCM: Flow could not measured

B. Post-Monsoon, 2023

During post mon-soon, 2023, monitoring of 326 drains discharging directly into river Ganga (188) and its tributaries (Ramganga & its tributaries-29, Kali East-29, Pandu-09, Yamuna-30, Varuna & Moorwa-21, Jargo & Ojhla-8 & Mansahaita-12) were carried out by CPCB along with UPPCB in Uttar Pradesh during 2023. These drains carry wastewater which comprises sewage, industrial effluent, and surface run off. Out of 326 monitored drains, 101 were found tapped to various STPs. Monitoring was carried out to the nearest possible confluence point.

Significant Flow and BOD load were observed in drains discharging from following cities:

- Kanpur: Total flow & BOD load discharged into rivers from Kanpur is 213.01 MLD & 21.96 TPD respectively through 31 drains (22 drains discharging into river Ganga having flow 113.29 MLD and BOD Load 12.79 TPD and 9 drains discharging into river Pandu having flow 99.72 MLD and BOD Load 9.17 TPD).
- Bulandshahar: 12 drains discharging into river Kali East having flow 129.06 MLD and BOD Load 20.7 TPD.
- Meerut: 4 drains discharging into river Kali East having flow 911.66 MLD and BOD Load 241.25 TPD.
- Bareilly: 3 drains discharging into river Ramganga having flow 311.36 MLD and BOD Load 18.8 TPD.
- Moradabad: 24 drains discharging into river Ramganga & Gagan having flow 176.05 MLD and BOD Load 27.05 TPD.

The brief status of monitored drains in Uttar Pradesh is given in Table-3 and district wise status is given in Table-4.

Table-3: Status of drains of river Ganga and its tributaries of Uttar Pradesh state during Post monsoon 2023

River	Post-Monsoon 2023
-------	-------------------

	Monitored Drains	Flow (MLD)	BOD Load (TPD)	Tapped Drains	Interim measure adopted	Domestic	Mixed
Ganga	188	1135.50	60.00	63	52	170	18
Ramganga, Kosi & Gagan	29	622.78	51.46	1	1	16	13
Kali East	29	1158.10	274.45	5	4	20	9
Pandu	9	99.72	9.17	6	-	2	7
Yamuna	30	24.23	2.35	11	4	29	1
Varuna & Moorwa	21	460.31	49.58	3	1	18	3
Jargo & Ojhala	8	12.92	2.12	-	4	7	1
Mansahaita	12	-	-	12	2	12	-
Total	326	3513.56	499.13	101	68	274	52

Table-4: District wise status of drains discharging into river Ganga and its tributaries in Uttar Pradesh

River	Monitored Drains	Flow (MLD)	BOD Load (TPD)	Tapped Drains	Interim measure adopted	Domestic	Mixed
25.Amroha							
Ganga	1	Dry	-	-	-	-	1
26.Balia							
Ganga	1	64.8	4.3	-	-	1	-
27.Bareilly							
Ramganga	3	311.36	18.8	-	-	1	2
28.Bhadohi							
Ganga	1	3.01	0.04	-	1	-	1
Varuna & Moorwa	5	24.81	1.39	-	1	2	3
Total	6	27.82	1.43	-	2	2	4
29.Bijnor							

Ganga	2	296.16	4.55	-	-	1	1
Ramganga	1	63.8	1.40	-	-	-	1
Total	3	359.96	5.95	-	-	1	2
30.Bulandshahar							
Kali East	12	129.06	20.7	-	4	9	3
31.Chandauli							
Ganga	5	78.19	1.0	-	2	3	2
32.Farrukhabad							
Ganga	6	70.15	2.3	2	1	4	2
33.Fatehpur							
Yamuna	1	FCM	-	-	-	1	-
34.Ghazipur							
Ganga	31	68.01	5.2	-	15	31	-
35.Hapur							
Ganga	2	21.68	0.74	-	-	2	-
Kali East	5	100.25	12.24	-	-	4	1
Total	7	121.93	12.98	-	-	6	1
36.Kannauj							
Kali East	3	17.14	0.2	3	-	3	-
37.Kanpur							
Ganga	22	113.29	12.79	10	6	17	5
Pandu	9	99.72	9.17	6	-	2	7
Total	31	213.01	21.96	16	6	19	12
38.Kasganj							
Kali East	4	-	-	2	-	4	-
39.Meerut							
Ganga	1	24.88	0.30	-	-	1	-
Kali East	4	911.66	241.25	-	-	-	4
Total	5	936.54	241.55	-	-	1	4
40.Mirzapur							
Ganga	37	129.85	11.14	10	14	35	2
Jargo-Ojhala	8	13.93	2.13	-	4	7	1
Total	45	143.78	13.27	10	18	42	3

41.Moradabad							
Ramganga & Gagan (tributary of river Ramganga)	24	176.05	27.05	1	1	15	9
42.Muzaffarnagar							
Kali East	1	FCM	-	-	-	-	1
43.Pratapgarh							
Ganga	6	5.73	0.144	-	-	6	-
44.Prayagraj							
Ganga	28	140.86	3.28	12	8	28	-
Yamuna	29	24.23	2.35	11	3	28	1
Manashita (tributary of river Ganga)	12	-	-	12	2	12	-
Total	69	165.09	5.62	35	13	68	1
45.Raebareli							
Ganga	8	0.086	0.004	-	5	7	1
46.Rampur							
Kosi (tributary of river Ramganga)	1	71.57	4.22	-	-	-	1
47.Unnao							
Ganga	6	69.49	11.37	-	-	4	2
48.Varanasi							
Ganga	31	49.32	2.77	29	-	30	1
Varuna	16	435.5	48.20	3	-	16	-
Total	47	484.82	50.97	32	-	46	1

FCM: Flow could not measured

The district-wise names and details of drains located in the state of Uttar Pradesh which have potential to discharge waste water in the main stem of River Ganga is placed as Annexure II.

Photographs of these drains along with their location is given in Annexure III.

2. Status of Sewage Management in Ganga front towns in Uttar Pradesh

There are 41 STPs located in 16 Ganga front towns in Uttar Pradesh. As per CPCB monitoring carried out during the April-July,2024 of STPs located in Ganga Front Towns of Uttar Pradesh, out of 41 STPs, 35 STPs were found operational and 6 STPs were found non-operational. 01 STP was found complying and 34 STPs were found non-complying w.r.t. Hon'ble NGT norms dated 30.04.2019. However, w.r.t. treated sewage discharge norms notified by Ministry of Environment Forests & Climate Change (MoEF & CC) dated 13.10.2017, 12 STP was found complying and 23 STPs were found non-complying.

The compliance verification of STPs are assessed on the basis of following standards:

- a. *NGT Standards: Compliance based on norms prescribed by Hon'ble NGT vide order dt 30.04.2019 in the matter of OA no. 1069/2018 (pH – 5.5-9.0, BOD <10mg/l, TSS< 20mg/l, COD< 50mg/l; Faecal Coliform – desirable <100MPN/100ml & permissible < 230 MPN/100 ml, Nitrogen-Total < 10 mg/l and Phosphorous-Total < 1.0 mg/l (TP compliance for discharge into ponds and lakes).*
- b. *Compliance compared with MoEF&CC notification dt. 13.10.2017: Standard for treated sewage from STPs for cities other than metro cities, state capitals and union territories were notified as pH-6.5-9.0, BOD as 30mg/L, Total suspended solids (TSS) as less than 100mg/L and Faecal coliform as less than 1000MPN per 100mL.*

The details of the 41 STPs located in 16 Ganga Front Towns are given below:

- Commissioned STPs – 41 (16 towns) with designed capacity – 1338.0 MLD
- Operational STPs – 35 (Operational capacity –1301.2 MLD) with Utilized capacity – 1116.23 MLD (~85.8% of operational capacity)
- Compliance Status of operational STPs.

	Compliance w.r.t. Hon'ble NGT vide order 30.04.2019	Compliance Status w.r.t MoEF & CC norms dated 13.10.2017
Complying	1	12
Non-complying	34	23

- Non-operational STPs – 06 (Designed capacity – 36.8 MLD)
- STPs complying for Faecal Coliform norms (<230 MPN/100ml) – 12
- STPs non-complying for Faecal Coliform norms (>230 MPN/100ml) – 23
- STPs having disinfection system – 34
- STPs operating over-capacity - 13 STP (Designed capacity – 404.86 MLD: Utilized Capacity – 470.95 MLD)
- Under-construction/ Under Trial STPs-11
- 15 MLD Baniyapur STP, Kanpur is completed but not-commissioned since more than three years.
- All 02 STPs located in Farrukhabad are non-operational leading to discharge of untreated sewage to river Ganga.

Table 5: District-wise summary of Sewage treatment plants located in Uttar Pradesh

Sr. No.	District	Town	No. of STPs	Designed capacity	Operational status	Utilized Capacity	Non-operational	Non-operational Capacity
1	Bijnor	1	1	24	1	23.87	0	-
2	Hapur	1	2	9	2	4.99	0	-
3	Bulandshahar	2	6	11.31	6	8.365	0	-
4	Farrukhabad	1	2	2.732	0	-	2	2.732
5	Kannauj	1	1	13	0	-	1	13
6	Kanpur Nagar	2	7	460.08	6	334.46	1	5
7	Mirzapur	3	3	21.01	3	13.33	0	.-
8	Prayagraj	1	10	340	9	373.9	1	16
9	Unnao	1	1	0.032	0	0	1	0.032
10	Varanasi	2	7	421.8	7	336.9	0	0
11	Bareilly	1	1	35	1	20.42	0	0
	Total	16	41	1337.96	35	1116.24	6	36.76

Out of 35 STPs found operational, 34 were found non-complying w.r.t Hon'ble NGT norms dated 30.4.2019. The operational and compliance status of these STPs is given in the table below:

Table 6: Operational & Compliance status of STPs

S. No.	Name of STPs	Ganga Front Town	District	Treatment Technology	Designed Capacity (MLD)	Date of Monitoring	Operational/ Non-Operational Status	Compliance Status w.r.t Hon'ble NGT norms dated 30.4.2019	Compliance w.r.t. MoEF & CC norms dated 13.10.2017
1	24 MLD STP Bijnor, Near Hemraj Colony	Bijnor	Bijnor	UASB	24	29.07.2024	Operational	Non-complying w.r.t BOD, CO D, FC & TN	Non-complying w.r.t FC
2	Brajghat (03 MLD) STP	Garhmukteshwar	Hapur	UASB	3	15.07.2024	Operational	Non-complying w.r.t FC	Complying
3	Garhmukteshwar STP	Garhmukteshwar	Hapur	UASB	6	15.07.2024	Operational	Non-complying w.r.t pH, BOD, CO D & TSS	Non-complying w.r.t. pH, BOD & TSS
4	Narora NAPS Township STP	Narora	Bulandshahar	ASP	2.25	28.05.2024	Operational	Non-complying w.r.t. BOD, CO D, TN & FC	Non-complying w.r.t. BOD & FC
5	Narora Town (4.0 MLD)	Narora	Bulandshahar	SBR	4	28.05.2024	Operational	Non-complying w.r.t BOD, COD, TSS & FC	Non-complying w.r.t FC

6	Anupshahar 1.5 MLD STP, Zone A	Anupshahr	Bulandshahr	MBBR	1.5	03.06.2024	Operational	Non-complying w.r.t. BOD, COD, TSSFC & TN	Non-complying w.r.t. BOD & FC
7	Anupshahar 0.81 MLD STP, Zone A	Anupshahr	Bulandshahr	WSP	0.81	03.06.2024	Operational	Non-complying w.r.t. BOD, COD, TN & FC	Non-complying w.r.t. FC
8	Anupshahar 1.75 MLD STP, Zone B	Anupshahr	Bulandshahr	WSP	1.75	03.06.2024	Operational	Non-complying w.r.t. COD, TSS, TN & FC	Non-complying w.r.t. FC
9	Anupshahar 1.0 MLD STP, Zone B	Anupshahr	Bulandshahr	MBBR	1	03.06.2024	Operational	Non-complying w.r.t. BOD, COD, TSS, TN & FC	Non-complying w.r.t. BOD & FC
10	2.7 MLD Fatehgarh	Farrukhabad	Farrukhabad	OP	2.7	24.01.2024	Non-Operational		
11	32 KLD FSTP, Near Bairoghat Temple	Farrukhabad	Farrukhabad	ABR	0.032	15.05.2024	Non-operational		
12	Jalalpur Amara (13 MLD) STP	Kannaunj	Kannaunj	SBR	13	14.05.2024	Non-operational		
13	130 MLD Jajmau STP Kanpur	Kanpur	Kanpur	ASP	130	30.04.2024	Operational	Non-complying w.r.t. BOD, COD, TSS & FC	Non-complying w.r.t. BOD & FC
14	Jajmau (43 MLD) Kanpur	Kanpur	Kanpur	ASP	43	30.04.2024	Operational	Non-complying	Non-complying

								w.r.t. BO D,COD,T SSTN & F C	w.r.t. B OD,TSS & FC
15	Jajmau (5 MLD) Kanpur	Kanpur	Kanpur	UASB	5	06.05.2024	Non-operational		
16	Bingawan (210 MLD) STP, Kanpur	Kanpur	Kanpur	UASB	210	14.05.2024	Operational	Non-complying w.r.t. BO D,COD,TN & FC	Non-complying w.r.t FC
17	30 MLD STP at Pankha	Kanpur	Kanpur	SBR	30	22.05.2024	Operational	Non-complying w.r.t. BO D,COD,T S,TN & FC	Non-complying w.r.t. BOD & FC
18	Sajari STP, Kanpur	Kanpur	Kanpur	ASP	42	21.06.2024	Operational	Non-complying w.r.t. BO D,COD & TN	Complying
19	Bithoor (80 KLD) STP	Bithoor	Kanpur	Constructed wetland	0.08	25.04.2024	Operational	Non-complying w.r.t. BO D,COD,TN & FC	Non-complying w.r.t FC
20	32 KLD FSTP, Nandauli Village	Unnao	Unnao	FSTP	0.032	15.5.2024	Non-operational		
21	29 MLD STP, Salori, Prayagraj	Prayagraj	Prayagraj	FAB reactor	29	11.06.2024	Operational	Non-complying w.r.t. BO D,TN & FC	Non-complying w.r.t FC
22	Salori (Bakshi Bandh) 14 MLD Prayagraj	Prayagraj	Prayagraj	SBR	14	11.06.2024	Operational	Complying	Complying

23	60 MLD STP, Rajapur, Prayagraj	Prayagraj	Prayagraj	UASB	60	12.06.2024	Operational	Non-complying w.r.t TN & BOD	Complying
24	10 MLD STP, Ponghat, Prayagraj	Prayagraj	Prayagraj	BTT followed by ASP	10	11.06.2024	Operational	Non-complying w.r.t TSS, TN, BOD & COD	Complying
25	25 MLD STP, Koda, Prayagraj	Prayagraj	Prayagraj	BTT followed by ASP	25	11.06.2024	Operational	Non-complying w.r.t TN	Complying
26	80 MLD STP, Nani, Prayagraj	Prayagraj	Prayagraj	ASP	80	11.06.2024	Operational	Non-complying w.r.t BOD, TN & FC	Non-complying w.r.t FC
27	42 MLD STP, Naini 2	Prayagraj	Prayagraj	FCR	42	11.06.2024	Operational	Non-complying w.r.t BOD, TSS, TN & FC	Non-complying w.r.t FC
28	50 MLD STP, Numayadhai, Prayagraj	Prayagraj	Prayagraj	BTT followed by ASP	50	10.06.2024	Operational	Non-complying w.r.t BOD, TN & FC	Non-complying w.r.t FC
29	14 MLD STP Phaphamau Prayagraj	Prayagraj	Prayagraj	FCR	14	10.06.2024	Operational	Non-complying w.r.t TN	Complying
30	16 MLD STP, Jhansi	Prayagraj	Prayagraj	FCR	16	11.06.2024	Non-operational		
31	14 MLD STP Mirzapur (Pakka Pokhra)	Mirzapur	Mirzapur	UASB	14	29.05.2024	Operational	Non-complying w.r.t BOD, COD, TN & FC	Non-complying w.r.t FC
32	7 MLD, STP, Vipur (V)	Mirzapur	Mirzapur	SBR	7	30.05.2024	Operational	Non-complying w.r.t	Non-complying

	ndhyach al,	indhya chal)						BOD,TN & FC	w.r.t FC
33	10 KLD FSTP Ch unar, Mi rzapur	Chuna r	Mirzap ur	FSTP	0.01	29.05. 2024	Operatio nal	Non-comp lying w.r.t. BOD,CO D,TS,TN & FC	Non-co mplying w.r.t. B OD & F C
34	80 MLD STP at D inapur	Varan asi	Varana si	TF & ASP	80	09.07. 2024	Operatio nal	Non-comp lying w.r.t BOD & T N	Complyi ng
35	50 MLD STP, Ra manna	Varan asi	Varana si	SBR	50	10.07. 2024	Operatio nal	Non-comp lying w.r.t. TN	Complyi ng
36	140 ML D STP at Dinapur	Varan asi	Varana si	ASP	140	09.07. 2024	Operatio nal	Non-comp lying w.r.t.TN	Complyi ng
37	10 MLD STP, Ra mnagar	Ramna gar, V aranasi	Varana si	A2O	10	10.07. 2024	Operatio nal	Non-comp lying w.r.t TSS, TN & CO D	Complyi ng
38	Bhagwa npur ST P	Varan asi	Varana si	ASP	9.8	09.07. 2024	Operatio nal	Non-comp lying w.r.t TN & FC	Non-co mplying w.r.t FC
39	120 ML D STP at Goithaha	Varan asi	Varana si	SBR	120	10.07. 2024	Operatio nal	Non-comp lying w.r.t. TN & FC	Non-co mplying w.r.t FC
40	12 MLD BLW (f ormer kn own as DLW)	Varan asi	Varana si	ASP	12	09.07. 2024	Operatio nal	Non-comp lying w.r.t. TN	Complyi ng
41	35 MLD STP Pla nt, Sarai Talfi, Ba	Bareill y	Bareill y	Exten ded A eration	35	14.05. 2024	Operatio nal	Non-comp lying w.r.t. BO D,COD,T	Non-co mplying w.r.t BO D & FC

reilly, U. P.						SSTN & F C
------------------	--	--	--	--	--	---------------

The detailed status of STPs in the state of Uttar Pradesh is placed as Annexure IV.

3. Status of water quality of River Ganga in Uttar Pradesh

Manual water quality monitoring of river Ganga is carried out by CPCB at 41 locations in Uttar Pradesh under National Water Quality Monitoring Programme (NWMP) through Uttar Pradesh Pollution Control Board on fortnightly basis.

River water quality is assessed for primary water quality criteria notified for outdoor bathing in terms of pH (6.5-8.5), Dissolved Oxygen (DO) (≥ 5 mg/L), Biochemical Oxygen Demand (BOD) (≤ 3 mg/L), Faecal Coliform (FC) (≤ 2500 MPN/100ml) and Faecal Streptococci (FS) (≤ 500 MPN/100ml).

Based on the water quality data of river Ganga from January 2024 to October 2024 (median values) in Uttar Pradesh, following observations have been made:

Entire stretch of river Ganga in Uttar Pradesh is meeting primary water quality criteria for outdoor bathing in terms of pH, DO, BOD, FC and FS except following stretches/locations:

❖ BOD

- i. Farrukhabad to Purana Rajapur, Kanpur
- ii. D/s Mirzapur to Tarighat, Ghazipur (except two locations namely U/s Varanasi & U/s Ghazipur)

❖ Faecal Coliform:

- i. upstream Kannauj to Purana Rajapur, Kanpur
- ii. (ii) D/s Mirzapur to Tarighat, Ghazipur (except U/s Varanasi)

❖ Faecal Streptococci:

- i. D/s Mirzapur to Tarighat, Ghazipur (except U/s Varanasi)

The water quality data of River Ganga at 41 locations in Uttar Pradesh during January- October, 2024 is placed as **Annexure V**.


(Reena Satavan)
Scientist 'E'

Central Pollution Control Board
14.02.2025

Item No. 16

Court No. 1

**BEFORE THE NATIONAL GREEN TRIBUNAL
PRINCIPAL BENCH, NEW DELHI**

Original Application No. 200/2014
(IA No 340/2022, MA No 872/2018, MA No
875/2014, IA No 389/2024, MA No 480/2018)

M. C. Mehta

Applicant

Versus

Union of India & Ors.

Respondent(s)

Date of hearing: 13.09.2024

**CORAM: HON'BLE MR. JUSTICE PRAKASH SHRIVASTAVA, CHAIRPERSON
HON'BLE MR. JUSTICE SUDHIR AGARWAL, JUDICIAL MEMBER
HON'BLE DR. A. SENTHIL VEL, EXPERT MEMBER**

Applicant: Ms. Katyayni, Advocate

Respondent: Mr. Gigi. C. George, Adv. with Mr. Pravin Kumar, Director, NMCG
(Through VC)
Mr. Saurabh Jain & Mr. Prayag Jain, Advs. for the State of Jharkhand
Mr. Jayesh Gaurav & Mr. Ishwar Chandra Roy, Advs. for Jharkhand
SPCB
Mr. Raj Kumar, Adv. for CPCB (Through VC)

ORDER

1. In this original application, the Tribunal is considering the issue of prevention and control of pollution in river Ganga and the matter is being taken up State-wise and District-wise.

2. Today, the matter is listed for considering the compliance status in the **State of Jharkhand**.

3. The reports on behalf of the DC, Dhanbad, Bokaro, Sahibganj and Ramgarh have been filed. The same has been examined by us. On examining reports of DCs for the Districts Sahibganj, Ramgarh, Dhanbaad and Bokaro, we find a very grim picture of sewage management. District-wise deficiencies and gaps are as follows:

1. District SahibganjSahibganj

- (i) Out of 8 MLD of sewage generation in Sahibganj, 6.8 MLD is treated in two STPs of 7.0 and 5.0 MLD. However, we find that only 6.2 MLD is discharged from two STPs.
- (ii) There is no disclosure about the performance of STPs for fecal coliform. Further, 1.2 MLD is still required to be connected with existing STPs.

Rajamahar

- (i) Out of 0.97 MLD of sewage generation, 0.91 is being treated in 3.5 MLD of STP. No data is disclosed about Fecal Coliform (FC) in treated sewage.
- (ii) Water quality data of river Ganga concerning FC has not been provided.
- (iii) For 87 km of stretch of river Ganga, 54.47 sq. km area is considered a flood plain zone which is based on submergence /HFL.

2. District Ramgarh

- (i) It has been disclosed that some wards are abutting river Damodar fully or partially but the basis of saying so is not clarified.
- (ii) For treating sewage generation of 32.38 MLD two STPs of 40 MLD and one STP based on the Pond system have been set up. However, there is no disclosure of the actual utilisation of installed facilities and their performance.

3. District Dhanbaad

- (i) It is a matter of great concern that no sewage treatment facilities exist. Tenders are now floated for setting up of 192.0 MLD of STP and this indicates that untreated sewage is being discharged. Further, there is no disclosure of the generation of sewage.
- (ii) We find that a large number of Hotels are operating without CTO and PCB has only written letters on 2.3.2024 to apply for CTO. This further raises the issue that effluents from the hotels must be either seeping or being discharged into drains.

- (iii) No data has been furnished on fecal coliform present in River Damodar. Further, we find that PCB has no testing facilities for fecal coliform. We direct that, in the next three months JSPCB should set up the required facilities and undertake analysis.

4. District Bokaro

- (i) Bokaro Steel Plant township generates 31.972 MLD sewage and 6 lagoons are provided for treatment. But the final mode of disposal and its quality have not been disclosed.
- (ii) We find that Nagar Nigam Chas is generating 12.44 MLD and is discharging sewage through 70 drains into the river Ganga. This clearly reflects violations of the Water Act and the order of the Hon'ble Supreme Court dated 22.02.2017 in Paryaavaran Suraksha.
- (iii) We also find that Nagar Nigam Phusro has no sewage treatment facilities for treating 3.92 MLD. Further, water quality data of river Damodar is not disclosed for FC.

4. Learned Counsel for the Applicant has pointed out that the Central Pollution Control Board (CPCB) has details of all the drains in different districts of the states and, therefore, the details relating to the drains abutting river Ganga and its tributaries and the drains falling in Ganga and its tributaries are also available with the CPCB. She has also submitted that the details of the sewage being discharged by these drains in Ganga and its tributaries are also available on the website of CPCB.

5. We find that for last more than one year whenever the matter is taken up, CPCB is not represented. When the issue of the availability of the details was raised by Counsel for the Applicant, at that stage, Counsel for the CPCB appeared virtually.

6. Learned Counsel for the CPCB submits that he will obtain instructions and place the complete record of drains in respect of all the districts of Jharkhand through which the river Ganga and its tributaries are flowing along with the details of outfall points and the quantity of

untreated sewage flowing in river Ganga and its tributaries. He is directed to provide such details in respect of other States and also district-wise one week in advance whenever those matters are taken up.

7. Learned Counsel for National Mission for Clean Ganga (NMCG Mr. Gigi. C. George, Advocate) is also present. Nothing has been pointed out as to what action the NMCG has taken to ensure the prevention of the flow of untreated sewage in river Ganga or its tributaries, except by stating that the funds have been provided for the construction of STPs in the districts under consideration and their monitoring is done and directions issued.

8. We take note of the fact that under clause 34 of the River Ganga (Rejuvenation, Protection and Management) Authorities Order, 2016 (2016 Order) the NMCG is an empowered organization and in terms of clause 39 of the 2016 order, NMCG has the following functions to perform:

“39. Functions of National Mission for Clean Ganga.- (1)
Without prejudice to the provisions of this Order, the National Mission for Clean Ganga shall identify or cause to be identified –

- (a) the specific threats to the River Ganga in areas in each village and town of such specified District abutting River Ganga and its tributaries, including sewerage and industrial waste, cremation and burial of corpses and disposal of animal carcasses, and threats from commercial, recreational and religious activities;*
- (b) the type of measures required to address such threat in each village and town of all districts abutting River Ganga and its tributaries;*
- (c) the specific areas where such remedial actions are required to be taken for rejuvenation and protection of River Ganga and its tributaries.*
- (d) the measures which may be necessary for reuse of treated water and enter in to Memorandum of Understanding in this regard with the Ministries of the Central Government like Railways, Power, Petroleum and Natural Gas etc., State Governments, autonomous bodies at the Central and State level, recognized Institutes and organizations which the National Mission for Clean Ganga may deem fit.*

(2). *The National Mission for Clean Ganga shall make or cause to make the River Ganga Basin Management Plan along with cost, timelines and allocation of responsibilities, among other things, for rejuvenation and protection of River Ganga and its tributaries in each village and town of specified District abutting River Ganga and its tributaries and execute projects there for.*

(3). *The National Mission for Clean Ganga shall*

- (a) *cause to be determined the magnitude of ecological flows in the River Ganga and its tributaries required to be maintained at different points in different areas at all times with the aim of ensuring water quality and environmentally sustainable rejuvenation, protection and management of River Ganga and its tributaries and notifying the same and take or direct all such measures necessary to maintain adequate ecological flows;*
- (b) *cause to be identified places where the environmental flow of water of River Ganga has been modified and take measures for correction thereof to maintain the continuous flow of water for rejuvenation, protection and management of River Ganga and its tributaries;*
- (c) *identify places of discontinuity of water in River Ganga and its tributaries due to engineered diversion of water or storage of water or by any other means and execute plans in respect thereof or take remedial action therefor;*
- (d) *devise a system to be put in place for continuous monitoring of flow of water and pollution levels in River Ganga and its tributaries;*
- (e) *take all such measures which may be necessary to give effect to the decisions of the National Ganga Council so as to maintain adequate ecological flows in the River Ganga and tributaries;*
- (f) *render assistance or cause them to be rendered by any agency for preparation of detailed project reports or execution of projects for abatement of pollution and rejuvenation, protection and management of the River Ganga and its tributaries to the State Governments, the State Ganga Committees, District Ganga Committees or local authorities or any person or body, any authority, Board or Corporation;*
- (g) *set up or facilitate setting up or designate and direct one or more existing centers to research, develop and disseminate knowledge base and analytical tools on abatement of pollution and rejuvenation, protection and management of River Ganga and its tributaries;*
- (h) *take any other measures which may be necessary for continuous flow of water and abatement of pollution in River Ganga and its tributaries*

(4) *The National Mission for Clean Ganga shall take all such other emergency measures as outlined in paragraph 7.”*

9. The powers of the NMCG have been set out in clause 41 of the 2016 order which reads as under:

“41. Powers of National Mission for Clean Ganga.- (1) *The National Mission for Clean Ganga being the national agency charged with the role, responsibility and powers to facilitate the task of rejuvenation, protection and management of River Ganga and its tributaries, under the supervision and direction of the National Ganga Council, shall recommend to the National Ganga Council or Central Government for issuing directions or issue directions itself, to the State Ganga Committees or District Ganga Committees or local authority or any other authority or any person, institution, consortium or agency, as it may decide, for the rejuvenation, protection and management of River Ganga and have the power to take all such measures and discharge such functions as it may deem necessary or expedient for prevention, control and abatement of environmental pollution in River Ganga and its tributaries so as to rejuvenate the River Ganga to its natural and pristine condition and ensure continuous and adequate flow of water in River Ganga and for protection and management of River Ganga and for matters connected therewith.*

(2) *In particular and without prejudice to the generality of the provisions of sub-paragraph (1), and save as otherwise provided in this Order, such directions may include all or any of the following matters in the management of River Ganga, namely:-*

- (a) *fulfillment of the functions mentioned in paragraph 55 in accordance with the principles in paragraph 4;*
- (b) *formulate, with the approval of the Central Government, the National policy for effective abatement of pollution and rejuvenation, protection and management of River Ganga;*
- (c) *enter into memorandum of understanding, with the approval of the Central Government, with any country or foreign agency for effective implementation of the River Ganga Basin Management Plan for rejuvenation, protection, prevention, control and abatement of pollution in the River Ganga and its tributaries;*
- (d) *approve, with or without modifications, the River Ganga Basin Management Plan and direct amendments, if any, to be made therein;*
- (e) *supervise and review the progress reports, and issue directions to the State Ganga Committees, District Ganga Committees or local authorities and other authorities in the implementation of the River Ganga Basin Management Plan and any other matter connected with affairs of the River Ganga and its tributaries;*
- (f) *approve the planning, financing and execution of programmes for abatement of pollution in the River Ganga including augmentation of sewerage and effluent treatment infrastructure, catchment area treatment, protection of flood plains, creating public awareness, conservation of aquatic and riparian life and biodiversity and such other measures for promoting environmentally sustainable river rejuvenation;*
- (g) *coordination, monitoring and review of the implementation of various programmes or activities taken up for prevention, control and abatement of pollution and*

protection and management in the River Ganga and its tributaries;

- (h) direct any person or authority to take measures for restoration of river ecology and management in the River Ganga Basin States;*
- (i) recommend to the Central Government, for creation of special purpose vehicles (whether as a company under the companies Act, 2013(18 of 2013) or Societies Registration Act, 1860 (21 of 1860) or a Trust under the Indian Trust Act, 1882 (2 of 1882)), as may be considered appropriate, for implementation of this Order and for the purposes of the Act;*
- (j) take such measures as may be necessary for the better co-ordination of policy and action to ensure effective prevention, control and abatement of pollution, rejuvenation and protection and management in the River Ganga and its tributaries;*
- (k) issue such directions to any person or authority, as it may consider necessary, for proper or prompt execution of the projects or cancel such projects or stop release of funds or direct refund of amount already released and assign the same to any other person or authority or Board or Corporation for prompt execution thereof;*
- (l) direct any person or authority to maintain such books of account or other documents, without prejudice to any law for the time being in force, as may be specified by the National Mission for Clean Ganga;*
- (m) take such other measures which may be necessary for achievement of prevention, control and abatement of pollution, rejuvenation and protection and management in the River Ganga and its tributaries;*

(3) The National Mission for Clean Ganga shall have the power to issue directions mentioned under section 5 of the Act.

(4) The National Mission for Clean Ganga may evolve an appropriate mechanism for implementation of its decisions and the decisions of the National Ganga Council.”

10. Hence, we require the NMCG to appraise the Tribunal by filing a report by way of an affidavit in respect of the exercise of these powers and discharge of these duties to prevent the flowing of untreated sewage in river Ganga or its tributaries.

11. We also take note of the fact that the information provided by the different districts of the State of Jharkhand is not complete in all respects. Therefore, we require them to furnish the information in the format mentioned below:

District Wise (including city and town) information on river Ganga and Tributaries

A. Sewage Management								
(i) Sewage generation	(ii) Existing Sewage Treatment Capacities	(iii) Quantity of sewage being treated (utilization capacity)	(iv) Performance of STPs particularly for FC	(v) Reasons for Underutilization of STPs (Connectivity of Households/ laying of sewer lines)	(vi) Current Gap in sewage treatment	(vii) Time bound plan for bridging the gap and tying up with financial arrangements and not delaying Tendering and identifying executing agencies or having any other issues	(viii) Where treated sewage is being discharged (to Ganga or tributaries)	(ix) Where untreated sewage is discharged (Drains joining Ganga/Tributaries)

District Wise (including city and town) information on river Ganga and Tributaries

B. Drains			
(i) Details of drains carrying sewage-sullage or industrial waste water joining Ganga/ tributaries and the Quantity	(ii) Drains joining outside city and town limits but either joining in village or nearby town	(iii) Inclusion of sewage flowing in drains into total sewage generation figures and their interception and diversion to STPs	(iv) Preventive steps taken for not encroachment of drains

District Wise (including city and town) information on river Ganga and Tributaries

C. Septage management (Septic tanks/soak pits)				
(i) Status of Septage management with reference to FSTP/STP	(ii) Management of Grey Water	(iii) Utilization of treated Grey water	(iv) Utilization and Disposal of Sludge	(v) Gap in sewage management and time plan

District Wise (including city and town) information on river Ganga and Tributaries

D. Industrial Pollution Control
No. of industries generating trade effluents, their place of disposal and compliance

E. District Wise (including city and town) information on river Ganga and Tributaries	
Water quality status of Ganga and its tributaries in the District and city/ town in terms of its fitness for Bathing water quality that is, FC and FS	Notification of Flood Plain Zones

District Wise (including city and town) information on river Ganga and Tributaries

F. Issues relating to Environmental Flow

12. List on 25.03.2025.

Prakash Shrivastava, CP

Sudhir Agarwal, JM

Dr. A. Senthil Vel, EM

September 13, 2024
Original Application No. 200/2014
(IA No 340/2022, MA No 872/2018, MA No
875/2014, IA No 389/2024, MA No 480/2018)
dv..

Pre-Monsoon 2023

Status of monitored drains of river Ganga and its tributaries of Uttar Pradesh state during Pre-monsoon 2023.

River Name	Pre-Monsoon 2023						
	Monitored Drains	Flow (MLD)	BOD Load (TPD)	Tapped Drains	Interim measures adopted	Domestic	Mixed
Ganga	179	673.9	34.20	62	80	164	15
Ramganga	24	443.4	36.16	-	1	15	9
Kali East	29	1393.3	321.66	4	3	19	10
Pandu	9	78.6	5.28	5	2	2	7
Yamuna	21	14.2	0.33	8	4	20	1
Varuna and Moorwa	22	224.9	11.46	10	3	19	3
Jargo and Ojhala	10	4.34	0.05	-	2	9	1
Duar and Mansahaita	13	26.7	1.10	6	6	13	-
Total	307	2859.39	410.23	95	101	261	46

Drains data of Uttar Pradesh district wise (Pre-Monsoon 2023)

S. No.	Name of Drain	District	Town/ City in Catchment/ nearby	Pollution Sources (Domestic/ Mixed/ Industrial)	Confluence to River	Sampling location		Tapped/ Untapped	Flow (MLD)	BOD Load (TPD)	BOD (mg/l)	COD (mg/l)
						Latitude	Longitude					
1.	Bagad drain	Amroha	Gajraula	Mixed	Ganga	28.80646	78.21688	Untapped	Dry	-	-	-
2.	Kathal Drain	Balia	Balia	Domestic	Ganga	25.73861	84.14404	Untapped	9.3	0.26	28.1	87.6
3.	Devraniya Drain	Bareilly	Bareilly	Mixed	Ramganga	28.34963	79.37829	Untapped	62.83	8.36	133	266
4.	Chaubari Drain	Bareilly	Bareilly	Domestic	Ramganga	28.28649	79.40418	Untapped	49.76	1.57	31.6	111
5.	Nakatiya Drain	Bareilly	Bareilly	Mixed	Ramganga	28.25047	79.43639	Untapped	40.43	1.35	33.5	115
6.	Chauri Drain	Bhadohi	Bhadohi	Domestic	Moorwa	25.36958	82.60557	Untapped	5.95	0.23	38	139
7.	Barbaspur Drain	Bhadohi	Bhadohi	Mixed	Moorwa	25.36367	82.55375	Untapped	10.01	0.20	20	52.2
8.	BIDA Drain	Bhadohi	Bhadohi	Mixed	Moorwa	25.38062	82.61452	Untapped	2.01	0.38	187	330
9.	Mamdevpur Drain	Bhadohi	Bhadohi	Mixed	Varuna	25.41669	82.56828	Untapped	7.03	0.22	31.8	87.5
10.	Nai Bazar Drain/ Chaura Drain	Bhadohi	Bhadohi	Domestic	Varuna	25.41392	82.57813	Untapped	16.69	0.88	52.5	121
11.	Nohra/ Nasiya drain/ Punsu drain	Bijnor	Bijnor	Mixed	Ramganga	29.10429	78.64804	Untapped	FCM (flood like situation)	-	-	-
12.	Gulaothi Drain	Bulandshahr	Gulaothi	Mixed	Kali-East	28.59129	77.80235	Untapped	23.22	4.18	180	486
13.	Maman Road Drain	Bulandshahr	Bulandshahr	Mixed	Kali-East	28.39277	77.86272	Untapped	24.66	0.76	31	100
14.	Aadil Drain	Bulandshahr	Bulandshahr	Domestic	Kali-East	28.39604	77.86252	Untapped	FCM (due to drain was covered with huge	-	50	230

S. No.	Name of Drain	District	Towns/ City in Catchment/ nearby	Pollution Sources (Domestic/ Mixed/ Industrial)	Confluence to River	Sampling location		Tapped/ Untapped	Flow (MLD)	BOD Load (TPD)	BOD (mg/l)	COD (mg/l)
						Latitude	Longitude					
									solid wastes)			
15.	Chandbhari Drain	Bulandshahr	Bulandshahr	Domestic	Kali-East	28.40006	77.86479	Untapped	1.94	0.36	186	484
16.	Cheel Ghat Drain	Bulandshahr	Bulandshahr	Mixed	Kali-East	28.40053	77.86669	Untapped	2.42	0.04	18	102
17.	Nishal Ghat Drain	Bulandshahr	Bulandshahr	Domestic	Kali-East	28.40461	77.86621	Untapped	FCM (due to covered drain and lean flow)	-	138	348
18.	Kasai Bada Drain	Bulandshahr	Bulandshahr	Domestic	Kali-East	28.40768	77.86196	Untapped	4.94	0.36	72	246
19.	Faisalabad Drain	Bulandshahr	Bulandshahr	Mixed	Kali-East	28.40851	77.86316	Untapped	5.3	0.37	69	187
20.	Behind Shanidev Mandir Drain	Bulandshahr	Bulandshahr	Domestic	Kali-East	28.40987	77.86076	Untapped	FCM (due to lean flow & solid waste found in drain)	-	129	294
21.	Devipura Drain	Bulandshahr	Bulandshahr	Domestic	Kali-East	28.41244	77.85833	Untapped	FCM (due to unapproachable site conditions)	-	125	281
22.	Behind Chamunda Mandir Drain	Bulandshahr	Bulandshahr	Domestic	Kali-East	28.41709	77.85347	Untapped	20.84	1.00	48	131
23.	DM Colony Drain	Bulandshahr	Bulandshahr	Domestic	Kali-East	28.41982	77.85166	Untapped	1.54	0.12	80	282
24.	Railway Drain	Chandauli	Mughalsarai	Mixed	Ganga	25.32094	83.14090	Untapped	44.24	1.08	24.4	53.1

S. No.	Name of Drain	District	Towns/ City in Catchment/ nearby	Pollution Sources (Domestic/ Mixed/ Industrial)	Confluence to River	Sampling location		Tapped/ Untapped	Flow (MLD)	BOD Load (TPD)	BOD (mg/l)	COD (mg/l)
						Latitude	Longitude					
25.	Mughalsarai / Local Drain / Ganda nala	Chandauli	Mughalsarai	Mixed	Ganga	25.32135	83.11424	Untapped	8.41	0.11	12.7	40
26.	NTPC Drain	Raebareli	Unchahar	Mixed	Ganga	25.89217	81.29525	Untapped	FCM (due to Planktonic growths in drain)	-	5.68	18.5
27.	Padwa Drain, Muraibagh, Shankar Nagar	Raebareli	Dalmau	Domestic	Ganga	26.07065	81.02847	Untapped	FCM	-	5.58	22.2
28.	Bada Math aur Chhota math ke beech ka naala, Sherandajpur	Raebareli	Dalmau	Domestic	Ganga	26.07065	81.02847	Untapped	Dry	-	-	-
29.	Barudda Ghat / Basuda Ghat Drain, Sherandajpur	Raebareli	Dalmau	Domestic	Ganga	26.05853	81.03153	Untapped	Dry (very lean flow)	-	-	-
30.	Shukla Ghat ka Nala, Sherandajpur	Raebareli	Dalmau	Domestic	Ganga	26.05942	81.02987	Untapped	Dry	-	-	-
31.	Pathvari Ghat ka Nala, Tikaitganj	Raebareli	Dalmau	Domestic	Ganga	26.06054	81.02910	Untapped	0.05	0.003	66	174
32.	Sadak Ghat Muroop Nala/ Sadak Ghat Drain, Tikaitganj	Raebareli	Dalmau	Domestic	Ganga	26.06442	81.02708	Untapped	1.18	0.02	20.7	60.4
33.	Deen shah Gaora Ghat	Raebareli	Dalmau	Domestic	Ganga	26.06054	81.02910	Untapped	Dry	-	-	-

S. No.	Name of Drain	District	Towns/ City in Catchment/ nearby	Pollution Sources (Domestic/ Mixed/ Industrial)	Confluence to River	Sampling location		Tapped/ Untapped	Flow (MLD)	BOD Load (TPD)	BOD (mg/l)	COD (mg/l)
						Latitude	Longitude					
	drain / Raja Tiloi Ghat Nala											
34.	Dhinapur Drain	Farrukhabad	Farrukhabad	Mixed	Ganga	27.40147	79.62268	Untapped	3.16	0.05	15.6	68.6
35.	Bhairoghat Drain	Farrukhabad	Farrukhabad	Mixed	Ganga	27.40369	79.61655	Untapped	15.55	0.37	23.7	61.2
36.	Hathikhana Drain	Farrukhabad	Farrukhabad	Domestic	Ganga	27.35330	79.63476	Partially tapped	9.95	0.11	10.6	46.5
37.	Bargadia Ghat Drain	Farrukhabad	Farrukhabad	Domestic	Ganga	27.36494	79.63866	Untapped	FCM (stagnant water)	-	48	98
38.	Cannt Drain	Farrukhabad	Farrukhabad	Domestic	Ganga	27.38473	79.63044	Partially tapped	9.96	0.44	43.7	116
39.	Navabag to Lodhiganj	Fatehpur	Fatehpur	Domestic	Yamuna	25.89869	80.84931	Untapped	10.53	0.073	6.95	42.8
40.	Kot Ghat Drain	Ghazipur	Saidpur	Domestic	Ganga	25.53300	83.22528	Untapped	1.47	0.02	11.4	64.9
41.	Budenath Mahadev Ghat Drain	Ghazipur	Saidpur	Domestic	Ganga	25.53320	83.22324	Untapped	0.07	0.00	24	109
42.	Pakka Ghat Drain	Ghazipur	Saidpur	Domestic	Ganga	25.53389	83.22070	Untapped	1.94	0.05	26.6	78.8
43.	Sangat Ghat Drain	Ghazipur	Saidpur	Domestic	Ganga	25.53423	83.21945	Untapped	FCM (due to meagre flow)	-	-	-
44.	Mahaveer Ghat Drain	Ghazipur	Saidpur	Domestic	Ganga	25.53428	83.21850	Untapped	1.60	0.03	16.3	92
45.	Ramghat/ Ward no. 15 Malhiya Basti Drain	Ghazipur	Saidpur	Domestic	Ganga	25.53462	83.21687	Untapped	0.04	0.001	21.8	86.6

S. No.	Name of Drain	District	Towns/ City in Catchment/ nearby	Pollution Sources (Domestic/ Mixed/ Industrial)	Confluence to River	Sampling location		Tapped/ Untapped	Flow (MLD)	BOD Load (TPD)	BOD (mg/l)	COD (mg/l)
						Latitude	Longitude					
46.	Rangmahal Ghat Drain	Ghazipur	Saidpur	Domestic	Ganga	25.53573	83.21202	Untapped	0.79	0.01	9.3	25.4
47.	Jauhargaj Drain	Ghazipur	Saidpur	Domestic	Ganga	25.53703	83.20321	Untapped	FCM (due to meagre flow)	-	-	-
48.	Kuluhaghat Drain	Ghazipur	Saidpur	Domestic	Ganga	25.53704	83.20407	Untapped	1.61	0.04	23.4	66.1
49.	Gorwa Drain	Ghazipur	Zamnia	Domestic	Ganga	25.42164	83.55626	Untapped	4.40	0.13	28.6	100
50.	Kankarwa Drain	Ghazipur	Zamnia	Domestic	Ganga	25.41707	83.55360	Untapped	1.16	0.05	46	112
51.	Kanpuimai Ghat Drain	Ghazipur	Zamnia	Domestic	Ganga	25.41503	83.55348	Untapped	4.15	0.10	23.2	64.9
52.	Bada Mahadev /Adarsh Bazar Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.56274	83.56169	Untapped	2.88	0.11	37.4	128
53.	Pear Nagar Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.56682	83.56358	Untapped	0.92	0.03	37.4	111
54.	Khirki Ghat Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.58327	83.59569	Untapped	FCM (due to less flow)	-	-	-
55.	DM Banglo Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.56716	83.56662	Untapped	15.50	0.47	30.2	93.2
56.	Afim Factory Colony Drain/ Mahala Basti / Sikandpur Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.56970	83.56843	Untapped	FCM (due to meagre flow)	-	-	-
57.	Dadri Ghat Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.57428	83.57740	Untapped	2.50	0.09	37.6	107
58.	Collector Ghat Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.57764	83.58400	Untapped	0.99	0.11	114	261

S. No.	Name of Drain	District	Towns/ City in Catchment/ nearby	Pollution Sources (Domestic/ Mixed/ Industrial)	Confluence to River	Sampling location		Tapped/ Untapped	Flow (MLD)	BOD Load (TPD)	BOD (mg/l)	COD (mg/l)
						Latitude	Longitude					
59.	Maksud Ghat Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.57936	83.58778	Untapped	0.60	0.02	41.2	117
60.	Gola Ghat Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.57878	83.58900	Untapped	FCM (due to meagre flow)	-	-	-
61.	Stimer Ghat Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.58075	83.59119	Untapped	1.38	0.15	111	265
62.	Chetnat Ghat Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.58093	83.59158	Untapped	0.32	0.01	21.4	72.4
63.	Anzahi Ghat Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.58232	83.59386	Untapped	42.30	1.86	44	123
64.	Theri bazar Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.58267	83.59501	Untapped	FCM (due to meagre flow)	-	336	935
65.	Posta Ghat Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.58445	83.59855	Untapped	FCM (due to irregular channel & less flow)	-	43.4	128
66.	Budhava Mahadeva Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.58543	83.59765	Untapped	FCM (due to less flow)	-	28.4	134
67.	Roohi Mandi Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.58441	83.59854	Untapped	FCM (due to the uneven channel)	-	47.6	143
68.	Shamshan Ghat Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.58626	83.60188	Untapped	FCM (due to uneven channel & solid waste dumping)	-	47.6	143
69.	Harizan Basti drain	Ghazipur	Ghazipur	Domestic	Ganga	25.58682	83.60301	Untapped	FCM (due to lean flow)	-	55.2	180

S. No.	Name of Drain	District	Towns/ City in Catchment/ nearby	Pollution Sources (Domestic/ Mixed/ Industrial)	Confluence to River	Sampling location		Tapped/ Untapped	Flow (MLD)	BOD Load (TPD)	BOD (mg/l)	COD (mg/l)
						Latitude	Longitude					
70.	Sai Mandir Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.57179	83.57228	Untapped	3.72	0.12	33.2	112
71.	Garh drain	Hapur	Garhmukhteshwar	Domestic	Ganga	28.77294	78.12950	Untapped	FCM (due to flooded conditions)	-	-	-
72.	Phuldera Drain	Hapur	Shimbhawali, Hapur	Domestic	Ganga	28.64572	78.06888	Untapped	Dry	-	-	-
73.	Chhoiya drain	Hapur	Hapur	Domestic	Kali-East	28.68481	77.78532	Untapped	FCM (due to eutrophication)	-	10	34
74.	Hapur drain	Hapur	Hapur	Domestic	Kali-East	28.68481	77.78532	Untapped	49.7	6.81	137	300
75.	Hapur city drain	Hapur	Hapur city	Domestic	Kali-East	77.83033	28.72598	Untapped	13.9	0.81	58	116
76.	Babugarh drain	Hapur	Babugarh, Hapur city	Domestic	Kali-East	28.72617	77.83174	Untapped	4.57	0.29	64	195
77.	Kadrabad drain	Hapur	Hapur and Modinagar	Mixed	Kali-East	28.63526	77.80486	Untapped	63.02	4.54	72	147
78.	Patta Nala	Kannauj	Kannauj	Domestic	Kali East	27.07623	79.92633	Partially tapped	9.216	0.10	11.3	35.5
79.	Adanga Nalla	Kannauj	Kannauj	Domestic	Kali East	27.06360	79.94460	Untapped	1.66	0.03	18.3	42.8
80.	Tammi Nalla	Kannauj	Kannauj	Domestic	Kali East	27.05140	79.93020	Partially tapped	1.01	-	< 5.0	9.75
81.	Luv-Kush Drain	Kanpur	Bithoor	Domestic	Ganga	26.59793	80.27353	Untapped	FCM (due to less flow)	-	41.8	122
82.	Bhannu Nala	Kanpur	Bithoor	Domestic	Ganga	26.60581	80.27357	Untapped	FCM (due to less flow)	-	20.7	79.1
83.	Peshwa Nala	Kanpur	Bithoor	Domestic	Ganga	26.60917	80.27364	Untapped	FCM (due to less flow)	-	21.4	73.8

S. No.	Name of Drain	District	Towns/ City in Catchment/ nearby	Pollution Sources (Domestic/ Mixed/ Industrial)	Confluence to River	Sampling location		Tapped/ Untapped	Flow (MLD)	BOD Load (TPD)	BOD (mg/l)	COD (mg/l)
						Latitude	Longitude					
84.	Brahamawat Ghat	Kanpur	Bithoor	Domestic	Ganga	26.61116	80.27483	Tapped	FCM (due to less flow)	-	9.65	40.2
85.	Laxman Ghat Drain	Kanpur	Bithoor	Domestic	Ganga	26.61568	80.27164	Untapped	FCM (due to less flow)	-	38.6	134
86.	Kalwari Ghat Drain	Kanpur	Bithoor	Domestic	Ganga	26.61899	80.27079	Untapped	FCM (due to less flow)	-	102	211
87.	Permiya Drain	Kanpur	Kanpur	Domestic	Ganga	26.50067	80.31929	Partially Tapped	57.60	1.47	25.6	53.9
88.	Ranighat Drain	Kanpur	Kanpur	Domestic	Ganga	26.49639	80.32329	Untapped	FCM (due to uneven path of drain)	-	93.6	221
89.	Sisamau Drain	Kanpur	Kanpur	Domestic	Ganga	26.49108	80.33276	Tapped	-	-	-	-
90.	Tefco Drain	Kanpur	Kanpur	Domestic	Ganga	26.48726	80.34445	Tapped	-	-	-	-
91.	Parmath Drain	Kanpur	Kanpur	Domestic	Ganga	26.48618	80.34670	Tapped	-	-	-	-
92.	Muir Drain	Kanpur	Kanpur	Domestic	Ganga	26.48236	80.35121	Tapped	-	-	-	-
93.	Police line Drain	Kanpur	Kanpur	Domestic	Ganga	26.48019	80.35538	Tapped	-	-	-	-
94.	Jail Drain	Kanpur	Kanpur	Domestic	Ganga	26.47974	80.35693	Tapped	-	-	-	-
95.	Gola Ghat Drain	Kanpur	Kanpur	Domestic	Ganga	26.46556	80.37551	Untapped	1.04	0.06	56	214
96.	Bhagwatdas Drain	Kanpur	Kanpur	Domestic	Ganga	26.47451	80.36388	Tapped	-	-	-	-
97.	Sattichaura Drain	Kanpur	Kanpur	Domestic	Ganga	26.45866	80.38119	Tapped	-	-	-	-
98.	Dabka Drain	Kanpur	Kanpur	Mixed	Ganga	26.44415	80.39384	Untapped	4.50	0.95	212	476
99.	Sheetla Bazar Drain	Kanpur	Kanpur	Mixed	Ganga	26.43721	80.40383	Tapped	-	-	-	-
100.	Airforce Drain	Kanpur	Kanpur	Domestic	Ganga	26.45914	80.38078	Untapped	0.38	0.01	32.2	123

S. No.	Name of Drain	District	Towns/ City in Catchment/ nearby	Pollution Sources (Domestic/ Mixed/ Industrial)	Confluence to River	Sampling location		Tapped/ Untapped	Flow (MLD)	BOD Load (TPD)	BOD (mg/l)	COD (mg/l)
						Latitude	Longitude					
101.	Budiyaghat Drain	Kanpur	Kanpur	Mixed	Ganga	26.43115	80.41162	Tapped	-	-	-	-
102.	Wajidpur Drain	Kanpur	Kanpur	Mixed	Ganga	26.42346	80.41915	Tapped	-	-	-	-
103.	Rooma Drain	Kanpur	Kanpur	Mixed	Ganga	26.35442	80.48606	Untapped	112.24	2.64	23.5	84
104.	Ratanpur Drain	Kanpur	Kanpur	Mixed	Pandu	26.46680	80.21079	Tapped	-	-	-	-
105.	ICICI Drain	Kanpur	Kanpur	Mixed	Pandu	26.43619	80.25377	Tapped	-	-	-	-
106.	Panki Drain	Kanpur	Kanpur	Mixed	Pandu	26.45590	80.22600	Untapped	8.58	0.72	84	299
107.	Halwakhanda Drain	Kanpur	Kanpur	Domestic	Pandu	26.40740	80.28996	Partially Tapped	Stagnant (due to solid waste dumping)	-	86	239
108.	Ganda Drain	Kanpur	Kanpur	Mixed	Pandu	26.43980	80.28735	Partially Tapped	59.9	4.07	68	192
109.	COD Drain	Kanpur	Kanpur	Mixed	Pandu	26.37547	80.30857	Tapped	-	-	-	-
110.	Arra Drain	Kanpur	Kanpur	Mixed	Pandu	26.40072	80.29353	Untapped	7.6	0.35	46.7	145
111.	Pipauri Drain	Kanpur	Kanpur	Mixed	Pandu	26.41341	80.27895	Untapped	Stagnant (due to dumped cow dung in drain & backflow from River Pandu)	-	-	-
112.	Sagar Puri Drain	Kanpur	Kanpur	Domestic	Pandu	26.39003	80.29644	Untapped	2.56	0.13	51.6	180
113.	Neem nala	Kasganj	Kasganj	Domestic	Kali East	27.80820	78.54090	Untapped	Dry	-	-	-
114.	Kasganj drain	Kasganj	Kasganj	Domestic	Kali East	27.79350	78.65280	Tapped	Tapped	-	-	-
115.	Shailee drain	Kasganj	Kasganj	Domestic	Kali East	27.81100	78.65600	Untapped	FCM	-	7	27
116.	Nadrai drain	Kasganj	Kasganj	Domestic	Kali East	27.79160	78.63530	Tapped	Tapped	-	-	-

S. No.	Name of Drain	District	Towns/ City in Catchment/ nearby	Pollution Sources (Domestic/ Mixed/ Industrial)	Confluence to River	Sampling location		Tapped/ Untapped	Flow (MLD)	BOD Load (TPD)	BOD (mg/l)	COD (mg/l)
						Latitude	Longitude					
117.	Chetawala Drain	Meerut	Hastinapur	River water/ field water only	Ganga	29.16642	78.02759	Untapped	21.60	0.216	10	39
118.	Saini Drain	Meerut	Saini	Mixed	Kali-East	29.03856	77.78377	Untapped	3.46	0.63	182	441
119.	Abu Nalla-1	Meerut	Meerut	Mixed	Kali-East	28.97506	77.76033	Untapped	39.74	2.86	72	196
120.	Abu Nalla-2	Meerut	Meerut	Mixed	Kali-East	28.93871	77.75366	Untapped	376.32	37.63	100	293
121.	Slaughter House/Odean Nallah	Meerut	Meerut	Mixed	Kali-East	28.93396	77.74784	Untapped	734.28	260.67	355	882
122.	Gode Shaheed Drain	Mirzapur	Mirzapur	Mixed	Ganga	25.15849	82.58488	Untapped	FCM (due to uneven path)	-	29.6	94.3
123.	Kachahari Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.15671	82.58140	Untapped	FCM (due to drain bed was filled with boulders)	-	35.8	116
124.	Morchaghar Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.16049	82.58836	Untapped	FCM (drain discharge through underground pipeline directly into R. Ganga)	-	-	-
125.	Lift Canal Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.16543	82.59372	Untapped	3.69	0.07	17.8	54
126.	Public Club Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.16797	82.59537	Untapped	FCM (drain discharge through underground)	-	-	-

S. No.	Name of Drain	District	Towns/ City in Catchment/ nearby	Pollution Sources (Domestic/ Mixed/ Industrial)	Confluence to River	Sampling location		Tapped/ Untapped	Flow (MLD)	BOD Load (TPD)	BOD (mg/l)	COD (mg/l)
						Latitude	Longitude					
									nd pipeline directly into Ganga)			
127.	Narghat Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.15110	82.56061	Tapped	-	-	-	-
128.	Koniya Ghat Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.15185	82.56482	Tapped	-	-	-	-
129.	Sundar Ghat Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.15254	82.56951	Partially Tapped	FCM	-	197	506
130.	Oliyar Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.15317	82.57097	Untapped	FCM (due to discharge through underground pipeline directly into Ganga)	-	-	-
131.	Hanuman Ghat Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.17496	82.59743	Untapped	FCM (due to less flow)	-	-	-
132.	Bisundarpur Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.17522	82.59749	Untapped	FCM (due to less flow)	-	13.1	38.8
133.	Barahimiliya Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.16670	82.59485	Untapped	Dry	-	-	-
134.	Shivpur Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.17186	82.49056	Untapped	0.12	0.003	27.2	64.9
135.	Patengra Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.16778	82.50023	Untapped	1.03	0.02	16.7	26.1
136.	Malahia Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.16719	82.50272	Untapped	0.39	0.02	41.3	79.4
137.	Gudara Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.16676	82.50366	Tapped	-	-	-	-
138.	Parshuram Ghat	Mirzapur	Mirzapur	Domestic	Ganga	25.16631	82.50480	Tapped	FCM (due to uneven	-	47.2	125

S. No.	Name of Drain	District	Towns/ City in Catchment/ nearby	Pollution Sources (Domestic/ Mixed/ Industrial)	Confluence to River	Sampling location		Tapped/ Untapped	Flow (MLD)	BOD Load (TPD)	BOD (mg/l)	COD (mg/l)
						Latitude	Longitude					
									path & solid waste dumping)			
139.	Balughat Kachha Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.16504	82.50786	Untapped	1.03	0.02	20.9	58.9
140.	Balughat Pakka Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.16493	82.50776	Tapped	-	-	-	-
141.	Diwan Ghat New Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.16391	82.51061	Untapped	Dry	-	-	-
142.	Diwan Ghat Old Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.15193	82.57293	Tapped	-	-	-	-
143.	Baswariya Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.16126	82.51262	Untapped	2.07	0.03	14	23.3
144.	Chorwa Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.15007	82.55100	Untapped	3.23	0.41	126	290
145.	Khandwa Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.15125	82.55469	Partially Tapped	40.31	3.28	81.3	147
146.	Balaji Temple Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.15143	82.55998	Untapped	2.74	0.22	81.6	194
147.	Kashi Ram Awas Drain	Mirzapur	Chunar	Domestic	Ganga	25.13324	82.88415	Untapped	2.13	0.03	16.1	109
148.	Chaura Mata Drain	Mirzapur	Chunar	Domestic	Ganga	25.12798	82.87751	Untapped	FCM (due to unapproachable site conditions)	-	31	76.1
149.	Balughat Drain/ Belbeer Ghat Drain	Mirzapur	Chunar	Domestic	Ganga	25.13081	82.87873	Untapped	FCM (due to irregular gradient)	-	61	97.1
150.	Gangeshwari Nishad Park Drain	Mirzapur	Chunar	Domestic	Ganga	25.12822	82.87797	Untapped	1.84	0.14	75.7	206
151.	Post Office South Drain	Mirzapur	Chunar	Domestic	Ganga	25.12791	82.87610	Untapped	-	-	-	-

S. No.	Name of Drain	District	Towns/ City in Catchment/ nearby	Pollution Sources (Domestic/ Mixed/ Industrial)	Confluence to River	Sampling location		Tapped/ Untapped	Flow (MLD)	BOD Load (TPD)	BOD (mg/l)	COD (mg/l)
						Latitude	Longitude					
152.	Post Office North Drain	Mirzapur	Chunar	Domestic	Ganga	25.12731	82.87733	Untapped	FCM (due to less flow)	-	47	113
153.	Santoshi Mata Mandir Drain	Mirzapur	Chunar	Domestic	Ganga	25.12692	82.87731	Untapped	FCM (due to less flow)	-	22.4	43.7
154.	Bhairamganj West Drain	Mirzapur	Chunar	Domestic	Ganga	25.11212	82.85876	Untapped	Dry	-	-	-
155.	Bhairamganj East Drain	Mirzapur	Chunar	Domestic	Ganga	25.11316	82.86097	Untapped	FCM (due to meagre flow)	-	-	-
156.	Dargah shareef Drain	Mirzapur	Chunar	Domestic	Ganga	25.11646	80.87068	Untapped	-	-	-	-
157.	Tambalganj	Mirzapur	Chunar	Domestic	Ganga	25.10786	82.85738	Untapped	-	-	-	-
158.	Chunar Tekur Drain/ Tekur Basti South Drain	Mirzapur	Chunar	Domestic	Ganga	25.11950	82.87741	Untapped	Stagnant	-	-	-
159.	Lohandi Drain	Mirzapur	Mirzapur	Mixed	Ojhala	25.14380	82.52927	Untapped	4.34	0.047	10.9	34.2
160.	Bharatpur Trimohani	Mirzapur	Chunar	Domestic	Jargo	25.12410	82.88163	Untapped	FCM (drain water utilized in irrigation by farmers)	-	-	-
161.	Bharatpur Kabristan Drain	Mirzapur	Chunar	Domestic	Jargo	25.11268	82.87840	Untapped	FCM (due to meagre flow)	-	-	-
162.	Saiddupur Drain	Mirzapur	Chunar	Domestic	Jargo	25.12540	82.88637	Untapped	FCM (drain covered by	-	19.4	65.8

S. No.	Name of Drain	District	Towns/ City in Catchment/ nearby	Pollution Sources (Domestic/ Mixed/ Industrial)	Confluence to River	Sampling location		Tapped/ Untapped	Flow (MLD)	BOD Load (TPD)	BOD (mg/l)	COD (mg/l)
						Latitude	Longitude					
									solid waste)			
163.	Pashuchikitsalaya Drain	Mirzapur	Chunar	Domestic	Jargo	25.12987	82.88652	Untapped	Stagnant	-	-	-
164.	Nagar Palika Drain	Mirzapur	Chunar	Domestic	Jargo	25.13342	82.89347	Untapped	FCM (due to very less flow)	-	-	-
165.	Pared Ground Drain	Mirzapur	Chunar	Domestic	Jargo	25.13606	82.89571	Untapped	FCM (due to unapproachable site conditions)	-	17.8	51.1
166.	Tekur Nagar Drain-1	Mirzapur	Chunar	Domestic	Jargo	25.13562	82.89851	Untapped	FCM (due to less flow)	-	-	-
167.	Tekur Nagar Drain -2	Mirzapur	Chunar	Domestic	Jargo	25.11952	82.87601	Untapped	FCM (due to meagre flow and covered by solid waste)	-	-	-
168.	Tekur Nagar Drain -3	Mirzapur	Chunar	Domestic	Jargo	25.12380	82.87988	Untapped	Dry	-	-	-
169.	Kudaghar Drain	Moradabad	Moradabad	Domestic	Ramganga	28.82931	78.79659	Untapped	0.40	0.02	50	203
170.	Deharia Drain	Moradabad	Moradabad	Domestic	Ramganga	28.83991	78.79252	Untapped	9.03	0.63	70	262
171.	Ghosiyan Drain	Moradabad	Moradabad	Domestic	Ramganga	28.83420	78.79521	Untapped	2.37	0.30	126	344
172.	Lalbagh Drain	Moradabad	Moradabad	Domestic	Ramganga	28.84128	78.79055	Untapped (Earlier it was tapped as per UPPCB)	3.47	1.39	401	1218

S. No.	Name of Drain	District	Towns/ City in Catchment/ nearby	Pollution Sources (Domestic/ Mixed/ Industrial)	Confluence to River	Sampling location		Tapped/ Untapped	Flow (MLD)	BOD Load (TPD)	BOD (mg/l)	COD (mg/l)
						Latitude	Longitude					
173.	Prabhat Nagar Drain	Moradabad	Moradabad	Mixed	Ramganga	28.80791	78.80505	Untapped	2.60	0.09	35	147
174.	Jhabbu ka Nala, Moradabad	Moradabad	Moradabad	Mixed	Ramganga	28.84763	78.78310	Untapped	60.52	5.08	84	298
175.	Delhi Road Right drain	Moradabad	Moradabad	Domestic	Gangan	28.82638	78.71864	Untapped	2.61	0.11	44	111
176.	Delhi Road Left drain	Moradabad	Moradabad	Mixed	Gangan	28.82601	78.71876	Untapped	9.07	0.24	27	88
177.	Chandausi Road Right drain	Moradabad	Moradabad	Mixed	Gagan	28.79512	78.76225	Untapped	5.62	0.17	31	90
178.	Chandausi Road left drain	Moradabad	Moradabad	Mixed	Gagan	28.79629	78.76263	Untapped	FCM (Very feeble flow & drain is very deep at location)	-	21	62
179.	Nawabpura Drain-1	Moradabad	Moradabad	Domestic	Ramganga	28.84705	78.78413	Untapped	FCM	-	244	572
180.	Nawabpura Drain-2	Moradabad	Moradabad	Domestic	Ramganga	28.84432	78.78626	Untapped	19.75	4.86	246	569
181.	Vivekanand Hospital Drain (Right)	Moradabad	Moradabad	Domestic	Ramganga	28.89030	78.74329	Untapped	10.50	0.36	34	117
182.	Vivekanand Drain (Left)	Moradabad	Moradabad	Domestic	Ramganga	28.89031	78.74328	Untapped	-	-	-	-
183.	Moksh Dham drain	Moradabad	Moradabad	Domestic	Ramganga	28.88108	78.75218	Untapped	24.64	0.67	27	63
184.	TDI City drain	Moradabad	Moradabad	Domestic	Ramganga	28.87561	78.75602	Untapped	41.47	1.00	24	73
185.	Chakkar ki Milak	Moradabad	Moradabad	Domestic	Ramganga	28.86074	78.77021	Untapped	7.71	1.36	176	410

S. No.	Name of Drain	District	Towns/ City in Catchment/ nearby	Pollution Sources (Domestic/ Mixed/ Industrial)	Confluence to River	Sampling location		Tapped/ Untapped	Flow (MLD)	BOD Load (TPD)	BOD (mg/l)	COD (mg/l)
						Latitude	Longitude					
186.	Jigar colony	Moradabad	Moradabad	Domestic	Ram Ganga	28.85423	78.77403	Untapped	1.27	0.24	186	300
187.	MIT Drain	Moradabad	Moradabad	Domestic	Ramganga	28.87160	78.75608	Untapped	19.87	0.85	43	102
188.	Sugar Mill Nala	Muzaffarnagar	Muzaffarnagar	Mixed	Kali-East	29.27755	77.77174	Untapped	11.6	0.09	8	53
189.	Pakka Nala/ Taar Nala	Pratapgarh	Manikpur	Domestic	Ganga	25.76678	81.40104	Untapped	0.86	0.01	14.6	48.5
190.	Raja Hela Nala	Pratapgarh	Manikpur	Domestic	Ganga	25.76972	81.39863	Untapped	Dry	-	-	-
191.	Prathmik Vidhyalay	Pratapgarh	Manikpur	Domestic	Ganga	25.76992	81.39839	Untapped	Dry	-	-	-
192.	Mallahan Tola	Pratapgarh	Manikpur	Domestic	Ganga	25.77216	81.39727	Untapped	Stagnant	-	-	-
193.	Post office Drain	Pratapgarh	Manikpur	Domestic	Ganga	25.75817	81.40562	Untapped	Dry	-	-	-
194.	Ganda Nala	Pratapgarh	Pratapgarh	Domestic	Duar	25.64517	81.56720	Untapped	Dry	-	-	-
195.	Nehru Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.46991	81.79313	Untapped	5.27	0.05	9.35	31.9
196.	Rasulabad-4 Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.49566	81.84836	Untapped	57.69	1.44	24.9	94.8
197.	Mehdauri Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.49851	81.85019	Tapped	-	-	-	-
198.	Rasulabad-3 Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.50023	81.85344	Untapped	5.83	0.26	44.4	66.1
199.	Rasulabad-2 Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.50209	81.85515	Tapped	-	-	-	-
200.	Rasulabad-1 Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.50248	81.85614	Tapped	-	-	-	-
201.	Chuhara Mandir-2 Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.50358	81.86069	Untapped	3.00	0.09	31.6	92.6
202.	Chuhara Mandir-1 Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.50343	81.85896	Tapped	-	-	-	-

S. No.	Name of Drain	District	Towns/ City in Catchment/ nearby	Pollution Sources (Domestic/ Mixed/ Industrial)	Confluence to River	Sampling location		Tapped/ Untapped	Flow (MLD)	BOD Load (TPD)	BOD (mg/l)	COD (mg/l)
						Latitude	Longitude					
203.	Sadanand Ashram Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.50382	81.86200	Untapped	0.37	0.01	22.3	40.4
204.	Salori Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.45792	81.88340	Untapped	16.57	1.31	79.2	217
205.	Mavaiya Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.39636	81.89170	Untapped	Stagnant	-	-	-
206.	Maniya Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.32552	81.95130	Untapped	5.22	1.92	368	582
207.	Bairagiya Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.31639	82.08375	Untapped	Stagnant	-	-	-
208.	Sadar Bazar Nala	Prayagraj	Prayagraj	Domestic	Ganga	25.47115	81.82050	Partially Tapped	0.29	0.01	30.2	73.3
209.	Mumfordganj Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.47478	81.84930	Tapped	-	-	-	-
210.	Jondhwal Ghat Drain/Chhuhara Mandir-2	Prayagraj	Prayagraj	Domestic	Ganga	25.50374	81.86063	Untapped	0.37	0.01	35.2	83.6
211.	Shivkuti Drain No. 1	Prayagraj	Prayagraj	Domestic	Ganga	25.50277	81.87357	Untapped	0.07	0.002	25.6	73.6
212.	Shivkuti Drain No. 3	Prayagraj	Prayagraj	Domestic	Ganga	25.50330	81.87185	Untapped	FCM (due to meager flow)	-	-	-
213.	Allenganj Nala / Buxi Bund Nala	Prayagraj	Prayagraj	Domestic	Ganga	25.48433	81.87996	Partially Tapped	33.00	1.60	48.4	109
214.	Morigate Nala	Prayagraj	Prayagraj	Domestic	Ganga	25.44128	81.88321	Tapped	-	-	-	-
215.	Drains of Daraganj Area	Prayagraj	Prayagraj	Domestic	Ganga	25.44275	81.88443	Tapped	-	-	-	-
216.	Basna Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.50975	81.86499	Tapped	-	-	-	-
217.	Shankar ghat drain	Prayagraj	Prayagraj	Domestic	Ganga	25.50433	81.86536	Untapped	0.001	0.0001	68	113
218.	Shankar ghat Colony drain	Prayagraj	Prayagraj	Domestic	Ganga	25.50387	81.86217	Untapped	0.02	0.0004	24.6	73.3
219.	Ponghat Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.46062	81.75908	Tapped	-	-	-	-

S. No.	Name of Drain	District	Towns/ City in Catchment/ nearby	Pollution Sources (Domestic/ Mixed/ Industrial)	Confluence to River	Sampling location		Tapped/ Untapped	Flow (MLD)	BOD Load (TPD)	BOD (mg/l)	COD (mg/l)
						Latitude	Longitude					
220.	Kodra Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.46500	81.77566	Tapped	-	-	-	-
221.	Lakkar Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.41763	81.90133	Untapped	2.31	0.04	18.3	43.2
222.	Arail Drain	Prayagraj	Prayagraj	Domestic	Yamuna	25.42021	81.88231	Untapped	Stagnant	-	-	-
223.	Sasurkhaderi River/Drain	Prayagraj	Prayagraj	Domestic	Yamuna	25.40552	81.80855	Partially Tapped	FCM (due to unapproachable site conditions)	-	33.8	99.6
224.	Karela Bagh Drain	Prayagraj	Prayagraj	Domestic	Yamuna	25.41142	81.81432	Untapped	0.38	0.012	31	91.9
225.	Main Ghaghar Nala	Prayagraj	Prayagraj	Domestic	Yamuna	25.42052	81.82235	Tapped	-	-	-	-
226.	Ghaghar Nala 1-A/Sadiyapur Drain	Prayagraj	Prayagraj	Domestic	Yamuna	25.42038	81.82490	Untapped	1.42	0.172	121	280
227.	Ghaghar Nala 1-A1	Prayagraj	Prayagraj	Mixed	Yamuna	25.41961	81.82956	Untapped	1.42	0.052	36.5	135
228.	Ghaghar Nala 1-B	Prayagraj	Prayagraj	Domestic	Yamuna	25.41983	81.83013	Untapped	0.38	0.012	32.8	117
229.	Dariyabad Kakahraghat Drain Meerapur	Prayagraj	Prayagraj	Domestic	Yamuna	25.41900	81.82531	Untapped	0.07	0.005	68	188
230.	Dariyabad Jogighat Drain Meerapur	Prayagraj	Prayagraj	Domestic	Yamuna	25.42055	81.83361	Untapped	FCM (due to meager flow)	-	-	-
231.	Dariyabad Pipalghat Drain	Prayagraj	Prayagraj	Domestic	Yamuna	25.42085	81.83464	Untapped	FCM (due to meager flow)	-	-	-
232.	Chachar Nala	Prayagraj	Prayagraj	Domestic	Yamuna	25.42480	81.83778	Tapped	-	-	-	-
233.	Drainat Gate No.9	Prayagraj	Prayagraj	Domestic	Yamuna	25.42697	81.85080	Untapped	FCM (due to unapproac	-	32.4	98.5

S. No.	Name of Drain	District	Towns/ City in Catchment/ nearby	Pollution Sources (Domestic/ Mixed/ Industrial)	Confluence to River	Sampling location		Tapped/ Untapped	Flow (MLD)	BOD Load (TPD)	BOD (mg/l)	COD (mg/l)
						Latitude	Longitude					
									hable site conditions)			
234.	Drainat Gate No.13	Prayagraj	Prayagraj	Domestic	Yamuna	25.42744	81.85278	Tapped	-	-	-	-
235.	Fort DrainNo.1	Prayagraj	Prayagraj	Domestic	Yamuna	25.42833	81.87572	Untapped (Dry)	Dry	-	-	-
236.	Fort DrainNo.2	Prayagraj	Prayagraj	Domestic	Yamuna	25.43070	81.86411	Untapped (Dry)	Dry	-	-	-
237.	Mahewa Ghat Drain no.1	Prayagraj	Prayagraj	Domestic	Yamuna	25.41579	81.83788	Tapped	-	-	-	-
238.	Mahewa Ghat Drain no.2	Prayagraj	Prayagraj	Domestic	Yamuna	25.41604	81.83784	Tapped	-	-	-	-
239.	Emergency Outfall Drain	Prayagraj	Prayagraj	Domestic	Yamuna	25.42882	81.85210	Untapped (Dry)	Dry	-	-	-
240.	Arail Drain No. 2 (Kharkauni drain)	Prayagraj	Prayagraj	Domestic	Yamuna	25.42090	81.87694	Tapped	-	-	-	-
241.	Sachcha Baba Ashram Drain	Prayagraj	Prayagraj	Domestic	Yamuna	25.42020	81.88236	Tapped	-	-	-	-
242.	Chatnag Drain	Prayagraj	Prayagraj	Domestic	Mansahaita	25.42180	81.89971	Partially tapped	26.56	1.09	41.2	66.2
243.	Jhunsi Drain	Prayagraj	Prayagraj	Domestic	Mansahaita	25.43453	81.90081	Tapped	-	-	-	-
244.	Augharwa Nala (New)	Prayagraj	Prayagraj	Domestic	Mansahaita	25.44273	81.90655	Untapped	FCM (due to meager flow)	-	-	-
245.	Bhole Mandir Nala (New)	Prayagraj	Prayagraj	Domestic	Mansahaita	25.44154	81.90425	Untapped	FCM (due to meager flow)	-	-	-
246.	Gangoli Shivala Nalla-01 (New)	Prayagraj	Prayagraj	Domestic	Mansahaita	25.44007	81.90231	Untapped	FCM (due to meager flow)	-	-	-

S. No.	Name of Drain	District	Towns/ City in Catchment/ nearby	Pollution Sources (Domestic/ Mixed/ Industrial)	Confluence to River	Sampling location		Tapped/ Untapped	Flow (MLD)	BOD Load (TPD)	BOD (mg/l)	COD (mg/l)
						Latitude	Longitude					
247.	Gangoli Shivala Nalla-02 (New)/ Shavitri Nagar Bazar-2	Prayagraj	Prayagraj	Domestic	Mansahaita	25.43885	81.90198	Untapped	FCM (due to meager flow)	-	13.8	53.5
248.	Shavitri Nagar Nalla (New)	Prayagraj	Prayagraj	Domestic	Mansahaita	25.43717	81.90143	Untapped	0.07	0.01	135	300
249.	Shastri Bridge Nala (New)	Prayagraj	Prayagraj	Domestic	Mansahaita	25.43265	81.90042	Untapped	0.07	0.0005	7.6	37.4
250.	Triveni Marg Nala-01(New)	Prayagraj	Prayagraj	Domestic	Mansahaita	25.42946	81.89869	Tapped	-	-	-	-
251.	Triveni Marg Nala-02 (New)	Prayagraj	Prayagraj	Domestic	Mansahaita	25.42729	81.89869	Tapped	-	-	-	-
252.	Ulta Kila Darin-01 (New)	Prayagraj	Prayagraj	Domestic	Mansahaita	25.42520	81.89830	Tapped	-	-	-	-
253.	Ulta Kila Darin-02 (New)	Prayagraj	Prayagraj	Domestic	Mansahaita	25.42498	81.89815	Tapped	-	-	-	-
254.	Rampur Drain	Rampur	Rampur	Mixed	Kosi	28.75585	79.02199	Untapped	69.49	7.50	108	249
255.	City Jail Drain	Unnao	Unnao	Mixed	Ganga	26.38358	80.51182	Untapped	22.39	3.18	142	570
256.	Loni River/ Drain	Unnao	Unnao	Mixed	Ganga	26.28523	80.81823	Untapped	FCM (stagnant water)	-	14.2	63.3
257.	Ganga Vishnu Drain	Unnao	Shuklaganj	Domestic	Ganga	26.47622	80.37276	Untapped	0.07	0.01	75.5	178
258.	Indira Nagar Drain	Unnao	Shuklaganj	Domestic	Ganga	26.46946	80.38438	Untapped	8.09	0.67	82.9	212
259.	Ravidas Nagar	Unnao	Shuklaganj	Domestic	Ganga	26.46548	80.39726	Untapped	2.03	0.11	55.4	144
260.	Srinagar Drain (New)	Unnao	Shuklaganj	Domestic	Ganga	26.46445	80.39852	Untapped	5.41	0.34	62.2	152

S. No.	Name of Drain	District	Towns/ City in Catchment/ nearby	Pollution Sources (Domestic/ Mixed/ Industrial)	Confluence to River	Sampling location		Tapped/ Untapped	Flow (MLD)	BOD Load (TPD)	BOD (mg/l)	COD (mg/l)
						Latitude	Longitude					
261.	Ramnagar Drain	Varanasi	Varanasi	Mixed	Ganga	25.25640	83.03487	Untapped	15.79	3.79	240	384
262.	Asi/ Nagwa Drain	Varanasi	Mughalsarai	Domestic	Ganga	25.28256	83.00880	Partially Tapped	18.75	2.51	134	284
263.	Shivala Drain	Varanasi	Varanasi	Domestic	Ganga	25.29627	83.00772	Tapped	-	-	-	-
264.	Nakhi Drain	Varanasi	Varanasi	Domestic	Ganga	25.26730	83.01633	Untapped	24.44	1.41	57.5	166
265.	Samne Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.27199	83.01526	Tapped	-	-	-	-
266.	Harishchandra Drain	Varanasi	Varanasi	Domestic	Ganga	25.29794	83.00757	Tapped	-	-	-	-
267.	Mansarovar Drain	Varanasi	Varanasi	Domestic	Ganga	25.30110	83.00777	Tapped	-	-	-	-
268.	Pandey Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.30378	83.00844	Tapped	-	-	-	-
269.	Dr. R. P. Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.30839	83.01115	Tapped	-	-	-	-
270.	Meer Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.30891	83.01240	Tapped	-	-	-	-
271.	Lalita Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.30996	83.01336	Tapped	-	-	-	-
272.	Jalasen Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.30982	83.01304	Tapped	-	-	-	-
273.	Manikarnika Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.31058	83.01464	Tapped	FCM (due to meagre flow & unapproachable site conditions)	-	-	-
274.	Sankatha Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.31274	83.01624	Tapped	-	-	-	-
275.	Mehta Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.31391	83.01697	Tapped	-	-	-	-

S. No.	Name of Drain	District	Towns/ City in Catchment/ nearby	Pollution Sources (Domestic/ Mixed/ Industrial)	Confluence to River	Sampling location		Tapped/ Untapped	Flow (MLD)	BOD Load (TPD)	BOD (mg/l)	COD (mg/l)
						Latitude	Longitude					
276.	Ram Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.31418	83.01718	Tapped	-	-	-	-
277.	Panchganga Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.315038	83.018301	Tapped	-	-	-	-
278.	Brahma Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.31573	83.01903	Tapped	-	-	-	-
279.	Lal Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.31738	83.02086	Tapped	-	-	-	-
280.	Trilochan Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.31887	83.02347	Tapped	-	-	-	-
281.	Teliya Drain	Varanasi	Varanasi	Domestic	Ganga	25.32101	83.02730	Tapped	-	-	-	-
282.	Bhainsassur Drain	Varanasi	Varanasi	Domestic	Ganga	25.32341	83.03180	Tapped	-	-	-	-
283.	Rajghat Drain (small)	Varanasi	Varanasi	Domestic	Ganga	25.32422	83.03298	Tapped	-	-	-	-
284.	Rajghat Drain/Rajghat Outfall/Khirkiya	Varanasi	Varanasi	Domestic	Ganga	25.32682	83.03782	Tapped	-	-	-	-
285.	Gola Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.31935	83.02437	Partially Tapped	FCM (due to underground flow)	-	-	-
286.	Balua Ghat Drain	Varanasi	Ramnagar	Domestic	Ganga	25.27209	83.02391	Untapped	-	-	-	-
287.	Shakti Ghat Drain	Varanasi	Ramnagar	Domestic	Ganga	25.27385	83.02408	Tapped	-	-	-	-
288.	Salotri Ghat Drain	Varanasi	Ramnagar	Domestic	Ganga	25.27282	83.02352	Tapped	-	-	-	-
289.	Hanuman Ghat Drain	Varanasi	Ramnagar	Domestic	Ganga	25.26799	83.02590	Tapped	-	-	-	-
290.	Rambag Ghat Drain	Varanasi	Ramnagar	Domestic	Ganga	25.27593	83.02203	Tapped	-	-	-	-

S. No.	Name of Drain	District	Town/ City in Catchment/ nearby	Pollution Sources (Domestic/ Mixed/ Industrial)	Confluence to River	Sampling location		Tapped/ Untapped	Flow (MLD)	BOD Load (TPD)	BOD (mg/l)	COD (mg/l)
						Latitude	Longitude					
291.	Phulwariya Drain	Varanasi	Varanasi	Domestic	Varuna	25.33950	82.96328	Tapped	-	-	-	-
292.	Sadar Bazar Drain	Varanasi	Varanasi	Domestic	Varuna	25.33818	82.97565	Partially Tapped	FCM (due to Eutrophication)	-	59.8	119
293.	RajaBazarDrain	Varanasi	Varanasi	Domestic	Varuna	25.33594	82.99146	Tapped	-	-	-	-
294.	Nakkhighat Drain	Varanasi	Varanasi	Domestic	Varuna	25.34123	83.00859	Tapped	-	-	-	-
295.	Narokhar Drain	Varanasi	Varanasi	Domestic	Varuna	25.34092	83.02871	Untapped	80.78	1.39	17.2	52
296.	SarangTalabDrain	Varanasi	Varanasi	Domestic	Varuna	25.34191	83.00877	Tapped	-	-	-	-
297.	Nai Basti	Varanasi	Varanasi	Domestic	Varuna	25.34360	83.00125	Tapped	-	-	-	-
298.	Teliya Bag Drain	Varanasi	Varanasi	Domestic	Varuna	25.33474	82.99747	Partially Tapped	2.89	0.12	42.5	66.6
299.	Central Jail Drain	Varanasi	Varanasi	Domestic	Varuna	25.34263	82.96759	Untapped	33.18	1.48	44.5	100
300.	Ordely Bazar Drain	Varanasi	Varanasi	Domestic	Varuna	25.34159	82.98474	Partially Tapped	8.29	0.53	64.2	128
301.	Chamrautha Drain	Varanasi	Varanasi	Domestic	Varuna	25.33962	82.96081	Untapped	15.03	1.83	122	178
302.	Khajury ColonyDrain	Varanasi	Varanasi	Domestic	Varuna	25.34111	82.98926	Untapped	5.53	0.21	37.1	77.5
303.	Banaras Drain No.-5	Varanasi	Varanasi	Domestic	Varuna	25.33981	82.99990	Untapped	Stagnant	-	-	-
304.	Hukulganj Drain	Varanasi	Varanasi	Domestic	Varuna	25.33730	82.99963	Tapped	-	-	-	-
305.	Durga/ Daniyal/Lohtha Drain	Varanasi	Varanasi	Domestic	Varuna	25.32023	82.95563	Untapped	37.2	3.94	106	296

S. No.	Name of Drain	District	Towns/ City in Catchment/ nearby	Pollution Sources (Domestic/ Mixed/ Industrial)	Confluence to River	Sampling location		Tapped/ Untapped	Flow (MLD)	BOD Load (TPD)	BOD (mg/l)	COD (mg/l)
						Latitude	Longitude					
306.	Purana Pul Drain	Varanasi	Varanasi	Domestic	Varuna	25.34082	83.02078	Partially Tapped	0.28	0.06	203	343
307.	Pagal Baba Masjid Drain	Varanasi	Varanasi	Domestic	Varuna	25.34040	83.01943	Untapped	Stagnant (due to Eutrophication)	-	81	178
Total									2859.40	410.23		

FCM= Flow could not be measured

Post-Monsoon 2023

Status of monitored drains of river Ganga and its tributaries of Uttar Pradesh state during Post monsoon 2023.

River	Post-Monsoon 2023						
	Monitored Drains	Flow (MLD)	BOD Load (TPD)	Tapped Drains	Interim measure adopted	Domestic	Mixed
Ganga	188	1135.50	60.00	63	52	170	18
Ramganga-Kosi & Gagan	29	622.78	51.46	1	1	16	13
Kali East	29	1158.10	274.45	5	4	20	9
Pandu	9	99.72	9.17	6	-	2	7
Yamuna	30	24.23	2.35	11	4	29	1
Varuna & Moorwa	21	460.31	49.58	3	1	18	3
Jargo & Ojhala	8	12.92	2.12	-	4	7	1
Mansahaita	12	-	-	12	2	12	-
Total	326	3513.56	499.13	101	68	274	52

Drains data of Uttar Pradesh district wise (Post-Monsoon 2023)

S. No.	Name of Drain	District	Towns/City in Catchment/ nearby	Pollution Sources (Domestic/ Mixed/ Industrial)	Confluence to River	Latitude (Sampling location)	Longitude (Sampling location)	Tapped/ Untapped (T/UT)	Flow (MLD)	BOD Load (TPD)	BOD (mg/l)	COD (mg/l)
1.	Bagad Drain	Amroha	Gajaraula town	Mixed	Ganga	28.806227	78.217229	Untapped	-	-	-	-
2.	Kathal Drain	Balia	Balia	Domestic	Ganga	25.750062	84.152928	Untapped	64.8	4.32	66.7	217
3.	Devraniya Drain	Bareilly	Bareilly	Mixed	Ramganga	28.321473	79.375486	Untapped	217.23	14.49	66.7	254
4.	Chaubari Drain	Bareilly	Bareilly	Domestic	Ramganga	28.28633	79.404447	Untapped	23.04	0.87	37.8	105
5.	Nakatiya River/ Drain	Bareilly	Bareilly	Mixed	Ramganga	28.21057	79.427332	Untapped	71.09	3.43	48.2	131
6.	Jhiriya Drain, Gopiganj	Bhadohi	Gopiganj	Mixed	Ganga	25.24942	82.422744	Untapped	3.01	0.043	14.3	43.4
7.	Chauri Drain	Bhadohi	Bhadohi	Domestic	Morwa	25.369578	82.605569	Untapped	2.76	0.177	64	142
8.	Barbaspur Drain	Bhadohi	Bhadohi	Mixed	Morwa	25.364013	82.553872	Untapped	4.23	0.231	54.5	99.6
9.	BIDA Drain	Bhadohi	Bhadohi	Mixed	Morwa	25.380623	82.614517	Untapped	2.76	0.500	181	560
10.	Mamdevpur Drain	Bhadohi	Bhadohi	Mixed	Varuna	25.416812	82.568215	Untapped	9.8	0.240	24.5	80.8
11.	Nai Bazar Drain/ Chaura Drain	Bhadohi	Bhadohi	Domestic	Varuna	25.413916	82.578131	Untapped	5.26	0.240	45.6	148
12.	Chhoiya drain (Ganga)	Bijnor	Bijnor	Mixed	Ganga	29.248198	78.17006	Untapped	36.96	1.18	32	120
13.	Hemraj Drain	Bijnor	Bijnor	Domestic	Ganga	29.376661	78.084177	Untapped	259.2	3.37	13	79
14.	Punsi drain/Nasiya d/s drain	Bijnor	Bijnor	Mixed	Ramganga	29.099	78.645	Untapped	63.8	1.40	22	94
15.	Gulaothi Drain	Bulandshahar	Gulaothi	Mixed	Kali East	28.591343	77.802933	Untapped	11.15	2.62	235	542
16.	DM Colony Drain	Bulandshahar	Bulandshahar	Domestic	Kali East	28.419821	77.851662	Untapped	0.13	0.01	51	168

17.	Behind Chamunda Mandir Drain	Bulandshahar	Bulandshahar	Domestic	Kali East	28.417086	77.85347	Untapped	13.41	1.25	93	264
18.	Faisalabad Drain	Bulandshahar	Bulandshahar	Mixed	Kali East	28.408678	77.863804	Untapped	3.016	0.47	155	473
19.	Kasai Bada Drain	Bulandshahar	Bulandshahar	Domestic	Kali East	28.407678	77.861957	Untapped	3.11	0.42	136	361
20.	Behind Shanidev Mandir Drain	Bulandshahar	Bulandshahar	Domestic	Kali East	28.409805	77.86076	Untapped	stagnant and clogged due solid-waste dumping	-	-	-
21.	Devipura Drain	Bulandshahar	Bulandshahar	Domestic	Kali East	28.412403	77.858532	Untapped	0.71	0.08	114	312
22.	Nishal Ghat Drain	Bulandshahar	Bulandshahar	Domestic	Kali East	28.40461	77.866206	Untapped	1.52	0.84	551	1487
23.	Cheel Ghat Drain	Bulandshahar	Bulandshahar	Domestic	Kali East	28.400402	27.867102	Untapped	14.1	0.96	68	236
24.	Chandbhari Drain	Bulandshahar	Bulandshahar	Domestic	Kali East	28.400133	77.864871	Untapped	0.33	0.15	446	1192
25.	Aadil Drain	Bulandshahar	Bulandshahar	Domestic	Kali East	28.396067	77.862407	Untapped	9.9	3.41	344	695
26.	Maman Road Drain	Bulandshahar	Bulandshahar	Mixed	Kali East	28.392626	77.863309	Untapped	71.68	10.54	147	472
27.	Shahid Baba Mazar drain/ Kaili Drain	Chandauli	Mughalsarai	Domestic	Ganga	25.326381	83.149998	Untapped	7.5	0.07	9.75	29.2
28.	Kaili-02 drain	Chandauli	Mughalsarai	Domestic	Ganga	25.335347	83.162503	Untapped	FCM	-	-	-
29.	Railway Drain	Chandauli	Mughalsarai	Mixed	Ganga	25.319038	83.140411	Untapped	51.84	0.79	15.2	35.2
30.	Bhapuli Drain	Chandauli	Mughalsarai	Domestic	Ganga	25.340213	83.164832	Untapped	FCM	-	-	-
31.	Mughalsarai / Local Drain / Ganda nala	Chandauli	Mughalsarai	Mixed	Ganga	25.321347	83.114238	Untapped	18.85	0.16	8.24	19.4
32.	B.B. Ganj Nala	Farrukhabad	Farrukhabad	Domestic	Ganga	27.414739	79.570333	Untapped	14.5	0.71	49.2	173
33.	Dhinapur Drain	Farrukhabad	Farrukhabad	Mixed	Ganga	27.401468 0	79.622676 0	Untapped	0.92	0.04	42	131

34.	Bhairoghat Drain	Farrukhabad	Farrukhabad	Mixed	Ganga	27.403687	79.616548	Untapped	33.18	1.04	31.3	102
35.	Hathikhana Drain	Farrukhabad	Farrukhabad	Domestic	Ganga	27.353296	79.634760	Partially tapped	2.53	0.07	27.5	112
36.	Bargadia Ghat Drain	Farrukhabad	Farrukhabad	Domestic	Ganga	27.365003	79.63851	Untapped	9.95	0.25	25.2	129
37.	Cantt Drain	Farrukhabad	Farrukhabad	Domestic	Ganga	27.384725	79.630439	Partially tapped	9.07	0.23	25	99.2
38.	Navabag to Lodhiganj	Fatehpur	Fatehpur	Domestic	Yamuna	25.89869	80.849305	Untapped	FCM	-	22	56.5
39.	Kot Ghat Drain	Ghazipur	Saidpur	Domestic	Ganga	25.532816	83.225232	Untapped	0.432	0.030	68.5	163
40.	Budenath Mahadev Ghat Drain	Ghazipur	Saidpur	Domestic	Ganga	25.533155	83.223275	Untapped	0.0192	0.001	26.3	51.1
41.	Pakka Ghat Drain	Ghazipur	Saidpur	Domestic	Ganga	25.533733	83.220617	Untapped	0.432	0.025	57.5	99.1
42.	Sangat Ghat Drain	Ghazipur	Saidpur	Domestic	Ganga	25.534049	83.219374	Untapped	0.018	0.001	72.5	163
43.	Mahaveer Ghat Drain	Ghazipur	Saidpur	Domestic	Ganga	25.53428	83.218399	Untapped	FCM	-	-	-
44.	Ramghat/ Ward no. 15 Malhiya Basti Drain	Ghazipur	Saidpur	Domestic	Ganga	25.534693	83.216856	Untapped	FCM	-	-	-
45.	Rangmahal Ghat Drain	Ghazipur	Saidpur	Domestic	Ganga	25.535632	83.211908	Untapped	1.769	0.051	28.6	58.9
46.	Jauhargaj Drain (Kuluha Drain)	Ghazipur	Saidpur	Domestic	Ganga	25.537006	83.203988	Untapped	0.288	0.017	57.8	122
47.	Kuluha Drain (Jauhargaj Drain)	Ghazipur	Saidpur	Domestic	Ganga	25.537042	83.204072	Untapped	0.288	0.017	57.8	122
48.	Gorwa Drain	Ghazipur	Zamnia	Domestic	Ganga	25.421695	83.553227	Untapped	0.864	0.034	39.8	67.2
49.	Kankarwa Drain	Ghazipur	Zamnia	Domestic	Ganga	25.417261	83.552917	Untapped	0.288	0.013	45.5	80
50.	Kanpuimai Ghat Drain	Ghazipur	Zamnia	Domestic	Ganga	25.415018	83.553149	Untapped	0.0864	0.002	25.6	63.8

51.	Bada Mahadev /Adarsh Bazar Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.562737	83.56169	Untapped	4.77	0.062	13.1	47.7
52.	Pear Nagar Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.56682	83.563581	Untapped	FCM	-	53.6	126
53.	Khirki Ghat Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.583146	83.595814	Untapped	0.0388	0.003	66.8	158
54.	Afim Factory Colony Drain/ Mahala Basti / Sikandpur Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.569702	83.568425	Untapped	-	-	-	-
55.	Dadri Ghat Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.574284	83.577395	Untapped	9.18	0.441	48	161
56.	Collector Ghat Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.577604	83.584179	Untapped	4.96	0.684	138	309
57.	Maksud Ghat Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.579363	83.587780	Untapped	0.5	0.009	17.1	48.8
58.	Gola Ghat Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.579683	83.588925	Untapped	0.48	0.028	58.8	170
59.	Stimer Ghat Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.58088	83.591177	Untapped	0.59	0.040	68	189
60.	Chetnat Ghat Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.580934	83.591578	Untapped	6.14	0.231	37.6	140
61.	Anzahi Ghat Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.582319	83.593856	Untapped	36.87	3.521	95.5	233
62.	Theri bazar Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.582674	83.595006	Untapped	FCM	-	796	1463
63.	Posta Ghat Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.584446	83.598549	Untapped	FCM	-	58.3	174
64.	Budhava Mahadeva Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.584598	83.598815	Untapped	FCM	-	153	384
65.	Roohi / Rui Mandi Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.584405	83.598536	Untapped	FCM	-	58.3	192
66.	Shamshan Ghat Drain	Ghazipur	Ghazipur	Domestic	Ganga	25.586258	83.601884	Untapped	FCM	-	39.4	134

67.	Harizan Basti drain	Ghazipur	Ghazipur	Domestic	Ganga	25.586818	83.603010	Untapped	FCM	-	179	420
68.	Drain at left of Pakka Ghat	Ghazipur	Ghazipur	Domestic	Ganga	25.580278	83.585278	Untapped	-	-	-	-
69.	Drain at right of Pakka Ghat	Ghazipur	Ghazipur	Domestic	Ganga	25.578611	83.601667	Untapped	FCM	-	88.5	245
70.	Fuldehra drain	Hapur	Simbhaoli, Buxer	Domestic	Ganga	28.645693	78.068741	Untapped	FCM	-	20	85
71.	Garh drain	Hapur	Garh drain	Domestic	Ganga	28.769227	78.105659	Untapped	21.678	0.74	34	132
72.	Hapur drain	Hapur	Hapur	Domestic	Kali East	28.684869	77.78531	Untapped	71.43	10.14	142	414
73.	Kadrabad drain	Hapur	Hapur	Mixed	Kali East	28.639333	77.783775	Untapped	15.50	1.35	87	294
74.	Babugarh drain	Hapur	Babugarh	Domestic	Kali East	28.72616	77.831812	Untapped	2.06	0.14	68	217
75.	Chhoiya drain	Hapur	Hapur	Domestic	Kali East	28.727877	77.87204	Untapped	FCM	-	33	125
76.	Hapur city drain	Hapur	Hapur	Domestic	Kali East	28.726207	77.829544	Untapped	11.256	0.61	54	169
77.	Tammi Drain	Kannauj	Kannauj	Domestic	Kali East	25.051404	79.930201	Partially Tapped	3.49	0.06	18.2	55.1
78.	Patta Drain	Kannauj	Kannauj	Domestic	Kali East	25.076229	79.926327	Partially Tapped	10.69	0.13	11.8	62
79.	Adanga Drain	Kannauj	Kannauj	Domestic	Kali East	27.063600	79.944600	Partially Tapped	2.96	0.03	11.2	47.1
80.	Permiya Drain	Kanpur	Kanpur	Domestic	Ganga	26.5007	80.319825	Partially Tapped	78.23	2.15	27.5	79
81.	Ranighat Drain	Kanpur	Kanpur	Domestic	Ganga	26.49613	80.32394	Untapped	2.99	0.14	47.4	140
82.	Sisamau Drain	Kanpur	Kanpur	Domestic	Ganga	26.491293	80.332656	Tapped	FCM	-	83.2	179
83.	Tefco Drain	Kanpur	Kanpur	Domestic	Ganga	26.48679	80.346851	Tapped	-	-	-	-
84.	Parmath Drain	Kanpur	Kanpur	Domestic	Ganga	26.487218	80.346851	Tapped	-	-	-	-
85.	Muir Drain	Kanpur	Kanpur	Domestic	Ganga	26.482435	80.351215	Tapped	-	-	-	-
86.	Police line Drain	Kanpur	Kanpur	Domestic	Ganga	26.480285	80.355318	Tapped	-	-	-	-
87.	Jail Drain	Kanpur	Kanpur	Domestic	Ganga	26.479735	80.356932	Tapped	-	-	-	-
88.	Gola Ghat Drain	Kanpur	Kanpur	Domestic	Ganga	26.465561	80.375509	Untapped	0.43	0.06	141	240

89.	Bhagwatdas Drain	Kanpur	Kanpur	Domestic	Ganga	26.474509	80.363879	Tapped	FCM	-	75	144
90.	Sattichaura Drain	Kanpur	Kanpur	Domestic	Ganga	26.345974	80.380435	Untapped	0.108	0.02	152	227
91.	Dabka-1, 2 & 3 Drain	Kanpur	Kanpur	Mixed	Ganga	26.444153	80.393839	Untapped	21.5	0.98	45.6	107
92.	Sheetla Bazar Drain	Kanpur	Kanpur	Mixed	Ganga	26.437205	80.403828	Untapped(tapping provision defunct during visit)	7.94	5.57	702	1314
93.	Budhiyaghat Drain	Kanpur	Kanpur	Mixed	Ganga	26.430855	80.411271	Tapped	2.094	3.86	1845	3139
94.	Wajidpur Drain	Kanpur	Kanpur	Mixed	Ganga	26.42346	80.419146	Tapped	-	-	-	-
95.	Rooma Drain	Kanpur	Kanpur	Mixed	Ganga	26.354418	80.486057	Untapped	FCM	-	99	345
96.	Luv-Kush Drain	Kanpur	Bithoor	Domestic	Ganga	26.597927	80.273529	Untapped	FCM	-	109	297
97.	Bhannu Nala	Kanpur	Bithoor	Domestic	Ganga	26.605807	80.273569	Untapped	FCM	-	32	112
98.	Peshwa Nala	Kanpur	Bithoor	Domestic	Ganga	26.609173	80.273636	Untapped	FCM	-	26.6	92.3
99.	Brahamawat Ghat	Kanpur	Bithoor	Domestic	Ganga	26.611157	80.274826	Untapped	FCM	-	24.4	93.1
100.	Laxman Ghat Drain	Kanpur	Bithoor	Domestic	Ganga	26.615684	80.271642	Untapped	FCM	-	20.1	73.3
101.	Kalwari Ghat Drain	Kanpur	Bithoor	Domestic	Ganga	26.618991	80.270787	Untapped	FCM	-	95	264
102.	Ratanpur Drain	Kanpur	Kanpur	Mixed	Pandu	26.466797	80.210792	Tapped	-	-	-	-
103.	ICICI Drain	Kanpur	Kanpur	Mixed	Pandu	26.436189	80.253772	Tapped	-	-	-	-
104.	Panki Drain	Kanpur	Kanpur	Mixed	Pandu	26.4559	80.226001	Partially Tapped	FCM	-	-	-
105.	Halwakhanda Drain	Kanpur	Kanpur	Domestic	Pandu	26.407399	80.28996	Partially Tapped	FCM	-	119	218
106.	Ganda Drain	Kanpur	Kanpur	Mixed	Pandu	26.439796	80.287351	Partially Tapped	94.92	8.78	92.5	194
107.	COD Drain	Kanpur	Kanpur	Mixed	Pandu	26.375471	80.30857	Tapped	-	-	-	-
108.	Arra Drain	Kanpur	Kanpur	Mixed	Pandu	26.400717	80.29353	Untapped	4.8	0.39	81.6	189
109.	Pipauri Drain	Kanpur	Kanpur	Mixed	Pandu	26.413408	80.278954	Untapped	FCM	-	-	-

110.	Sagar Puri Drain	Kanpur	Kanpur	Domestic	Pandu	26.390031	80.296437	Untapped	FCM	-	123	346
111.	Kasganj drain	Kasganj	Kasganj	Domestic	Kali East	27.796199	78.652595	Tapped	-	-	-	-
112.	Nadarai drain	Kasganj	Kasganj	Domestic	Kali East	27.791781	78.634957	Tapped	-	-	-	-
113.	Shailaee drain	Kasganj	Kasganj	Domestic	Kali East	27.79253	78.676573	Untapped	-	-	-	-
114.	Neem Nala	Kasganj	Kasganj	Domestic	Kali East	27.815485	78.53648	Untapped	-	-	-	-
115.	Chetawala Drain	Meerut	Hastinapur	Domestic	Ganga	29.166419	78.027587	Untapped	24.88	0.30	12	49
116.	Saini Drain at Saini village	Meerut	Meerut	Mixed	Kali East	29.03856	77.783765	Untapped	2.68	2.28	851	1784
117.	Abu Nallah-1 in Risna Village	Meerut	Meerut	Mixed	Kali East	28.97506	77.760326	Untapped	95.39	14.50	152	405
118.	Odean Nala (Slaughter house drain)	Meerut	Meerut	Mixed	Kali East	28.933955	77.747842	Untapped	487	174.83	359	1150
119.	Abu Nallah 2	Meerut	Meerut	Mixed	Kali East	28.938712	77.753661	Untapped	326.59	49.64	152	481
120.	Gode Shaheed Drain	Mirzapur	Mirzapur	Mixed	Ganga	25.158464	82.584863	Untapped	55.464	5.30	95.5	331
121.	Kachahari Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.156732	82.581387	Tapped	-	-	-	-
122.	Morchaghar Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.160515	82.588437	Untapped	FCM	-	146	496
123.	Lift Canal Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.165393	82.593734	Untapped	-	-	-	-
124.	Public Club Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.167969	82.595454	Untapped	FCM	-	-	-
125.	Narghat Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.151095	82.560622	Tapped	-	-	-	-
126.	Koniya Ghat Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.152059	82.564357	Tapped	-	-	-	-
127.	Sundar Ghat Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.153047	82.570995	Tapped	-	-	-	-
128.	Oliyar Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.153165	82.570973	Tapped	-	-	-	-
129.	Hanuman Ghat Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.17494	82.597472	Untapped	0.1728	0.00	28	135
130.	Bisundarpur Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.17519	82.597701	Untapped	7.728	0.13	16.6	96.2

131.	Barahmiliah Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.166588	82.594857	Untapped	-	-	-	-
132.	Shivpur Drain	Mirzapur	Vindhyachal, Mirzapur	Domestic	Ganga	25.171863	82.490555	Untapped	FCM	-	-	-
133.	Patengra Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.167778	82.500228	Untapped	1.42	0.10	68	101
134.	Malahia Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.16719	82.502719	Untapped	0.4	0.004	9.7	54.4
135.	Gudara Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.166091	82.504878	Tapped	-	-	-	-
136.	Parshuram Ghat	Mirzapur	Mirzapur	Domestic	Ganga	25.166311	82.504795	Tapped	-	-	-	-
137.	Balughat Kachha Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.165042	82.50786	Untapped	FCM	-	71.2	148
138.	Balughat Pakka Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.164926	82.507761	Tapped	FCM	-	-	-
139.	Diwan Ghat New Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.163914	82.51061	Untapped	Dry	-	-	-
140.	Diwan Ghat Old Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.151928	82.572925	Tapped	FCM	-	-	-
141.	Baswariya Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.161259	82.512619	Untapped	9.75	0.28	29.2	116
142.	Chorwa Drain	Mirzapur	Mirzapur	Mixed	Ganga	25.150073	82.551004	Untapped	3.95	0.53	135	413
143.	Khandwa Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.151246	82.554691	Partial Tapped	48.2	4.70	97.5	283
144.	Balaji Temple Drain	Mirzapur	Mirzapur	Domestic	Ganga	25.151428	82.559975	Untapped	FCM	-	33	119
145.	Kashi Ram Awas Drain	Mirzapur	Chunar	Domestic	Ganga	25.133842	82.884974	Untapped	1.73	0.073	42.3	121
146.	Chaura Mata Drain	Mirzapur	Chunar	Domestic	Ganga	25.131205	82.878633	Untapped	FCM	-	-	-
147.	Balughat Drain	Mirzapur	Chunar	Domestic	Ganga	25.130814	82.878729	Untapped	Dry	-	-	-
148.	Gangeshwari Nishad Park Drain	Mirzapur	Chunar	Domestic	Ganga	25.128618	82.877568	Untapped	1.04	0.018	17.4	52.6
149.	Post Office South Drain	Mirzapur	Chunar	Domestic	Ganga	25.126870	82.877307	Untapped	-	-	-	-
150.	Post Office North Drain	Mirzapur	Chunar	Domestic	Ganga	25.127422	82.877284	Untapped	FCM	-	-	-

151.	Santoshi Mata Mandir Drain	Mirzapur	Chunar	Domestic	Ganga	25.127033	82.877326	Untapped	FCM	-	-	-
152.	Bhairamganj West Drain	Mirzapur	Chunar	Domestic	Ganga	25.112103	82.859889	Untapped	FCM	-	-	-
153.	Bhairamganj East Drain	Mirzapur	Chunar	Domestic	Ganga	25.113161	82.860970	Untapped	FCM	-	-	-
154.	Dargah shareef Drain	Mirzapur	Chunar	Domestic	Ganga	25.117479	82.869984	Untapped	FCM	-	-	-
155.	Tambalganj	Mirzapur	Chunar	Domestic	Ganga	25.109438	82.857762	Untapped	-	-	-	-
156.	Chunar Tekur Drain/ Tekur Basti South Drain	Mirzapur	Chunar	Domestic	Ganga	25.120896	82.873603	Untapped	FCM	-	-	-
157.	Lohandi Drain	Mirzapur	Mirzapur	Mixed	Ojhala	25.143804	82.52927	Untapped	1.01	0.01	9.5	46.2
158.	Bharatpur Trimohani	Mirzapur	Chunar	Domestic	Jargo	25.122868	82.881886	Untapped	1.93	0.259	134	337
159.	Bharatpur Kabristan Drain	Mirzapur	Chunar	Domestic	Jargo	25.113024	82.879208	Untapped	-	-	-	-
160.	Saiddupur Drain	Mirzapur	Chunar	Domestic	Jargo	25.126403	82.886542	Untapped	7.78	1.782	229	556
161.	Pashuchikitsal aya Drain	Mirzapur	Chunar	Domestic	Jargo	25.129584	82.888176	Untapped	FCM	-	47.7	191
162.	Nagar Palika Drain	Mirzapur	Chunar	Domestic	Jargo	25.133583	82.892834	Untapped	FCM	-	-	-
163.	Pared Ground Drain	Mirzapur	Chunar	Domestic	Jargo	25.136178	82.894915	Untapped	1.97	0.043	21.8	60.7
164.	Tekur Nagar Drain -3	Mirzapur	Chunar	Domestic	Jargo	25.11770	82.877613	Untapped	1.24	0.035	28.3	108
165.	Delhi Road Right drain	Moradabad	Moradabad	Domestic	Gagan	28.826376	78.718635	Untapped	8.64	0.41	48	166
166.	Delhi Road Left drain	Moradabad	Moradabad	Mixed	Gagan	28.826592	78.718909	Untapped	10.16	0.27	27	91
167.	Chandausi Road left drain	Moradabad	Moradabad	Mixed	Gagan	28.796294	78.762628	Untapped	FCM	-	31	115
168.	Kudaghar Drain	Moradabad	Moradabad	Domestic	Ramganga	28.829075	78.796166	Untapped	FCM	-	84	275

169.	Deharia Drain	Moradabad	Moradabad	Domestic	Ramganga	28.839451	78.791646	Untapped	9.53	1.82	191	548
170.	Ghosiyan Drain	Moradabad	Moradabad	Domestic	Ramganga	28.834105	78.794756	Untapped	FCM	-	784	2493
171.	Lalbagh Drain	Moradabad	Moradabad	Domestic	Ramganga	28.841119	78.78999	Untapped	6.3	3.00	476	1620
172.	Prabhat Nagar Drain	Moradabad	Moradabad	Mixed	Ramganga	28.805294	78.800988	Untapped	3.75	0.17	46	163
173.	Barbalan Drain	Moradabad	Moradabad	Mixed	Ramganga	28.83204	78.79333	Untapped	FCM	-	181	500
174.	Jama Masjid Drain Left	Moradabad	Moradabad	Mixed	Ramganga	28.835473	78.793397	Untapped	FCM	-	292	906
175.	Jama Masjid Drain Right	Moradabad	Moradabad	Mixed	Ramganga	28.834021	78.795059	Untapped	FCM	-	-	-
176.	Chandausi Road Right drain	Moradabad	Moradabad	Mixed	Gagan	28.795116	78.762247	Untapped	FCM	-	19	72
177.	Vivekanand Hospital Drain (Right)	Moradabad	Moradabad	Domestic	Ramganga	28.890299	78.743293	Untapped	24.4	2.68	110	254
178.	Vivekanand Drain (Left)	Moradabad	Moradabad	Domestic	Ramganga	28.890305	78.743284	Untapped	-	-	-	-
179.	Moksh Dham drain	Moradabad	Moradabad	Domestic	Ramganga	28.881078	78.752181	Untapped	19.8	1.31	66	142
180.	TDI City drain	Moradabad	Moradabad	Domestic	Ramganga	28.87561	78.756022	Untapped	8.7	1.44	166	273
181.	Chakkar ki Milak	Moradabad	Moradabad	Domestic	Ramganga	28.860741	78.770212	Untapped	3.63	0.93	257	524
182.	Jigar colony	Moradabad	Moradabad	Domestic	Ramganga	28.854233	78.774033	Tapped	1.73	0.30	171	455
183.	MIT Drain	Moradabad	Moradabad	Domestic	Ramganga	28.871596	78.756084	Untapped	12.94	0.47	36	145
184.	Jhabbu ka Nala	Moradabad	Moradabad	Mixed	Ramganga	28.84767	78.78299	Untapped	53.56	9.37	175	462
185.	Nawabpura Drain-1	Moradabad	Moradabad	Domestic	Ramganga	28.84714	78.78401	Untapped	4.51	2.98	661	1197
186.	Nawabpura Drain-2	Moradabad	Moradabad	Domestic	Ramganga	28.84451	78.78631	Untapped	8.4	1.88	224	566
187.	Katghar Railway Station Drain, Moradabad, UP	Moradabad	Moradabad	Domestic	Ramganga	28.82509	78.79861	Untapped	FCM	-	114	443

188.	Moradabad/ Karula Drain	Moradabad	Moradabad	Mixed	Ramganga	28.77705	78.80609	Untapped	FCM	-	102	274
189.	Sugar Mill Nala	Muzaffarnagar	Khatauli	Mixed	Kali East	29.278452	77.787762	Untapped	Negligible flow	-	389	670
190.	Taar Nala Babaganj/ Ganda Nala/ Duar River	Pratapgarh	Pratapgarh	Domestic	Ganga	25.645167	81.567201	Untapped	FCM	-	< 5.0	< 5.0
191.	Pakka Nala/ Taar Nala	Pratapgarh	Manikpur	Domestic	Ganga	25.766779	81.401041	Untapped	3.07	0.12	39.3	90.2
192.	Raja Hela Nala	Pratapgarh	Manikpur	Domestic	Ganga	25.769718	81.398633	Untapped		-	-	-
193.	Prathmik Vidhyalay	Pratapgarh	Manikpur	Domestic	Ganga	25.769919	81.398394	Untapped		-	-	-
194.	Mallahan Tola	Pratapgarh	Manikpur	Domestic	Ganga	25.772155	81.39727	Untapped	2.66	0.02	8.96	33.6
195.	Post office Drain	Pratapgarh	Manikpur	Domestic	Ganga	25.758166	81.40562	Untapped	-	-	-	-
196.	Rasulabad-4 Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.495659	81.848358	Untapped	94.79	2.02	21.3	86.3
197.	Mehdauri Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.498513	81.850193	Tapped	-	-	-	-
198.	Rasulabad-3 Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.500232	81.853438	Untapped	8.57	0.08	9.5	34.6
199.	Rasulabad-2 Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.502646	80.856004	Tapped	0.432	0.003	6.3	16.2
200.	Rasulabad-1 Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.502484	81.856135	Tapped	-	-	-	-
201.	Chuhara Mandir-2 Drain/ Jondhwal Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.503582	81.860694	Untapped	20.9	0.51	24.6	55.3
202.	Chuhara Mandir-1 Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.503431	81.85896	Tapped	-	-	-	-
203.	Sadanand Ashram Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.503817	81.861997	Untapped	2.11	0.03	14.8	30.9
204.	Salori Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.484327	81.879961	Tapped	7.38	0.25	34	79.6

205.	Mavaiya Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.396363	81.891702	Tapped	-	-	-	-
206.	Manaiya Drain/ Muglaha	Prayagraj	Prayagraj	Domestic	Ganga	25.325517	81.951301	Untapped	3.11	0.32	104	156
207.	Bairagiya Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.316393	82.083749	Untapped	-	-	-	-
208.	Sadar Bazar Nala	Prayagraj	Prayagraj	Domestic	Ganga	25.491839	81.830348	Untapped	0.78	0.01	16.9	53.1
209.	Mumfordganj Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.474777	81.849295	Tapped	-	-	-	-
210.	Shivkuti Drain No. 1	Prayagraj	Prayagraj	Domestic	Ganga	25.503475	81.870973	Untapped	FCM	-	-	-
211.	Shivkuti Drain No. 2	Prayagraj	Prayagraj	Domestic	Ganga	25.503122	81.871761	Untapped	FCM	-	-	-
212.	Shivkuti Drain No. 5	Prayagraj	Prayagraj	Domestic	Ganga	25.502163	81.872909	Untapped	1.2	0.02	13.5	64.1
213.	Allenganj Nala / Buxi Bund Nala	Prayagraj	Prayagraj	Domestic	Ganga	25.45724	81.879996	Untapped	FCM	-	< 5.0	5.9
214.	Morigate Nala	Prayagraj	Prayagraj	Domestic	Ganga	25.441344	81.881934	Tapped	-	-	-	-
215.	Drains of Daraganj Area	Prayagraj	Prayagraj	Domestic	Ganga	25.442745	81.884425	Tapped	-	-	-	-
216.	Basna Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.521247	81.865794	Untapped	0.12504	0.00	21.9	50.8
217.	Shankar ghat drain-01	Prayagraj	Prayagraj	Domestic	Ganga	25.504279	81.865413	Untapped	0.11	0.00	18.4	43.5
218.	Shankar ghat drain-02	Prayagraj	Prayagraj	Domestic	Ganga	25.503789	81.863636	Untapped	FCM	-	10.5	27.2
219.	Shankar ghat Colony drain	Prayagraj	Prayagraj	Domestic	Ganga	25.503874	81.861989	Untapped	0.38	0.00	9.05	17.7
220.	Ponghat Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.460622	81.759082	Tapped	-	-		
221.	Kodra Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.465002	81.775658	Tapped	-	-		
222.	Yadavpur Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.466309	81.780317	Untapped	0.968	0.02	15.6	49.6
223.	Lakkar Drain	Prayagraj	Prayagraj	Domestic	Ganga	25.417778	81.90126	Tapped	-	-	-	-
224.	Arail Drain/ Sachhababa Ashram	Prayagraj	Prayagraj	Domestic	Yamuna	25.420213	81.882314	Tapped	-	-	-	-

225.	Sasurkhaderi River/Drain	Prayagraj	Prayagraj	Domestic	Yamuna	25.405516	81.808553	Tapped	13.54	1.37	101	170
226.	Balughat JCC Backside drain	Prayagraj	Prayagraj	Domestic	Yamuna	25.423987	81.840283	Tapped	FCM	-	123	217
227.	Karela Bagh Drain	Prayagraj	Prayagraj	Domestic	Yamuna	25.411415	81.814324	Untapped	FCM	-	42.5	76.2
228.	Karela Bagh Drain-1	Prayagraj	Prayagraj	Domestic	Yamuna	25.412601	81.81532	Untapped	Dry	-	-	-
229.	Karela Bagh Drain-2	Prayagraj	Prayagraj	Domestic	Yamuna	25.412775	81.815522	Untapped	FCM	-	-	-
230.	Main Ghaghar Nala	Prayagraj	Prayagraj	Domestic	Yamuna	25.420518	81.822352	Tapped	1.81	0.06	34.2	70.8
231.	GhagharNala 1 -A/ Sadiyapur Drain	Prayagraj	Prayagraj	Domestic	Yamuna	25.420379	81.824897	Untapped	4.1	0.35	86	237
232.	Ghaghar Nala 1-A1	Prayagraj	Prayagraj	Mixed	Yamuna	25.420918	81.829469	Untapped	2.9	0.44	150	318
233.	Ghaghar Nala 1-B	Prayagraj	Prayagraj	Domestic	Yamuna	25.419852	81.830146	Untapped	0.006	0.0004	64.8	158
234.	Dariyabad Kakahraghat Drain Meerapur	Prayagraj	Prayagraj	Domestic	Yamuna	25.41888	81.825383	Untapped	0.34	0.06	171	375
235.	Dariyabad Jogighat Drain Meerapur	Prayagraj	Prayagraj	Domestic	Yamuna	25.420554	81.833614	Untapped	0.12	0.01	75.3	211
236.	Dariyabad Pipalghat Drain	Prayagraj	Prayagraj	Domestic	Yamuna	25.420917	81.834678	Untapped	0.034	0.003	78.7	212
237.	Chachar Nala	Prayagraj	Prayagraj	Domestic	Yamuna	25.424798	81.837782	Tapped	-	-	-	-
238.	Drainat Gate No.9	Prayagraj	Prayagraj	Domestic	Yamuna	25.42697	81.850797	Untapped	1.02	0.05	52.8	96.7
239.	Drainat Gate No.13	Prayagraj	Prayagraj	Domestic	Yamuna	25.427436	81.852776	Tapped	-	-	-	-
240.	Fort DrainNo.1	Prayagraj	Prayagraj	Domestic	Yamuna	25.428333	81.875719	Untapped	-	-	-	-
241.	Fort DrainNo.2	Prayagraj	Prayagraj	Domestic	Yamuna	25.430703	81.864109	Untapped	-	-	-	-

242.	Mahewa Ghat Drain no.1	Prayagraj	Prayagraj	Domestic	Yamuna	25.415901	81.837997	Tapped	-	-	-	-
243.	Mahewa Ghat Drain no.2	Prayagraj	Prayagraj	Domestic	Yamuna	25.415917	81.838069	Tapped	-	-	-	-
244.	Mahewa Ghat Drain no.3	Prayagraj	Prayagraj	Domestic	Yamuna	25.416350	81.839243	Tapped	-	-	-	-
245.	Mahewaghat drain-04	Prayagraj	Prayagraj	Domestic	Yamuna	25.417311	81.841126	Untapped	0.3	0.01	23.6	63.1
246.	Mahewa Pasi Tola drain-1	Prayagraj	Prayagraj	Domestic	Yamuna	25.415408	81.836854	Untapped	0.061	-	-	-
247.	Mahewa Pasi Tola drain-2	Prayagraj	Prayagraj	Domestic	Yamuna	25.415121	81.836138	Untapped	FCM	-	-	-
248.	Mahewa Pasi Tola drain-3	Prayagraj	Prayagraj	Domestic	Yamuna	25.415083	81.835697	Untapped	FCM	-	-	-
249.	Mahewa Pasi Tola drain-4	Prayagraj	Prayagraj	Domestic	Yamuna	25.414982	81.835485	Untapped	Stagnant	-	-	-
250.	Mahewa Pasi Tola drain-5	Prayagraj	Prayagraj	Domestic	Yamuna	25.414595	81.834888	Untapped	Stagnant	-	-	-
251.	Emergency Outfall Drain	Prayagraj	Prayagraj	Domestic	Yamuna	25.428816	81.852097	Tapped	-	-	-	-
252.	Arail Drain No. 2	Prayagraj	Prayagraj	Domestic	Yamuna	25.421224	81.877226	Tapped	-	-	-	-
253.	Chhatnag Drain (Lotey Haren Nala), Jhunsi	Prayagraj	Prayagraj	Domestic	Mansahita	25.421803	81.899713	Tapped	-	-	-	-
254.	Jhunsi Drain	Prayagraj	Prayagraj	Domestic	Mansahita	25.434534	81.900811	Tapped	-	-	-	-
255.	Augharwa Nala (New)	Prayagraj	Prayagraj	Domestic	Mansahita	25.442975	81.906424	Tapped	-	-	-	-
256.	Bhole Mandir Nala (New)	Prayagraj	Prayagraj	Domestic	Mansahita	25.444775	81.903981	Tapped	-	-	25	68
257.	Gangoli Shivala Nalla-01 (New)	Prayagraj	Prayagraj	Domestic	Mansahita	25.43977	81.902641	Tapped	-	-	-	-
258.	Gangoli Shivala Nalla-02 (New)/	Prayagraj	Prayagraj	Domestic	Mansahita	25.438853	81.901982	Tapped	-	-	-	-

	Shavitri Nagar Bazar-2											
259.	Shavitri Nagar Nalla (New)	Prayagraj	Prayagraj	Domestic	Mansahita	25.43713	81.901356	Tapped	-	-	-	-
260.	Shastri Bridge Nala (New)	Prayagraj	Prayagraj	Domestic	Mansahita	25.432661	81.900339	Tapped	-	-	-	-
261.	Triveni Marg Nala-01(New)	Prayagraj	Prayagraj	Domestic	Mansahita	25.429493	81.899645	Tapped	-	-	-	-
262.	Triveni Marg Nala-02 (New)	Prayagraj	Prayagraj	Domestic	Mansahita	25.427181	81.898635	Tapped	-	-	-	-
263.	Ulta Kila Darin-01 (New)	Prayagraj	Prayagraj	Domestic	Mansahita	25.425206	81.898297	Tapped	-	-	-	-
264.	Ulta Kila Darin-02 (New)	Prayagraj	Prayagraj	Domestic	Mansahita	25.423883	81.89896	Tapped	-	-	-	-
265.	NTPC Drain/ Ahiyari Drain	Raebareli	Unchahar	Mixed	Ganga	25.892174	81.295246	Untapped	FCM	-	9.65	33.8
266.	Padva Nala (Muraibagh), Shankar Nagar	Raebareli	Dalmau	Domestic	Ganga	26.070647	81.028466	Untapped	FCM	-	2.26	9.23
267.	Bada Math - Chhota Math ke beach ka Nala/(Sherandajpur)	Raebareli	Dalmau	Domestic	Ganga	26.056599	81.032893	Untapped	-	-	-	-
268.	Barudda Ghat Drain/ Busda / Ghat ka Nala / (Sherandajpur)	Raebareli	Dalmau	Domestic	Ganga	26.058531	81.031533	Untapped	-	-	-	-
269.	Shukla Ghat ka Nala / (Sherandajpur)	Raebareli	Dalmau	Domestic	Ganga	26.05942	81.029874	Untapped	-	-	-	-
270.	Pathvari Ghat ka Nala / (Tikaitganj)	Raebareli	Dalmau	Domestic	Ganga	26.061705	81.029333	Untapped	FCM	-	-	-

271.	Sadak Ghat Muroop Nala / (Tikaitganj)/ Sadak Ghat Drain	Raebareli	Dalmau	Domestic	Ganga	26.064856	81.029302	Untapped	0.0864	0.004	44.4	136
272.	Raja Tiloi Ghat Nala/ Mo. Sherndajpur / Deen shah Gaora Ghat	Raebareli	Dalmau	Domestic	Ganga	26.060535	81.029101	Untapped	-	-	-	-
273.	Rampur Drain	Rampur	Rampur	Mixed	Kosi	28.755724	79.022007	Untapped	71.57	4.22	59	278
274.	City Jail Drain	Unnao	Unnao	Mixed	Ganga	26.38358	80.511818	Untapped	33.18	10.02	302	390
275.	Loni River/ Drain	Unnao	Unnao	Mixed	Ganga	26.285226	80.818234	Untapped	22.81	0.19	8.33	39.6
276.	Ganga Vishnu Drain	Unnao	Shuklaganj	Domestic	Ganga	26.47622	80.372764	Untapped	FCM	-	60.6	119
277.	Indira Nagar Drain	Unnao	Shuklaganj	Domestic	Ganga	26.469457	80.38438	Untapped	7.37	0.81	110	253
278.	Ravidas Nagar	Unnao	Shuklaganj	Domestic	Ganga	26.465476	80.39726	Untapped	3.318	0.15	46.3	154
279.	Srinagar Drain (New)	Unnao	Shuklaganj	Domestic	Ganga	26.464454	80.398519	Untapped	2.807	0.19	68	190
280.	Balua Ghat Drain	Varanasi	Ramnagar	Domestic	Ganga	25.272087	83.023907	Tapped	-	-	-	-
281.	Shakti Ghat Drain	Varanasi	Ramnagar	Domestic	Ganga	25.273849	83.02408	Tapped	-	-	-	-
282.	Salotri Ghat Drain	Varanasi	Ramnagar	Domestic	Ganga	25.272823	83.023524	Tapped	-	-	-	-
283.	Hanuman Ghat Drain	Varanasi	Ramnagar	Domestic	Ganga	25.267991	83.025902	Tapped	-	-	-	-
284.	Rambag Ghat Drain	Varanasi	Ramnagar	Domestic	Ganga	25.275932	83.022034	Tapped	-	-	-	-
285.	Ramnagar Drain	Varanasi	Varanasi	Mixed	Ganga	25.256403	83.034866	Untapped	10.368	0.415	40	152
286.	Man Mandir Ghat Nala	Varanasi	Varanasi	Domestic	Ganga	25.319346	83.024368	Tapped	-	-	-	-
287.	Asi/ Nagwa Drain	Varanasi	Varanasi	Domestic	Ganga	25.282562	83.008800	Partially Tapped	19.21	1.65	86	180

288.	Shivala Drain	Varanasi	Varanasi	Domestic	Ganga	25.29627	83.007724	Tapped	-	-	-	-
289.	Nakkhi Drain	Varanasi	Varanasi	Domestic	Ganga	25.267303	83.016328	Untapped	19.74	0.703	35.6	86.2
290.	Samne Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.271989	83.015255	Partially Tapped	FCM	-	-	-
291.	Harishchandra Drain	Varanasi	Varanasi	Domestic	Ganga	25.29794	83.00757	Tapped	-	-	-	-
292.	Mansarovar Drain	Varanasi	Varanasi	Domestic	Ganga	25.301097	83.007772	Tapped	-	-	-	-
293.	Pandey Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.303777	83.008438	Tapped	-	-	-	-
294.	Dr. R. P. Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.308388	83.011154	Tapped	-	-	-	-
295.	Meer Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.308914	83.012401	Tapped	-	-	-	-
296.	Lalita Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.309964	83.013364	Tapped	-	-	-	-
297.	Jalasen Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.30982	83.013039	Tapped	-	-	-	-
298.	Manikarnika Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.310578	83.014642	Tapped	-	-	-	-
299.	Sankatha Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.312735	83.016235	Tapped	-	-	-	-
300.	Mehta Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.31391	83.016967	Tapped	-	-	-	-
301.	Ram Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.314182	83.01718	Tapped	-	-	-	-
302.	Panchganga Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.315038	83.018301	Tapped	-	-	-	-
303.	Brahma Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.315725	83.019029	Tapped	-	-	-	-
304.	Lal Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.317384	83.020861	Tapped	-	-	-	-
305.	Trilochan Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.318872	83.023471	Tapped	-	-	-	-
306.	Teliya Drain	Varanasi	Varanasi	Domestic	Ganga	25.321007	83.027299	Tapped	-	-	-	-
307.	Bhainsasur Drain	Varanasi	Varanasi	Domestic	Ganga	25.323411	83.031795	Tapped	-	-	-	-

308.	Rajghat Drain (small)	Varanasi	Varanasi	Domestic	Ganga	25.324217	83.032981	Tapped	-	-	-	-
309.	Rajghat Drain/Rajghat Outfall/ Khirkiya	Varanasi	Varanasi	Domestic	Ganga	25.326824	83.037816	Tapped	-	-	-	-
310.	Gola Ghat Drain	Varanasi	Varanasi	Domestic	Ganga	25.319346	83.024368	Tapped	-	-	-	-
311.	Phulwariya Drain	Varanasi	Varanasi	Domestic	Varuna	25.339498	82.963276	Untapped	FCM	-	17.6	71.4
312.	SadarBazar Drain	Varanasi	Varanasi	Domestic	Varuna	25.338136	82.975549	Untapped	FCM	-	25.7	89.3
313.	RajaBazar Drain	Varanasi	Varanasi	Domestic	Varuna	25.335902	82.991427	Tapped	-	-	-	-
314.	Nakkhi Ghat Drain	Varanasi	Varanasi	Domestic	Varuna	25.341232	83.008589	Tapped	-	-	-	-
315.	Narokhar Drain	Varanasi	Varanasi	Domestic	Varuna	25.346123	83.026897	Untapped	117.74	1.099	9.33	45.8
316.	SarangTalab Drain	Varanasi	Varanasi	Domestic	Varuna	25.341910	83.008772	Untapped	4.68	0.491	105	269
317.	Nai Basti	Varanasi	Varanasi	Domestic	Varuna	25.343596	83.00125	Untapped	FCM	-	163	343
318.	Teliya Bag Drain	Varanasi	Varanasi	Domestic	Varuna	25.334699	82.997566	Tapped	-	-	-	-
319.	Central Jail Drain	Varanasi	Varanasi	Domestic	Varuna	25.342634 0	82.967590 0	Untapped	60.83	5.493	90.3	176
320.	Ordely Bazar Drain	Varanasi	Varanasi	Domestic	Varuna	25.341585	82.984743	Untapped	FCM	-	63	93.9
321.	Chamrautha Drain	Varanasi	Varanasi	Domestic	Varuna	25.339617	82.960807	Untapped	28.8	2.799	97.2	210
322.	Khajury Colony Drain	Varanasi	Varanasi	Domestic	Varuna	25.341113	82.989259	Untapped	5.73	0.865	151	289
323.	Banaras Drain No.-5	Varanasi	Varanasi	Domestic	Varuna	25.339808	82.999899	Untapped	FCM	-	91.3	203
324.	Hukulganj Drain	Varanasi	Varanasi	Domestic	Varuna	25.337303	82.999632	Untapped	FCM	-	66	140
325.	Durga/ Daniyal/ Lohtha Drain	Varanasi	Varanasi	Domestic	Varuna	25.320228	82.955631	Untapped	217.72	37.448	172	332

39635

326.	Purana Pul Drain	Varanasi	Varanasi	Domestic	Varuna	25.340818	83.020779	Untapped	FCM	-	31.2	72.5
Total									3513.56	499.13		

FCM= Flow could not be measured

Details of drain name, co-ordinates and photographs during post-monsoon 2023

Sl. No.	Name of Drain	Photograph of sampling/tapping point	Photograph of confluence point
1.	Chhoiya drain (Ganga), Bijnor		
2.	Hemraj Drain, Bijnor		
3.	Dhinapur Drain, Farrukhabad		
4.	Bhairoghat Drain, Farrukhabad		
5.	Bhannu Nala, Bithoor		

<p>6.</p>	<p>Brahamawat Ghat, Bithoor</p>		
<p>7.</p>	<p>Laxman Ghat Drain, Bithoor</p>		
<p>8.</p>	<p>Ranighat Drain, Kanpur</p>		
<p>9.</p>	<p>Sisamau Drain, Kanpur</p>		
<p>10.</p>	<p>Parmath Drain, Kanpur</p>		

<p>11.</p>	<p>Gola Ghat Drain, Kanpur</p>	 <p>Latitude: 26.445585 Longitude: 80.375524 Elevation: 143.15536 m Accuracy: 19.9 m Time: 30-10-2023 15:01 Note: Gola ghat drain 2</p>	 <p>Latitude: 26.445585 Longitude: 80.375524 Elevation: 143.15536 m Accuracy: 19.9 m Time: 30-10-2023 15:01 Note: Gola ghat drain 2</p>
<p>12.</p>	<p>Dabka-1, 2 & 3 Drain, Kanpur</p>	 <p>Latitude: 26.444796 Longitude: 80.394231 Elevation: 115.21220 m Accuracy: 9.9 m Time: 30-10-2023 15:40 Note: Dabka drain 2</p>	 <p>Latitude: 26.444793 Longitude: 80.394238 Elevation: 114.21220 m Accuracy: 9.9 m Time: 30-10-2023 15:41 Note: Dabka drain 4</p>
<p>13.</p>	<p>Sheetla Bazar Drain, Kanpur</p>	 <p>Latitude: 26.437148 Longitude: 80.403444 Elevation: 141.5446 m Accuracy: 20.2 m Time: 30-10-2023 16:05 Note: Sheetla Bazar 1</p>	 <p>Latitude: 26.437148 Longitude: 80.403444 Elevation: 141.5446 m Accuracy: 20.2 m Time: 30-10-2023 16:05 Note: Sheetla Bazar 1</p>
<p>14.</p>	<p>Budhiya Ghat Drain, Kanpur</p>	 <p>Latitude: 26.431022 Longitude: 80.411395 Elevation: 148.58116 m Accuracy: 13.8 m Time: 30-10-2023 16:35 Note: Budhiyaghat drain 2</p>	 <p>Latitude: 26.430855 Longitude: 80.411271 Elevation: 148.58214 m Accuracy: 32.8 m Time: 30-10-2023 16:54 Note: Budhiyaghat drain</p>
<p>15.</p>	<p>Wajidpur Drain, Kanpur</p>	 <p>Latitude: 26.422302 Longitude: 80.413086 Elevation: 140.52717 m Accuracy: 47.9 m Time: 30-10-2023 16:54 Note: Wajidpur drain</p>	

<p>16.</p>	<p>Arra Drain, Kanpur</p>	 <p>Latitude: 26.404577 Longitude: 80.297488 Elevation: 161.01 m Accuracy: 14.8 m Time: 10:40:2023 10:21 Note: Arra Drain</p>	 <p>Latitude: 26.404577 Longitude: 80.297488 Elevation: 161.01 m Accuracy: 14.8 m Time: 10:40:2023 10:21 Note: Arra Drain</p>
<p>17.</p>	<p>City Jail Drain, Unnao</p>		
<p>18.</p>	<p>Ganga Vishnu Drain Shuklaganj</p>	 <p>Latitude: 26.413023 Longitude: 80.297488 Elevation: 161.01 m Accuracy: 14.8 m Time: 11:30:2023 10:30 Note: Ganga Vishnu Drain</p>	 <p>Latitude: 26.413023 Longitude: 80.297488 Elevation: 161.01 m Accuracy: 14.8 m Time: 11:30:2023 10:30 Note: Ganga Vishnu Drain</p>
<p>19.</p>	<p>Indira Nagar Drain, Shuklaganj</p>	 <p>Latitude: 26.413023 Longitude: 80.297488 Elevation: 161.01 m Accuracy: 14.8 m Time: 11:30:2023 10:30 Note: Indira Nagar Drain</p>	 <p>Latitude: 26.413023 Longitude: 80.297488 Elevation: 161.01 m Accuracy: 14.8 m Time: 11:30:2023 10:30 Note: Indira Nagar Drain</p>
<p>20.</p>	<p>Srinagar Drain, Shuklaganj</p>	 <p>Latitude: 26.413023 Longitude: 80.297488 Elevation: 161.01 m Accuracy: 14.8 m Time: 11:30:2023 10:30 Note: Srinagar Drain</p>	 <p>Latitude: 26.413023 Longitude: 80.297488 Elevation: 161.01 m Accuracy: 14.8 m Time: 11:30:2023 10:30 Note: Srinagar Drain</p>

<p>21.</p>	<p>Pathvari Ghat ka Nala / (Tikaitganj), Dalmau</p>	 <p>Latitude: 26.962796 Longitude: 81.029103 Elevation: 135.081100 m Accuracy: 96.0 m Time: 12-19-2023 13:59 Note: pathvari ghat bioremediation</p>	 <p>Latitude: 26.961778 Longitude: 81.028646 Elevation: 134.71221 m Accuracy: 3.9 m Time: 12-19-2023 13:54 Note: pathvari ghat</p>
<p>22.</p>	<p>Pakka Nala/ Taar Nala, Manikpur</p>		
<p>23.</p>	<p>Raja Hela Nala, Manikpur</p>		
<p>24.</p>	<p>Prathmik Vidhyalay, Manikpur</p>		
<p>25.</p>	<p>Mallahan Tola, Manikpur</p>		

<p>26.</p>	<p>Yadavpur Drain, Prayagraj</p>	 <p>Latitude: 25.466299 Longitude: 81.796259 Elevation: 85.14415 m Accuracy: 11.8 m Time: 18-12-2023 10:29 Note: Yadavpur drain</p>	 <p>Latitude: 25.466815 Longitude: 81.793476 Elevation: 71.12512 m Accuracy: 7.5 m Time: 18-12-2023 10:51 Note: Yadavpur drain</p>
<p>27.</p>	<p>Lakkar Drain, Prayagraj</p>	 <p>Latitude: 25.47778 Longitude: 81.90126 Elevation: 105.6449 m Accuracy: 3.7 m Time: 08-12-2023 15:53 Note: Lakkar drain, Prayagraj</p>	 <p>Latitude: 25.47767 Longitude: 81.90847 Elevation: 105.5419 m Accuracy: 12.0 m Time: 08-12-2023 15:56 Note: Lakkar drain, Prayagraj</p>
<p>28.</p>	<p>Rasulabad-4 Drain, Prayagraj</p>	 <p>Time: 26-12-2023 16:11 Note: Rasulabad drain 4</p>	 <p>Latitude: 25.694077 Longitude: 85.86894 Elevation: 77.18228 m Accuracy: 13.0 m Time: 26-12-2023 16:12 Note: Rasulabad drain 2</p> <p><i>Confluence of the drain into the outlet of STP Rajapur and ultimately confluences with R. Ganga</i></p>
<p>29.</p>	<p>Mehdauri Drain, Prayagraj</p>	 <p>Latitude: 25.43856 Longitude: 81.890152 Elevation: 76.19416 m Accuracy: 6.0 m Time: 21-12-2023 15:25 Note: M. drain</p>	 <p>Time: 26-12-2023 15:23 Note: M. drain</p>
<p>30.</p>	<p>Rasulabad-3 Drain, Prayagraj</p>	 <p>Latitude: 25.501264 Longitude: 81.833369 Elevation: 122.1524 m Accuracy: 18.0 m Time: 27-12-2023 16:43 Note: Rasulabad drain 3</p>	 <p>Latitude: 25.50111 Longitude: 81.83314 Elevation: 89.97812 m Accuracy: 5.6 m Time: 20-12-2023 11:39 Note: Rasulabad 03 confluence</p>

<p>31.</p>	<p>Rasulabad-2 Drain, Prayagraj</p>	 <p>Latitude: 25.502546 Longitude: 81.855004 Elevation: 77.21452 m Accuracy: 16.0 m Time: 27-12-2023 17:09 Note: Rasulabad drain 2d</p>	 <p>Latitude: 25.502556 Longitude: 81.855001 Elevation: 79.21454 m Accuracy: 10.0 m Time: 27-12-2023 17:08 Note: Rasulabad drain 2c</p>
<p>32.</p>	<p>Chuhara Mandir-2 Drain/ Jonhwal Drain, Prayagraj</p>	 <p>Time: 27-12-2023 16:09 Note: Chuhara mata mandir 2</p>	 <p>Latitude: 25.501757 Longitude: 81.856063 Elevation: 81.22119 m Accuracy: 7.6 m Time: 27-12-2023 16:12 Note: Chuhara mata mandir 2c</p>
<p>33.</p>	<p>Chuhara Mandir-1 Drain, Prayagraj</p>	 <p>Latitude: 25.502823 Longitude: 81.859173 Elevation: 77.62114 m Accuracy: 100.0 m Time: 27-12-2023 16:04 Note: Chuhara Mata Mandir 2c</p>	 <p>Latitude: 25.502823 Longitude: 81.859173 Elevation: 77.62114 m Accuracy: 100.0 m Time: 27-12-2023 16:05 Note: Chuhara Mata Mandir 2c</p>
<p>34.</p>	<p>Sadanand Ashram Drain, Prayagraj</p>	 <p>Latitude: 25.503902 Longitude: 81.862056 Elevation: 67.22124 m Accuracy: 12.5 m Time: 27-12-2023 16:30 Note: Sadanand Ashram drain</p>	 <p>Latitude: 25.503911 Longitude: 81.862056 Elevation: 69.22118 m Accuracy: 9.8 m Time: 27-12-2023 16:20 Note: Sadanand Ashram</p>
<p>35.</p>	<p>Mavaiya Drain, Prayagraj</p>	 <p>Latitude: 25.316649 Longitude: 81.091181 Elevation: 116.18452 m Accuracy: 1.6 m Time: 27-12-2023 14:10</p>	

<p>36.</p>	<p>Manaiya Drain/ Muglaha, Prayagraj</p>	 <p>Latitude: 25.515732 Longitude: 81.951725 Elevation: 1147.646192 m Accuracy: 18.0 m Time: 27-12-2023 13:33 Note: Manaiya drain</p>	
<p>37.</p>	<p>Sadar Bazar Nala, Prayagraj</p>	 <p>Time: 26-12-2023 15:46 Note: Sadar Bazar Nala</p>	 <p>Latitude: 25.491629 Longitude: 81.933048 Elevation: 75.13419 m Accuracy: 5.3 m Time: 26-12-2023 15:46 Note: Sadar Bazar Nala 2</p>
<p>38.</p>	<p>Shivkuti Drain No. 1, Prayagraj</p>	 <p>Latitude: 25.502544 Longitude: 81.923532 Elevation: 114.9016 m Accuracy: 27.3 m Time: 26-12-2023 16:00 Note: Shiv Kuti 5 Prayagraj</p>	
<p>39.</p>	<p>Shivkuti Drain No. 2, Prayagraj</p>		 <p>Latitude: 25.502544 Longitude: 81.923532 Elevation: 114.9016 m Accuracy: 27.3 m Time: 26-12-2023 16:00 Note: Shiv Kuti 5 Prayagraj</p>
<p>40.</p>	<p>Shivkuti Drain No. 5, Prayagraj</p>		 <p>Latitude: 25.502544 Longitude: 81.923532 Elevation: 114.9016 m Accuracy: 27.3 m Time: 26-12-2023 16:00 Note: Shiv Kuti 5 Prayagraj</p>

41.	Shankar ghat Colony drain, Prayagraj	 <p>Latitude: 25.502874 Longitude: 81.661989 Elevation: 112.5248 m Accuracy: 4.0 m Time: 26-12-2023 17:33 Note: Shankar ghat colony Prayagraj</p>	 <p>Latitude: 25.504023 Longitude: 81.662058 Elevation: 112.52477 m Accuracy: 8.0 m Time: 26-12-2023 17:35 Note: Shankar ghat colony</p>
42.	Arail Drain/ Sachhababa Ashram, Prayagraj	 <p>Latitude: 25.419746 Longitude: 81.681984 Elevation: 91.116 m Accuracy: 3.3 m Time: 19-12-2023 16:05 Note: Arail drain</p>	 <p>Latitude: 25.420191 Longitude: 81.682523 Elevation: 79.9148 m Accuracy: 5.4 m Time: 19-12-2023 16:13 Note: Arail drain</p>
43.	Sasurkhaderi River/Drain, Prayagraj	 <p>2023/11/7 10:48</p>	 <p>2023/11/7 10:54</p>
44.	Balughat JCC Backside drain, Prayagraj	 <p>Latitude: 25.424055 Longitude: 81.646221 Elevation: 100.2746 m Accuracy: 3.2 m Time: 18-12-2023 15:15 Note: Balughat JCC drain</p>	 <p>Latitude: 25.429315 Longitude: 81.646495 Elevation: 88.4124 m Accuracy: 5.9 m Time: 18-12-2023 15:21 Note: Balughat JCC drain</p>
45.	Karela Bagh Drain, Prayagraj	 <p>Latitude: 25.412097 Longitude: 81.674092 Elevation: 95.262079 Accuracy: 5.4 m Time: 19-12-2023 16:33 Note: Karela Bagh drain</p>	 <p>Latitude: 25.411568 Longitude: 81.681199 Elevation: 82.7416 m Accuracy: 7.5 m Time: 19-12-2023 16:18 Note: Karela Bagh drain</p>

<p>46.</p>	<p>Main Ghaghar Nala, Prayagraj</p>		
<p>47.</p>	<p>GhagharNala 1-A/ Sadiyapur Drain, Prayagraj</p>		
<p>48.</p>	<p>Ghaghar Nala 1-A1, Prayagraj</p>		
<p>49.</p>	<p>Ghaghar Nala 1-B, Prayagraj</p>		
<p>50.</p>	<p>Dariyabad Pipalghat Drain, Prayagraj</p>		

<p>51.</p>	<p>Chachar Nala, Prayagraj</p>		
<p>52.</p>	<p>Drain at Gate No.9, Prayagraj</p>		
<p>53.</p>	<p>Arail Drain No. 2, Prayagraj</p>	 <p>Latitude: 25.423919 Longitude: 81.875918 Elevation: 76.41121m Accuracy: 8.4m Time: 19-12-2023 15:09 Note: Arail Drain 2</p>	 <p>Latitude: 25.028954 Longitude: 81.877104 Elevation: 158.921161ft Accuracy: 7.0 m Time: 16-12-2023 15:00 Note: Arail Drain 2</p>
<p>54.</p>	<p>Ghode Shaheed Drain, Mirzapur</p>		 <p>Latitude: 25.158418 Longitude: 83.334189 Elevation: 228.16108 m Accuracy: 0.9 m Time: 21-11-2023 10:01 Note: GHODE SHAHEED DRAIN</p>
<p>55.</p>	<p>Morchaghar Drain, Mirzapur</p>		

56.	Hanuman Ghat Drain, Mirzapur	 <p>Latitude: 25.17354 Longitude: 82.596715 Altitude: 42.9211 m Accuracy: 12.2 m Time: 21-11-2023 10:38 Note: HANUMAN GHAT DRAIN MIRZAPUR</p>	 <p>Latitude: 25.174198 Longitude: 82.595728 Elevation: 105.89234 m Accuracy: 11.3 m Time: 21-11-2023 10:42 Note: HANUMAN GHAT DRAIN MIRZAPUR</p>
57.	Bisundarpur Drain, Mirzapur	 <p>Latitude: 25.175167 Longitude: 82.597547 Elevation: 65.3500 m Accuracy: 5.9 m Time: 21-11-2023 11:50 Note: BISUNDARPUR DRAIN</p>	 <p>Latitude: 25.175167 Longitude: 82.597547 Elevation: 65.3500 m Accuracy: 5.9 m Time: 21-11-2023 11:50 Note: BISUNDARPUR DRAIN</p>
58.	Patengra Drain, Mirzapur	 <p>Latitude: 25.165994 Longitude: 82.590058 Elevation: 89.8718 m Accuracy: 6.4 m Time: 22-11-2023 13:00 Note: Patengra drain</p>	 <p>Latitude: 25.168914 Longitude: 82.591156 Elevation: 74.028 m Accuracy: 7.5 m Time: 22-11-2023 13:39 Note: Patengra drain</p>
59.	Malahia Drain, Mirzapur	 <p>Latitude: 25.162274 Longitude: 82.592519 Elevation: 75.1912 m Accuracy: 7.5 m Time: 22-11-2023 13:42 Note: Malahya drain.</p>	 <p>Latitude: 25.161983 Longitude: 82.592906 Elevation: 68.098 m Accuracy: 8.4 m Time: 22-11-2023 13:48 Note: Malahya drain</p>
60.	Parshuram Ghat, Mirzapur	 <p>Latitude: 25.162274 Longitude: 82.594711 Elevation: 61.98172 m Accuracy: 7.5 m Time: 22-11-2023 14:07 Note: Parshuram ghat drain</p>	 <p>Latitude: 25.166516 Longitude: 82.594833 Elevation: 74.726 m Accuracy: 8.6 m Time: 22-11-2023 14:06 Note: Parshuram ghat drain</p>

61.	Balughat Kachha Drain, Mirzapur	 <p>Latitude: 25.164451 Longitude: 82.539559 Elevation: 93.8316 m Accuracy: 19.3 m Time: 22-11-2023 12:01 Note: Balughat Kachha drain</p>	 <p>Latitude: 25.165158 Longitude: 82.537883 Elevation: 72.8912 m Accuracy: 6.4 m Time: 22-11-2023 11:39 Note: Balughat Kachha drain</p>
62.	Baswariya Drain, Mirzapur	 <p>Latitude: 25.161224 Longitude: 82.531254 Elevation: 62.3824 m Accuracy: 15.0 m Time: 22-11-2023 10:44 Note: Baswariya drain</p>	 <p>Latitude: 25.162608 Longitude: 82.533314 Elevation: 78.9412 m Accuracy: 8.8 m Time: 22-11-2023 11:09 Note: Baswariya drain</p>
63.	Chorwa Drain, Mirzapur	 <p>Latitude: 25.148894 Longitude: 82.530683 Elevation: 77.3518 m Accuracy: 11.8 m Time: 22-11-2023 09:18 Note: Chorwa drain</p>	 <p>Latitude: 25.151184 Longitude: 82.532143 Elevation: 78.2515 m Accuracy: 8.8 m Time: 22-11-2023 08:76 Note: Chorwa drain</p>
64.	Khandwa Drain, Mirzapur	 <p>Latitude: 25.149097 Longitude: 82.555224 Elevation: 76.37148 m Accuracy: 19.3 m Time: 22-11-2023 07:35 Note: Khandwa drain</p>	 <p>Latitude: 25.151347 Longitude: 82.554663 Elevation: 77.0716 m Accuracy: 13.2 m Time: 22-11-2023 07:50 Note: Khandwa drain</p>
65.	Balaji Temple Drain, Mirzapur	 <p>Latitude: 25.151022 Longitude: 82.55976 Elevation: 100.73482 m Accuracy: 19.6 m Time: 21-11-2023 12:41 Note: BALAJI TEMPLE DRAIN MIRZAPUR</p>	 <p>Latitude: 25.150813 Longitude: 82.559771 Elevation: 103.63450 m Accuracy: 7.6 m Time: 21-11-2023 12:41 Note: BALAJI TEMPLE DRAIN MIRZAPUR</p>

<p>66.</p>	<p>Lohandi Drain, Mirzapur</p>	 <p>Latitude: 25.143823 Longitude: 82.529012 Elevation: 74.78112 m Accuracy: 7.5 m Time: 21-11-2023 16:18 Note: Lohandi drain Powered by NiteGeo</p>	 <p>Latitude: 25.143228 Longitude: 82.579326 Elevation: 76.9958 m Accuracy: 4.3 m Time: 21-11-2023 16:20 Note: Lohandi drain Powered by NiteGeo</p>
<p>67.</p>	<p>Kashi Ram Awash Drain, Chunar</p>	 <p>Latitude: 25.133365 Longitude: 82.864136 Elevation: 94.95418 m Accuracy: 12.4 m Time: 22-11-2023 11:26 Note: Kashi Ram awash drain, Chunar Powered by NiteGeo</p>	 <p>Latitude: 25.133842 Longitude: 82.864974 Elevation: 94.4623 m Accuracy: 7.84 m Time: 22-11-2023 11:53 Note: Kashi Ram awash drain, Chunar Powered by NiteGeo</p>
<p>68.</p>	<p>Chaura Mata Drain, Chunar</p>	 <p>Latitude: 25.132265 Longitude: 82.818633 Elevation: 83.6182 m Accuracy: 6.4 m Time: 22-11-2023 12:41 Note: Chaura mata drain, Chunar near flow Powered by NiteGeo</p>	 <p>Latitude: 25.131896 Longitude: 82.876425 Elevation: 78.3635 m Accuracy: 9.9 m Time: 22-11-2023 12:41 Note: Chaura mata drain, Chunar near flow Powered by NiteGeo</p>
<p>69.</p>	<p>Balughat Drain/ Balbeer drain, Chunar</p>	 <p>Latitude: 25.122035 Longitude: 82.871869 Elevation: 97.2417 m Accuracy: 13.6 m Time: 22-11-2023 13:56 Note: Balughat drain by Powered by NiteGeo</p>	 <p>Latitude: 25.120344 Longitude: 82.878033 Elevation: 95.31117 m Accuracy: 88.3 m Time: 22-11-2023 12:50 Note: Balughat drain near flow, Chunar near flow Powered by NiteGeo</p>
<p>70.</p>	<p>Gangeshwari Nishad Park Drain, Chunar</p>	 <p>Latitude: 25.126518 Longitude: 82.877948 Elevation: 65.62110 m Accuracy: 7.5 m Time: 22-11-2023 12:53 Note: Gangeshwari nishad drain, Chunar near flow Powered by NiteGeo</p>	 <p>Latitude: 25.126518 Longitude: 82.877948 Elevation: 65.62110 m Accuracy: 7.5 m Time: 22-11-2023 12:53 Note: Gangeshwari nishad drain, Chunar near flow Powered by NiteGeo</p>


<p>71.</p>	<p>Post Office North Drain, Chunar</p>	 <p>Latitude: 25.127422 Longitude: 82.8776 Elevation: 95.41221 m Accuracy: 8.8 m Time: 22-11-2023 13:09 Note: Post office North</p>	 <p>Latitude: 25.127422 Longitude: 82.8776 Elevation: 95.41221 m Accuracy: 8.8 m Time: 22-11-2023 13:09 Note: Post office North</p>
<p>72.</p>	<p>Santoshi Mata Mandir Drain, Chunar</p>	 <p>Latitude: 25.127033 Longitude: 82.877076 Elevation: 95.31529 m Accuracy: 8.8 m Time: 22-11-2023 13:17 Note: Santoshi mata mandir</p>	 <p>Latitude: 25.127033 Longitude: 82.877076 Elevation: 95.31529 m Accuracy: 8.8 m Time: 22-11-2023 13:16 Note: Santoshi mata mandir</p>
<p>73.</p>	<p>Bhairamganj West Drain, Chunar</p>	 <p>Latitude: 25.112209 Longitude: 82.877076 Elevation: 95.31529 m Accuracy: 8.8 m Time: 22-11-2023 13:17 Note: Bhairamganj west drain</p>	 <p>Latitude: 25.112209 Longitude: 82.877076 Elevation: 95.31529 m Accuracy: 8.8 m Time: 22-11-2023 13:16 Note: Bhairamganj west drain</p>
<p>74.</p>	<p>Bhairamganj East Drain, Chunar</p>	 <p>Latitude: 25.112209 Longitude: 82.877076 Elevation: 95.31529 m Accuracy: 8.8 m Time: 22-11-2023 13:17 Note: Bhairamganj east drain</p>	 <p>Latitude: 25.112209 Longitude: 82.877076 Elevation: 95.31529 m Accuracy: 8.8 m Time: 22-11-2023 13:16 Note: Bhairamganj east drain</p>
<p>75.</p>	<p>Dargah shareef Drain, Chunar</p>	 <p>Latitude: 25.112209 Longitude: 82.877076 Elevation: 95.31529 m Accuracy: 8.8 m Time: 22-11-2023 13:16 Note: Dargah Shareef drain</p>	 <p>Latitude: 25.112209 Longitude: 82.877076 Elevation: 95.31529 m Accuracy: 8.8 m Time: 22-11-2023 13:16 Note: Dargah Shareef drain</p>

<p>76.</p>	<p>Rambag Ghat Drain, Ramnagar</p>	 <p>Latitude: 25.315143 Longitude: 83.008403 Elevation: 11.111 m Accuracy: 11.111 m Time: 05-12-2023 16:30 Note: Rambag drain</p>	 <p>Latitude: 25.315143 Longitude: 83.008403 Elevation: 11.111 m Accuracy: 11.111 m Time: 05-12-2023 16:30 Note: Rambag drain</p>
<p>77.</p>	<p>Asi/ Nagwa Drain, Varanasi</p>	 <p>Latitude: 25.292792 Longitude: 83.027294 Elevation: 92.8414 m Accuracy: 50.4 m Time: 05-12-2023 16:30 Note: Nagwa drain</p>	 <p>Time: 05-12-2023 16:25 Note: Nagwa drain</p>
<p>78.</p>	<p>Nakkhi Drain, Varanasi</p>	 <p>Latitude: 25.367461 Longitude: 83.016613 Elevation: 96.8837 m Accuracy: 23.2 m Time: 05-12-2023 17:16 Note: Nakkhi drain</p>	
<p>79.</p>	<p>Samne Ghat Drain, Varanasi</p>	 <p>Latitude: 25.272366 Longitude: 83.015506 Elevation: 97.81161 m Accuracy: 36.3 m Time: 05-12-2023 17:05 Note: Samneghat drain</p>	 <p>Time: 05-12-2023 17:01 Note: Samneghat drain</p>
<p>80.</p>	<p>Mansarovar Drain, Varanasi</p>		 <p>Mansarovar Ghat Drain Varanasi 07-12-2023 13:39 25.30198, 83.00786 82AS=WZ15-Bunpatti, Varanasi-221001</p>


<p>81.</p>	<p>Pandey Ghat Drain, Varanasi</p>		
<p>82.</p>	<p>Sankatha Ghat Drain, Varanasi</p>		
<p>83.</p>	<p>Panchganga Ghat Drain, Varanasi</p>		
<p>84.</p>	<p>Lal Ghat Drain, Varanasi</p>		
<p>85.</p>	<p>Central Jail Drain, Varanasi</p>		

<p>86.</p>	<p>Ordely Bazar Drain, Varanasi</p>		
<p>87.</p>	<p>Chamrautha Drain, Varanasi</p>		
<p>88.</p>	<p>Khajury Colony Drain, Varanasi</p>		
<p>89.</p>	<p>Shahid Baba Mazar drain/ Kaili Drain, Mughalsarai</p>		 <p>Latitude: 25.220382 Longitude: 83.130902 Elevation: 70.99116 m Accuracy: 12.5 m Time: 06-12-2023 12:07 Note: Kaili drain.</p>
<p>90.</p>	<p>Railway Drain, Mughalsarai</p>	 <p>Latitude: 25.291275 Longitude: 83.139628 Altitude: 37.1515 m Accuracy: 29.4 m Time: 06-12-2023 14:18 Note: Rail way drain.msi</p>	

<p>91.</p>	<p>Mughalsarai / Local Drain / Ganda nala, Mughalsarai</p>	 <p>Latitude: 25.321165 Longitude: 83.114233 Elevation: 76.0224 m Accuracy: 45.8 m Time: 06-12-2023 12:04 Note: 25321165</p>	
<p>92.</p>	<p>Kot Ghat Drain, Saidpur</p>	 <p>Latitude: 25.320270 Longitude: 83.225270 Elevation: 76.0181 m Accuracy: 6.2 m Time: 19-12-2023 11:51 Note: 25320270</p>	 <p>Latitude: 25.320270 Longitude: 83.225270 Elevation: 76.0181 m Accuracy: 6.2 m Time: 19-12-2023 11:51 Note: 25320270</p>
<p>93.</p>	<p>Budenath Mahadev Ghat Drain, Saidpur</p>	 <p>Latitude: 25.320111 Longitude: 83.225270 Elevation: 76.0181 m Accuracy: 6.2 m Time: 19-12-2023 11:51 Note: 25320111</p>	 <p>Latitude: 25.320111 Longitude: 83.225270 Elevation: 76.0181 m Accuracy: 6.2 m Time: 19-12-2023 11:51 Note: 25320111</p>
<p>94.</p>	<p>Pakka Ghat Drain, Saidpur</p>	 <p>Latitude: 25.320270 Longitude: 83.225270 Elevation: 76.0181 m Accuracy: 6.2 m Time: 19-12-2023 11:51 Note: 25320270</p>	 <p>Latitude: 25.320270 Longitude: 83.225270 Elevation: 76.0181 m Accuracy: 6.2 m Time: 19-12-2023 11:51 Note: 25320270</p>
<p>95.</p>	<p>Mahaveer Ghat Drain, Saidpur</p>	 <p>Latitude: 25.320270 Longitude: 83.225270 Elevation: 76.0181 m Accuracy: 6.2 m Time: 19-12-2023 11:51 Note: 25320270</p>	 <p>Latitude: 25.320270 Longitude: 83.225270 Elevation: 76.0181 m Accuracy: 6.2 m Time: 19-12-2023 11:51 Note: 25320270</p>

<p>96.</p>	<p>Rangmahal Ghat Drain, Saidpur</p>		
<p>97.</p>	<p>Jauharganj Drain / Kolhua Ghat drain, Saidpur</p>		
<p>98.</p>	<p>Bada Mahadev /Adarsh Bazar Drain, Ghazipur</p>		
<p>99.</p>	<p>Pear Nagar Drain, Ghazipur</p>		
<p>100.</p>	<p>Khirki Ghat Drain, Ghazipur</p>		

<p>101.</p>	<p>Dadri Ghat Drain, Ghazipur</p>		
<p>102.</p>	<p>Collector Ghat Drain, Ghazipur</p>		
<p>103.</p>	<p>Maksud Ghat Drain, Ghazipur</p>		
<p>104.</p>	<p>Gola Ghat Drain, Ghazipur</p>		
<p>105.</p>	<p>Stimer Ghat Drain, Ghazipur</p>		

<p>106.</p>	<p>Anzahi Ghat Drain, Ghazipur</p>		
<p>107.</p>	<p>Drain at left of Pakka Ghat, Ghazipur</p>		
<p>108.</p>	<p>Kathal Drain, Balia</p>		
<p>109.</p>	<p>Deharia Drain, Moradabad</p>		

<p>110.</p>	<p>Ghosiyan Drain, Moradabad</p>		
<p>111.</p>	<p>Jama Masjid Left Drain, Moradabad</p>		
<p>112.</p>	<p>Jama Masjid Right Drain, Moradabad</p>		
<p>113.</p>	<p>Vivekanand Hospital (Right) Drain, Moradabad</p>		
<p>114.</p>	<p>Moksh Dham drain, Moradabad</p>		

<p>115.</p>	<p>Chakkar ki Milak, Moradabad</p>	 <p>GPS Map VQ69 + SVM jilani masjid, Chakkar Ki Milak, Moradabad, Uttar Pradesh, 244001, India Latitude: 28.86075117° Longitude: 78.77023472° Local 02:23:19 PM GMT 09:13:19 AM Altitude: 193 meters Monday, 26.02.2024</p>	 <p>GPS Map VQ69 + SVM jilani masjid, Chakkar Ki Milak, Moradabad, Uttar Pradesh, 244001, India Latitude: 28.86080167° Longitude: 78.77031117° Local 02:26:30 PM GMT 09:16:30 AM Altitude: 193 meters Monday, 26.02.2024</p>
<p>116.</p>	<p>Jigar Colony, Moradabad</p>	 <p>GPS Map B-143, Jigar Colony, Moradabad, Uttar Pradesh 244001, India Latitude: 28.85412686° Longitude: 78.77401181° Local 02:48:39 PM GMT 09:18:39 AM Altitude: 197 meters Monday, 26.02.2024</p>	 <p>GPS Map B-143, Jigar Colony, Moradabad, Uttar Pradesh 244001, India Latitude: 28.85417603° Longitude: 78.77409978° Local 02:48:02 PM GMT 09:18:02 AM Altitude: 195 meters Monday, 26.02.2024</p>
<p>117.</p>	<p>Jhabbu ka Nala, Moradabad</p>		
<p>118.</p>	<p>Moradabad/ Karula Drain, Moradabad</p>		
<p>119.</p>	<p>Odean Nala / Slaughter house drain, Meerut</p>		

<p>120.</p>	<p>Devipura Drain, Bulandshahr</p>	 <p>CV66+3CV, Tatarpur Rd, Kidwai Nagar, Milka Mosamgarh, Bulandshahr, Uttar Pradesh 203001, India Latitude: 28.40995698° Longitude: 77.86076621° Local 01:50:20 PM Altitude: 202 meters GMT 08:20:20 AM Friday, 09.02.2024</p>	 <p>CV56+P92, Samsan Ghat Rd, Devipura-1, Bulandshahr, Uttar Pradesh 203001, India Latitude: 28.41000493° Longitude: 77.86081802° Local 01:53:15 PM Altitude: 201 meters GMT 08:23:15 AM Friday, 09.02.2024</p>
<p>121.</p>	<p>Aadil Drain, Bulandshahr</p>		
<p>122.</p>	<p>Maman Road Drain, Bulandshahr</p>		
<p>123.</p>	<p>Adanga Drain, Kannauj</p>		
<p>124.</p>	<p>Barbaspur Drain, Bhadohi</p>		

<p>125.</p>	<p>BIDA Drain, Bhadohi</p>	 <p>Location: 23.866775 Longitude: 87.984738 Elevation: 166.4 Accuracy: 1.5 m Date: 2019-08-05 10:21 User: 555</p>	 <p>Location: 23.866775 Longitude: 87.984738 Elevation: 166.4 Accuracy: 1.5 m Date: 2019-08-05 10:21 User: 555</p>
<p>126.</p>	<p>Mamdevpur Drain, Bhadohi</p>	 <p>Location: 23.866775 Longitude: 87.984738 Elevation: 166.4 Accuracy: 1.5 m Date: 2019-08-05 10:21 User: 555</p>	 <p>Location: 23.866775 Longitude: 87.984738 Elevation: 166.4 Accuracy: 1.5 m Date: 2019-08-05 10:21 User: 555</p>

Status of Sewage Treatment Plants in Uttar Pradesh (April-July, 2024)

- STPs complying to BOD Norms (≤ 10 mg/l) in Uttar Pradesh (April-July,2024) w.r.t. NGT and MoEF&CC norms

S.No.	Name of STPs	Ganga Front Town	Designed Capacity (MLD)	BOD (≤ 10 mg/l)
1.	Brajghat (03 MLD) STP	Garhmukteshwar	3	3
2.	Anupsahar 1.75 MLD STP, Zone B	Anupshahr	1.75	10
3.	Salori (Bakshi Bandh) 14 MLD Prayagraj	Prayagraj	14	6.2
4.	25 MLD STP , Kodra, Prayagraj	Prayagraj	25	5.11
5.	14 MLD STP Phaphamau Prayagraj	Prayagraj	14	8.77
6.	50 MLD STP, Ramanna	Varanasi	50	5.9
7.	140 MLD STP at Dinapur	Varanasi	140	5.6
8.	10 MLD STP, Ramnagar	Ramnagar, Varanasi	10	7.7
9.	Bhagwanpur, Varanasi	Varanasi	9.8	BDL<5
10.	120 MLD STP at Goithaha	Varanasi	120	5.28
11.	12 MLD BLW (former known as DLW)	Varanasi	12	<5

- STPs complying to BOD Norms (11-30mg/l) in Uttar Pradesh (April-July,2024) w.r.t. MoEF&CC norms

S. No.	Name of STPs	Ganga Front Town	Designed Capacity	BOD (11 mg/l to 30 mg/l)
1	24 MLD STP Bijnor, Near Hemraj Colony	Bijnor	24	15
2	Narora Town (4.0 MLD)	Narora	4	17
3	Anupsahar 0.81 MLD STP, Zone A	Anupshahr	0.81	23
4	Bingawan (210 MLD) STP, Kanpur	Kanpur	210	24
5	Sajari STP, Kanpur	Kanpur	42	23.2
6	Bithoor (80 KLD) STP	Bithoor	0.08	23.6
7	29 MLD STP , Salori, Prayagraj	Prayagraj	29	18.4
8	60 MLD STP, Rajapur, Prayagraj	Prayagraj	60	11.2
9	10 MLD STP , Ponghat, Prayagraj	Prayagraj	10	15
10	80 MLD STP , Nani, Prayagraj	Prayagraj	80	12.1
11	42 MLD STP, Naini 2	Prayagraj	42	13.5
12	50 MLD STP , Numayadhai, Prayagraj	Prayagraj	50	13
13	14 MLD STP Mirzapur (Pakka Pokhra)	Mirzapur	14	16.6
14	7 MLD, STP, Vindhyachal,	Mirzapur	7	11.1
15	80 MLD STP at Dinapur	Varanasi	80	12.2

- STPs non-complying to BOD Norms (> 30mg/l) in Uttar Pradesh (April-July,2024) w.r.t. NGT and MoEF&CC norms

S. No.	Name of STPs	Ganga Front Town	Designed Capacity	BOD (> 30 mg/l)
1	Garhmukteshwar STP	Garhmukteshwar	6	31
2	Narora NAPS Township STP	Narora	2.25	148
3	Anupsahar 1.5 MLD STP, Zone A	Anupshahr	1.5	37
4	Anupsahar 1.0 MLD STP, Zone B	Anupshahr	1	41
5	130 MLD Jajmau STP Kanpur	Kanpur	130	84
6	Jajmau (43 MLD) Kanpur	Kanpur	43	80
7	30 MLD STP at Pankha	Kanpur	30	33.2
8	10 KLD FSTP Chunar, Mirzapur	Chunar	0.01	101
9	35 MLD STP Plant, Sarai Talfi, Bareilly	Bareilly	35	55

- STPs complying to COD (≤ 50 mg/l) in Uttar Pradesh (April-July,2024) w.r.t. NGT Norms

S. No.	Name of STPs	Ganga Front Town	Designed Capacity (MLD)	COD (≤ 50 mg/l)
1	Brajghat (03 MLD) STP	Garhmukteshwar	3	17
2	29 MLD STP, Salori, Prayagraj	Prayagraj	29	49.8
3	Salori (Bakshi Bandh) 14 MLD Prayagraj	Prayagraj	14	15.3
4	60 MLD STP, Rajapur, Prayagraj	Prayagraj	60	35.6
5	25 MLD STP, Kodra, Prayagraj	Prayagraj	25	16
6	80 MLD STP, Nani, Prayagraj	Prayagraj	80	29.3
7	42 MLD STP, Naini 2	Prayagraj	42	38.7
8	50 MLD STP, Numayadhai, Prayagraj	Prayagraj	50	44.3
9	14 MLD STP Phaphamau Prayagraj	Prayagraj	14	27.9
10	7 MLD, STP, Vindhyachal,	Mirzapur	7	39.3
11	80 MLD STP at Dinapur	Varanasi	80	40.9
12	50 MLD STP, Ramanna	Varanasi	50	15
13	140 MLD STP at Dinapur	Varanasi	140	14.6
14	Bhagwanpur, Varanasi	Varanasi	9.8	BDL<5
15	120 MLD STP at Goithaha	Varanasi	120	12.8
16	12 MLD BLW (former known as DLW)	Varanasi	12	15.4

- STPs non-complying to COD (≥ 50 mg/l) in Uttar Pradesh (April-July,2024) w.r.t. NGT norms

S. No.	Name of STPs	Ganga Front Town	Designed Capacity (MLD)	COD (≥ 50 mg/l)
1	24 MLD STP Bijnor, Near Hemraj Colony	Bijnor	24	51
2	Garhmukteshwar STP	Garhmukteshwar	6	125
3	Narora NAPS Township STP	Narora	2.25	698
4	Narora Town (4.0 MLD)	Narora	4	64
5	Anupsahar 1.5 MLD STP, Zone A	Anupshahr	1.5	113
6	Anupsahar 0.81 MLD STP, Zone A	Anupshahr	0.81	103
7	Anupsahar 1.75 MLD STP, Zone B	Anupshahr	1.75	118
8	Anupsahar 1.0 MLD STP, Zone B	Anupshahr	1	175
9	130 MLD Jajmau STP Kanpur	Kanpur	130	156
10	Jajmau (43 MLD) Kanpur	Kanpur	43	168
11	Bingawan (210 MLD) STP, Kanpur	Kanpur	210	109
12	30 MLD STP at Pankha	Kanpur	30	126
13	Sajari STP, Kanpur	Kanpur	42	91.1
14	Bithoor (80 KLD) STP	Bithoor	0.08	68.6
15	10 MLD STP, Ponghat, Prayagraj	Prayagraj	10	52.3
16	14 MLD STP Mirzapur (Pakka Pokhra)	Mirzapur	14	63.4
17	10 KLD FSTP Chunar, Mirzapur	Chunar	0.01	262
18	10 MLD STP, Ramnagar	Ramnagar, Varanasi	10	73.2
19	35 MLD STP Plant, Sarai Talfi, Bareilly, U.P.	Bareilly	35	115

• STPs complying to TSS (≤ 20 mg/l) in Uttar Pradesh (April-July, 2024) w.r.t. NGT and MoEF&CC norms

S. No.	Name of STPs	Ganga Front Town	Designed Capacity (MLD)	TSS (≤ 20 mg/l)
1.	24 MLD STP Bijnor, Near Hemraj Colony	Bijnor	24	BDL
2.	Brajghat (03 MLD) STP	Garhmukteshwar	3	BDL
3.	Narora NAPS Township STP	Narora	2.25	16
4.	Anupsahar 0.81 MLD STP, Zone A	Anupshahr	0.81	18
5.	Bingawan (210 MLD) STP, Kanpur	Kanpur	210	16.8
6.	Sajari STP, Kanpur	Kanpur	42	13.8
7.	Bithoor (80 KLD) STP	Bithoor	0.08	11.8
8.	29 MLD STP, Salori, Prayagraj	Prayagraj	29	16.7
9.	Salori (Bakshi Bandh) 14 MLD Prayagraj	Prayagraj	14	2.53
10.	60 MLD STP, Rajapur, Prayagraj	Prayagraj	60	9.27
11.	25 MLD STP, Kodra, Prayagraj	Prayagraj	25	3.3

S. No.	Name of STPs	Ganga Front Town	Designed Capacity (MLD)	TSS (≤ 20 mg/l)
12.	80 MLD STP , Nani, Prayagraj	Prayagraj	80	12.5
13.	50 MLD STP , Numayadhai, Prayagraj	Prayagraj	50	10.1
14.	14 MLD STP Phaphamau Prayagraj	Prayagraj	14	6.34
15.	14 MLD STP Mirzapur (Pakka Pokhra)	Mirzapur	14	8.35
16.	7 MLD, STP, Vindhyachal,	Mirzapur	7	2.93
17.	80 MLD STP at Dinapur	Varanasi	80	7.75
18.	50 MLD STP, Ramanna	Varanasi	50	12.6
19.	140 MLD STP at Dinapur	Varanasi	140	4
20.	Bhagwanpur, Varanasi	Varanasi	9.8	3.6
21.	120 MLD STP at Goithaha	Varanasi	120	2.6
22.	12 MLD BLW (former known as DLW)	Varanasi	12	9.8

- STPs complying to TSS (20 mg/l - 100 mg/l) in Uttar Pradesh (April-July,2024) w.r.t. MoEF&CC norms

S. No.	Name of STPs	Ganga Front Town	Designed Capacity (MLD)	TSS (20 mg/l - 100 mg/l)
1.	Narora Town (4.0 MLD)	Narora	4	23
2.	Anupsahar 1.5 MLD STP, Zone A	Anupshahr	1.5	48
3.	Anupsahar 1.75 MLD STP, Zone B	Anupshahr	1.75	34
4.	Anupsahar 1.0 MLD STP, Zone B	Anupshahr	1	25
5.	130 MLD Jajmau STP Kanpur	Kanpur	130	64
6.	30 MLD STP at Pankha	Kanpur	30	37.2
7.	10 MLD STP , Ponghat, Prayagraj	Prayagraj	10	38.6
8.	42 MLD STP, Naini 2	Prayagraj	42	24.8
9.	10 KLD FSTP Chunar, Mirzapur	Chunar	0.01	67.7
10.	10 MLD STP, Ramnagar	Ramnagar, Varanasi	10	66.2
11.	35 MLD STP Plant, Sarai Talfi, Bareilly	Bareilly	35	75.2

- STPs non-complying to TSS (≥ 100 mg/l) in Uttar Pradesh (April-July,2024) w.r.t. MoEF&CC norms

S. No.	Name of STPs	Ganga Front Town	Designed Capacity (MLD)	TSS (≥ 100 mg/l)
1	Garhmukteshwar STP	Garhmukteshwar	6	170
2	Jajmau (43 MLD) Kanpur	Kanpur	43	118

- STPs complying to FC (≤ 230 MPN/100 ml) in Uttar Pradesh (April-July,2024) w.r.t. NGT and MoEF&CC norms

S. No.	Name of STPs	Ganga Front Town	Designed Capacity	FC (≤ 230 MPN/100 ml)
1	Garhmukteshwar STP	Garhmukteshwar	6	BDL

S. No.	Name of STPs	Ganga Front Town	Designed Capacity	FC (≤ 230 MPN/100 ml)
2	Sajari STP, Kanpur	Kanpur	42	<1.8
3	Salori (Bakshi Bandh) 14 MLD Prayagraj	Prayagraj	14	<1.8
4	60 MLD STP, Rajapur, Prayagraj	Prayagraj	60	<1.8
5	10 MLD STP, Ponghat, Prayagraj	Prayagraj	10	<1.8
6	25 MLD STP, Kodra, Prayagraj	Prayagraj	25	<1.8
7	14 MLD STP Phaphamau Prayagraj	Prayagraj	14	<1.8
8	80 MLD STP at Dinapur	Varanasi	80	<1.8
9	50 MLD STP, Ramanna	Varanasi	50	<1.8
10	140 MLD STP at Dinapur	Varanasi	140	<1.8
11	10 MLD STP, Ramnagar	Ramnagar, Varanasi	10	<1.8
12	12 MLD BLW (former known as DLW)	Varanasi	12	<1.8

- STPs complying to FC (230 - 1000 MPN/100 ml) in Uttar Pradesh (April-July,2024) w.r.t. MoEF&CC norms

S. No.	Name of STPs	Ganga Front Town	Designed Capacity (MLD)	FC (230 - 1000 MPN/100 ml)
1	Brajghat (03 MLD) STP	Garhmukteshwar	3	490

- STPs non-complying to FC (≥ 1000 MPN/100 ml) in Uttar Pradesh (April-July,2024) w.r.t. MoEF&CC norms

S. No.	Name of STPs	Ganga Front Town	Designed Capacity (MLD)	FC (≥ 1000 MPN/100 ml)
1.	24 MLD STP Bijnor, Near Hemraj Colony	Bijnor	24	13×10^2
2.	Narora NAPS Township STP	Narora	2.25	24×10^4
3.	Narora Town (4.0 MLD)	Narora	4	13×10^5
4.	Anupsahar 1.5 MLD STP, Zone A	Anupshahr	1.5	79×10^6
5.	Anupsahar 0.81 MLD STP, Zone A	Anupshahr	0.81	82×10^5
6.	Anupsahar 1.75 MLD STP, Zone B	Anupshahr	1.75	35×10^4
7.	Anupsahar 1.0 MLD STP, Zone B	Anupshahr	1	17×10^5
8.	130 MLD Jajmau STP Kanpur	Kanpur	130	2.2×10^6
9.	Jajmau (43 MLD) Kanpur	Kanpur	43	1.3×10^6
10.	Bingawan (210 MLD) STP, Kanpur	Kanpur	210	1.3×10^6
11.	30 MLD STP at Pankha	Kanpur	30	2.0×10^3
12.	Bithoor (80 KLD) STP	Bithoor	0.08	5.4×10^6
13.	29 MLD STP, Salori, Prayagraj	Prayagraj	29	1.3×10^4
14.	80 MLD STP, Nani, Prayagraj	Prayagraj	80	17000
15.	42 MLD STP, Naini 2	Prayagraj	42	11000

S. No.	Name of STPs	Ganga Front Town	Designed Capacity (MLD)	FC (≥ 1000 MPN/100 ml)
16.	50 MLD STP , Numayadhai, Prayagraj	Prayagraj	50	2000
17.	14 MLD STP Mirzapur (Pakka Pokhra)	Mirzapur	14	2.0×10^3
18.	7 MLD, STP, Vindhyachal,	Mirzapur	7	7×10^5
19.	10 KLD FSTP Chunar, Mirzapur	Chunar	0.01	3.4×10^5
20.	Bhagwanpur, Varanasi	Varanasi	9.8	7.9×10^4
21.	120 MLD STP at Goithaha	Varanasi	120	1.3×10^5
22.	35 MLD STP Plant, Sarai Talfi, Bareilly, U.P.	Bareilly	35	4.9×10^5

- STPs having Disinfection system

S. No.	Name of STPs/CETPs	Ganga Front Town	Designed Capacity (MLD)	Disinfection Technology
1	24 MLD STP Bijnor, Near Hemraj Colony	Bijnor	24	Chlorination
2	Brajghat (03 MLD) STP	Garhmukteshwar	3	Chlorination
3	Garhmukteshwar STP	Garhmukteshwar	6	Chlorination
4	Narora NAPS Township STP	Narora	2.25	Chlorination
5	Narora Town (4.0 MLD)	Narora	4	Chlorination
6	Anupsahar 1.5 MLD STP, Zone A	Anupshahr	1.5	Chlorination
7	Anupsahar 0.81 MLD STP, Zone A	Anupshahr	0.81	Chlorination
8	Anupsahar 1.75 MLD STP, Zone B	Anupshahr	1.75	Chlorination
9	Anupsahar 1.0 MLD STP, Zone B	Anupshahr	1	Chlorination
10	130 MLD Jajmau STP Kanpur	Kanpur	130	Chlorination
11	Jajmau (43 MLD) Kanpur	Kanpur	43	Chlorination
12	Bingawan (210 MLD) STP, Kanpur	Kanpur	210	Chlorination
13	30 MLD STP at Pankha	Kanpur	30	Chlorination
14	Sajari STP, Kanpur	Kanpur	42	Chlorination
15	29 MLD STP , Salori, Prayagraj	Prayagraj	29	Chlorination
16	Salori (Bakshi Bandh) 14 MLD Prayagraj	Prayagraj	14	Chlorination

17	60 MLD STP, Rajapur, Prayagraj	Prayagraj	60	Chlorination
18	10 MLD STP, Ponghat, Prayagraj	Prayagraj	10	Chlorination
19	25 MLD STP, Kodra, Prayagraj	Prayagraj	25	Chlorination
20	80 MLD STP, Nani, Prayagraj	Prayagraj	80	Chlorination
21	42 MLD STP, Naini 2	Prayagraj	42	Chlorination
22	50 MLD STP, Numayadhai, Prayagraj	Prayagraj	50	Chlorination
23	14 MLD STP Phaphamau Prayagraj	Prayagraj	14	Chlorination
24	16 MLD STP, Jhunsi	Prayagraj	16	Chlorination
25	14 MLD STP Mirzapur (Pakka Pokhra)	Mirzapur	14	Chlorination
26	7 MLD, STP, Vindhyachal,	Mirzapur	7	Chlorination
27	80 MLD STP at Dinapur	Varanasi	80	Chlorination
28	50 MLD STP, Ramanna	Varanasi	50	Chlorination
29	140 MLD STP at Dinapur	Varanasi	140	Chlorination
30	10 MLD STP, Ramnagar	Ramnagar, Varanasi	10	Chlorination
31	Bhagwanpur, Varanasi	Varanasi	9.8	Chlorination
32	120 MLD STP at Goithaha	Varanasi	120	UV
33	12 MLD BLW (former known as DLW)	Varanasi	12	Chlorination
34	35 MLD STP Plant, Sarai Talfi, Bareilly, U.P.	Bareilly	35	UV chamber

• **STPs working below capacity (75% of designed capacity)**

S. No.	Name of STPs	Ganga Front Town	Treatment Technology	Designed Capacity (MLD)	Utilized capacity (MLD)	Compliance Status w.r.t Hon'ble NGT norms dated 30.4.2019	Compliance w.r.t. MoEF norms dtd 13.10.2017
1.	Brajghat (03 MLD) STP	Garhmukteshwar	UASB	3	1.54	Non-complying	Complying
2.	Garhmukteshwar STP	Garhmukteshwar	UASB	6	3.45	Non-complying	Non-complying
3.	Narora NAPS Township STP	Narora	ASP	2.25	1.15	Non-complying	Non-complying
4.	Narora Town (4.0 MLD)	Narora	SBR	4	0.975	Non-complying	Non-complying

S. No.	Name of STPs	Ganga Front Town	Treatment Technology	Designed Capacity (MLD)	Utilized capacity (MLD)	Compliance Status w.r.t Hon'ble NGT norms dated 30.4.2019	Compliance w.r.t. MoEF norms dtd 13.10.2017
5.	Bingawan (210 MLD) STP, Kanpur	Kanpur	UASB	210	135	Non-complying	Non-complying
6.	30 MLD STP at Pankha	Kanpur	SBR	30	21.74	Non-complying	Non-complying
7.	Sajari STP, Kanpur	Kanpur	ASP	42	21.86	Non-complying	Complying
8.	14 MLD STP Mirzapur (Pakka Pokhra)	Mirzapur	UASB	14	10.01	Non-complying	Non-complying
9.	7 MLD, STP, Vindhyachal,	Mirzapur	SBR	7	3.321	Non-complying	Non-complying
10.	10 KLD FSTP Chunar, Mirzapur	Chunar	FSTP	0.01	0.003	Non-complying	Non-complying
11.	120 MLD STP at Goithaha	Varanasi	SBR	120	53	Non-complying	Non-complying
12.	12 MLD BLW (former known as DLW)	Varanasi	ASP	12	3.16	Non-complying	Complying
13.	35 MLD STP Plant, Sarai Talfi, Bareilly, U.P.	Bareilly	Extended Aeration	35	20.42	Non-complying	Non-complying

• **STPs working over capacity**

S. No.	Name of STPs/CETPs	Ganga Front Town	Treatment Technology	Designed Capacity (MLD)	Utilized capacity (MLD)	Compliance Status w.r.t Hon'ble NGT norms dated 30.4.2019	Compliance w.r.t. MoEF norms dtd 13.10.2017
1	Anupsahar 1.5 MLD STP, Zone A	Anupshahr	MBBR	1.5	2.1	Non-complying	Non-complying
2	Anupsahar 0.81 MLD STP, Zone A	Anupshahr	WSP	0.81	0.86	Non-complying	Non-complying
3	Anupsahar 1.75 MLD STP, Zone B	Anupshahr	WSP	1.75	2.48	Non-complying	Non-complying
4	Jajmau (43 MLD) Kanpur	Kanpur	ASP	43	44.78	Non-complying	Non-complying
5	29 MLD STP, Salori, Prayagraj	Prayagraj	FAB reactor	29	36.93	Non-complying	Non-complying

S. No.	Name of STPs/CETPs	Ganga Front Town	Treatment Technology	Designed Capacity (MLD)	Utilized capacity (MLD)	Compliance Status w.r.t Hon'ble NGT norms dated 30.4.2019	Compliance w.r.t. MoEF norms dtd 13.10.2017
6	60 MLD STP, Rajapur, Prayagraj	Prayagraj	UASB	60	74.23	Non-complying	Complying
7	10 MLD STP, Ponghat, Prayagraj	Prayagraj	BTT followed by ASP	10	13.42	Non-complying	Complying
8	25 MLD STP, Kodra, Prayagraj	Prayagraj	BTT followed by ASP	25	29	Non-complying	Complying
9	80 MLD STP, Nani, Prayagraj	Prayagraj	ASP	80	98.96	Non-complying	Non-complying
10	50 MLD STP, Numayadhai, Prayagraj	Prayagraj	BTT followed by ASP	50	55.5	Non-complying	Non-complying
11	14 MLD STP Phaphamau Prayagraj	Prayagraj	FCR	14	16.89	Non-complying	Complying
12	80 MLD STP at Dinapur	Varanasi	TF & ASP	80	85.73	Non-complying	Complying
13	Bhagwanpur, Varanasi	Varanasi	ASP	9.8	10.07	Non-complying	Non-complying

- Under-construction / Under Trial STPs

S. No.	Name of STPs/CETPs	Ganga Front Town	Treatment Technology	Designed Capacity (MLD)	Date of Monitoring	Under Construction/ Under Trial/ DPR
1.	20 MLD STP Chaubari Drain,	Bareilly	SBR	20	14.05.2024	Under trial
2.	42 MLD STP, Harunagla	Bareilly	SBR	42	13.05.2024	Under trial
3.	01 MLD STP Tatarpur Village	Bareilly	SBR	1	13.05.2024	Under trial
4.	30 MLD STP, near Bhaioghat Temple,	Farrukhabad	SBR	30	15.05.2024	Under construction
5.	17.7 MLD STP, Fatehgarh	Farrukhabad	SBR	17.7	15.05.2024	Under construction
6.	Ballia-19.6 MLD STP,	Ballia	SBR	20	05.06.2024	Under construction
7.	Dakari-15 MLD, STP	Unnao	SBR	15	16.05.2024	running under trial
8.	8.5 MLD, STP, Visundarpur Drain	Mirzapur	SBR	8.5	29.05.2024	Under construction
9.	8.5 MLD, New STP, Pakka Pokhra	Mirzapur	SBR	8.5	29.05.2024	Under construction
10.	Shuklaganj-05 MLD STP, Unnao	Unnao	SBR	5	25.04.2024	Under construction
11.	15 MLD STP, Baniyapur	Kanpur	SBR	15	11.01.2024	Non-operational

NGT Standards: Compliance based on norms prescribed by Hon'ble NGT vide order dt 30.04.2019 in the matter of OA no. 1069/2018 (pH – 5.5-9.0, BOD <10mg/l, TSS< 20mg/l, COD< 50mg/l; Faecal Coliform – desirable <100MPN/100ml & permissible < 230 MPN/100 ml, Nitrogen-Total < 10 mg/l and Phosphorous-Total < 1.0 mg/l (TP compliance for discharge into ponds and lakes).

Compliance compared with MoEF&CC notification dt. 13.10.2017: Standard for treated sewage from STPs for cities other than metro cities, state capitals and union territories were notified as pH-6.5-9.0, BOD as 30mg/L, Total suspended solids (TSS) as less than 100mg/L and Faecal coliform as less than 1000MPN per 100mL.

Water quality data of river Ganga 2024 (Jan-Oct) (Median) -Uttar Pradesh

Si. No.	Station Code	Station name	pH	DO (mg/l)	BOD (mg/l)	FC (MPN/100 ml)	FS (MPN/100 ml)
1.	10150	MADHYA GANGA BARRAGE (BIJNOR)	7.8	9.1	1.2	490	1.8
2.	5707	NANDAUR NEAR HASTINAPUR	7.4	8.8	1.6	610	-
3.	5708	TIGRI GANGA GHAT, AMROHA	7.8	8.9	1.3	700	1.8
4.	10149	U/S BRIJGHAT, GARHMUKTESHWAR	7.4	10.4	2.1	350	170
5.	1062	BRIJGHAT D/S, GHARMUKTESHWAR	7.4	10.3	2.4	690	240
6.	2488	U/S ANOOPSHAHAR	7.2	8.6	2.1	390	-
7.	2489	ANOOPSHAHAR D/S	7.2	8.8	2.0	315	-
8.	1145	NARORA (BULANDSAHAR)	7.2	8.7	2.0	540	-
9.	2490	KACHHLA GHAT (ALIGARH)	7.7	9.9	1.4	320	1.8
10.	10151	FARRUKHABAD	8.3	7.8	3.2	2250	3.6
11.	1063	U/S KANNAUJ (RAJGHAT)	8.3	7.5	3.6	2600	1.8
12.	1066	KANNAUJ D/S	8.3	7.4	3.8	2950	2.9
13.	5709	NANAMAU GANGA BRIDGE , KANPUR	8.2	7.6	3.7	3600	30
14.	1146	BITHOOR (KANPUR)	8.4	7.5	3.5	3250	27
15.	1067	U/S KANPUR (RANIGHAT)	8.4	8.0	3.5	3400	3.6
16.	10154	U/s SHUKLAGANJ	8.4	7.6	3.7	3550	54
17.	10155	SHUKLAGANJ D/S	8.3	7.8	3.8	3400	5.5
18.	10156	BATHING GHAT (GOLA GHAT)	8.3	7.5	4.1	3500	2.8
19.	10157	BATHING GHAT (JAJMAU BRIDGE)	8.3	7.6	4.2	6300	25
20.	1068	KANPUR D/S (JAJMAU PUMPING STATION)	8.3	7.0	4.5	10200	6.1
21.	5710	PURANA RAJAPUR, KANPUR	8.3	7.4	4.1	7900	7.6
22.	5711	A/C PANDU RIVER, DEOMAI	8.1	8.6	2.5	645	-
23.	5712	MATA GANGA BRIDGE, FATEHPUR	-	-	-	-	-
24.	1147	DALMAU (RAI BAREILLY)	8.0	8.4	3.0	1250	14
25.	2498	KALA KANKAR (PRATAPGARH)	8.2	8.5	2.9	1100	13.5
26.	2487	KADAGHAT (KAUSHAMBI)	8.2	8.5	2.8	680	-
27.	5713	DHEEMI, PRATAPGARH	8.1	8.7	2.7	1015	12.5
28.	1046	PRAYAGRAJ (RASOOLABAD)	8.2	8.5	2.8	680	-
29.	1049	PRAYAGRAJ D/S (SANGAM)	8.1	8.5	2.8	845	-

Si. No.	Station Code	Station name	pH	DO (mg/l)	BOD (mg/l)	FC (MPN/100 ml)	FS (MPN/100 ml)
30.	5714	B/C TAMSA RIVER AT PRACHIN SHIVALAYA DUMDUMA GHAT	8.2	8.6	2.7	605	-
31.	10158	A/C TAMAS RIVER (SIRSA)	8.1	8.5	2.7	645	-
32.	2485	U/S, VINDHYACHAL (MIRZAPUR)	8.0	7.7	2.5	790	460
33.	2486	D/S, MIRZAPUR	7.7	7.0	3.6	8400	3450
34.	10153	CHUNAR	7.9	7.3	3.2	6050	3100
35.	1070	U/S VARANASI (VISHWA SUNDARI BRIDGE)	8.2	7.7	2.4	700	335
36.	1071	VARANASI D/S (MALVIYA BRIDGE)	7.8	7.0	3.5	7900	3450
37.	5715	B/C GOMTI RIVER AT BALUA GHAT BRIDGE, VARANASI	7.9	7.3	3.3	6050	3200
38.	10152	A/C GOMTI RIVER (BHUSAULA)	7.9	7.3	3.1	4900	2650
39.	5716	U/S GHAZIPUR, ZAMANIA	8.0	7.6	2.9	3800	2000
40.	1073	TARIGHAT (GHAZIPUR)	7.8	6.8	3.7	9400	4750
41.	5717	BALLIA D/S AT BEYASI BALLIA BRIDGE	-	-	-	-	-