

**BEFORE THE NATIONAL GREEN TRIBUNAL
PRINCIPAL BENCH, NEW DELHI
ORIGINAL APPLICATION NO. 1060/2024**

IN THE MATTER OF:

SWAMI GURUCHARAN MISHRA

...APPLICANT

VERSUS

UNION OF INDIA & ORS.

...RESPONDENT(s)

INDEX

S. NO.	PARTICULARS	PAGE NO.
1.	RESPONSE ON BEHALF OF RESPONDENT NO. 3 STATE OF U.P. IN COMPLIANCE OF ORDER DATED 16.04.2025 PASSED BY THE HON'BLE NATIONAL GREEN TRIBUNAL, PRINCIPAL BENCH, NEW DELHI	
2.	A COPY OF THE ANALYSIS REPORT IS ANNEXED HEREWITH AND MARKED AS ANNEXURE-1	
3.	A COPY OF THE REPORT OF NATIONAL WATER QUALITY MONITORING PROGRAMME IS ANNEXED HEREWITH AND MARKED AS ANNEXURE-2	
4.	A COPY OF THE REPORT BY THE SMCG IS ANNEXED HEREWITH AND MARKED AS ANNEXURE-3	

THROUGH COUNSEL

A handwritten signature in black ink, appearing to read 'Bpsjadon', with a long horizontal stroke extending to the right.

BHANWAR LAL SINGH JADON
STANDING COUNSEL FOR THE STATE OF U.P.
bhanwar09jadon@gmail.com | 6375115224

DATE: 12.01.2026
PLACE: NOIDA

**BEFORE THE NATIONAL GREEN TRIBUNAL
PRINCIPAL BENCH, NEW DELHI
ORIGINAL APPLICATION NO. 1060/2024**

**IN THE MATTER OF:
SWAMI GURUCHARAN MISHRA**

...APPLICANT

VERSUS

UNION OF INDIA & ORS.

...RESPONDENT(s)

**RESPONSE ON BEHALF OF RESPONDENT NO. 3 STATE OF U.P. IN
COMPLIANCE OF ORDER DATED 16.04.2025 PASSED BY THE
HON'BLE NATIONAL GREEN TRIBUNAL, PRINCIPAL BENCH, NEW
DELHI**

I, JOGINDER SINGH , aged about 36 years, S/o Shri Vijay Singh, Posted as Project director, SMCG, U.P., do hereby most solemnly state and affirm as under:

That I, the Deponent, am fully conversant with the facts of the case and am competent and authorized to swear the present Affidavit.

1. That the present original application has been filed by the Applicant raising the issue of pollution of River Ganga. Learned counsel for the applicant had approached the Hon'ble Supreme Court by Writ Petition Civil No. 1373/2023 under Article 32 of the constitution and the Hon'ble Supreme Court had expressed that it was not inclined to entertain such a petition directly. Hence, the petitioner has been relegated to this Tribunal and the Writ Petition has been disposed of the by the Hon'ble Supreme Court.

2. That the present affidavit is being filed to place on record a comprehensive and updated status report of policies, schemes, projects, programmes and achievements undertaken under the **Namami Gange Programme** in the State of Uttar Pradesh, for the purpose of ensuring the cleanliness, ecological restoration, and uninterrupted flow of the River Ganga and its tributaries.
3. That the Hon'ble Tribunal vide order dated 16.04.2025 directed the respondents to file their reply.

ACTIONS TAKEN TO CURB THE POLLUTION OF RIVER GANGA

ARE AS BELOW:

4. That in the State of UP, the sewage generated, at present, is approximately **5,500 MLD**. That for the treatment of the sewage generated, total of 158 STPs having the combined capacity of approximately 4772.60 MLD have been established by the State. Out of these 158 established STPs, 3 are in Trial and Run Stage.
5. That out of the total 158 established STPs, 54 STPs have been established under SMCG having a total capacity of 1933.43 MLD. Furthermore, at



present, 21 STPs having a combined capacity of 1064.10 MLD are under construction. Additionally, 12 STPs having the capacity of 453 MLD are under the stage of work order issuance/tendering.

6. The current status of Sewage related projects in the state of Uttar Pradesh funded by NMCG is shown below.


Sl. No.	Details of projects	Number of projects
1	Ongoing	21
2	Under Tendering Stage	12
3	Completed	41
	Total Projects	74

7. That upon completion of all the above mentioned STPs, a total capacity of 2424.80 MLD of STP (#86) shall be available in the State through Namami Gange program.

INDUSTRIAL EFFLUENT TREATMENT PROJECTS

8. That it is submitted before the Hon'ble Tribunal that five (05) industrial effluent treatment projects were approved at Kanpur, Unnao, Banthar, Mathura and Gorakhpur. Their location and status are as follows:

LOCATION	STATUS
Mathura Industrial Area	Completed as on October, 2022
Kanpur (Jajmau Tannery Cluster)	Completed and operational, as on August, 2024



Banthar	70% work completed, to be completed by March, 2026
Unnao	Contract execution in progress
Gorakhpur CETP	Revised DPR submitted to NMCG

RIVER WATER QUALITY MONITORING AND IMPROVEMENT

9. That the Uttar Pradesh Pollution Control Board regularly conducts river water quality monitoring at 41 identified locations as per prescribed protocols. The parameters tested include DO, BOD, COD, TSS, Faecal Coliform, Total Coliform, and reports are regularly uploaded on the official portal.

A copy of the analysis report is annexed herewith and marked as ANNEXURE-1.

10. That Real-Time/Continuous Water Quality Monitoring Stations have been installed by CPCB at multiple locations, including Phaphamau (Prayagraj), Balua Ghat Bridge (Mirzapur) and downstream locations in Ghazipur, besides 12 other locations across the State.

11. That 1,294 OCEMS have been installed on grossly polluting industries and are subject to continuous monitoring by the UP PCB and CPCB.




12. That under the National Water Quality Monitoring Programme, samples collected in November, 2025 from 41 locations indicated DO levels ranging between 7.00 to 10.40 ppm, and BOD levels ranging between 1.10 to 3.6 ppm.

A copy of the report of National Water Quality Monitoring Programme for Month of **November 2025** is annexed herewith and marked as **ANNEXURE-2**.

**BIODIVERSITY, WETLANDS AND ECOLOGICAL
CONSERVATION**

13. That 275 wetlands have been identified along the Ganga, out of which 231 Integrated Wetland Management Plans have been prepared. Further, 40 high-priority wetlands are under the process of notification by State Wetland Authority-UP.


14. That programmes for conservation of Ganga Dolphin are being implemented, and as per the 2022 WII Census, 2,397 dolphins were recorded in Uttar Pradesh, the highest among all Ganga basin States.



15. That 07 Ganga Biodiversity Parks are being established at Mirzapur, Bulandshahr, Badaun, Hapur, Bijnor, Ayodhya and Pratapgarh.
16. That large-scale plantation has been undertaken under CAMPA, Namami Gange and other schemes, including plantation of 31.84 crore trees in Ganga districts and 2.26 crore trees within 10 km of the Ganga riverbank in the last four years, by State Forest Department-UP.

**REUSE OF TREATED WATER AND SMALL RIVER
REJUVENATION**

24. That reuse of treated water is being promoted for thermal power plants, railways, irrigation and horticulture, and a State Policy on Reuse of Treated Water has been drafted and the policy is currently under formulation.
25. That for rejuvenation of small rivers, works are being undertaken by the state under the concept of "One District, One River", covering rivers such as Gomti, Varuna, Kali East, Chhoti Gandak, Tamsa and others.



**PUBLIC AWARENESS, COMMUNITY PARTICIPATION AND ARTH
GANGA**

26. That extensive IEC and public awareness activities have been conducted, including Swachhata Pakhwada, Ganga Utsav, Mission LiFE campaigns, exhibitions, seminars, river dialogues, radio and digital campaigns.
27. That during Mahakumbh-2025, over 50,000 sq. ft. area was painted under the Paint My City Campaign, exhibitions were organised, and 1,500 Ganga Doots were deployed for sanitation monitoring.
28. That the concept of "Arth Ganga" is being implemented through inter-departmental coordination to integrate river conservation with agriculture, tourism, fisheries, education, culture, rural development and urban planning.
17. That it is submitted before the Hon'ble Tribunal that the SMCG is continuously taking requisite actions required to ensure that untreated water is discharged into the River Ganga and causing pollution. Several projects by the SMCG are under progress and are expected to be completed expeditiously.




A copy of the report by the SMCG is annexed herewith and marked as
ANNEXURE-3.


FUTURE ACTION PLAN

18. That the timeline of the STPs are as stated bellow:

Sl. No.	District / Town	River	Name of the Project	Date of Completion as per C.B. / Extended	No. of Drains to be Tapped	Proposed STP Capacity (MLD)
01	Agra / Agra	Yamuna	Rehabilitation / Renovation of Agra Sewerage Scheme (I&D works) (HAM) including 15 years O&M	Feb - 2026	23	177.60 (13 no.)
02	Chhata / Mathura	Yamuna	I & D works for Chhata, Distt. Mathura (DBOT)	Aug - 2026	11	06
03	Mathura / Vrindavan	Yamuna	I & D of Vrindavan town (Chaitanya Vihar, Kosi Drain 1/3) at Distt. Mathura (DBOT)	Mar - 2026	02	13
04	Shamli / Banat Town	Krishni	I & D works for Banat Town Drain at Distt. Shamli (DBOT)	Apr - 2026	02	05
05	Shamli / Babri-Bantikhera	Krishni	I & D works for Babri-Bantikhera Village Drain at Distt. Shamli (DBOT)	Apr - 2026	04	05
06	Shamli / Shamli	Krishni	I & D works for Shamli Town Drain at Distt. Shamli (DBOT)	Apr - 2026	01	40
07	Shamli / Thanabhawan	Krishni	I & D works for Thanabhawan Town Drain at Distt. Shamli (DBOT)	Apr - 2026	03	10



Sl. No.	District / Town	River	Name of the Project	Date of Completion as per C.B. / Extended	No. of Drains to be Tapped	Proposed STP Capacity (MLD)
08	Hapur / Hapur	Kali	I & D & STP works at District Hapur (DBOT)	May - 2026	01	06
09	Hathras / Hathras	Karwan / Yamuna	I & D and STP works at Hathras (DBOT)	June - 2026	10	24
10	Mathura / Kosi Kalan	Yamuna	I & D works for Kosi Kalan NP at Distt. Mathura (DBOT)	July - 2026	01	12
11	Meerut / Meerut	Kali	Pollution Abatement works for River Kali at Meerut Town (HAM)	Nov - 2026	02	220
12	Varanasi / Varanasi	Ganga	I & D of Assi Nala and additional construction of STP at Ramna, Varanasi (DBOT)	Dec - 2025	02	55 (STP ready)
13	Unnao / Shuklaganj	Ganga	I & D and STP works at Shuklaganj, Distt. Unnao (HAM) including 15 years O&M	Dec - 2025	05	05 (STP ready)
14	Unnao / Unnao	Ganga	I & D and STP works at Unnao (HAM) including 15 years O&M	Dec - 2025	01	(*1 no.) (STP ready)
15	Prayagraj / Prayagraj	Ganga	I & D of 13 drains and augmentation of Salori STP at Prayagraj (DBOT)	Feb - 2026	13	43
16	Prayagraj / Prayagraj	Ganga	I & D of 7 drains and augmentation of Rajapur STP at Prayagraj (DBOT)	Feb - 2026	07	90
17	Prayagraj / Prayagraj	Yamuna	I & D of 02 drains and augmentation of Naini-2 STP at Prayagraj (DBOT)	July - 2026	02	50
18	Mathura / Mathura	Yamuna	I & D works of balance drains at Distt. Mathura (HAM)	Nov - 2026	04	60




Sl. No.	District / Town	River	Name of the Project	Date of Completion as per C.B. / Extended	No. of Drains to be Tapped	Proposed STP Capacity (MLD)
19	Lucknow / Lucknow	Gomti	I & D and STP works at Lucknow (DBOT) including 15 years O&M	Feb - 2026 (for 3.5 MLD)	03	42.50 (2 no.) (*1 no.)
20	Lucknow / Lucknow	Gomti	I & D and STP works at Lucknow, Phase-II, Part-I (DBOT)	Mar -- 2026	03	50
21	Saharanpur / Saharanpur	Hindan	I & D and STP works at Saharanpur (HAM)	Oct - 2027	61	135
Total					161	1010.10 (32 no.)

19.Hence, the present affidavit is being filed for the kind consideration and perusal of this Hon'ble Tribunal.

20.I state that everything stated above has been stated by me in my official capacity on and derived from the official records and I state that nothing material has been concealed therefrom.


DEPONENT
 राज्य स्वच्छ गंगा मिशन-उ०प्र०
 लखनऊ



Verified at Lucknow on this 12th day of JANUARY, 2026,
that the contents of the above affidavit from paragraphs 1 to 20 are believed
to be true and correct to the best of my knowledge and belief. No part of it is
false and nothing material has been concealed therefrom.


DEPONENT

परियोजना निदेशक
राज्य स्वच्छ गंगा मिशन-उ०प्र०
लखनऊ



ATTESTED
K.P. YADAV
NOTARY PUBLIC

12 JAN 2026

Operational Status of Sewage Treatment Plants			
S.No	Total Installed STPs	Month: October 2025	Operational STPs
1	156	First Week	144
		Second Week	143
		Third Week	143
		Last Week	141

Note :-

The standards as per MoEF&CC Notification dated 13.10.2017, titled "A

For State Capital: pH-6.5-9.0; BOD - <20 mg/l; TSS- <50 mg/l & FC- <10

Other than State Capital: pH-6.5-9.0; BOD - <30 mg/l; TSS- <100 mg/l &

Water Treatment Plants (STPs) in Uttar Pradesh

STPs Achieving Norms	STPs Not Achieving Norms	STP Not in Operation	Under Trial Run	Total STPs
140	4	8	4	156
139	4	9	4	156
139	4	9	4	156
138	3	11	4	156

Applicable Effluent Discharge Standards for STPs" are as follows:

000 MPN/100 ml

z FC- <1000 MPN/100 ml

Performance of Existing STPs in U.P. OCTOBER- 2025																			
WEEKLY DATA OF STPs																			
Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Utilized Capacity (MLD)	Technology / process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Rural (R)/Urban(U)/Other(O)	Sampling Period	Date of Sampling	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100 ml)	FC (MPN/100 ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)	
1	10.445 MLD STP near Tixi Tempel (Karanpur)	2001	Etawah	10.445	8	WSP	UP Jal Nigam	R	1st Week	08.10.2025	Grab	8.2	28	130	48	12000	930	Achieving	
									2nd Week	14.10.2025	Grab	8	26	150	47	9400	910	Achieving	
									3rd Week	24.10.2025	Grab	8.1	27	160	57	11000	920	Achieving	
									4th Week	28.10.2025	Grab	7.8	28	160	47	12000	930	Achieving	
2	21 MLD STP Etawah	2022	Etawah	21	20	SBR	UP Jal Nigam	R	1st Week	08.10.2025	Grab	7.8	9	60	8	8400	780	Achieving	
									2nd Week	14.10.2025	Grab	8.2	8.8	60	9	7900	780	Achieving	
									3rd Week	24.10.2025	Grab	7.8	9.2	40	7	7000	680	Achieving	
									4th Week	28.10.2025	Grab	8	12	60	11	9400	810	Achieving	
3	13.5 MLD STP at Mauja Umrain	2013	Etawah	13.5	12.5	SBR	UP Jal Nigam	R	1st Week	08/10/2025	Grab	8	25	140	43	11000	910	Achieving	
									2nd Week	14.10.2025	Grab	7.8	24	120	46	8400	820	Achieving	
									3rd Week	24.10.2025	Grab	8	22	110	38	7900	830	Achieving	
									4th Week	28.10.2025	-	Not operational Due to Maintenance Work							
4	03 MLD STP Firozabad	2014	Firozabad	3	1.4	UASB	Nagar Palika Parishad	O	1st Week	08.10.2025	Grab	8.5	26	150	40	12000	920	Achieving	
									2nd Week	13.10.2025	Grab	8.1	27	170	43	11000	830	Achieving	
									3rd Week	24.10.2025	Grab	7.9	24	140	46	9400	810	Achieving	
									4th Week	29.10.2025	Grab	7.9	21	110	39	8400	830	Achieving	
5	67 MLD STP Mohammadpur, Biharipur	2020	Firozabad	67	52	ASP+ extended aeration	U.P. Jal Nigam	U	1st Week	08.10.2025	Grab	7.9	14	80	13	9400	810	Achieving	
									2nd Week	13.10.2025	Grab	7.9	8.4	60	9	8400	780	Achieving	
									3rd Week	24.10.2025	Grab	7.8	9.6	70	8	7000	610	Achieving	
									4th Week	29.10.2025	Grab	7.8	10.4	80	11	7900	680	Achieving	
6	1.65 MLD STP Saifai (Paramedicals)	2013	Etawah	1.65	0.9	SBR	Nagar Palika Parishad	O	1st Week	08.10.2025	Grab	8	23	120	38	9400	810	Achieving	
									2nd Week	14.10.2025	Grab	7.9	25	140	36	9400	830	Achieving	
									3rd Week	24.10.2025	Grab	7.7	22	120	35	8400	910	Achieving	
									4th Week	28.10.2025	Grab	7.9	18	80	17	7900	780	Achieving	
7	23 MLD STP at Mauja Odenya, Padaria	2014	Mainpuri	23	17	UASB	U.P. Jal Nigam	U	1st Week	06.10.2025	Grab	8	26	160	44	11000	920	Achieving	
									2nd Week	13.10.2025	Grab	7.9	24	140	40	9400	830	Achieving	
									3rd Week	24.10.2025	Grab	7.8	23	130	41	7900	780	Achieving	
									4th Week	27.10.2025	Grab	7.7	26	160	45	11000	920	Achieving	
8	1.5 MLD STP Saifai Village, Etawah	2006	Etawah	1.5	1.1	Oxidation Pond	U.P. Jal Nigam	U	1st Week	08.10.2025	Grab	8.2	26	150	42	11000	910	Achieving	
									2nd Week	14.10.2025	Grab	8	27	170	47	12000	930	Achieving	
									3rd Week	24.10.2025	Grab	7.9	25	140	42	9400	910	Achieving	
									4th Week	28.10.2025	Grab	8.1	28	170	48	11000	920	Achieving	
9	26 MLD STP Jhansi Laxmi Taal	2021	Jhansi	(22+4) 26	22	SBR	U.P. Jal Nigam	U	1st Week	03.10.2025	Grab	6.92	21	104.76	16	4100	1200	Not Achieving	
									2nd Week	09.10.2025	Composite	7.29	25.6	42.68	12	-	-	-	Achieving
									3rd Week	17.10.2025	Grab	7.67	26	106.92	12	3400	930	Achieving	
									4th Week	24.10.2025	Grab	7.36	27	51.48	13	3400	920	Achieving	
									5th Week	31.10.2025	Grab	7.18	9.5	15.84	11	3400	830	Achieving	
9	26 MLD STP Jhansi Laxmi Taal	2021	Jhansi	(22+4) 26	4	SBR	U.P. Jal Nigam	U	1st Week	03.10.2025	Grab	7.26	17	77.6	12	3400	910	Achieving	
									2nd Week	09.10.2025	Composite	7.12	22.5	72.96	10	-	-	-	Achieving
									3rd Week	17.10.2025	Grab	7.45	23	75.24	11	3400	920	Achieving	
									4th Week	24.10.2025	Grab	7.21	21	67.32	11	3400	910	Achieving	
									5th Week	31.10.2025	Grab	6.89	19	31.68	10	3400	810	Achieving	
10	26 MLD STP Smart City, Lahargird	2025	Jhansi	26	26	SBR	Nagar Nigam	O	1st Week	03.10.2025	Grab	7.23	22.5	151.32	12	3400	930	Achieving	
									2nd Week	09.10.2025	Composite	7.4	20.95	34.92	10	-	-	-	Achieving
									3rd Week	14.10.2025	Grab	7.58	28.5	49.92	11	3400	930	Achieving	
									4th Week	25.10.2025	Grab	7.34	28	63.36	13	3400	910	Achieving	
									5th Week	30.10.2025	Grab	7.39	21	233.64	11	3400	930	Achieving	
11	3.42 MLD STP Near Divyang kendra	2000	Chitrakoot	3.42	3.42	Oxidation Pond	Nagar Palika Parishad	O	1st Week	13.10.2025	Grab	7.94	27.5	128.04	19	3400	920	Achieving	
									2nd Week	13.10.2025	Grab	7.94	27.5	128.04	19	3400	920	Achieving	
									3rd Week	28.10.2025	Grab	7.89	28.51	47.52	16	1800	680	Achieving	
									4th Week	28.10.2025	Grab	7.89	28.51	47.52	16	1800	680	Achieving	
12	42 MLD STP,	2016-17	Kannur Nagar	42	22	ASP	U.P. Jal Nigam	R	1st Week	07.10.2025	Grab	7.72	22.5	150	48	270	140	Achieving	
									2nd Week	14.10.2025	Grab	7.71	21	140	52	-	-	-	Achieving

	Sajari Kanpur	2010-17	Kanpur Nagar	210	110	UASB	U.P. Jal Nigam	R	3rd Week	21.10.2025	Grab	7.77	22.5	150	54	-	-	Achieving
									4th Week	28.10.2025	Grab	7.75	24	160	50	-	-	Achieving
13	210 MLD STP, Bingawan Kanpur	2015-16	Kanpur Nagar	210	110	UASB	U.P. Jal Nigam	R	1st Week	07.10.2025	Grab	7.69	36	170	68	81000	61000	Not Achieving
									2nd Week	14.10.2025	Grab	7.7	39	180	64	-	-	Not Achieving
									3rd Week	21.10.2025	Grab	7.76	40.5	190	64	-	-	Not Achieving
									4th Week	28.10.2025	Grab	7.73	60	200	58	-	-	Not Achieving
14	130 MLD STP Jajmau, Kanpur	1998-99	Kanpur Nagar	130	115	ASP	U.P. Jal Nigam	R	1st Week	07.10.2025	Grab	7.75	18	160	56	1400	320	Achieving
									2nd Week	14.10.2025	Grab	7.73	19.5	170	62	-	-	Achieving
									3rd Week	21.10.2025	Grab	7.79	21	180	62	-	-	Achieving
									4th Week	28.10.2025	Grab	7.82	18	190	58	-	-	Achieving
15	43 MLD STP Jajmau, Kanpur	2020	Kanpur Nagar	43	40	UASB	U.P. Jal Nigam	R	1st Week	07.10.2025	Grab	7.78	16.5	140	52	1400	320	Achieving
									2nd Week	14.10.2025	Grab	7.89	18	150	48	-	-	Achieving
									3rd Week	21.10.2025	Grab	7.94	18	160	56	-	-	Achieving
									4th Week	28.10.2025	Grab	7.98	19.5	170	54	-	-	Achieving
16	13 MLD STP Jalalpur, Amrapur, Kannauj	2017	Kanpur Dehat	13	12	SBR	U.P. Jal Nigam	U	1st Week	01.10.2025	Grab	7.6	18	100	52	330	270	Achieving
									2nd Week	07.10.2025	Grab	7.7	22.5	110	54	380	260	Achieving
									3rd Week	14.10.2025	Grab	7.4	24	120	57	-	-	Achieving
									4th Week	28.10.2025	Grab	7.6	25.5	130	52	-	-	Achieving
17	30 MLD STP Pankha, Kanpur	2023	Kanpur Nagar	30	30	SBR	U.P. Jal Nigam	R	1st Week	07.10.2025	Grab	7.62	21	140	52	250	150	Achieving
									2nd Week	14.10.2025	Grab	7.64	19.5	130	44	-	-	Achieving
									3rd Week	21.10.2025	Grab	7.7	24	120	46	-	-	Achieving
									4th Week	28.10.2025	Grab	7.74	22.5	130	42	-	-	Achieving
18	36 MLD STP Jajmau, Kanpur	9+27 MLD (1992) = 36 MLD (2024)	Kanpur Nagar	36	25	UASB	U.P. Jal Nigam	U	1st Week	07.10.2025	Grab	7.85	40.5	180	62	84000	63000	Not Achieving
									2nd Week	14.10.2025	Grab	7.88	39	170	60	-	-	Not Achieving
									3rd Week	21.10.2025	Grab	7.93	42	190	66	-	-	Not Achieving
									4th Week	28.10.2025	Grab	7.96	39	180	68	-	-	Not Achieving
19	17.7 MLD STP Fatehgarh, Farrukhabad	2024	Kanpur Nagar	17.7	17.7	SBR	U.P. Jal Nigam	R	1st Week	07.10.2025	Grab	7.95	24	130	52	790	490	Not Achieving
									2nd Week	14.10.2025	Grab	7.93	18	140	62	-	-	Achieving
									3rd Week	21.10.2025	Grab	7.98	19.5	160	50	-	-	Achieving
									4th Week	28.10.2025	Grab	7.99	21	150	56	-	-	Achieving
20	30 MLD STP Farrukhabad	2024	Kanpur Nagar	30	30	SBR	U.P. Jal Nigam	R	1st Week	07.10.2025	Grab	7.86	18	130	54	810	600	Achieving
									2nd Week	14.10.2025	Grab	7.85	42.5	160	58	-	-	Not Achieving
									3rd Week	21.10.2025	Grab	7.91	21	170	64	-	-	Achieving
									4th Week	28.10.2025	Grab	7.94	18	180	60	-	-	Achieving
21	50 MLD STP Numayadahi	2013	Prayagraj	50	50	HRBF	Ganga Pollution control unit, U.P. Jal Nigam	R	1st Week	07.10.2025	Grab	7.51	25.4	72	67	22000	780	Achieving
									2nd Week	13.10.2025	Grab	7.11	24.8	64	56	2300	780	Achieving
									3rd Week	25.10.2025	Composite	7.86	24.8	60	58	-	-	Achieving
									4th Week	29.10.2025	Grab	7.38	24	60	50	2100	780	Achieving
22	10 MLD STP Ponghat	2013	Prayagraj	10	10	HRBF	Ganga Pollution control unit, U.P. Jal Nigam	R	1st Week	07.10.2025	Grab	7.68	22.8	48	41	1400	610	Achieving
									2nd Week	13.10.2025	Grab	7.03	22	40	32	1700	700	Achieving
									3rd Week	25.10.2025	Composite	7.9	24.2	52	50	-	-	Achieving
									4th Week	29.10.2025	Grab	7.28	23.5	56	54	1400	610	Achieving
23	25 MLD STP Kodra	2013	Prayagraj	25	25	HRBF	Ganga Pollution control unit, U.P. Jal Nigam	R	1st Week	07.10.2025	Grab	7.78	24	64	58	2000	680	Achieving
									2nd Week	13.10.2025	Grab	7.13	23.6	60	50	2100	780	Achieving
									3rd Week	25.10.2025	Composite	7.8	23.7	48	35	-	-	Achieving
									4th Week	29.10.2025	Grab	7.06	23.4	52	45	2000	610	Achieving
24	60 MLD STP Rajapur	2013	Prayagraj	60	60	UASB	Ganga Pollution control unit, U.P. Jal Nigam	R	1st Week	07.10.2025	Grab	7.74	27.2	92	76	2700	930	Achieving
									2nd Week	14.10.2025	Grab	7.26	27.4	88	72	2400	930	Achieving
									3rd Week	18.10.2025	Composite	7.6	28.6	92	74	-	-	Achieving
									4th Week	29.10.2025	Grab	7.21	28.6	80	78	2600	930	Achieving
25	29 MLD STP Salori-1	2007	Prayagraj	29	29	FAB	Ganga Pollution control unit, U.P. Jal Nigam	R	1st Week	07.10.2025	Grab	7.72	26.5	80	70	2400	920	Achieving
									2nd Week	14.10.2025	Grab	7.31	26.2	76	64	2600	930	Achieving
									3rd Week	17.10.2025	Composite	6.98	26.9	64	60	-	-	Achieving
									4th Week	29.10.2025	Grab	7.16	26.6	68	66	2400	920	Achieving
26	14 MLD STP Salori-2 Expansion	2016	Prayagraj	14	14	SBR	Ganga Pollution control unit, U.P. Jal Nigam	U	1st Week	07.10.2025	Grab	7.66	19	40	32	1700	610	Achieving
									2nd Week	14.10.2025	Grab	7.09	17.6	32	22	1700	610	Achieving
									3rd Week	17.10.2025	Composite	7.08	20.6	40	33	-	-	Achieving
									4th Week	29.10.2025	Grab	7.06	20.4	48	36	1700	680	Achieving
27	80 MLD STP Naini	2013	Prayagraj	80	80	ASP	Ganga Pollution control unit, U.P. Jal Nigam	R	1st Week	07.10.2025	Grab	7.81	27	88	73	2600	920	Achieving
									2nd Week	13.10.2025	Grab	7.39	26.8	84	68	2400	920	Achieving
									3rd Week	17.10.2025	Composite	6.94	27.8	80	68	-	-	Achieving
									4th Week	29.10.2025	Grab	7.02	26.8	64	75	2100	920	Achieving
28	42 MLD STP, Naini	2023	Prayagraj	42	36	FCR	U.P. Jal Nigam	R	1st Week	07.10.2025	Grab	7.63	24.9	68	63	2100	780	Achieving
									2nd Week	13.10.2025	Grab	7.21	25.2	72	64	2200	680	Achieving
									3rd Week	17.10.2025	Composite	7.09	23	56	50	-	-	Achieving

									4th Week	29.10.2025	Grab	7.34	24.2	60	48	2000	680	Achieving
									1st Week	07.10.2025	Grab	7.59	23.2	56	49	1700	700	Achieving
									2nd Week	14.10.2025	Grab	7.15	23	52	42	2000	610	Achieving
									3rd Week	18.10.2025	Composite	7.37	24.2	72	52	-	-	Achieving
									4th Week	29.10.2025	Grab	7.39	24.5	76	56	1700	610	Achieving
									1st Week	07.10.2025	-	-	-	-	-	-	-	Not operational Due to Maintenance Work
									2nd Week	14.10.2025	-	-	-	-	-	-	-	Not operational Due to Maintenance Work
									3rd Week	18.10.2025	-	-	-	-	-	-	-	Not operational Due to Maintenance Work
									4th Week	29.10.2025	-	-	-	-	-	-	-	Not operational Due to Maintenance Work
									1st Week	30.09.2025	Grab	7.64	12.2	60	24	540	170	Achieving
									2nd Week	10.10.2025	Grab	7.6	14.4	68	18	430	220	Achieving
									3rd Week	16.10.2025	Grab	7.48	16.8	74	22	280	130	Achieving
									4th Week	25.10.2025	Grab	7.43	14.4	78	16	630	230	Achieving
									1st Week	01.10.2025	Grab	7.69	28.4	166	96	540	220	Achieving
									2nd Week	10.10.2025	Grab	7.56	29	172	92	430	170	Achieving
									3rd Week	16.10.2025	Grab	7.53	26.9	158	84	630	230	Achieving
									4th Week	25.10.2025	Grab	7.62	24.2	142	88	430	220	Achieving
									1st Week	30.09.2025	Grab	7.59	28.9	172	92	840	630	Achieving
									2nd Week	10.10.2025	Grab	7.52	26.2	144	86	920	240	Achieving
									3rd Week	16.10.2025	Grab	7.58	27.3	158	86	630	230	Achieving
									4th Week	25.10.2025	Grab	7.47	28.4	162	92	430	220	Achieving
									1st Week	01.10.2025	Grab	7.42	9.4	46	14	350	130	Achieving
									2nd Week	10.10.2025	Grab	7.64	8.2	40	18	250	130	Achieving
									3rd Week	16.10.2025	Grab	7.72	13.6	42	16	430	220	Achieving
									4th Week	25.10.2025	Grab	7.68	12.8	40	14	390	220	Achieving
									1st Week	01.10.2025	Grab	7.54	8.8	44	16	430	170	Achieving
									2nd Week	10.10.2025	Grab	7.62	8.4	40.8	16	430	150	Achieving
									3rd Week	16.10.2025	Grab	7.61	12.2	38	14	430	170	Achieving
									4th Week	25.10.2025	Grab	7.52	15.4	44	18	310	170	Achieving
									1st Week	30.09.2025	Grab	7.43	36.2	180	90	820	610	Not Achieving
									2nd Week	10.10.2025	Grab	7.36	26.2	194	96	840	330	Achieving
									3rd Week	16.10.2025	Grab	7.42	29.2	184	84	350	140	Achieving
									4th Week	25.10.2025	Grab	7.51	28.1	178	90	250	130	Achieving
									1st Week	30.09.2025	-	-	-	-	-	-	-	Not operational Due to Maintenance Work
									2nd Week	10.10.2025	-	-	-	-	-	-	-	Not operational Due to Maintenance Work
									3rd Week	16.10.2025	-	-	-	-	-	-	-	Not operational Due to Maintenance Work
									4th Week	25.10.2025	Grab	7.34	20.2	108	34	840	330	Achieving
									1st Week	30.09.2025	Grab	7.66	8	36	6.2	390	220	Achieving
									2nd Week	09.10.2025	Grab	7.69	7.6	42	8.4	310	170	Achieving
									3rd Week	16.10.2025	Grab	7.58	7.3	38	8	350	130	Achieving
									4th Week	25.10.2025	Grab	7.56	9.4	46	7	250	130	Achieving
									1st Week	28.10.2025	Grab	7.58	8.2	46	18	430	220	Achieving
									2nd Week	28.10.2025	Grab	7.58	8.2	46	18	430	220	Achieving
									3rd Week	28.10.2025	Grab	7.58	8.2	46	18	430	220	Achieving
									4th Week	28.10.2025	Grab	7.58	8.2	46	18	430	220	Achieving
									1st Week	28.10.2025	Grab	7.46	28.2	142	48	1100	790	Achieving
									2nd Week	28.10.2025	Grab	7.46	28.2	142	48	1100	790	Achieving
									3rd Week	28.10.2025	Grab	7.46	28.2	142	48	1100	790	Achieving
									4th Week	28.10.2025	Grab	7.46	28.2	142	48	1100	790	Achieving
									1st Week	28.10.2025	Grab	7.52	8.6	44	16	350	170	Achieving
									2nd Week	28.10.2025	Grab	7.52	8.6	44	16	350	170	Achieving
									3rd Week	28.10.2025	Grab	7.52	8.6	44	16	350	170	Achieving
									4th Week	28.10.2025	Grab	7.52	8.6	44	16	350	170	Achieving
									1st Week	28.10.2025	Grab	7.62	8	40	18	280	130	Achieving
									2nd Week	28.10.2025	Grab	7.62	8	40	18	280	130	Achieving
									3rd Week	28.10.2025	Grab	7.62	8	40	18	280	130	Achieving
									4th Week	28.10.2025	Grab	7.62	8	40	18	280	130	Achieving
									1st Week	08.10.2025	Grab	7.71	8.5	36	25	2000	820	Achieving
									2nd Week	14.10.2025	Grab	7.98	8	32	22	1700	780	Achieving
									3rd Week	21.10.2025	Grab	7.7	7.5	24	25	2100	910	Achieving
									4th Week	28.10.2025	Grab	7.58	8.5	36	27	2100	930	Achieving
									1st Week	08.10.2025	Grab	7.71	8.5	36	25	2000	820	Achieving
									2nd Week	14.10.2025	Grab	7.98	8	32	22	1700	780	Achieving
									3rd Week	21.10.2025	Grab	7.7	7.5	24	25	2100	910	Achieving
									4th Week	28.10.2025	Grab	7.58	8.5	36	27	2100	930	Achieving

45	30 MLD S.T.P. Opp. Manyavar Kanshiram Shabri Garib Awaz Yojna,	2015	Gorakhpur	30	19.83	SBR	U.P. Jal Nigam	U	1st Week	08.10.2025	Grab	7.82	8	32	22	2100	910	Achieving
									2nd Week	14.10.2025	Grab	7.64	9	40	27	2000	930	Achieving
									3rd Week	21.10.2025	Grab	7.6	7	28	27	1700	780	Achieving
									4th Week	28.10.2025	Grab	7.61	9	42	25	1700	780	Achieving
46	10 MLD STP Gorakhpur	2024	Gorakhpur	10	10	SBR	U.P. Jal Nigam	U	1st Week	14.10.2025	Grab	7.9	8.5	36	25	2100	910	Achieving
									2nd Week	14.10.2025	Grab	7.9	8.5	36	25	2100	910	Achieving
									3rd Week	21.10.2025	Grab	7.65	8	32	22	2000	930	Achieving
									4th Week	28.10.2025	Grab	7.64	8	40	26	2000	920	Achieving
47	8 MLD STP Azamgarh	2024	Azamgarh	8	0	SBR	U.P. Jal Nigam	U	1st Week	01.10.2025	-	Under Trial Run						
									2nd Week	10.10.2025	-	Under Trial Run						
									3rd Week	16.10.2025	-	Under Trial Run						
									4th Week	25.10.2025	-	Under Trial Run						
48	38 MLD STP, Mahilpur Road	1998	Saharanpur	38	38	UASB	U.P. Jal Nigam	U	1st Week	08.10.2025	Grab	7.3	24	172	40	660	320	Achieving
									2nd Week	14.10.2025	Grab	7.4	25	180	42	690	320	Achieving
									3rd Week	21.10.2025	Grab	7.5	26	188	45	720	660	Achieving
									4th Week	28.10.2025	Grab	7.5	25	184	44	660	210	Achieving
49	6.5 MLD STP Awaz vikas Parishad STP	2018	Lucknow	6.5	6.5	SBR	Jal Kal	O	1st Week	08.10.2025	Grab	7.3	18	90	48	4900	930	Achieving
									2nd Week	16.10.2025	Grab	7.35	16	70	38	7000	780	Achieving
									3rd Week	24.10.2025	Grab	7.25	17	76	42	3900	920	Achieving
									4th Week	31.10.2025	-	Not operational Due to Maintenance Work						
50	37.5 MLD STP Awaz vikas Parishad STP	2017	Lucknow	37.5	37.5	SBR	U.P. Awaz vikas Parishad	O	1st Week	08.10.2025	Grab	7.43	12	56	38	4000	610	Achieving
									2nd Week	16.10.2025	Grab	7.42	14	48	30	4900	680	Achieving
									3rd Week	24.10.2025	Grab	7.33	15	74	32	4000	610	Achieving
									4th Week	31.10.2025	Grab	7.5	13	68	33	2600	780	Achieving
51	345 MLD STP, Bharwara	2011	Lucknow	345	345	UASB	U.P. Jal Nigam	U	1st Week	08.10.2025	Grab	7.5	16	74	45	4900	780	Achieving
									2nd Week	16.10.2025	Grab	7.36	18	82	48	3200	930	Achieving
									3rd Week	24.10.2025	Grab	7.11	17	88	47	5400	940	Achieving
									4th Week	31.10.2025	Grab	7.37	18	94	46	2000	920	Achieving
53	56 MLD STP, Daulatganj	2003 & 2009	Lucknow	56 (42+14)	56	FAB	U.P. Jal Nigam	U	1st Week	09.10.2025	Grab	7.38	17	98	46	7000	780	Achieving
									2nd Week	15.10.2025	Grab	7.39	16	108	47	9400	920	Achieving
									3rd Week	24.10.2025	Grab	7.33	18	92	48	7000	930	Achieving
									4th Week	31.10.2025	Grab	7.49	16	85	47	3500	940	Achieving
54	1.5 MLD STP Hathi Park, (Smart City)	2021	Lucknow	1.5	1.5	MBBR	Nagar Nigam (Smart City)	O	1st Week	09.10.2025	Grab	7.29	17	82	46	3400	450	Achieving
									2nd Week	15.10.2025	-	Not operational Due to Maintenance Work						
									3rd Week	24.10.2025	-	Not operational Due to Maintenance Work						
									4th Week	31.10.2025	-	Not operational Due to Maintenance Work						
55	39 MLD STP, Sajjadbah, Daulatganj	2024	Lucknow	39	39	SBR	U.P. Jal Nigam	R	1st Week	09.10.2025	Grab	7.53	14	62	40	2200	680	Achieving
									2nd Week	15.10.2025	Grab	7.35	13	66	28	3400	450	Achieving
									3rd Week	24.10.2025	Grab	7.32	11	57	30	3200	610	Achieving
									4th Week	31.10.2025	Grab	7.65	12	59	38	3400	680	Achieving
56	120 MLD STP near 1090 Chauraha	2025	Lucknow	120	80	SBR	U.P. Jal Nigam	U	1st Week	08.10.2025	Grab	7.32	13	66	44	4600	780	Achieving
									2nd Week	15.10.2025	Grab	7.31	12	64	24	2600	610	Achieving
									3rd Week	24.10.2025	Grab	7.38	14	72	34	3900	780	Achieving
									4th Week	31.10.2025	Grab	7.52	13	68	42	2200	700	Achieving
57	19 MLD STP C.G. City, Lucknow	2023	Lucknow	19	0	SBR	LDA	O	1st Week	09.10.2025	-	Not operational Due to Maintenance Work						
									2nd Week	15.10.2025	-	Not operational Due to Maintenance Work						
									3rd Week	24.10.2025	-	Not operational Due to Maintenance Work						
									4th Week	31.10.2025	-	Not operational Due to Maintenance Work						
58	56 MLD STP Trans Hindon (Indirapuram), Ghaziabad	2000	Ghaziabad	56	56	UASB	U.P. Jal Nigam	U	1st Week	8.10.2025	Grab	7.42	18	86	42	2100	610	Achieving
									2nd Week	15.10.2025	Grab	7.63	24	92	55	2800	790	Achieving
									3rd Week	25.10.2025	Grab	7.55	22	88	50	2400	780	Achieving
									4th Week	30.10.2025	Grab	7.46	16	76	40	2200	790	Achieving
59	30 MLD STP, Sadullabad (Loni), Ghaziabad	2012	Ghaziabad	30	20	MBBR	U.P. Jal Nigam	U	1st Week	3.10.2025	Grab	7.53	9	78	10	1600	540	Achieving
									2nd Week	14.10.2025	Grab	7.42	8	66	9	2500	780	Achieving
									3rd Week	24.10.2025	Grab	7.57	9	74	10	1600	920	Achieving
									4th Week	30.10.2025	Grab	7.48	8	62	9	2100	780	Achieving
60	74 MLD STP S.B.R., Indirapuram, Ghaziabad	2013	Ghaziabad	74	74	SBR	U.P. Jal Nigam	U	1st Week	8.10.2025	Grab	7.55	9	80	10	2200	400	Achieving
									2nd Week	15.10.2025	Grab	7.51	8	68	9	1600	540	Achieving
									3rd Week	25.10.2025	Grab	7.58	9	82	10	1700	680	Achieving
									4th Week	30.10.2025	Grab	7.5	8	54	9	2000	610	Achieving
61	56 MLD STP S.B.R., Bapudham, Ghaziabad	2014	Ghaziabad	56	1.5	SBR	GDA	O	1st Week	3.10.2025	Grab	7.34	8	52	10	1100	400	Achieving
									2nd Week	13.10.2025	Grab	7.4	7	32	9	2100	780	Achieving
									3rd Week	24.10.2025	Grab	7.5	8	38	8	1600	280	Achieving
									4th Week	30.10.2025	Grab	7.53	7	28	9	1600	220	Achieving
	6 MLD STP Garh					UASB			1st Week	6.10.2025	Grab	7.41	8	40	10	2100	610	Achieving

62	Zone, Garhmukeshwar Hapur	2011	Hapur / Garhmukeshwar	6	4.62	followed by extended aeration	U.P. Jal Nigam (NGRBA)	R	2nd Week	13.10.2025	Grab	7.4	9	44	10	2700	680	Achieving
									3rd Week	24.10.2025	Grab	7.44	7	36	8	3400	610	Achieving
									4th Week	27.10.2025	Grab	7.52	8	42	9	1700	400	Achieving
									1st Week	6.10.2025	Grab	7.44	9	32	10	2500	450	Achieving
63	3 MLD STP Brijghat Zone, Garhmukeshwar Hapur	2011	Hapur / Garhmukeshwar	3	2.57	UASB followed by extended aeration	U.P. Jal Nigam (NGRBA)	R	2nd Week	13.10.2025	Grab	7.52	8	38	9	1700	680	Achieving
									3rd Week	24.10.2025	Grab	7.56	9	40	10	2100	400	Achieving
									4th Week	27.10.2025	Grab	7.47	8	42	9	1700	400	Achieving
									1st Week	8.10.2025	Grab	7.5	7	42	9	2800	790	Achieving
64	56 MLD STP , Indirapuram, (GDA), Ghaziabad	2012	Ghaziabad	56	20	SBR	Nagar Nigam	O	2nd Week	15.10.2025	Grab	7.54	9	60	10	1600	540	Achieving
									3rd Week	25.10.2025	Grab	7.48	8	44	9	1400	790	Achieving
									4th Week	30.10.2025	Grab	7.6	7	38	8	1600	540	Achieving
									1st Week	8.10.2025	Grab	7.38	9	64	10	2500	830	Achieving
65	56 MLD STP S.B.R., Dudahaida Vijay Nagar, Ghaziabad	2013	Ghaziabad	56	56	SBR	U.P. Jal Nigam	U	2nd Week	15.10.2025	Grab	7.45	8	60	9	2700	680	Achieving
									3rd Week	25.10.2025	Grab	7.56	9	52	10	1600	540	Achieving
									4th Week	30.10.2025	Grab	7.48	7	36	9	2200	400	Achieving
									1st Week	8.10.2025	Grab	7.76	22	94	40	2100	930	Achieving
66	70 MLD STP U.A.S.B.R. Dudahaida Vijay Nagar, Ghaziabad	2000	Ghaziabad	70	70	UASB	U.P. Jal Nigam	U	2nd Week	15.10.2025	Grab	7.57	20	98	45	3200	920	Achieving
									3rd Week	25.10.2025	Grab	7.65	26	90	49	2200	790	Achieving
									4th Week	30.10.2025	Grab	7.68	18	80	42	1600	540	Achieving
									1st Week	6.10.2025	Grab	7.44	20	76	45	1600	920	Achieving
67	3 MLD STP Palkhaun	2015	Ghaziabad	3	2.57	UASB	U.P. Jal Nigam	U	2nd Week	13.10.2025	Grab	7.46	16	64	40	2200	450	Achieving
									3rd Week	22.10.2025	Grab	7.4	18	72	47	2100	780	Achieving
									4th Week	27.10.2025	Grab	7.57	12	68	35	2000	610	Achieving
									1st Week	3.10.2025	Grab	7.58	10	96	42	2200	400	Achieving
68	5 MLD STP Trans Delhi Signature City (Tronica City), Loni	2019	Ghaziabad	5	3.81	MBBR	UPSIDA	O	2nd Week	14.10.2025	Grab	7.45	16	118	50	1400	610	Achieving
									3rd Week	24.10.2025	Grab	7.5	12	92	42	1600	540	Achieving
									4th Week	30.10.2025	Grab	7.42	14	78	40	2500	830	Achieving
									1st Week	3.10.2025	Grab	7.62	8	60	9	1600	540	Achieving
69	56 MLD STP S.B.R. Govindpuram, Ghaziabad	2014	Ghaziabad	56	14	SBR	GDA	O	2nd Week	13.10.2025	Grab	7.49	9	56	10	2200	450	Achieving
									3rd Week	24.10.2025	Grab	7.4	8	40	9	1600	350	Achieving
									4th Week	30.10.2025	Grab	7.45	9	48	10	2200	400	Achieving
									1st Week	3.10.2025	Grab	7.5	16	86	45	2400	780	Achieving
70	20 MLD STP Modinagar	2023	Modinagar, Ghaziabad	20	7.8	SBR	U.P. Jal Nigam	U	2nd Week	14.10.2025	Grab	7.44	10	78	39	2200	400	Achieving
									3rd Week	24.10.2025	Grab	7.55	14	80	35	2100	830	Achieving
									4th Week	29.10.2025	Grab	7.9	18	96	50	2100	610	Achieving
									1st Week	8.10.2025	Grab	7.43	14	70	43	1700	400	Achieving
71	56 MLD STP S.B.R., Morty, Ghaziabad	2018	Ghaziabad	56	27	SBR	Nagar Nigam	O	2nd Week	15.10.2025	Grab	7.54	12	80	35	2200	790	Achieving
									3rd Week	25.10.2025	Grab	7.47	9	76	10	2700	680	Achieving
									4th Week	30.10.2025	Grab	7.58	12	88	22	3500	790	Achieving
									1st Week	6.10.2025	Grab	7.64	18	136	50	2200	790	Achieving
72	30 MLD STP, Rampur Road, Hapur	2022	Hapur, Ghaziabad	30	8	SBR	U.P. Jal Nigam	U	2nd Week	13.10.2025	Grab	7.49	14	122	48	2000	610	Achieving
									3rd Week	22.10.2025	Grab	7.5	16	118	55	2200	450	Achieving
									4th Week	27.10.2025	Grab	7.44	20	120	50	2500	830	Achieving
									1st Week	8.10.2025	Grab	7.65	14	80	37	1600	540	Achieving
73	21.5 MLD STP Siddharthvihar, Ghaziabad	2024	Ghaziabad	21.5	4.5	SBR	Awass Vikas	O	2nd Week	15.10.2025	Grab	7.55	10	68	35	2500	780	Achieving
									3rd Week	25.10.2025	Grab	7.47	18	84	47	2000	610	Achieving
									4th Week	30.10.2025	Grab	7.44	14	76	38	2700	680	Achieving
									1st Week	04.10.2025	Grab	7.86	25	100	34	4800	680	Achieving
74	78 MLD STP Dhadhpura, Agra	2013	Agra	78	78	UASB	U.P. Jal Nigam	U	2nd Week	10.10.2025	Grab	7.86	26	120	44	4800	680	Achieving
									3rd Week	17.10.2025	Grab	7.84	24	130	48	5800	910	Achieving
									4th Week	25.10.2025	Grab	7.88	26	110	46	4600	920	Achieving
									1st Week	04.10.2025	Grab	7.88	28	120	40	6300	810	Achieving
75	2.25 MLD STP Budi ka Nagla, Agra	2000	Agra	2.25	2.25	WSP	U.P. Jal Nigam	U	2nd Week	10.10.2025	Grab	7.92	27	120	40	5800	910	Achieving
									3rd Week	17.10.2025	Grab	7.89	26	120	42	4800	680	Achieving
									4th Week	25.10.2025	Grab	7.95	27	100	38	5800	910	Achieving
									1st Week	04.10.2025	Grab	7.89	26	160	44	3400	930	Achieving
76	10 MLD STP Peelakhar, Agra	2000	Agra	10	10	WSP	U.P. Jal Nigam	U	2nd Week	10.10.2025	Grab	7.81	28	140	38	3400	930	Achieving
									3rd Week	17.10.2025	Grab	7.88	28	100	40	6300	810	Achieving
									4th Week	25.10.2025	Grab	7.92	26	120	42	5800	910	Achieving
									1st Week	04.10.2025	Grab	7.7	24	120	36	3800	910	Achieving
77	12 MLD STP Devri Road, (Bhimnagri), Agra	2011	Agra	12	8	UASB	U.P. Jal Nigam	U	2nd Week	10.10.2025	Grab	7.7	23	100	42	4800	680	Achieving
									3rd Week	17.10.2025	Grab	7.7	25	120	38	3400	930	Achieving
									4th Week	25.10.2025	Grab	7.76	28	130	46	6300	810	Achieving
									1st Week	04.10.2025	Grab	7.91	22	100	38	3400	930	Achieving
78	14 MLD STP	2011	Agra	14	14	UASB	U.P. Jal Nigam	U	2nd Week	10.10.2025	Grab	7.91	24	120	38	6300	810	Achieving

76	Sikandarpur, Agra	2011	Agra	40	28.5	UASB	U.P. Jal Nigam	U	3rd Week	17.10.2025	Grab	7.9	23	100	36	5800	910	Achieving
									4th Week	25.10.2025	Grab	7.91	28	140	40	3800	910	Achieving
79	40 MLD STP Sadarban, Bichhpuri, Agra	2013	Agra	40	28.5	UASB	U.P. Jal Nigam	U	1st Week	04.10.2025	Grab	7.92	28	140	48	3100	680	Achieving
									2nd Week	10.10.2025	Grab	7.98	28	130	48	6300	810	Achieving
									3rd Week	17.10.2025	Grab	7.84	28	100	46	3400	930	Achieving
									4th Week	25.10.2025	Grab	7.83	27	120	42	3400	930	Achieving
80	36 MLD STP Sadarwan (Bichpuri) New	2018	Agra	36	36	SBR	ADA	O	1st Week	04.10.2025	Grab	7.98	27	140	58	6300	810	Achieving
									2nd Week	10.10.2025	Grab	7.93	27	150	60	3100	680	Achieving
									3rd Week	17.10.2025	Grab	7.69	27	120	54	6300	810	Achieving
									4th Week	25.10.2025	Grab	7.84	28	140	64	3100	680	Achieving
81	24 MLD STP Dhadhpura (New), Agra	2014	Agra	24	15	UASB	U.P. Jal Nigam	U	1st Week	04.10.2025	Grab	7.83	24	120	34	4800	680	Achieving
									2nd Week	10.10.2025	Grab	7.89	25	100	36	3100	680	Achieving
									3rd Week	17.10.2025	Grab	7.81	21	90	30	3100	680	Achieving
									4th Week	25.10.2025	Grab	7.84	22	120	34	4800	680	Achieving
82	4.50 MLD STP Kalindi Vihar, Agra	2014	Agra	4.5	4.5	UASB	ADA	O	1st Week	04.10.2025	Grab	7.27	27	140	56	5800	910	Achieving
									2nd Week	10.10.2025	Grab	7.83	29	130	62	4800	680	Achieving
									3rd Week	17.10.2025	Grab	7.58	27	110	52	4800	680	Achieving
									4th Week	25.10.2025	-	Not operational Due to Maintenance Work						
83	03 MLD STP Pandav Nagar, Meerut	2013	Meerut	3	2.7	ASP	MDA	O	1st Week	04.10.2025	Grab	7.61	17	136	64	930	780	Achieving
									2nd Week	09.10.2025	Grab	7.51	20	180	52	930	830	Achieving
									3rd Week	16.10.2025	Grab	7.54	22	188	80	930	810	Achieving
									4th Week	24.10.2025	Grab	7.52	20	160	92	930	820	Achieving
									5th Week	31.10.2025	Grab	7.48	18	104	88	930	780	Achieving
84	07 MLD STP Pallavpuram-1, Meerut	2012	Meerut	7	6.5	ASP	MDA	O	1st Week	04.10.2025	Grab	7.38	15	92	40	830	610	Achieving
									2nd Week	09.10.2025	Grab	7.55	17	104	50	920	680	Achieving
									3rd Week	16.10.2025	Grab	7.55	14	88	44	830	610	Achieving
									4th Week	24.10.2025	Grab	7.51	14	88	48	830	680	Achieving
									5th Week	31.10.2025	Grab	7.42	16	94	50	820	600	Achieving
85	11 MLD STP Pallavpuram-2, Meerut	2008	Meerut	11	7	ASP	MDA	O	1st Week	04.10.2025	Grab	7.45	16	104	44	910	680	Achieving
									2nd Week	09.10.2025	Grab	7.38	15	68	48	830	610	Achieving
									3rd Week	16.10.2025	Grab	7.47	14	76	52	820	600	Achieving
									4th Week	24.10.2025	Grab	7.44	15	80	45	910	780	Achieving
									5th Week	31.10.2025	Grab	7.39	12	84	48	910	600	Achieving
86	06 MLD STP Rakshapuram, Meerut	2011	Meerut	6	4.4	ASP	MDA	O	1st Week	04.10.2025	Grab	7.56	16	112	56	910	680	Achieving
									2nd Week	09.10.2025	Grab	7.47	17	108	44	920	780	Achieving
									3rd Week	16.10.2025	Grab	7.39	18	136	58	930	810	Achieving
									4th Week	24.10.2025	Grab	7.46	16	120	62	920	680	Achieving
									5th Week	31.10.2025	Grab	7.52	15	120	55	820	560	Achieving
87	10 MLD STP Lohiya Nagar, Meerut	2010	Meerut	10	2	ASP	MDA	O	1st Week	04.10.2025	Grab	7.29	8	28	22	680	560	Achieving
									2nd Week	09.10.2025	Grab	7.39	8	24	20	780	550	Achieving
									3rd Week	16.10.2025	Grab	7.41	10	28	18	810	560	Achieving
									4th Week	24.10.2025	Grab	7.39	8	20	20	810	600	Achieving
									5th Week	31.10.2025	Grab	7.47	10	88	18	810	610	Achieving
88	15 MLD STP Shatabdinagar, Meerut	2010	Meerut	15	4.8	ASP	MDA	O	1st Week	04.10.2025	Grab	7.36	8	32	20	780	600	Achieving
									2nd Week	09.10.2025	Grab	7.41	8	28	18	810	560	Achieving
									3rd Week	16.10.2025	Grab	7.47	10	24	20	810	560	Achieving
									4th Week	24.10.2025	Grab	7.42	8	20	22	780	550	Achieving
									5th Week	31.10.2025	Grab	7.38	12	24	20	730	830	Achieving
89	15 MLD STP Vedvyasपुरी Meerut	2011	Meerut	15	4.5	ASP	MDA	O	1st Week	04.10.2025	Grab	7.43	12	36	28	780	600	Achieving
									2nd Week	09.10.2025	Grab	7.43	10	32	32	810	560	Achieving
									3rd Week	16.10.2025	Grab	7.41	12	28	24	810	600	Achieving
									4th Week	24.10.2025	Grab	7.38	10	24	26	610	780	Achieving
									5th Week	31.10.2025	Grab	7.39	10	28	24	830	810	Achieving
90	06 MLD STP Shradhapuri-1, Meerut	2012	Meerut	6	5.5	ASP	MDA	O	1st Week	04.10.2025	Grab	7.42	14	96	56	910	680	Achieving
									2nd Week	09.10.2025	Grab	7.44	16	82	46	920	780	Achieving
									3rd Week	16.10.2025	Grab	7.48	15	92	50	830	680	Achieving
									4th Week	24.10.2025	Grab	7.44	16	104	52	920	780	Achieving
									5th Week	31.10.2025	Grab	7.45	15	96	56	910	680	Achieving
91	06 MLD STP Sainik Vihar	2017	Meerut	6	5.95	UASB	MDA	O	1st Week	04.10.2025	Grab	7.42	10	36	20	780	600	Achieving
									2nd Week	09.10.2025	Grab	7.38	12	40	24	830	560	Achieving
									3rd Week	16.10.2025	Grab	7.44	10	32	22	810	600	Achieving
									4th Week	24.10.2025	Grab	7.38	12	24	24	830	610	Achieving
									5th Week	31.10.2025	Grab	7.43	14	64	22	820	680	Achieving
								1st Week	04.10.2025	Grab	7.33	14	72	32	830	610	Achieving	
								2nd Week	09.10.2025	Grab	7.54	15	84	36	910	680	Achieving	

92	5 MLD STP Modipuram Tiraha	2016	Meerut	5	4.9	ASP	MDA	O	3rd Week	16.10.2025	Grab	7.46	14	72	40	920	610	Achieving
									4th Week	24.10.2025	Grab	7.51	15	64	38	910	680	Achieving
									5th Week	31.10.2025	Grab	7.46	12	72	44	830	610	Achieving
93	07 MLD STP Sports Goods Complex, Meerut	2012	Meerut	7	4	ASP	MDA	O	1st Week	04.10.2025	Grab	7.41	16	100	48	920	780	Achieving
									2nd Week	09.10.2025	Grab	7.46	14	88	40	910	680	Achieving
									3rd Week	16.10.2025	Grab	7.51	16	96	44	920	780	Achieving
									4th Week	24.10.2025	Grab	7.51	14	88	48	830	680	Achieving
									5th Week	31.10.2025	Grab	7.42	16	94	50	820	600	Achieving
94	72 MLD STP Garh road (Jagrati vihar) Kamalpur	2018	Meerut	72	72	ASP	U.P. Jal Nigam	U	1st Week	09.10.2025	Grab	7.43	8	24	8	810	610	Achieving
									2nd Week	16.10.2025	Grab	7.37	9	28	10	820	600	Achieving
									3rd Week	24.10.2025	Grab	7.42	8	20	8	810	610	Achieving
									4th Week	31.10.2025	Grab	7.41	10	60	10	780	600	Achieving
95	10 MLD STP Ganga Nagar, Meerut	2011	Meerut	10	3.8	SBR	MDA	O	1st Week	04.10.2025	Grab	7.31	10	32	24	780	560	Achieving
									2nd Week	09.10.2025	Grab	7.41	8	28	22	810	560	Achieving
									3rd Week	16.10.2025	Grab	7.38	9	24	10	780	550	Achieving
									4th Week	24.10.2025	Grab	7.41	8	18	8	810	560	Achieving
									5th Week	31.10.2025	Grab	7.38	10	84	10	910	600	Achieving
96	06 MLD STP Shradhapuri- Phase-2, Meerut	2012	Meerut	6	5.6	SBR	MDA	O	1st Week	04.10.2025	Grab	7.52	17	112	50	930	830	Achieving
									2nd Week	09.10.2025	Grab	7.52	18	124	60	920	830	Achieving
									3rd Week	16.10.2025	Grab	7.53	17	132	56	930	820	Achieving
									4th Week	24.10.2025	Grab	7.52	18	140	60	930	780	Achieving
									5th Week	31.10.2025	Grab	7.51	16	120	52	810	780	Achieving
97	14 MLD STP Baghat, Meerut	2021	Baghat, Meerut	14	7.8	SBR	U.P. Jal Nigam	R	1st Week	04.10.2025	Grab	7.44	15	92	56	910	680	Achieving
									2nd Week	09.10.2025	Grab	7.39	22	188	44	930	830	Achieving
									3rd Week	13.10.2025	Grab	7.57	20	148	58	930	810	Achieving
									4th Week	24.10.2025	Grab	7.52	18	164	80	930	780	Achieving
									5th Week	31.10.2025	Grab	7.49	30	168	64	910	720	Not Achieving
98	32.5 MLD STP (WSP) Nagar Palika Parishad, Kidwai nagar	2001	Muzaffar Nagar	32.5	32.5	WSP	U.P. Jal Nigam	U	1st Week	08.10.2025	Grab	7.5	22	76	40	1700	840	Achieving
									2nd Week	14.10.2025	Grab	7.3	20	64	48	2100	700	Achieving
									3rd Week	21.10.2025	Grab	7.4	24	88	40	1700	680	Achieving
									4th Week	28.10.2025	Composite	7.6	22	76	38	-	-	Achieving
99	32.5 MLD STP Near A2Z Garbage plant KidwaiNagar	2025	Muzaffar Nagar	32.5	18.48	SBR	U.P. Jal Nigam	R	1st Week	08.10.2025	Grab	7.6	9	28	16	1100	210	Achieving
									2nd Week	14.10.2025	Grab	7.5	6	24	16	1400	110	Achieving
									3rd Week	21.10.2025	Composite	7.5	9	28	18	-	-	Achieving
									4th Week	28.10.2025	Grab	7.5	6	24	16	1300	140	Achieving
100	10 MLD STP Budhana	2024	Muzaffar Nagar	10	7.32	SBR	U.P. Jal Nigam	R	1st Week	08.10.2025	Grab	7.2	8	26	16	1100	130	Achieving
									2nd Week	14.10.2025	Grab	7.4	8	24	18	1700	140	Achieving
									3rd Week	21.10.2025	Grab	7.5	8	28	18	1300	110	Achieving
									4th Week	28.10.2025	Composite	7.5	9	28	16	-	-	Achieving
101	22 MLD STP Sahawali, Muzaffarnagar	2023	Muzaffar Nagar	22	21.18	SBR	U.P. Jal Nigam	R	1st Week	08.10.2025	Grab	7.4	7	24	14	1300	140	Achieving
									2nd Week	14.10.2025	Grab	7.6	7	26	14	1100	130	Achieving
									3rd Week	21.10.2025	Grab	7.6	7	24	16	1300	170	Achieving
									4th Week	28.10.2025	Composite	7.4	8	26	14	-	-	Achieving
102	15 MLD STP Kairana, Shamli, Muzaffarnagar	2024	Muzaffar Nagar	15	15	SBR	U.P. Jal Nigam	U	1st Week	08.10.2025	Grab	7.3	6	22	18	1400	170	Achieving
									2nd Week	14.10.2025	Grab	7.6	9	28	12	1300	170	Achieving
									3rd Week	21.10.2025	Composite	7.6	9	26	14	-	-	Achieving
									4th Week	28.10.2025	Grab	7.6	6	22	18	1700	210	Achieving
103	12 MLD STP Ayodhya	2014	Ayodhya	12	7	UASB	U.P. Jal Nigam	U	1st Week	06.10.2025	Grab	7.05	18	89	40	4900	780	Achieving
									2nd Week	13.10.2025	Grab	7.25	24	122	68	4600	780	Achieving
									3rd Week	21.10.2025	Grab	7.52	20	98	65	4000	920	Achieving
									4th Week	28.10.2025	Grab	7.33	18	90	58	3500	700	Achieving
104	6 MLD STP Ramghat, Ayodhya	2023	Ayodhya	6	4	SBR	U.P. Jal Nigam	U	1st Week	06.10.2025	-	-	-	-	-	-	-	Not Operational Due To Maintenance Work
									2nd Week	13.10.2025	Grab	7.28	19	81	56	3900	920	Achieving
									3rd Week	21.10.2025	Grab	7.62	18	86	52	2600	680	Achieving
									4th Week	28.10.2025	Grab	7.4	13	62	48	2100	780	Achieving
105	13.59 (6.8) MLD STP, Masani, Mathura	2007	Mathura	6.8	6.8	WSP	U.P. Jal Nigam	R	1st Week	09.10.2025	Grab	8.1	27	248	88	3900	930	Achieving
									2nd Week	14.10.2025	Composite	7.9	26	232	84	-	-	Achieving
									3rd Week	25.10.2025	Grab	8	25	224	76	3800	920	Achieving
									4th Week	28.10.2025	Grab	8.1	27	240	88	3900	930	Achieving
106	04 MLD STP Vrindavan Near Pagal Baba Mandir, Mathura	2007	Mathura	4	4	WSP	U.P. Jal Nigam	R	1st Week	08.10.2025	Grab	7.9	26	248	90	3800	920	Achieving
									2nd Week	14.10.2025	Composite	7.7	25	232	86	-	-	Achieving
									3rd Week	25.10.2025	Grab	7.8	27	240	92	3900	920	Achieving
									4th Week	28.10.2025	Grab	7.9	26	224	80	3300	930	Achieving
107	08 MLD STP Near 100 Bed Hospital	2015	Mathura	8	8	UASB	U.P. Jal Nigam	U	1st Week	08.10.2025	Grab	8	25	216	80	3200	920	Achieving
									2nd Week	14.10.2025	Composite	7.8	24	200	68	-	-	Achieving

107	Vrindavan, Manth road	2015	Mathura	14.5	14.5	WSP	U.P. Jal Nigam	R	3rd Week	25.10.2025	Grab	7.9	26	216	76	3300	930	Achieving	
									4th Week	28.10.2025	Grab	7.8	27	232	84	3400	930	Achieving	
108	14.5 MLD STP Trans-yamuna, Jamunapar, Mathura	2007	Mathura	14.5	14.5	WSP	U.P. Jal Nigam	R	1st Week	09.10.2025	Grab	8.4	40	416	174	11000	2700	Not Achieving	
									2nd Week	14.10.2025	Composite	8.7	52	432	188	-	-	-	Not Achieving
									3rd Week	25.10.2025	Grab	8.2	48	384	164	13000	3300	Not Achieving	
									4th Week	29.10.2025	Grab	8	44	368	148	12000	3200	Not Achieving	
109	30 MLD STP Masani Mathura	2020	Mathura	30	30	SBR	U.P. Jal Nigam	R	1st Week	09.10.2025	Grab	7.8	25	216	76	2600	920	Achieving	
									2nd Week	14.10.2025	Composite	7.5	23	192	70	-	-	-	Achieving
									3rd Week	25.10.2025	Grab	7.7	22	184	58	2700	930	Achieving	
									4th Week	28.10.2025	Grab	7.8	24	200	66	3100	910	Achieving	
110	16 MLD STP Trans Yamuna, Laxmi Nagar, Mathura	2015	Mathura	16	15	UASB	U.P. Jal Nigam	R	1st Week	09.10.2025	Grab	7.9	24	224	74	3300	930	Achieving	
									2nd Week	14.10.2025	Composite	8.1	26	240	88	-	-	-	Achieving
									3rd Week	25.10.2025	Grab	7.9	27	248	96	3400	930	Achieving	
									4th Week	29.10.2025	Grab	8	25	232	82	3200	920	Achieving	
111	2.76 MLD STP Goverdhan STP	2011	Mathura	2.76	0	WSP	Nagar Palika Parishad	O	1st Week	09.10.2025	-	-	-	-	-	-	-	Not operational Due to Maintenance Work	
									2nd Week	14.10.2025	-	-	-	-	-	-	-	-	Not operational Due to Maintenance Work
									3rd Week	25.10.2025	-	-	-	-	-	-	-	-	Not operational Due to Maintenance Work
									4th Week	29.10.2025	-	-	-	-	-	-	-	-	Not operational Due to Maintenance Work
112	33 MLD STP Sector-54, Noida	2011	Noida	33	13	SBR	Noida Authority	O	1st Week	06.10.2025	Grab	7.45	14.6	128	32	1600	540	Achieving	
									2nd Week	13.10.2025	Grab	7.37	13.7	112.8	27	1400	680	Achieving	
									3rd Week	17.10.2025	Composite	7.39	15.3	127.2	37	-	-	-	Achieving
									4th Week	21.10.2025	Grab	7.45	12.3	85.6	25	1600	540	Achieving	
									5th Week	27.10.2025	Grab	7.16	9.3	53.6	21	1600	220	Achieving	
113	25 MLD STP Sector-50, Noida	2015	Noida	25	14	SBR	Noida Authority	O	1st Week	06.10.2025	Grab	7.31	14.1	96.8	28	2400	920	Achieving	
									2nd Week	13.10.2025	-	-	-	-	-	-	-	-	Not operational Due to Maintenance Work
									3rd Week	17.10.2025	-	-	-	-	-	-	-	-	Not operational Due to Maintenance Work
									4th Week	21.10.2025	-	-	-	-	-	-	-	-	Not operational Due to Maintenance Work
114	35 MLD STP Sector-123, Noida	2011	Noida	35	17	SBR	Noida Authority	O	1st Week	06.10.2025	Grab	7.63	13.5	120	30	2500	830	Achieving	
									2nd Week	13.10.2025	Grab	7.28	12.9	16.8	26	2700	830	Achieving	
									3rd Week	17.10.2025	Composite	7.53	15.7	128	35	-	-	-	Achieving
									4th Week	21.10.2025	Grab	7.51	12.5	96.4	27	1600	920	Achieving	
									5th Week	27.10.2025	Grab	7.26	11.1	59.2	24	2200	450	Achieving	
115	50 MLD STP Sector-168, Noida	2015	Noida	50	17	SBR	Noida Authority	O	1st Week	06.10.2025	Grab	7.51	15.6	118.4	33	2200	680	Achieving	
									2nd Week	13.10.2025	Grab	7.31	14.7	127.2	32	2500	910	Achieving	
									3rd Week	17.10.2025	Composite	7.55	13.9	85.6	24	-	-	-	Achieving
									4th Week	21.10.2025	Grab	7.29	10.7	84.8	22	1100	790	Achieving	
									5th Week	27.10.2025	Grab	7.2	14	74.4	39	1500	610	Achieving	
116	34 MLD STP Sector -50 Noida	2012	Noida	34	31	SBR	Noida Authority	O	1st Week	06.10.2025	Grab	7.37	13.3	108.8	26	1200	610	Achieving	
									2nd Week	13.10.2025	Grab	7.25	14.5	123.2	29	2100	930	Achieving	
									3rd Week	17.10.2025	Composite	7.23	14.9	110.4	34	-	-	-	Achieving
									4th Week	21.10.2025	Grab	7.34	11.6	80.8	21	1700	400	Achieving	
									5th Week	27.10.2025	Grab	7.43	13.7	65.6	28	1600	540	Achieving	
117	54 MLD STP Sector- 54, Noida	2012	Noida	54	43	SBR	Noida Authority	O	1st Week	06.10.2025	Grab	7.51	13.2	82.2	24	1200	610	Achieving	
									2nd Week	13.10.2025	Grab	7.63	14.1	110.4	25	1500	610	Achieving	
									3rd Week	17.10.2025	Composite	7.45	16.7	134.4	41	-	-	-	Achieving
									4th Week	21.10.2025	Grab	7.51	10.9	80	17	1500	400	Achieving	
									5th Week	27.10.2025	Grab	7.11	12.6	57.6	36	1200	630	Achieving	
118	100 MLD STP Sector- 168, Noida	2023	Noida	100	61	SBR	Noida Authority	O	1st Week	06.10.2025	Grab	7.62	12.5	85.6	33	1700	200	Achieving	
									2nd Week	13.10.2025	Grab	7.42	13.5	97.6	19	2200	450	Achieving	
									3rd Week	17.10.2025	Composite	7.59	17.3	139.2	45	-	-	-	Achieving
									4th Week	21.10.2025	Grab	7.69	13.7	108	31	1600	350	Achieving	
									5th Week	27.10.2025	Grab	7.51	12.5	72.4	22	1500	400	Achieving	
119	80 MLD STP Sector- 123, Noida	2023	Noida	80	64	SBR	Noida Authority	O	1st Week	06.10.2025	Grab	7.68	12.4	102.4	23	1700	400	Achieving	
									2nd Week	13.10.2025	Grab	7.56	11.5	99.2	21	1600	540	Achieving	
									3rd Week	17.10.2025	Composite	7.67	14.8	108	29	-	-	-	Achieving
									4th Week	21.10.2025	Grab	7.59	11.1	81.6	26	1600	240	Achieving	
									5th Week	27.10.2025	Grab	7.11	12.6	57.6	36	1200	630	Achieving	
120	2.0 MLD STP Greater Noida Authority STP, Vill-Badalpur	2015	Greater Noida	2	2	SBR	GNIDA	O	1st Week	09.10.2025	Grab	7.48	10	78	35	2600	780	Achieving	
									2nd Week	14.10.2025	Grab	7.44	16	80	40	2400	780	Achieving	
									3rd Week	25.10.2025	Grab	7.37	12	66	22	1600	350	Achieving	
									4th Week	27.10.2025	Grab	7.66	16	96	40	1700	400	Achieving	
121	15 MLD STP ECO tech -2	2018	Greater Noida	15	8	SBR	GNIDA	O	1st Week	09.10.2025	Grab	7.22	12	76	40	2200	790	Achieving	
									2nd Week	14.10.2025	Grab	7.22	10	48	30	1700	450	Achieving	
									3rd Week	25.10.2025	Grab	7.55	14	48	20	1400	610	Achieving	
									4th Week	27.10.2025	Grab	7.62	12	80	30	2700	930	Achieving	

122	20 MLD STP ECO tech -3	2018	Greater Noida	20	14	SBR	GNIDA	O	1st Week	09.10.2025	Grab	7.35	10	60	32	1600	220	Achieving
									2nd Week	14.10.2025	Grab	7.35	8	54	25	1600	540	Achieving
									3rd Week	25.10.2025	Grab	7.4	16	62	25	2200	400	Achieving
									4th Week	27.10.2025	Grab	7.85	8	44	17	2200	680	Achieving
123	137 MLD STP Kasana, GreaterNoida	2015	Greater Noida	137	95	SBR	GNIDA	O	1st Week	09.10.2025	Grab	7.48	16	84	47	2200	790	Achieving
									2nd Week	14.10.2025	Grab	7.32	14	60	35	2700	680	Achieving
									3rd Week	25.10.2025	Grab	7.6	20	78	36	3300	680	Achieving
									4th Week	27.10.2025	Grab	7.55	10	56	25	2100	610	Achieving
124	0.805 MLD STP Ahara Road, Zone-A, Anoopshahar	2003	Bulandshahar	0.805	0.805	WSP	U.P. Jal Nigam	U	1st Week	06.10.2025	Grab	7.74	22	92	41	1200	610	Achieving
									2nd Week	13.10.2025	Grab	7.67	26	88	45	920	540	Achieving
									3rd Week	20.10.2025	Grab	7.65	24	96	43	1200	610	Achieving
									4th Week	27.10.2025	Grab	7.71	26	92	47	920	540	Achieving
125	1.75 MLD STP Ahara Road, (Shivanand Ashram) Zone-B,	2003	Bulandshahar	1.75	1.75	WSP	U.P. Jal Nigam	U	1st Week	06.10.2025	Grab	7.67	20	88	44	1400	680	Achieving
									2nd Week	13.10.2025	Grab	7.71	24	92	43	2200	689	Achieving
									3rd Week	20.10.2025	Grab	7.68	22	84	49	1700	930	Achieving
									4th Week	27.10.2025	Grab	7.64	26	96	52	1600	920	Achieving
126	2.25 MLD STP Narora Atomic power Station Narora Township	2000	Bulandshahar	2.25	2.25	ASP	Narora Atomic power Station	O	1st Week	06.10.2025	Grab	7.52	16	64	47	540	240	Achieving
									2nd Week	13.10.2025	Grab	7.45	18	68	53	1100	400	Achieving
									3rd Week	20.10.2025	Grab	7.48	16	76	46	920	540	Achieving
									4th Week	27.10.2025	Grab	7.51	20	88	41	1100	400	Achieving
127	01 MLD STP Zone-B Anoopshahar	2016	Bulandshahar	1	1	MBBR	U.P. Jal Nigam	R	1st Week	06.10.2025	Grab	7.63	24	112	81	2100	780	Achieving
									2nd Week	13.10.2025	Grab	7.61	26	124	89	1700	930	Achieving
									3rd Week	20.10.2025	Grab	7.66	28	132	91	2000	680	Achieving
									4th Week	27.10.2025	Grab	7.73	24	144	87	2200	680	Achieving
128	1.5 MLD STP Anoopshahar Zone A (NGRBA)	2016	Bulandshahar	1.5	1.5	UASB	U.P. Jal Nigam	R	1st Week	13.10.2025	Grab	8.93	28	140	87	2100	920	Achieving
									2nd Week	13.10.2025	Grab	8.93	28	140	87	2100	920	Achieving
									3rd Week	20.10.2025	Grab	8.88	26	148	94	2200	680	Achieving
									4th Week	20.10.2025	Grab	8.88	26	148	94	2200	680	Achieving
129	40 MLD STP Bulandshahar	2023	Bulandshahar	40	20	SBR	U.P. Jal Nigam	U	1st Week	06.10.2025	Grab	7.61	18	88	55	1100	400	Achieving
									2nd Week	13.10.2025	Grab	7.55	20	96	51	1300	680	Achieving
									3rd Week	20.10.2025	Grab	7.51	22	104	53	1500	840	Achieving
									4th Week	27.10.2025	Grab	7.54	24	116	58	2100	920	Achieving
130	04 MLD STP , Narora (NGRBA)	2015	Bulandshahar	4	4	UASB	U.P. Jal Nigam	R	1st Week	06.10.2025	Grab	7.71	20	128	62	1700	930	Achieving
									2nd Week	13.10.2025	Grab	7.76	22	112	69	1200	610	Achieving
									3rd Week	20.10.2025	Grab	7.74	26	120	71	1600	920	Achieving
									4th Week	27.10.2025	Grab	7.67	22	112	65	1500	840	Achieving
131	24 MLD STP, Bijnor	2018	Bijnor	24	23.5	UASB	U.P. Jal Nigam	U	1st Week	04.10.2025	Grab	7.6	10	40	22	940	110	Achieving
									2nd Week	10.10.2025	Grab	7.39	14	48	25	1300	130	Achieving
									3rd Week	25.10.2025	Grab	7.5	8	32	20	790	120	Achieving
									4th Week	27.10.2025	Grab	7.62	10	40	23	1100	110	Achieving
									5th Week	31.10.2025	Grab	7.56	8	32	19	940	130	Achieving
132	58 MLD STP Moradabad	2018	Moradabad	58	24	UASB	U.P. Jal Nigam	R	1st Week	02.10.2025	Grab	7.61	6.2	72	7	930	61	Achieving
									2nd Week	14.10.2025	Grab	7.52	6.5	82	8	610	61	Achieving
									3rd Week	21.10.2025	Grab	7.59	6.4	68	6	920	61	Achieving
									4th Week	28.10.2025	Grab	7.61	6.6	76	8	680	61	Achieving
133	20 MLD STP Moradabad	2017	Moradabad	20	14	SBR	MDA	O	1st Week	02.10.2025	Grab	7.64	14	74	32	1700	680	Achieving
									2nd Week	14.10.2025	Grab	7.78	12	86	34	1200	680	Achieving
									3rd Week	21.10.2025	Grab	7.59	13	76	30	1300	780	Achieving
									4th Week	28.10.2025	Grab	7.66	15	82	28	1700	680	Achieving
134	14 MLD STP, Benzipur	2016	Rampur	14	10	UASB	U.P. Jal Nigam	U	1st Week	02.10.2025	Grab	7.73	22	78	28	1400	610	Achieving
									2nd Week	14.10.2025	Grab	7.81	24	72	32	2000	920	Achieving
									3rd Week	21.10.2025	Grab	7.82	20	88	34	2100	930	Achieving
									4th Week	28.10.2025	Grab	7.92	21	82	30	1700	680	Achieving
135	5 MLD STP , Rampur	2016	Rampur	5	4	SBR	U.P. Jal Nigam	U	1st Week	02.10.2025	Grab	7.58	6.4	82	6	680	61	Achieving
									2nd Week	14.10.2025	Grab	7.67	6.2	84	7	930	68	Achieving
									3rd Week	21.10.2025	Grab	7.56	6.6	82	7	610	61	Achieving
									4th Week	28.10.2025	Grab	7.44	6.7	78	6	930	68	Achieving
136	15 MLD STP Pehrigaon	2015	Rampur	15	11	UASB	U.P. Jal Nigam	U	1st Week	02.10.2025	Grab	7.76	20	76	34	2100	930	Achieving
									2nd Week	14.10.2025	Grab	7.7	22	78	30	2000	920	Achieving
									3rd Week	21.10.2025	Grab	7.68	24	72	32	1700	680	Achieving
									4th Week	28.10.2025	Grab	7.52	22	80	34	2100	930	Achieving
137	15 MLD STP, Kasganj	2022	Kasganj, Aligarh	15	9.6	SBR	U.P. Jal Nigam	R	1st Week	10.10.2025	Grab	7.38	24.8	104	76	1500	840	Achieving
									2nd Week	16.10.2025	Grab	7.13	28.1	120	86	1700	680	Achieving
									3rd Week	24.10.2025	Grab	7.47	22	96	78	1600	920	Achieving
									4th Week	28.10.2025	Grab	7.43	18	96	72	1400	680	Achieving

138	24 MLD STP, Manpur, Etah	2023	Etah, Aligarh	24	16	SBR	U.P. Jal Nigam	U	1st Week	10.10.2025	Grab	7.48	16.4	96	52	2600	920	Achieving				
									2nd Week	16.10.2025	Grab	6.89	18.2	94	43	2200	930	Achieving				
									3rd Week	24.10.2025	Grab	7.22	14	44	69	1500	840	Achieving				
									4th Week	27.10.2025	Grab	7.63	12	52	38	1200	610	Achieving				
139	45 MLD STP Laxmi Nagar, Aligarh	2023	Aligarh	45	18	SBR	U.P. Jal Nigam	U	1st Week	10.10.2025	Grab	7.34	27.8	244	89	2100	930	Achieving				
									2nd Week	16.10.2025	Grab	7.28	28.6	142.4	68	3400	780	Achieving				
									3rd Week	24.10.2025	Grab	7.38	16	84	87	2600	920	Achieving				
									4th Week	28.10.2025	Grab	7.28	22	108	88	4000	610	Achieving				
140	8.95 MLD STP Bela, Pratapgarh	2023	Pratapgarh	8.95	7.2	FAB	U.P. Jal Nigam	U	1st Week	01.10.2025	Grab	7.94	22.0	52.80	36.0	700	230	Achieving				
									2nd Week	08.10.2025	Grab	7.90	21.0	49.60	32.0	680	200	Achieving				
									3rd Week	15.10.2025	Grab	7.95	24.0	48.00	30.0	780	230	Achieving				
									4th Week	22.10.2025	Grab	7.90	26.0	50.56	34.0	700	240	Achieving				
141	5 MLD STP Palhipur, Sultanpur	2024	Sultanpur	5	1.4	SBR	U.P. Jal Nigam	R	1st Week	04.10.2025	Grab	8.01	20.0	57.60	32.0	2100	930	Achieving				
									2nd Week	09.10.2025	Grab	8.05	22.0	59.20	36.0	2000	780	Achieving				
									3rd Week	16.10.2025	Grab	8.02	23.0	60.48	30.0	2300	930	Achieving				
									4th Week	23.10.2025	Grab	8.07	20.0	57.60	34.0	2100	920	Achieving				
142	2 MLD STP Miranpur, Sadar, Sultanpur	2024	Sultanpur	2	4.3	SBR	U.P. Jal Nigam	R	1st Week	04.10.2025	Grab	8.05	27.0	62.4	34.0	2100	920	Achieving				
									2nd Week	09.10.2025	Grab	8.10	28.0	60.8	30.0	2000	780	Achieving				
									3rd Week	16.10.2025	Grab	8.05	26.0	58.88	32.0	2000	680	Achieving				
									4th Week	23.10.2025	Grab	8.09	22.0	56.00	36.0	2200	920	Achieving				
143	10 MLD STP Hathia Nala, Lolepur	2006	Sultanpur	10	7.1	Aerated Lagoon	U.P. Jal Nigam	R	1st Week	04.10.2025	Grab	7.06	23.0	64.00	35.0	2000	930	Achieving				
									2nd Week	09.10.2025	Grab	7.94	21.0	60.80	38.0	1700	780	Achieving				
									3rd Week	16.10.2025	Grab	7.91	20.0	59.20	40.0	2100	920	Achieving				
									4th Week	23.10.2025	Grab	7.94	22.0	61.44	35.0	2000	920	Achieving				
144	18 MLD STP Raebareli	2023	Raebareli	18	4.8	SBR	U.P. Jal Nigam	U	1st Week	06.10.2025	Grab	7.99	8.0	42.88	7.0	790	210	Achieving				
									2nd Week	13.10.2025	Grab	7.96	9.0	40.96	8.0	680	200	Achieving				
									3rd Week	20.10.2025	Grab	7.94	8.0	41.92	9.0	790	200	Achieving				
									4th Week	27.10.2025	Grab	7.99	9.0	40.00	7.0	780	200	Achieving				
145	35 MLD STP, Saraitalfi	2023	Bareilly	35	0	ASP	Nagar Nigam	O	1st Week	8.10.2025	-	-	-	-	-	-	-	Not operational Due to Maintenance Work				
									2nd Week	14.10.2025	-	-	-	-	-	-	-	-	-	-	Not operational Due to Maintenance Work	
									3rd Week	24.10.2025	-	-	-	-	-	-	-	-	-	-	-	Not operational Due to Maintenance Work
									4th Week	30.10.2025	-	-	-	-	-	-	-	-	-	-	-	Not operational Due to Maintenance Work
146	42 MLD STP, HarooNagla, Bareilly	2024	Bareilly	42	42	SBR	U.P. Jal Nigam	R	1st Week	8.10.2025	Grab	7.6	6	48	14	220	79	Achieving				
									2nd Week	14.10.2025	Grab	7.5	8	40	15	150	59	Achieving				
									3rd Week	24.10.2025	Grab	7.4	6	32	16	170	68	Achieving				
									4th Week	30.10.2025	Grab	7.3	8	40	17	210	79	Achieving				
147	20 MLD STP Barinagla, Bareilly	2024	Bareilly	20	18	SBR	U.P. Jal Nigam	R	1st Week	8.10.2025	Grab	7.3	8	36	17	210	79	Achieving				
									2nd Week	14.10.2025	Grab	7.6	8	32	18	170	68	Achieving				
									3rd Week	24.10.2025	Grab	7.2	6	40	15	220	79	Achieving				
									4th Week	30.10.2025	Grab	7.6	6	36	18	210	92	Achieving				
148	01 MLD STP, Girdaripur, Bareilly	2024	Bareilly	1	1	SBR	U.P. Jal Nigam	R	1st Week	8.10.2025	Grab	7.5	6	32	13	220	79	Achieving				
									2nd Week	14.10.2025	Grab	7.2	6	48	17	170	68	Achieving				
									3rd Week	24.10.2025	Grab	7.4	8	40	15	210	68	Achieving				
									4th Week	30.10.2025	Grab	7.6	6	32	14	170	94	Achieving				
149	40 MLD STP, Shahjahanpur	2025	Shahjahanpur	40	10	SBR	U.P. Jal Nigam	U	1st Week	8.10.2025	Grab	7.2	6	32	9	210	68	Achieving				
									2nd Week	14.10.2025	Grab	7.6	8	40	8	220	98	Achieving				
									3rd Week	24.10.2025	Grab	7.4	6	32	7	170	68	Achieving				
									4th Week	30.10.2025	Grab	7.6	8	40	8	220	90	Achieving				
150	15 MLD STP Unnao	2024	Unnao	15	13	SBR	U.P. Jal Nigam	R	1st Week	04.10.2025	Grab	8.26	14.8	152	76.2	4100	930	Achieving				
									2nd Week	10.10.2025	Grab	8.02	16.2	168	66.8	4700	680	Achieving				
									3rd Week	17.10.2025	Grab	8.16	19	156	56	5400	2200	Not Achieving				
									4th Week	29.10.2025	Grab	8.2	18.8	148	58	4700	680	Achieving				
151	21 MLD STP Mau Road, Ghazipur	2024	Ghazipur, Varanasi	21	12	SBR	U.P. Jal Nigam	R	1st Week	06.10.2025	Grab	7.61	6.7	38	7.8	350	170	Achieving				
									2nd Week	14.10.2025	Grab	7.56	7.2	42	9	480	220	Achieving				
									3rd Week	25.10.2025	Grab	7.65	6.3	36	7.2	470	170	Achieving				
									4th Week	01.11.2025	Grab	7.52	-	-	-	-	-	-	-	-		
152	33 MLD STP Ayodhya	2025	Ayodhya	33	0	SBR	UPJN (Rural)	R	1st Week	06.10.2025	-	-	-	-	-	-	-	Under Trial Run				
									2nd Week	13.10.2025	-	-	-	-	-	-	-	-	-	-	Under Trial Run	
									3rd Week	21.10.2025	-	-	-	-	-	-	-	-	-	-	Under Trial Run	
									4th Week	28.10.2025	-	-	-	-	-	-	-	-	-	-	Under Trial Run	
153	15 MLD STP Baniyapur	2018	Kanpur Nagar	15	0	SBR	UPJN (Urban)	U	1st Week	01.10.2025	-	-	-	-	-	-	-	Not operational Due to Maintenance Work				
									2nd Week	07.10.2025	-	-	-	-	-	-	-	-	-	-	Not operational Due to Maintenance Work	
									3rd Week	14.10.2025	-	-	-	-	-	-	-	-	-	-	Not operational Due to Maintenance Work	
									4th Week	28.10.2025	-	-	-	-	-	-	-	-	-	-	Not operational Due to Maintenance Work	
	5 MLD STP								1st Week	09.10.2025	-	-	-	-	-	-	Not operational Due to Maintenance Work					

154	Yamuna Expressway Industrial	2023	Jewar (Gt. Noida)	5	0	SBR	UPJN (Rural)	R	2nd Week	14.10.2025	-	Not operational Due to Maintenance Work
									3rd Week	25.10.2025	-	Not operational Due to Maintenance Work
									4th Week	27.10.2025	-	Not operational Due to Maintenance Work
									1st Week	01.10.2025	-	Under Trial Run
155	20 MLD STP Ballia	2025	Ballia	20	0	SBR	UPJN (Urban)	U	2nd Week	10.10.2025	-	Under Trial Run
									3rd Week	16.10.2025	-	Under Trial Run
									4th Week	25.10.2025	-	Under Trial Run
									1st Week	02.10.2025	-	Under Trial Run
156	25 MLD STP Moradabad	2025	Moradabad	25	0	SBR	UPJN(Rural)	R	2nd Week	14.10.2025	-	Under Trial Run
									3rd Week	21.10.2025	-	Under Trial Run
									4th Week	28.10.2025	-	Under Trial Run
									Note :- The standards as per MoEF&CC Notification dated 13.10.2017, titled "Applicable Effluent Discharge Standards for STPs" are as follows:			
For State Capital: pH-6.5-9.0; BOD - <20 mg/l; TSS- <50 mg/l & FC- <1000 MPN/100 ml												
Other than State Capital: pH-6.5-9.0; BOD - <30 mg/l; TSS- <100 mg/l & FC- <1000 MPN/100 ml												
Note:- As per the data received from Regional offices, UPPCB												

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)
1	10.445 MLD STP near Tixi Tempel (Karanpur)	2001	Etawah	10.445
2	21 MLD STP Etawah	2022	Etawah	21
3	13.5 MLD STP at Mauja Umrain	2013	Etawah	13.5
4	03 MLD STP Firozabad	2014	Firozabad	3
5	67 MLD STP Mohammadpur, Biharipur	2020	Firozabad	67
6	1.65 MLD STP Saifai (Paramedicals)	2013	Etawah	1.65
7	23 MLD STP at Mauja Odenya, Padaria	2014	Mainpuri	23
8	1.5 MLD STP Saifai Village, Etawah	2006	Etawah	1.5
9	26 MLD STP Jhansi Laxmi Taal	2021	Jhansi	26
10	26 MLD STP Jhansi Laxmi Taal	2021	Jhansi	26
11	26 MLD STP Smart City, Lahargird	2025	Jhansi	26
12	3.42 MLD STP Near Divyang kendra	2000	Chitrakoot	3.42
13	42 MLD STP, Sajari Kanpur	2016-17	Kanpur Nagar	42
14	210 MLD STP, Bingawan Kanpur	2015-16	Kanpur Nagar	210
15	130 MLD STP Jajmau, Kanpur	1998-99	Kanpur Nagar	130
16	43 MLD STP Jajmau, Kanpur	2020	Kanpur Nagar	43
17	13 MLD STP Jalalpur, Amrapur, Kannuaj	2017	Kanpur Dehat	13
18	30 MLD STP Pankha, Kanpur	2023	Kanpur Nagar	30
19	36 MLD STP Jajmau, Kanpur	9+27 MLD (1992) = 36 MLD (2024)	Kanpur Nagar	36

20	17.7 MLD STP Fatehgarh, Farrukhabad	2024	Kanpur Nagar	17.7
21	30 MLD STP Farrukhabad	2024	Kanpur Nagar	30
22	50 MLD STP Numayadahi	2013	Prayagraj	50
23	10 MLD STP Ponghat	2013	Prayagraj	10
24	25 MLD STP Kodra	2013	Prayagraj	25
25	60 MLD STP Rajapur	2013	Prayagraj	60
26	29 MLD STP Salori-1	2007	Prayagraj	29
27	14 MLD STP Salori-2 Expansion	2016	Prayagraj	14
28	80 MLD STP Naini	2013	Prayagraj	80
29	42 MLD STP, Naini	2023	Prayagraj	42
30	14 MLD STP Phaphamau	2023	Prayagraj	14
31	16 MLD STP Jhunsi	2023	Prayagraj	16
32	10 MLD STP Ramnagar	2021	Varanasi	10
33	80 MLD STP Dinapur	1994	Varanasi	80
34	9.8 MLD STP Bhagwanpur	1989	Varanasi	9.8
35	140 MLD STP Dinapur	2018	Varanasi	140
36	120 MLD STP Goithaha	2019	Varanasi	120
37	12 MLD BLW STP	1989	Varanasi	12
38	50 MLD STP Ramana	2021	Varanasi	50
39	30 MLD STP Pachhahatiya Jaunpur	2023	Jaunpur, Varanasi	30
40	07 MLD Vindyachal Mirzapur	2022	Mirzapur	7
41	14 MLD STP Pakka Pokhra	1994	Mirzapur	14
42	8.5 MLD STP Pakka Pokhra, Mirzapur	2024	Mirzapur	8.5
43	8.5 MLD STP Bisunderpur, Mirzapur	2024	Mirzapur	8.5

44	15 MLD S.T.P. Jharkhandi, Maherwa ki Bari	2015	Gorakhpur	15
45	5 MLD S.T.P. Jharkhandi, Maherwa ki Bari	2023	Gorakhpur	5
46	30 MLD S.T.P. Opp. Manyavar Kanshiram Shahri Garib Awas Yojna, Deoria bypass Road	2015	Gorakhpur	30
47	10 MLD STP Gorakhpur	2024	Gorakhpur	10
48	8 MLD STP Azamgarh	2024	Azamgarh	8
49	38 MLD STP, Mahilpur Road	1998	Saharanpur	38
50	6.5 MLD STP Awasi vikas Parishad STP	2018	Lucknow	6.5
51	37.5 MLD STP Awasi vikas Parishad STP	2017	Lucknow	37.5
52	345 MLD STP, Bharwara	2011	Lucknow	345
53	56 MLD STP, Daulatganj	2003 & 2009	Lucknow	56 (42+14)
54	1.5 MLD STP Hathi Park, (Smart City)	2021	Lucknow	1.5
55	39 MLD STP, Sajjadbagh, Daulatganj	2024	Lucknow	39
56	120 MLD STP near 1090 Chauraha	2025	Lucknow	120
57	19 MLD STP C.G. City, Lucknow	2023	Lucknow	19
58	56 MLD STP Trans Hindon (Indirapuram), Ghaziabad	2000	Ghaziabad	56
59	30 MLD STP, Sadullabad (Loni), Ghaziabad	2012	Ghaziabad	30
60	74 MLD STP S.B.R., Indirapuram, Ghaziabad	2013	Ghaziabad	74
61	56 MLD STP S.B.R., Bapudham, Ghaziabad	2014	Ghaziabad	56
62	6 MLD STP Garh Zone, Garhmukteswar Hapur	2011	Hapur / Garhmukteswar	6
63	3 MLD STP Brijghat Zone, Garhmukteswar Hapur	2011	Hapur / Garhmukteswar	3
64	56 MLD STP, Indirapuram, (GDA), Ghaziabad	2012	Ghaziabad	56
65	56 MLD STP S.B.R., Dudahaida Vijay Nagar, Ghaziabad	2013	Ghaziabad	56

66	70 MLD STP U.A.S.B.R. Dudahaida Vijay Nagar, Ghaziabad	2000	Ghaziabad	70
67	3 MLD STP Pilkhaun	2015	Ghaziabad	3
68	5 MLD STP Trans Delhi Signature City (Tronica City), Loni	2019	Ghaziabad	5
69	56 MLD STP S.B.R. Govindpuram, Ghaziabad	2014	Ghaziabad	56
70	20 MLD STP Modinagar	2023	Modinagar, Ghaziabad	20
71	56 MLD STP S.B.R., Morty, Ghaziabad	2018	Ghaziabad	56
72	30 MLD STP, Rampur Road, Hapur	2022	Hapur, Ghaziabad	30
73	21.5 MLD STP Siddharthvihar, Ghaziabad	2024	Ghaziabad	21.5
74	78 MLD STP Dhadhupura, Agra	2013	Agra	78
75	2.25 MLD STP Budi ka Nagla, Agra	2000	Agra	2.25
76	10 MLD STP Peelakhar, Agra	2000	Agra	10
77	12 MLD STP Devri Road, (Bhimnagri), Agra	2011	Agra	12
78	14 MLD STP Jaganpur, Sikandarpur, Agra	2011	Agra	14
79	40 MLD STP Sadarban, Bichhpuri, Agra	2013	Agra	40
80	36 MLD STP Sadarwan (Bichpuri) New	2018	Agra	36
81	24 MLD STP Dhadhupura (New), Agra	2014	Agra	24
82	4.50 MLD STP Kalindi Vihar, Agra	2014	Agra	4.5
83	03 MLD STP Pandav Nagar, Meerut	2013	Meerut	3
84	07 MLD STP Pallavpuram-1, Meerut	2012	Meerut	7
85	11 MLD STP Pallavpuram-2, Meerut	2008	Meerut	11
86	06 MLD STP Rakshapuram, Meerut	2011	Meerut	6
87	10 MLD STP Lohiya Nagar, Meerut	2010	Meerut	10
88	15 MLD STP Shatabdinagar, Meerut	2010	Meerut	15
89	15 MLD STP Vedvyaspuri Meerut	2011	Meerut	15
90	06 MLD STP Shradhapuri-1, Meerut	2012	Meerut	6
91	06 MLD STP Sainik Vihar	2017	Meerut	6
92	5 MLD STP Modipuram Tiraha	2016	Meerut	5

93	07 MLD STP Sports Goods Complex, Meerut	2012	Meerut	7
94	72 MLD STP Garh road (Jagruti vihar) Kamalpur	2018	Meerut	72
95	10 MLD STP Ganga Nagar, Meerut	2011	Meerut	10
96	06 MLD STP Shradhapuri- Phase-2, Meerut	2012	Meerut	6
97	14 MLD STP Baghpat, Meerut	2021	Baghpat, Meerut	14
98	32.5 MLD STP (WSP) Nagar Palika Parishad, Kidwai nagar	2001	Muzaffar Nagar	32.5
99	32.5 MLD STP Near A2Z Garbage plant KidwaiNagar	2025	Muzaffar Nagar	32.5
100	10 MLD STP Budhana	2024	Muzaffar Nagar	10
101	22 MLD STP Sahawali, Muzaffarnagar	2023	Muzaffar Nagar	22
102	15 MLD STP Kairana, Shamli, Muzaffarnagar	2024	Muzaffar Nagar	15
103	12 MLD STP Ayodhya	2014	Ayodhya	12
104	6 MLD STP Ramghat, Ayodhya	2023	Ayodhya	6
105	13.59 (6.8) MLD STP, Masani, Mathura	2007	Mathura	6.8
106	04 MLD STP Vrindavan Near Pagal Baba Mandir, Mathura	2007	Mathura	4
107	08 MLD STP Near 100 Bed Hospital Vrindavan, Manth road	2015	Mathura	8
108	14.5 MLD STP Trans-yamuna, Jamunapar, Mathura	2007	Mathura	14.5
109	30 MLD STP Masani Mathura	2020	Mathura	30
110	16 MLD STP Trans Yamuna, Laxmi Nagar, Mathura	2015	Mathura	16
111	2.76 MLD STP Goverdhan STP	2011	Mathura	2.76
112	33 MLD STP Sector-54, Noida	2011	Noida	33
113	25 MLD STP Sector-50, Noida	2015	Noida	25
114	35 MLD STP Sector-123, Noida	2011	Noida	35
115	50 MLD STP Sector-168, Noida	2015	Noida	50
116	34 MLD STP Sector -50 Noida	2012	Noida	34
117	54 MLD STP Sector- 54, Noida	2012	Noida	54
118	100 MLD STP Sector- 168, Noida	2023	Noida	100
119	80 MLD STP Sector- 123, Noida	2023	Noida	80
120	2.0 MLD STP Greater Noida Authority STP, Vill- Badalpur	2015	Greater Noida	2
121	15 MLD STP ECO tech -2	2018	Greater Noida	15

122	20 MLD STP ECO tech -3	2018	Greater Noida	20
123	137 MLD STP Kasana, GreaterNoida	2015	Greater Noida	137
124	0.805 MLD STP Ahara Road, Zone-A, Anoopshahar	2003	Bulandshahar	0.805
125	1.75 MLD STP Ahara Road, (Shivanand Ashram) Zone-B, Anoopshahar	2003	Bulandshahar	1.75
126	2.25 MLD STP Narora Atomic power Station Narora Township	2000	Bulandshahar	2.25
127	01 MLD STP Zone-B Anoopshahar	2016	Bulandshahar	1
128	1.5 MLD STP Anoopshahar Zone A (NGRBA)	2016	Bulandshahar	1.5
129	40 MLD STP Bulandshahar	2023	Bulandshahar	40
130	04 MLD STP , Narora (NGRBA)	2015	Bulandshahar	4
131	24 MLD STP, Bijnor	2018	Bijnor	24
132	58 MLD STP Moradabad	2018	Moradabad	58
133	20 MLD STP Moradabad	2017	Moradabad	20
134	14 MLD STP, Benzirpur	2016	Rampur	14
135	5 MLD STP , Rampur	2016	Rampur	5
136	15 MLD STP Pehrigaon	2015	Rampur	15
137	15 MLD STP, Kasganj	2022	Kasganj, Aligarh	15
138	24 MLD STP, Manpur, Etah	2023	Etah, Aligarh	24
139	45 MLD STP Laxmi Nagar, Aligarh	2023	Aligarh	45
140	8.95 MLD STP Bela, Pratapgarh	2023	Pratapgarh	8.95
141	5 MLD STP Palhipur, Sultanpur	2024	Sultanpur	5
142	2 MLD STP Miranpur, Sadar, Sultanpur	2024	Sultanpur	2
143	10 MLD STP Hathia Nala, Lolepur	2006	Sultanpur	10
144	18 MLD STP Raebareli	2023	Raebareli	18
145	35 MLD STP, Saraitafi	2023	Bareilly	35
146	42 MLD STP, HarooNagla, Bareilly	2024	Bareilly	42
147	20 MLD STP Barinagla, Bareilly	2024	Bareilly	20
148	01 MLD STP, Girdaripur, Bareilly	2024	Bareilly	1
149	40 MLD STP, Shahjahanpur	2025	Shahjahanpur	40
150	15 MLD STP Unnao	2024	Unnao	15
151	21 MLD STP Mau Road, Ghazipur	2024	Ghazipur, Varanasi	21
152	33 MLD STP Ayodhya	2025	Ayodhya	33
153	15 MLD STP Baniyapur	2018	Kanpur Nagar	15

154	5 MLD STP Yamuna Expressway Industrial Development Authority (YIDA)	2023	Jewar (Gt. Noida)	5
155	20 MLD STP Ballia	2025	Ballia	20
156	25 MLD STP Moradabad	2025	Moradabad	25

Note :- The standards as per MoEF&CC Notification dated 13.10.2017, titled "A

For State Capital: pH-6.5-9.0; BOD - <20 mg/l; TSS- <50 mg/l & FC- <1000 MPN

Other than State Capital: pH-6.5-9.0; BOD - <30 mg/l; TSS- <100 mg/l & FC- <10

Note:- As per the data received from Regional offices, UPPCB

Performance of Existing STPs in U.P. OCTOBER- 2025**Fisrt Week**

Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Rural (R)\Urban(U)\Other(O)	Date of Sampling	Sampling Method (Grab or Composite)
8	WSP	UP Jal Nigam	R	08.10.2025	Grab
20	SBR	UP Jal Nigam	R	08.10.2025	Grab
12.5	SBR	UP Jal Nigam	R	08/10/2025	Grab
1.4	UASB	NPP	O	08.10.2025	Grab
52	ASP+ extended aeration	U.P. Jal Nigam	U	08.10.2025	Grab
0.9	SBR	Others	O	08.10.2025	Grab
17	UASB	U.P. Jal Nigam	U	06.10.2025	Grab
1.1	Oxidation Pond	U.P. Jal Nigam	U	08.10.2025	Grab
22	SBR	U.P. Jal Nigam	U	03.10.2025	Grab
4	SBR	U.P. Jal Nigam	U	03.10.2025	Grab
26	SBR	Nagar Nigam	O	03.10.2025	Grab
3.42	Oxidation Pond	Nagar Palika Parishad	O	13.10.2025	Grab
22	ASP	U.P. Jal Nigam	R	07.10.2025	Grab
110	UASB	U.P. Jal Nigam	R	07.10.2025	Grab
115	ASP	U.P. Jal Nigam	R	07.10.2025	Grab
40	UASB	U.P. Jal Nigam	R	07.10.2025	Grab
12	SBR	U.P. Jal Nigam	U	01.10.2025	Grab
30	SBR	U.P. Jal Nigam	R	07.10.2025	Grab
25	UASB	U.P. Jal Nigam	U	07.10.2025	Grab

17.7	SBR	U.P. Jal Nigam	R	07.10.2025	Grab
30	SBR	U.P. Jal Nigam	R	07.10.2025	Grab
50	HRBF	Ganga Pollution control unit, U.P. Jal Nigam	R	07.10.2025	Grab
10	HRBF	Ganga Pollution control unit, U.P. Jal Nigam	R	07.10.2025	Grab
25	HRBF	Ganga Pollution control unit, U.P. Jal Nigam	R	07.10.2025	Grab
60	UASB	Ganga Pollution control unit, U.P. Jal Nigam	R	07.10.2025	Grab
29	FAB	Ganga Pollution control unit, U.P. Jal Nigam	R	07.10.2025	Grab
14	SBR	Ganga Pollution control unit, U.P. Jal Nigam	U	07.10.2025	Grab
80	ASP	Ganga Pollution control unit, U.P. Jal Nigam	R	07.10.2025	Grab
36	FCR	U.P. Jal Nigam	R	07.10.2025	Grab
14	FCR	U.P. Jal Nigam	R	07.10.2025	Grab
0	FCR	U.P. Jal Nigam	R	07.10.2025	-
9.5	Anaerobic Anoxic Oxic (A2O)	U.P. Jal Nigam	R	10.10.2025	Grab
68	ASP	U.P. Jal Nigam	U	01.10.2025	Grab
9.8	ASP	U.P. Jal Nigam	R	10.10.2025	Grab
99	ASP	U.P. Jal Nigam	U	01.10.2025	Grab
40	UASB	U.P. Jal Nigam	U	01.10.2025	Grab
12	ASP	BLW	O	10.10.2025	Grab
50	SBR	U.P. Jal Nigam	R	10.10.2025	-
30	A2O	U.P. Jal Nigam	R	09.10.2025	Grab
4.933	WSP	Nagarpalika	U	28.10.2025	Grab
13.22	UASB	U.P. Jal Nigam	R	28.10.2025	Grab
4.15	SBR	U.P. Jal Nigam	R	28.10.2025	Grab
7.6	SBR	U.P. Jal Nigam	R	28.10.2025	Grab

11.89	SBR	U.P. Jal Nigam	U	08.10.2025	Grab
4.5	SBR	U.P. Jal Nigam	U	08.10.2025	Grab
19.83	SBR	U.P. Jal Nigam	U	08.10.2025	Grab
10	SBR	U.P. Jal Nigam	U	14.10.2025	Grab
0	SBR	U.P. Jal Nigam	U	01.10.2025	-
38	UASB	U.P. Jal Nigam	U	08.10.2025	Grab
6.5	SBR	Jal Kal	O	08.10.2025	Grab
37.5	SBR	U.P. Awas vikas Parishad	O	08.10.2025	Grab
345	UASB	U.P. Jal Nigam	U	08.10.2025	Grab
56	FAB	U.P. Jal Nigam	U	09.10.2025	Grab
1.5	MBBR	Nagar Nigam (Smart City)	O	09.10.2025	Grab
39	SBR	U.P. Jal Nigam	R	09.10.2025	Grab
80	SBR	U.P. Jal Nigam	U	08.10.2025	Grab
0	SBR	LDA	O	08.10.2025	-
56	UASB	U.P. Jal Nigam	U	8.10.2025	Grab
20	MBBR	U.P. Jal Nigam	U	3.10.2025	Grab
74	SBR	U.P. Jal Nigam	U	8.10.2025	Grab
1.5	SBR	GDA	O	3.10.2025	Grab
4.62	UASB followed by extended aeration	U.P. Jal Nigam (NGRBA)	R	6.10.2025	Grab
2.57	UASB followed by extended aeration	U.P. Jal Nigam (NGRBA)	R	6.10.2025	Grab
20	SBR	Nagar Nigam	O	8.10.2025	Grab
56	SBR	U.P. Jal Nigam	U	8.10.2025	Grab

70	UASB	U.P. Jal Nigam	U	8.10.2025	Grab
2.57	UASB	U.P. Jal Nigam	U	6.10.2025	Grab
3.81	MBBR	UPSIDA	O	3.10.2025	Grab
14	SBR	GDA	O	3.10.2025	Grab
7.8	SBR	U.P. Jal Nigam	U	3.10.2025	Grab
27	SBR	Nagar Nigam	O	8.10.2025	Grab
8	SBR	U.P. Jal Nigam	U	6.10.2025	Grab
4.5	SBR	Awas Vikas	O	8.10.2025	Grab
78	UASB	U.P. Jal Nigam	U	04.10.2025	Grab
2.25	WSP	U.P. Jal Nigam	U	04.10.2025	Grab
10	WSP	U.P. Jal Nigam	U	04.10.2025	Grab
8	UASB	U.P. Jal Nigam	U	04.10.2025	Grab
14	UASB	U.P. Jal Nigam	U	04.10.2025	Grab
28.5	UASB	U.P. Jal Nigam	U	04.10.2025	Grab
36	SBR	ADA	O	04.10.2025	Grab
15	UASB	U.P. Jal Nigam	U	04.10.2025	Grab
4.5	UASB	ADA	O	04.10.2025	Grab
2.7	ASP	MDA	O	04.10.2025	Grab
6.5	ASP	MDA	O	04.10.2025	Grab
7	ASP	MDA	O	04.10.2025	Grab
4.4	ASP	MDA	O	04.10.2025	Grab
2	ASP	MDA	O	04.10.2025	Grab
4.8	ASP	MDA	O	04.10.2025	Grab
4.5	ASP	MDA	O	04.10.2025	Grab
5.5	ASP	MDA	O	04.10.2025	Grab
5.95	UASB	MDA	O	04.10.2025	Grab
4.9	ASP	MDA	O	04.10.2025	Grab

4	ASP	MDA	O	04.10.2025	Grab
72	ASP	U.P. Jal Nigam	U	09.10.2025	Grab
3.8	SBR	MDA	O	04.10.2025	Grab
5.6	SBR	MDA	O	04.10.2025	Grab
7.8	SBR	U.P. Jal Nigam	R	04.10.2025	Grab
32.5	WSP	U.P. Jal Nigam	U	08.10.2025	Grab
18.48	SBR	U.P. Jal Nigam	R	08.10.2025	Grab
7.32	SBR	U.P. Jal Nigam	R	08.10.2025	Grab
21.18	SBR	U.P. Jal Nigam	R	08.10.2025	Grab
15	SBR	U.P. Jal Nigam	U	08.10.2025	Grab
7	UASB	U.P. Jal Nigam	U	06.10.2025	Grab
4	SBR	U.P. Jal Nigam	U	06.10.2025	-
6.8	WSP	U.P. Jal Nigam	R	09.10.2025	Grab
4	WSP	U.P. Jal Nigam	R	08.10.2025	Grab
8	UASB	U.P. Jal Nigam	U	08.10.2025	Grab
14.5	WSP	U.P. Jal Nigam	R	09.10.2025	Grab
30	SBR	U.P. Jal Nigam	R	09.10.2025	Grab
15	UASB	U.P. Jal Nigam	R	09.10.2025	Grab
0	WSP	Nagar Palika Parishad	O	09.10.2025	-
13	SBR	Noida Authority	O	06.10.2025	Grab
14	SBR	Noida Authority	O	06.10.2025	Grab
17	SBR	Noida Authority	O	06.10.2025	Grab
17	SBR	Noida Authority	O	06.10.2025	Grab
31	SBR	Noida Authority	O	06.10.2025	Grab
43	SBR	Noida Authority	O	06.10.2025	Grab
61	SBR	Noida Authority	O	06.10.2025	Grab
64	SBR	Noida Authority	O	06.10.2025	Grab
2	SBR	GNIDA	O	09.10.2025	Grab
8	SBR	GNIDA	O	09.10.2025	Grab

14	SBR	GNIDA	O	09.10.2025	Grab
95	SBR	GNIDA	O	09.10.2025	Grab
0.805	WSP	U.P. Jal Nigam	U	06.10.2025	Grab
1.75	WSP	U.P. Jal Nigam	U	06.10.2025	Grab
2.25	ASP	Narora Atomic power Station	O	06.10.2025	Grab
1	MBBR	U.P. Jal Nigam	R	06.10.2025	Grab
1.5	UASB	U.P. Jal Nigam	R	13.10.2025	Grab
20	SBR	U.P. Jal Nigam	U	06.10.2025	Grab
4	UASB	U.P. Jal Nigam	R	06.10.2025	Grab
23.5	UASB	U.P. Jal Nigam	U	04.10.2025	Grab
24	UASB	U.P. Jal Nigam	R	02.10.2025	Grab
14	SBR	MDA	O	02.10.2025	Grab
10	UASB	U.P. Jal Nigam	U	02.10.2025	Grab
4	SBR	U.P. Jal Nigam	U	02.10.2025	Grab
11	UASB	U.P. Jal Nigam	U	02.10.2025	Grab
9.6	SBR	U.P. Jal Nigam	R	10.10.2025	Grab
16	SBR	U.P. Jal Nigam	U	10.10.2025	Grab
18	SBR	U.P. Jal Nigam	U	10.10.2025	Grab
7.2	FAB	U.P. Jal Nigam	U	01.10.2025	Grab
1.4	SBR	U.P. Jal Nigam	R	04.10.2025	Grab
4.3	SBR	U.P. Jal Nigam	R	04.10.2025	Grab
7.1	Aerated Lagoon	U.P. Jal Nigam	R	04.10.2025	Grab
4.8	SBR	U.P. Jal Nigam	U	06.10.2025	Grab
0	ASP	Nagar Nigam	O	8.10.2025	-
42	SBR	U.P. Jal Nigam	R	8.10.2025	Grab
18	SBR	U.P. Jal Nigam	R	8.10.2025	Grab
1	SBR	U.P. Jal Nigam	R	8.10.2025	Grab
10	SBR	U.P. Jal Nigam	U	8.10.2025	Grab
13	SBR	U.P. Jal Nigam	R	04.10.2025	Grab
12	SBR	U.P. Jal Nigam	R	06.10.2025	Grab
0	SBR	UPJN (Rural)	R	06.10.2025	-
0	SBR	UPJN (Urban)	U	01.10.2025	-

0	SBR	UPJN (Rural)	R	09.10.2025	-
0	SBR	UPJN (Urban)	U	01.10.2025	-
0	SBR	UPJN(Rural)	R	02.10.2025	-

Applicable Effluent Discharge Standards for STPs" are as follows:

√/100 ml

000 MPN/100 ml

pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/1 00ml)	FC (MPN/1 00ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
8.2	28	130	48	12000	930	Achieving
7.8	9	60	8	8400	780	Achieving
8	25	140	43	11000	910	Achieving
8.5	26	150	40	12000	920	Achieving
7.9	14	80	13	9400	810	Achieving
8	23	120	38	9400	810	Achieving
8	26	160	44	11000	920	Achieving
8.2	26	150	42	11000	910	Achieving
6.92	21	104.76	16	4100	1200	Not Achieving
7.26	17	77.6	12	3400	910	Achieving
7.23	22.5	151.32	12	3400	930	Achieving
7.94	27.5	128.04	19	3400	920	Achieving
7.72	22.5	150	48	270	140	Achieving
7.69	36	170	68	81000	61000	Not Achieving
7.75	18	160	56	1400	320	Achieving
7.78	16.5	140	52	1400	320	Achieving
7.6	18	100	52	330	270	Achieving
7.62	21	140	52	250	150	Achieving
7.85	40.5	180	62	84000	63000	Not Achieving

7.95	24	130	52	790	490	Achieving
7.86	18	130	54	810	600	Achieving
7.51	25.4	72	67	22000	780	Achieving
7.68	22.8	48	41	1400	610	Achieving
7.78	24	64	58	2000	680	Achieving
7.74	27.2	92	76	2700	930	Achieving
7.72	26.5	80	70	2400	920	Achieving
7.66	19	40	32	1700	610	Achieving
7.81	27	88	73	2600	920	Achieving
7.63	24.9	68	63	2100	780	Achieving
7.59	23.2	56	49	1700	700	Achieving
Not operational Due to Maintenance Work						
7.6	14.4	68	18	430	220	Achieving
7.69	28.4	166	96	540	220	Achieving
7.52	26.2	144	86	920	240	Achieving
7.42	9.4	46	14	350	130	Achieving
7.54	8.8	44	16	430	170	Achieving
7.36	26.2	194	96	840	330	Achieving
Not operational Due to Maintenance Work						
7.69	7.6	42	8.4	310	170	Achieving
7.58	8.2	46	18	430	220	Achieving
7.46	28.2	142	48	1100	790	Achieving
7.52	8.6	44	16	350	170	Achieving
7.62	8	40	18	280	130	Achieving

7.71	8.5	36	25	2000	820	Achieving
7.71	8.5	36	25	2000	820	Achieving
7.82	8	32	22	2100	910	Achieving
7.9	8.5	36	25	2100	910	Achieving
Under Trial Run						
7.3	24	172	40	660	320	Achieving
7.3	18	90	48	4900	930	Achieving
7.43	12	56	38	4000	610	Achieving
7.5	16	74	45	4900	780	Achieving
7.38	17	98	46	7000	780	Achieving
7.29	17	82	46	3400	450	Achieving
7.53	14	62	40	2200	680	Achieving
7.32	13	66	44	4600	780	Achieving
Not operational Due to Maintenance Work						
7.42	18	86	42	2100	610	Achieving
7.53	9	78	10	1600	540	Achieving
7.55	9	80	10	2200	400	Achieving
7.34	8	52	10	1100	400	Achieving
7.41	8	40	10	2100	610	Achieving
7.44	9	32	10	2500	450	Achieving
7.5	7	42	9	2800	790	Achieving
7.38	9	64	10	2500	830	Achieving

7.76	22	94	40	2100	930	Achieving
7.44	20	76	45	1600	920	Achieving
7.58	10	96	42	2200	400	Achieving
7.62	8	60	9	1600	540	Achieving
7.5	16	86	45	2400	780	Achieving
7.43	14	70	43	1700	400	Achieving
7.64	18	136	50	2200	790	Achieving
7.65	14	80	37	1600	540	Achieving
7.86	25	100	34	4800	680	Achieving
7.88	28	120	40	6300	810	Achieving
7.89	26	160	44	3400	930	Achieving
7.7	24	120	36	3800	910	Achieving
7.91	22	100	38	3400	930	Achieving
7.92	28	140	48	3100	680	Achieving
7.98	27	140	58	6300	810	Achieving
7.83	24	120	34	4800	680	Achieving
7.27	27	140	56	5800	910	Achieving
7.61	17	136	64	930	780	Achieving
7.38	15	92	40	830	610	Achieving
7.45	16	104	44	910	680	Achieving
7.56	16	112	56	910	680	Achieving
7.29	8	28	22	680	560	Achieving
7.36	8	32	20	780	600	Achieving
7.43	12	36	28	780	600	Achieving
7.42	14	96	56	910	680	Achieving
7.42	10	36	20	780	600	Achieving
7.33	14	72	32	830	610	Achieving

7.41	16	100	48	920	780	Achieving
7.43	8	24	8	810	610	Achieving
7.31	10	32	24	780	560	Achieving
7.52	17	112	50	930	830	Achieving
7.44	15	92	56	910	680	Achieving
7.5	22	76	40	1700	840	Achieving
7.6	9	28	16	1100	210	Achieving
7.2	8	26	16	1100	130	Achieving
7.4	7	24	14	1300	140	Achieving
7.3	6	22	18	1400	170	Achieving
7.05	18	89	40	4900	780	Achieving
Not Operational Due To Maintenance Work						
8.1	27	248	88	3900	930	Achieving
7.9	26	248	90	3800	920	Achieving
8	25	216	80	3200	920	Achieving
8.4	40	416	174	11000	2700	Not Achieving
7.8	25	216	76	2600	920	Achieving
7.9	24	224	74	3300	930	Achieving
Not operational Due to Maintenance Work						
7.45	14.6	128	32	1600	540	Achieving
7.31	14.1	96.8	28	2400	920	Achieving
7.63	13.5	120	30	2500	830	Achieving
7.51	15.6	118.4	33	2200	680	Achieving
7.37	13.3	108.8	26	1200	610	Achieving
7.51	13.2	82.2	24	1200	610	Achieving
7.62	12.5	85.6	33	1700	200	Achieving
7.68	12.4	102.4	23	1700	400	Achieving
7.48	10	78	35	2600	780	Achieving
7.22	12	76	40	2200	790	Achieving

7.35	10	60	32	1600	220	Achieving
7.48	16	84	47	2200	790	Achieving
7.74	22	92	41	1200	610	Achieving
7.67	20	88	44	1400	680	Achieving
7.52	16	64	47	540	240	Achieving
7.63	24	112	81	2100	780	Achieving
8.93	28	140	87	2100	920	Achieving
7.61	18	88	55	1100	400	Achieving
7.71	20	128	62	1700	930	Achieving
7.6	10	40	22	940	110	Achieving
7.61	6.2	72	7	930	61	Achieving
7.64	14	74	32	1700	680	Achieving
7.73	22	78	28	1400	610	Achieving
7.58	6.4	82	6	680	61	Achieving
7.76	20	76	34	2100	930	Achieving
7.38	24.8	104	76	1500	840	Achieving
7.48	16.4	96	52	2600	920	Achieving
7.34	27.8	244	89	2100	930	Achieving
7.94	22.0	52.80	36.0	700	230	Achieving
8.01	20.0	57.60	32.0	2100	930	Achieving
8.05	27.0	62.4	34.0	2100	920	Achieving
7.06	23.0	64.00	35.0	2000	930	Achieving
7.99	8.0	42.88	7.0	790	210	Achieving
Not operational Due to Maintenance Work						
7.6	6	48	14	220	79	Achieving
7.3	8	36	17	210	79	Achieving
7.5	6	32	13	220	79	Achieving
7.2	6	32	9	210	68	Achieving
8.26	14.8	152	76.2	4100	930	Achieving
7.61	6.7	38	7.8	350	170	Achieving
Under Trial Run						
Not operational Due to Maintenance Work						

Not operational Due to Maintenance Work	
Under Trial Run	
Under Trial Run	

Performa

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Utilized Capacity (MLD)	Technology/ process STP based
1	10.445 MLD STP near Tixi Tempel (Karanpur)	2001	Etawah	10.445	8	WSP
2	21 MLD STP Etawah	2022	Etawah	21	20	SBR
3	13.5 MLD STP at Mauja Umrain	2013	Etawah	13.5	12.5	SBR
4	03 MLD STP Firozabad	2014	Firozabad	3	1.4	UASB
5	67 MLD STP Mohammadpur, Biharipur	2020	Firozabad	67	52	ASP+ extended aeration
6	1.65 MLD STP Saifai (Paramedicals)	2013	Etawah	1.65	0.9	SBR
7	23 MLD STP at Mauja Odenya, Padaria	2014	Mainpuri	23	17	UASB
8	1.5 MLD STP Saifai Village, Etawah	2006	Etawah	1.5	1.1	Oxidation Pond
9	26 MLD STP Jhansi Laxmi Taal	2021	Jhansi	26	22	SBR
9	26 MLD STP Jhansi Laxmi Taal	2021	Jhansi	26	4	SBR

10	26 MLD STP Smart City, Lahargird	2025	Jhansi	26	26	SBR
11	3.42 MLD STP Near Divyang kendra	2000	Chitrakoot	3.42	3.42	Oxidatio n Pond
12	42 MLD STP, Sajari Kanpur	2016-17	Kanpur Nagar	42	22	ASP
13	210 MLD STP, Bingawan Kanpur	2015-16	Kanpur Nagar	210	110	UASB
14	130 MLD STP Jajmau, Kanpur	1998-99	Kanpur Nagar	130	115	ASP
15	43 MLD STP Jajmau, Kanpur	2020	Kanpur Nagar	43	40	UASB
16	13 MLD STP Jalalpur, Amrapur, Kannuaj	2017	Kanpur Dehat	13	12	SBR
17	30 MLD STP Pankha, Kanpur	2023	Kanpur Nagar	30	30	SBR
18	36 MLD STP Jajmau, Kanpur	9+27 MLD (1992) = 36 MLD (2024)	Kanpur Nagar	36	25	UASB
19	17.7 MLD STP Fatehgarh, Farrukhabad	2024	Kanpur Nagar	17.7	17.7	SBR
20	30 MLD STP Farrukhabad	2024	Kanpur Nagar	30	30	SBR
21	50 MLD STP Numayadahi	2013	Prayagraj	50	50	HRBF
22	10 MLD STP Ponghat	2013	Prayagraj	10	10	HRBF
23	25 MLD STP Kodra	2013	Prayagraj	25	25	HRBF
24	60 MLD STP Rajapur	2013	Prayagraj	60	60	UASB

25	29 MLD STP Salori-1	2007	Prayagraj	29	29	FAB
26	14 MLD STP Salori-2 Expansion	2016	Prayagraj	14	14	SBR
27	80 MLD STP Naini	2013	Prayagraj	80	80	ASP
28	42 MLD STP, Naini	2023	Prayagraj	42	36	FCR
29	14 MLD STP Phaphamau	2023	Prayagraj	14	14	FCR
30	16 MLD STP Jhunsi	2023	Prayagraj	16	0	FCR
31	10 MLD STP Ramnagar	2021	Varanasi	10	9.5	Anaerobic Anoxic Oxic (A2O)
32	80 MLD STP Dinapur	1994	Varanasi	80	68	ASP
33	9.8 MLD STP Bhagwanpur	1989	Varanasi	9.8	9.8	ASP
34	140 MLD STP Dinapur	2018	Varanasi	140	99	ASP
35	120 MLD STP Goithaha	2019	Varanasi	120	40	UASB
36	12 MLD BLW STP	1989	Varanasi	12	12	ASP
37	50 MLD STP Ramana	2021	Varanasi	50	50	SBR
38	30 MLD STP Pachhahatiya Jaunpur	2023	Jaunpur, Varanasi	30	30	A2O
39	07 MLD Vindychal Mirzapur	2022	Mirzapur	7	4.933	WSP
40	14 MLD STP Pakka Pokhra	1994	Mirzapur	14	13.22	UASB
41	8.5 MLD STP Pakka Pokhra, Mirzapur	2024	Mirzapur	8.5	4.15	SBR

42	8.5 MLD STP Bisunderpur, Mirzapur	2024	Mirzapur	8.5	7.6	SBR
43	15 MLD S.T.P. Jharkhandi, Maherwa ki Bari	2015	Gorakhpur	15	11.89	SBR
44	5 MLD S.T.P. Jharkhandi, Maherwa ki Bari	2023	Gorakhpur	5	4.5	SBR
45	30 MLD S.T.P. Opp. Manyavar Kanshiram Shahri Garib Awas Yojna, Deoria bypass Road	2015	Gorakhpur	30	19.83	SBR
46	10 MLD STP Gorakhpur	2024	Gorakhpur	10	10	SBR
47	8 MLD STP Azamgarh	2024	Azamgarh	8	0	SBR
48	38 MLD STP, Mahilpur Road	1998	Saharanpur	38	38	UASB
49	6.5 MLD STP Awas vikas Parishad STP	2018	Lucknow	6.5	6.5	SBR
50	37.5 MLD STP Awas vikas Parishad STP	2017	Lucknow	37.5	37.5	SBR
51	345 MLD STP, Bharwara	2011	Lucknow	345	345	UASB
53	56 MLD STP, Daulatganj	2003 & 2009	Lucknow	56 (42+14)	56	FAB
54	1.5 MLD STP Hathi Park, (Smart City)	2021	Lucknow	1.5	1.5	MBBR
55	39 MLD STP, Sajjadbagh, Daulatganj	2024	Lucknow	39	39	SBR
56	120 MLD STP near 1090 Chauraha	2025	Lucknow	120	80	SBR
57	19 MLD STP C.G. City, Lucknow	2023	Lucknow	19	0	SBR

58	56 MLD STP Trans Hindon (Indirapuram), Ghaziabad	2000	Ghaziabad	56	56	UASB
59	30 MLD STP, Sadullabad (Loni), Ghaziabad	2012	Ghaziabad	30	20	MBBR
60	74 MLD STP S.B.R., Indirapuram, Ghaziabad	2013	Ghaziabad	74	74	SBR
61	56 MLD STP S.B.R., Bapudham, Ghaziabad	2014	Ghaziabad	56	1.5	SBR
62	6 MLD STP Garh Zone, Garhmukeshwar Hapur	2011	Hapur / Garhmukteswar	6	4.62	UASB followed by extended aeration
63	3 MLD STP Brijghat Zone, Garhmukeshwar Hapur	2011	Hapur / Garhmukteswar	3	2.57	UASB followed by extended aeration
64	56 MLD STP , Indirapuram, (GDA), Ghaziabad	2012	Ghaziabad	56	20	SBR
65	56 MLD STP S.B.R., Dudahaida Vijay Nagar, Ghaziabad	2013	Ghaziabad	56	56	SBR
66	70 MLD STP U.A.S.B.R. Dudahaida Vijay Nagar, Ghaziabad	2000	Ghaziabad	70	70	UASB
67	3 MLD STP Pilkhaun	2015	Ghaziabad	3	2.57	UASB

68	5 MLD STP Trans Delhi Signature City (Tronica City), Loni	2019	Ghaziabad	5	3.81	MBBR
69	56 MLD STP S.B.R. Govindpuram, Ghaziabad	2014	Ghaziabad	56	14	SBR
70	20 MLD STP Modinagar	2023	Modinagar, Ghaziabad	20	7.8	SBR
71	56 MLD STP S.B.R., Morty, Ghaziabad	2018	Ghaziabad	56	27	SBR
72	30 MLD STP, Rampur Road, Hapur	2022	Hapur, Ghaziabad	30	8	SBR
73	21.5 MLD STP Siddharthvihar, Ghaziabad	2024	Ghaziabad	21.5	4.5	SBR
74	78 MLD STP Dhadhupura, Agra	2013	Agra	78	78	UASB
75	2.25 MLD STP Budi ka Nagla, Agra	2000	Agra	2.25	2.25	WSP
76	10 MLD STP Peelakhar, Agra	2000	Agra	10	10	WSP
77	12 MLD STP Devri Road, (Bhimnagri), Agra	2011	Agra	12	8	UASB
78	14 MLD STP Jaganpur, Sikandarpur, Agra	2011	Agra	14	14	UASB
79	40 MLD STP Sadarban, Bichhpuri, Agra	2013	Agra	40	28.5	UASB
80	36 MLD STP Sadarwan (Bichpuri) New	2018	Agra	36	36	SBR

81	24 MLD STP Dhadhupura (New), Agra	2014	Agra	24	15	UASB
82	4.50 MLD STP Kalindi Vihar, Agra	2014	Agra	4.5	4.5	UASB
83	03 MLD STP Pandav Nagar, Meerut	2013	Meerut	3	2.7	ASP
84	07 MLD STP Pallavpuram-1, Meerut	2012	Meerut	7	6.5	ASP
85	11 MLD STP Pallavpuram-2, Meerut	2008	Meerut	11	7	ASP
86	06 MLD STP Rakshapuram, Meerut	2011	Meerut	6	4.4	ASP
87	10 MLD STP Lohiya Nagar, Meerut	2010	Meerut	10	2	ASP
88	15 MLD STP Shatabdinagar, Meerut	2010	Meerut	15	4.8	ASP
89	15 MLD STP Vedvyaspuri Meerut	2011	Meerut	15	4.5	ASP
90	06 MLD STP Shradhapuri-1, Meerut	2012	Meerut	6	5.5	ASP
91	06 MLD STP Sainik Vihar	2017	Meerut	6	5.95	UASB
92	5 MLD STP Modipuram Tiraha	2016	Meerut	5	4.9	ASP
93	07 MLD STP Sports Goods Complex, Meerut	2012	Meerut	7	4	ASP
94	72 MLD STP Garh road (Jagruti vihar) Kamalpur	2018	Meerut	72	72	ASP

95	10 MLD STP Ganga Nagar, Meerut	2011	Meerut	10	3.8	SBR
96	06 MLD STP Shradhapuri- Phase-2, Meerut	2012	Meerut	6	5.6	SBR
97	14 MLD STP Baghpat, Meerut	2021	Baghpat, Meerut	14	7.8	SBR
98	32.5 MLD STP (WSP) Nagar Palika Parishad, Kidwai nagar	2001	Muzaffar Nagar	32.5	32.5	WSP
99	32.5 MLD STP Near A2Z Garbage plant KidwaiNagar	2025	Muzaffar Nagar	32.5	18.48	SBR
100	10 MLD STP Budhana	2024	Muzaffar Nagar	10	7.32	SBR
101	22 MLD STP Sahawali, Muzaffarnagar	2023	Muzaffar Nagar	22	21.18	SBR
102	15 MLD STP Kairana, Shamli, Muzaffarnagar	2024	Muzaffar Nagar	15	15	SBR
103	12 MLD STP Ayodhya	2014	Ayodhya	12	7	UASB
104	6 MLD STP Ramghat, Ayodhya	2023	Ayodhya	6	4	SBR
105	13.59 (6.8) MLD STP, Masani, Mathura	2007	Mathura	6.8	6.8	WSP
106	04 MLD STP Vrindavan Near Pagal Baba Mandir, Mathura	2007	Mathura	4	4	WSP
107	08 MLD STP Near 100 Bed Hospital Vrindavan, Manth road	2015	Mathura	8	8	UASB

108	14.5 MLD STP Trans-yamuna, Jamunapar, Mathura	2007	Mathura	14.5	14.5	WSP
109	30 MLD STP Masani Mathura	2020	Mathura	30	30	SBR
110	16 MLD STP Trans Yamuna, Laxmi Nagar, Mathura	2015	Mathura	16	15	UASB
111	2.76 MLD STP Goverdhan STP	2011	Mathura	2.76	0	WSP
112	33 MLD STP Sector-54, Noida	2011	Noida	33	13	SBR
113	25 MLD STP Sector-50, Noida	2015	Noida	25	14	SBR
114	35 MLD STP Sector-123, Noida	2011	Noida	35	17	SBR
115	50 MLD STP Sector-168, Noida	2015	Noida	50	17	SBR
116	34 MLD STP Sector -50 Noida	2012	Noida	34	31	SBR
117	54 MLD STP Sector- 54, Noida	2012	Noida	54	43	SBR
118	100 MLD STP Sector- 168, Noida	2023	Noida	100	61	SBR
119	80 MLD STP Sector- 123, Noida	2023	Noida	80	64	SBR
120	2.0 MLD STP Greater Noida Authority STP, Vill- Badalpur	2015	Greater Noida	2	2	SBR
121	15 MLD STP ECO tech -2	2018	Greater Noida	15	8	SBR
122	20 MLD STP ECO tech -3	2018	Greater Noida	20	14	SBR

123	137 MLD STP Kasana, GreaterNoida	2015	Greater Noida	137	95	SBR
124	0.805 MLD STP Ahara Road, Zone-A, Anoopshahar	2003	Bulandshahar	0.805	0.805	WSP
125	1.75 MLD STP Ahara Road, (Shivanand Ashram) Zone- B, Anoopshahar	2003	Bulandshahar	1.75	1.75	WSP
126	2.25 MLD STP Narora Atomic power Station Narora Township	2000	Bulandshahar	2.25	2.25	ASP
127	01 MLD STP Zone-B Anoopshahar	2016	Bulandshahar	1	1	MBBR
128	1.5 MLD STP Anoopshahar Zone A (NGRBA)	2016	Bulandshahar	1.5	1.5	UASB
129	40 MLD STP Bulandshahar	2023	Bulandshahar	40	20	SBR
130	04 MLD STP , Narora (NGRBA)	2015	Bulandshahar	4	4	UASB
131	24 MLD STP, Bijnor	2018	Bijnor	24	23.5	UASB
132	58 MLD STP Moradabad	2018	Moradabad	58	24	UASB
133	20 MLD STP Moradabad	2017	Moradabad	20	14	SBR
134	14 MLD STP, Benzirpur	2016	Rampur	14	10	UASB
135	5 MLD STP , Rampur	2016	Rampur	5	4	SBR
136	15 MLD STP Pehrigaon	2015	Rampur	15	11	UASB
137	15 MLD STP, Kasganj	2022	Kasganj, Aligarh	15	9.6	SBR

138	24 MLD STP, Manpur, Etah	2023	Etah, Aligarh	24	16	SBR
139	45 MLD STP Laxmi Nagar, Aligarh	2023	Aligarh	45	18	SBR
140	8.95 MLD STP Bela, Pratapgarh	2023	Pratapgarh	8.95	7.2	FAB
141	5 MLD STP Palhipur, Sultanpur	2024	Sultanpur	5	1.4	SBR
142	2 MLD STP Miranpur, Sadar, Sultanpur	2024	Sultanpur	2	4.3	SBR
143	10 MLD STP Hathia Nala, Lolepur	2006	Sultanpur	10	7.1	Aerated Lagoon
144	18 MLD STP Raebareli	2023	Raebareli	18	4.8	SBR
145	35 MLD STP, Saraitalfi	2023	Bareilly	35	0	ASP
146	42 MLD STP, HarooNagla, Bareilly	2024	Bareilly	42	42	SBR
147	20 MLD STP Barinagla, Bareilly	2024	Bareilly	20	18	SBR
148	01 MLD STP, Girdaripur, Bareilly	2024	Bareilly	1	1	SBR
149	40 MLD STP, Shahjahanpur	2025	Shahjahanpur	40	10	SBR
150	15 MLD STP Unnao	2024	Unnao	15	13	SBR
151	21 MLD STP Mau Road, Ghazipur	2024	Ghazipur, Varanasi	21	12	SBR
152	33 MLD STP Ayodhya	2025	Ayodhya	33	0	SBR
153	15 MLD STP Baniyapur	2018	Kanpur Nagar	15	0	SBR

154	5 MLD STP Yamuna Expressway Industrial Development Authority (YIDA)	2023	Jewar (Gt. Noida)	5	0	SBR
155	20 MLD STP Ballia	2025	Ballia	20	0	SBR
156	25 MLD STP Moradabad	2025	Moradabad	25	0	SBR

Note :- The standards as per MoEF&CC Notification dated 13.10.2017, ti

For State Capital: pH-6.5-9.0; BOD - <20 mg/l; TSS- <50 mg/l & FC- <100

Other than State Capital: pH-6.5-9.0; BOD - <30 mg/l; TSS- <100 mg/l &

Note:- As per the data received from Regional offices, UPPCB

Presence of Existing STPs in U.P. OCTOBER- 2025
Second Week

Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Rural (R)\Urban(U)\O ther(O)	Date of Sampling	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)
UP Jal Nigam	R	14.10.2025	Grab	8	26	150	47
UP Jal Nigam	R	14.10.2025	Grab	8.2	8.8	60	9
UP Jal Nigam	R	14.10.2025	Grab	7.8	24	120	46
NPP	O	13.10.2025	Grab	8.1	27	170	43
U.P. Jal Nigam	U	13.10.2025	Grab	7.9	8.4	60	9
Others	O	14.10.2025	Grab	7.9	25	140	36
U.P. Jal Nigam	U	13.10.2025	Grab	7.9	24	140	40
U.P. Jal Nigam	U	14.10.2025	Grab	8	27	170	47
U.P. Jal Nigam	U	09.10.2025	Composite	7.29	25.6	42.68	12
U.P. Jal Nigam	U	09.10.2025	Composite	7.12	22.5	72.96	10

Nagar Nigam	O	09.10.2025	Composite	7.4	20.95	34.92	10
Nagar Palika Parishad	O	13.10.2025	Grab	7.94	27.5	128.04	19
U.P. Jal Nigam	R	14.10.2025	Grab	7.71	21	140	52
U.P. Jal Nigam	R	14.10.2025	Grab	7.7	39	180	64
U.P. Jal Nigam	R	14.10.2025	Grab	7.73	19.5	170	62
U.P. Jal Nigam	R	14.10.2025	Grab	7.89	18	150	48
U.P. Jal Nigam	U	07.10.2025	Grab	7.7	22.5	110	54
U.P. Jal Nigam	R	14.10.2025	Grab	7.64	19.5	130	44
U.P. Jal Nigam	U	14.10.2025	Grab	7.88	39	170	60
U.P. Jal Nigam	R	14.10.2025	Grab	7.93	18	140	62
U.P. Jal Nigam	R	14.10.2025	Grab	7.85	42.5	160	58
Ganga Pollution control unit, U.P. Jal Nigam	R	13.10.2025	Grab	7.11	24.8	64	56
Ganga Pollution control unit, U.P. Jal Nigam	R	13.10.2025	Grab	7.03	22	40	32
Ganga Pollution control unit, U.P. Jal Nigam	R	13.10.2025	Grab	7.13	23.6	60	50
Ganga Pollution control unit, U.P. Jal Nigam	R	14.10.2025	Grab	7.26	27.4	88	72

Ganga Pollution control unit, U.P. Jal Nigam	R	14.10.2025	Grab	7.31	26.2	76	64
Ganga Pollution control unit, U.P. Jal Nigam	U	14.10.2025	Grab	7.09	17.6	32	22
Ganga Pollution control unit, U.P. Jal Nigam	R	13.10.2025	Grab	7.39	26.8	84	68
U.P. Jal Nigam	R	13.10.2025	Grab	7.21	25.2	72	64
U.P. Jal Nigam	R	14.10.2025	Grab	7.15	23	52	42
U.P. Jal Nigam	R	14.10.2025	-	Not operational Due to Mainten			
U.P. Jal Nigam	R	16.10.2025	Grab	7.48	16.8	74	22
U.P. Jal Nigam	U	10.10.2025	Grab	7.56	29	172	92
U.P. Jal Nigam	R	16.10.2025	Grab	7.58	27.3	158	86
U.P. Jal Nigam	U	10.10.2025	Grab	7.64	8.2	40	18
U.P. Jal Nigam	U	10.10.2025	Grab	7.62	8.4	40.8	16
BLW	O	16.10.2025	Grab	7.42	29.2	184	84
U.P. Jal Nigam	R	10.10.2025	-	Not operational Due to Mainten			
U.P. Jal Nigam	R	16.10.2025	Grab	7.58	7.3	38	8
Nagarpalika	U	28.10.2025	Grab	7.58	8.2	46	18
U.P. Jal Nigam	R	28.10.2025	Grab	7.46	28.2	142	48
U.P. Jal Nigam	R	28.10.2025	Grab	7.52	8.6	44	16

U.P. Jal Nigam	R	28.10.2025	Grab	7.62	8	40	18
U.P. Jal Nigam	U	14.10.2025	Grab	7.98	8	32	22
U.P. Jal Nigam	U	14.10.2025	Grab	7.98	8	32	22
U.P. Jal Nigam	U	14.10.2025	Grab	7.64	9	40	27
U.P. Jal Nigam	U	14.10.2025	Grab	7.9	8.5	36	25
U.P. Jal Nigam	U	10.10.2025	-	Under Trial Run			
U.P. Jal Nigam	U	14.10.2025	Grab	7.4	25	180	42
Jal Kal	O	16.10.2025	Grab	7.35	16	70	38
U.P. Awas vikas Parishad	O	16.10.2025	Grab	7.42	14	48	30
U.P. Jal Nigam	U	16.10.2025	Grab	7.36	18	82	48
U.P. Jal Nigam	U	15.10.2025	Grab	7.39	16	108	47
Nagar Nigam (Smart City)	O	15.10.2025	-	Not operational Due to Mainten			
U.P. Jal Nigam	R	15.10.2025	Grab	7.35	13	66	28
U.P. Jal Nigam	U	15.10.2025	Grab	7.31	12	64	24
LDA	O	15.10.2025	-	Not operational Due to Mainten			

U.P. Jal Nigam	U	15.10.2025	Grab	7.63	24	92	55
U.P. Jal Nigam	U	14.10.2025	Grab	7.42	8	66	9
U.P. Jal Nigam	U	15.10.2025	Grab	7.51	8	68	9
GDA	O	13.10.2025	Grab	7.4	7	32	9
U.P. Jal Nigam (NGRBA)	R	13.10.2025	Grab	7.4	9	44	10
U.P. Jal Nigam (NGRBA)	R	13.10.2025	Grab	7.52	8	38	9
Nagar Nigam	O	15.10.2025	Grab	7.54	9	60	10
U.P. Jal Nigam	U	15.10.2025	Grab	7.45	8	60	9
U.P. Jal Nigam	U	15.10.2025	Grab	7.57	20	98	45
U.P. Jal Nigam	U	13.10.2025	Grab	7.46	16	64	40

UPSIDA	O	14.10.2025	Grab	7.45	16	118	50
GDA	O	13.10.2025	Grab	7.49	9	56	10
U.P. Jal Nigam	U	14.10.2025	Grab	7.44	10	78	39
Nagar Nigam	O	15.10.2025	Grab	7.54	12	80	35
U.P. Jal Nigam	U	13.10.2025	Grab	7.49	14	122	48
Awas Vikas	O	15.10.2025	Grab	7.55	10	68	35
U.P. Jal Nigam	U	10.10.2025	Grab	7.86	26	120	44
U.P. Jal Nigam	U	10.10.2025	Grab	7.92	27	120	40
U.P. Jal Nigam	U	10.10.2025	Grab	7.81	28	140	38
U.P. Jal Nigam	U	10.10.2025	Grab	7.7	23	100	42
U.P. Jal Nigam	U	10.10.2025	Grab	7.91	24	120	38
U.P. Jal Nigam	U	10.10.2025	Grab	7.98	28	130	48
ADA	O	10.10.2025	Grab	7.93	27	150	60

U.P. Jal Nigam	U	10.10.2025	Grab	7.89	25	100	36
ADA	O	10.10.2025	Grab	7.83	29	130	62
MDA	O	09.10.2025	Grab	7.51	20	180	52
MDA	O	09.10.2025	Grab	7.55	17	104	50
MDA	O	09.10.2025	Grab	7.38	15	68	48
MDA	O	09.10.2025	Grab	7.47	17	108	44
MDA	O	09.10.2025	Grab	7.39	8	24	20
MDA	O	09.10.2025	Grab	7.41	8	28	18
MDA	O	09.10.2025	Grab	7.43	10	32	32
MDA	O	09.10.2025	Grab	7.44	16	82	46
MDA	O	09.10.2025	Grab	7.38	12	40	24
MDA	O	09.10.2025	Grab	7.54	15	84	36
MDA	O	09.10.2025	Grab	7.46	14	88	40
U.P. Jal Nigam	U	16.10.2025	Grab	7.37	9	28	10

MDA	O	09.10.2025	Grab	7.41	8	28	22
MDA	O	09.10.2025	Grab	7.52	18	124	60
U.P. Jal Nigam	R	09.10.2025	Grab	7.39	22	188	44
U.P. Jal Nigam	U	14.10.2025	Grab	7.3	20	64	48
U.P. Jal Nigam	R	14.10.2025	Grab	7.5	6	24	16
U.P. Jal Nigam	R	14.10.2025	Grab	7.4	8	24	18
U.P. Jal Nigam	R	14.10.2025	Grab	7.6	7	26	14
U.P. Jal Nigam	U	14.10.2025	Grab	7.6	9	28	12
U.P. Jal Nigam	U	13.10.2025	Grab	7.25	24	122	68
U.P. Jal Nigam	U	13.10.2025	Grab	7.28	19	81	56
U.P. Jal Nigam	R	14.10.2025	Compostie	7.9	26	232	84
U.P. Jal Nigam	R	14.10.2025	Composite	7.7	25	232	86
U.P. Jal Nigam	U	14.10.2025	Composite	7.8	24	200	68

U.P. Jal Nigam	R	14.10.2025	Composite	8.7	52	432	188
U.P. Jal Nigam	R	14.10.2025	Composite	7.5	23	192	70
U.P. Jal Nigam	R	14.10.2025	Composite	8.1	26	240	88
Nagar Palika Parishad	O	14.10.2025	-	Not operational Due to Mainten			
Noida Authority	O	13.10.2025	Grab	7.37	13.7	112.8	27
Noida Authority	O	13.10.2025	-	Not operational Due to Mainten			
Noida Authority	O	13.10.2025	Grab	7.28	12.9	16.8	26
Noida Authority	O	13.10.2025	Grab	7.31	14.7	127.2	32
Noida Authority	O	13.10.2025	Grab	7.25	14.5	123.2	29
Noida Authority	O	13.10.2025	Grab	7.63	14.1	110.4	25
Noida Authority	O	13.10.2025	Grab	7.42	13.5	97.6	19
Noida Authority	O	13.10.2025	Grab	7.56	11.5	99.2	21
GNIDA	O	14.10.2025	Grab	7.44	16	80	40
GNIDA	O	14.10.2025	Grab	7.22	10	48	30
GNIDA	O	14.10.2025	Grab	7.35	8	54	25

GNIDA	O	14.10.2025	Grab	7.32	14	60	35
U.P. Jal Nigam	U	13.10.2025	Grab	7.67	26	88	45
U.P. Jal Nigam	U	13.10.2025	Grab	7.71	24	92	43
Narora Atomic power Station	O	13.10.2025	Grab	7.45	18	68	53
U.P. Jal Nigam	R	13.10.2025	Grab	7.61	26	124	89
U.P. Jal Nigam	R	13.10.2025	Grab	8.93	28	140	87
U.P. Jal Nigam	U	13.10.2025	Grab	7.55	20	96	51
U.P. Jal Nigam	R	13.10.2025	Grab	7.76	22	112	69
U.P. Jal Nigam	U	10.10.2025	Grab	7.39	14	48	25
U.P. Jal Nigam	R	14.10.2025	Grab	7.52	6.5	82	8
MDA	O	14.10.2025	Grab	7.78	12	86	34
U.P. Jal Nigam	U	14.10.2025	Grab	7.81	24	72	32
U.P. Jal Nigam	U	14.10.2025	Grab	7.67	6.2	84	7
U.P. Jal Nigam	U	14.10.2025	Grab	7.7	22	78	30
U.P. Jal Nigam	R	16.10.2025	Grab	7.13	28.1	120	86

U.P. Jal Nigam	U	16.10.2025	Grab	6.89	18.2	94	43
U.P. Jal Nigam	U	16.10.2025	Grab	7.28	28.6	142.4	68
U.P. Jal Nigam	U	08.10.2025	Grab	7.90	21.0	49.60	32.0
U.P. Jal Nigam	R	09.10.2025	Grab	8.05	22.0	59.20	36.0
U.P. Jal Nigam	R	09.10.2025	Grab	8.10	28.0	60.8	30.0
U.P. Jal Nigam	R	09.10.2025	Grab	7.94	21.0	60.80	38.0
U.P. Jal Nigam	U	13.10.2025	Grab	7.96	9.0	40.96	8.0
Nagar Nigam	O	14.10.2025	-	Not operational Due to Mainten			
U.P. Jal Nigam	R	14.10.2025	Grab	7.5	8	40	15
U.P. Jal Nigam	R	14.10.2025	Grab	7.6	8	32	18
U.P. Jal Nigam	R	14.10.2025	Grab	7.2	6	48	17
U.P. Jal Nigam	U	14.10.2025	Grab	7.6	8	40	8
U.P. Jal Nigam	R	10.10.2025	Grab	8.02	16.2	168	66.8
U.P. Jal Nigam	R	14.10.2025	Grab	7.56	7.2	42	9
UPJN (Rural)	R	13.10.2025	-	Under Trial Run			
UPJN (Urban)	U	07.10.2025	-	Not operational Due to Mainten			

UPJN (Rural)	R	14.10.2025	-	Not operational Due to Mainten
UPJN (Urban)	U	10.10.2025	-	Under Trial Run
UPJN(Rural)	R	14.10.2025	-	Under Trial Run

itled "Applicable Effluent Discharge Standards for STPs" are as follows:

30 MPN/100 ml

FC- <1000 MPN/100 ml

TC (MPN/1 00ml)	FC (MPN/1 00ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
9400	910	Achieving
7900	780	Achieving
8400	820	Achieving
11000	830	Achieving
8400	780	Achieving
9400	830	Achieving
9400	830	Achieving
12000	930	Achieving
-	-	Achieving
-	-	Achieving

-	-	Achieving
3400	920	Achieving
-	-	Achieving
-	-	Not Achieving
-	-	Achieving
-	-	Achieving
380	260	Achieving
-	-	Achieving
-	-	Not Achieving
-	-	Achieving
-	-	Not Achieving
2300	780	Achieving
1700	700	Achieving
2100	780	Achieving
2400	930	Achieving

2600	930	Achieving
1700	610	Achieving
2400	920	Achieving
2200	680	Achieving
2000	610	Achieving

ance Work

280	130	Achieving
430	170	Achieving
630	230	Achieving
250	130	Achieving
430	150	Achieving
350	140	Achieving

ance Work

350	130	Achieving
430	220	Achieving
1100	790	Achieving
350	170	Achieving

280	130	Achieving
1700	780	Achieving
1700	780	Achieving
2000	930	Achieving
2100	910	Achieving
690	320	Achieving
7000	780	Achieving
4900	680	Achieving
3200	930	Achieving
9400	920	Achieving
ance Work		
3400	450	Achieving
2600	610	Achieving
ance Work		

2800	790	Achieving
2500	780	Achieving
1600	540	Achieving
2100	780	Achieving
2700	680	Achieving
1700	680	Achieving
1600	540	Achieving
2700	680	Achieving
3200	920	Achieving
2200	450	Achieving

1400	610	Achieving
2200	450	Achieving
2200	400	Achieving
2200	790	Achieving
2000	610	Achieving
2500	780	Achieving
4800	680	Achieving
5800	910	Achieving
3400	930	Achieving
4800	680	Achieving
6300	810	Achieving
6300	810	Achieving
3100	680	Achieving

3100	680	Achieving
4800	680	Achieving
930	830	Achieving
920	680	Achieving
830	610	Achieving
920	780	Achieving
780	550	Achieving
810	560	Achieving
810	560	Achieving
920	780	Achieving
830	560	Achieving
910	680	Achieving
910	680	Achieving
820	600	Achieving

810	560	Achieving
920	830	Achieving
930	830	Achieving
2100	700	Achieving
1400	110	Achieving
1700	140	Achieving
1100	130	Achieving
1300	170	Achieving
4600	780	Achieving
3900	920	Achieving
-	-	Achieving
-	-	Achieving
-	-	Achieving

-	-	Not Achieving
-	-	Achieving
-	-	Achieving
ance Work		
1400	680	Achieving
ance Work		
2700	830	Achieving
2500	910	Achieving
2100	930	Achieving
1500	610	Achieving
2200	450	Achieving
1600	540	Achieving
2400	780	Achieving
1700	450	Achieving
1600	540	Achieving

2700	680	Achieving
920	540	Achieving
2200	689	Achieving
1100	400	Achieving
1700	930	Achieving
2100	920	Achieving
1300	680	Achieving
1200	610	Achieving
1300	130	Achieving
610	61	Achieving
1200	680	Achieving
2000	920	Achieving
930	68	Achieving
2000	920	Achieving
1700	680	Achieving

2200	930	Achieving
3400	780	Achieving
680	200	Achieving
2000	780	Achieving
2000	780	Achieving
1700	780	Achieving
680	200	Achieving
ance Work		
150	59	Achieving
170	68	Achieving
170	68	Achieving
220	98	Achieving
4700	680	Achieving
480	220	Achieving
ance Work		

ance Work	

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Utilized Capacity (MLD)
1	10.445 MLD STP near Tixi Tempel (Karanpur)	2001	Etawah	10.445	8
2	21 MLD STP Etawah	2022	Etawah	21	20
3	13.5 MLD STP at Mauja Umrain	2013	Etawah	13.5	12.5
4	03 MLD STP Firozabad	2014	Firozabad	3	1.4
5	67 MLD STP Mohammadpur, Biharipur	2020	Firozabad	67	52
6	1.65 MLD STP Saifai (Paramedicals)	2013	Etawah	1.65	0.9
7	23 MLD STP at Mauja Odenya, Padaria	2014	Mainpuri	23	17
8	1.5 MLD STP Saifai Village, Etawah	2006	Etawah	1.5	1.1
9	26 MLD STP Jhansi Laxmi Taal	2021	Jhansi	26	22
9	26 MLD STP Jhansi Laxmi Taal	2021	Jhansi	26	4
10	26 MLD STP Smart City, Lahargird	2025	Jhansi	26	26
11	3.42 MLD STP Near Divyang kendra	2000	Chitrakoot	3.42	3.42

12	42 MLD STP, Sajari Kanpur	2016-17	Kanpur Nagar	42	22
13	210 MLD STP, Bingawan Kanpur	2015-16	Kanpur Nagar	210	110
14	130 MLD STP Jajmau, Kanpur	1998-99	Kanpur Nagar	130	115
15	43 MLD STP Jajmau, Kanpur	2020	Kanpur Nagar	43	40
16	13 MLD STP Jalalpur, Amrapur, Kannauj	2017	Kanpur Dehat	13	12
17	30 MLD STP Pankha, Kanpur	2023	Kanpur Nagar	30	30
18	36 MLD STP Jajmau, Kanpur	9+27 MLD (1992) = 36 MLD (2024)	Kanpur Nagar	36	25
19	17.7 MLD STP Fatehgarh, Farrukhabad	2024	Kanpur Nagar	17.7	17.7
20	30 MLD STP Farrukhabad	2024	Kanpur Nagar	30	30
21	50 MLD STP Numayadahi	2013	Prayagraj	50	50
22	10 MLD STP Ponghat	2013	Prayagraj	10	10
23	25 MLD STP Kodra	2013	Prayagraj	25	25
24	60 MLD STP Rajapur	2013	Prayagraj	60	60
25	29 MLD STP Salori-1	2007	Prayagraj	29	29
26	14 MLD STP Salori-2 Expansion	2016	Prayagraj	14	14
27	80 MLD STP Naini	2013	Prayagraj	80	80
28	42 MLD STP, Naini	2023	Prayagraj	42	36

29	14 MLD STP Phaphamau	2023	Prayagraj	14	14
30	16 MLD STP Jhunsi	2023	Prayagraj	16	0
31	10 MLD STP Ramnagar	2021	Varanasi	10	9.5
32	80 MLD STP Dinapur	1994	Varanasi	80	68
33	9.8 MLD STP Bhagwanpur	1989	Varanasi	9.8	9.8
34	140 MLD STP Dinapur	2018	Varanasi	140	99
35	120 MLD STP Goithaha	2019	Varanasi	120	40
36	12 MLD BLW STP	1989	Varanasi	12	12
37	50 MLD STP Ramana	2021	Varanasi	50	50
38	30 MLD STP Pachhahatiya Jaunpur	2023	Jaunpur, Varanasi	30	30
39	07 MLD Vindychal Mirzapur	2022	Mirzapur	7	4.933
40	14 MLD STP Pakka Pokhra	1994	Mirzapur	14	13.22
41	8.5 MLD STP Pakka Pokhra, Mirzapur	2024	Mirzapur	8.5	4.15
42	8.5 MLD STP Bisunderpur, Mirzapur	2024	Mirzapur	8.5	7.6
43	15 MLD S.T.P. Jharkhandi, Maherwa ki Bari	2015	Gorakhpur	15	11.89
44	5 MLD S.T.P. Jharkhandi, Maherwa ki Bari	2023	Gorakhpur	5	4.5

45	30 MLD S.T.P. Opp. Manyavar Kanshiram Shahri Garib Awas Yojna, Deoria bypass Road	2015	Gorakhpur	30	19.83
46	10 MLD STP Gorakhpur	2024	Gorakhpur	10	10
47	8 MLD STP Azamgarh	2024	Azamgarh	8	0
48	38 MLD STP, Mahilpur Road	1998	Saharanpur	38	38
49	6.5 MLD STP Awas vikas Parishad STP	2018	Lucknow	6.5	6.5
50	37.5 MLD STP Awas vikas Parishad STP	2017	Lucknow	37.5	37.5
51	345 MLD STP, Bharwara	2011	Lucknow	345	345
53	56 MLD STP, Daulatganj	2003 & 2009	Lucknow	56 (42+14)	56
54	1.5 MLD STP Hathi Park, (Smart City)	2021	Lucknow	1.5	1.5
55	39 MLD STP, Sajjadbagh, Daulatganj	2024	Lucknow	39	39
56	120 MLD STP near 1090 Chauraha	2025	Lucknow	120	80
57	19 MLD STP C.G. City, Lucknow	2023	Lucknow	19	0
58	56 MLD STP Trans Hindon (Indirapuram), Ghaziabad	2000	Ghaziabad	56	56
59	30 MLD STP, Sadullabad (Loni), Ghaziabad	2012	Ghaziabad	30	20

60	74 MLD STP S.B.R., Indirapuram, Ghaziabad	2013	Ghaziabad	74	74
61	56 MLD STP S.B.R., Bapudham, Ghaziabad	2014	Ghaziabad	56	1.5
62	6 MLD STP Garh Zone, Garhmukteswar Hapur	2011	Hapur / Garhmukteswar	6	4.62
63	3 MLD STP Brijghat Zone, Garhmukteswar Hapur	2011	Hapur / Garhmukteswar	3	2.57
64	56 MLD STP , Indirapuram, (GDA), Ghaziabad	2012	Ghaziabad	56	20
65	56 MLD STP S.B.R., Dudahaida Vijay Nagar, Ghaziabad	2013	Ghaziabad	56	56
66	70 MLD STP U.A.S.B.R. Dudahaida Vijay Nagar, Ghaziabad	2000	Ghaziabad	70	70
67	3 MLD STP Pilkhaun	2015	Ghaziabad	3	2.57
68	5 MLD STP Trans Delhi Signature City (Tronica City), Loni	2019	Ghaziabad	5	3.81
69	56 MLD STP S.B.R. Govindpuram, Ghaziabad	2014	Ghaziabad	56	14
70	20 MLD STP Modinagar	2023	Modinagar, Ghaziabad	20	7.8
71	56 MLD STP S.B.R., Morty, Ghaziabad	2018	Ghaziabad	56	27

72	30 MLD STP, Rampur Road, Hapur	2022	Hapur, Ghaziabad	30	8
73	21.5 MLD STP Siddharthvihar, Ghaziabad	2024	Ghaziabad	21.5	4.5
74	78 MLD STP Dhadhupura, Agra	2013	Agra	78	78
75	2.25 MLD STP Budi ka Nagla, Agra	2000	Agra	2.25	2.25
76	10 MLD STP Peelakhar, Agra	2000	Agra	10	10
77	12 MLD STP Devri Road, (Bhimnagri), Agra	2011	Agra	12	8
78	14 MLD STP Jaganpur, Sikandarpur, Agra	2011	Agra	14	14
79	40 MLD STP Sadarban, Bichhpuri, Agra	2013	Agra	40	28.5
80	36 MLD STP Sadarwan (Bichpuri) New	2018	Agra	36	36
81	24 MLD STP Dhadhupura (New), Agra	2014	Agra	24	15
82	4.50 MLD STP Kalindi Vihar, Agra	2014	Agra	4.5	4.5
83	03 MLD STP Pandav Nagar, Meerut	2013	Meerut	3	2.7
84	07 MLD STP Pallavpuram-1, Meerut	2012	Meerut	7	6.5
85	11 MLD STP Pallavpuram-2, Meerut	2008	Meerut	11	7
86	06 MLD STP Rakshapuram, Meerut	2011	Meerut	6	4.4

87	10 MLD STP Lohiya Nagar, Meerut	2010	Meerut	10	2
88	15 MLD STP Shatabdinagar, Meerut	2010	Meerut	15	4.8
89	15 MLD STP Vedvyaspuri Meerut	2011	Meerut	15	4.5
90	06 MLD STP Shradhapuri-1, Meerut	2012	Meerut	6	5.5
91	06 MLD STP Sainik Vihar	2017	Meerut	6	5.95
92	5 MLD STP Modipuram Tiraha	2016	Meerut	5	4.9
93	07 MLD STP Sports Goods Complex, Meerut	2012	Meerut	7	4
94	72 MLD STP Garh road (Jagriti vihar) Kamalpur	2018	Meerut	72	72
95	10 MLD STP Ganga Nagar, Meerut	2011	Meerut	10	3.8
96	06 MLD STP Shradhapuri- Phase-2, Meerut	2012	Meerut	6	5.6
97	14 MLD STP Baghpat, Meerut	2021	Baghpat, Meerut	14	7.8
98	32.5 MLD STP (WSP) Nagar Palika Parishad, Kidwai nagar	2001	Muzaffar Nagar	32.5	32.5
99	32.5 MLD STP Near A2Z Garbage plant KidwaiNagar	2025	Muzaffar Nagar	32.5	18.48
100	10 MLD STP Budhana	2024	Muzaffar Nagar	10	7.32
101	22 MLD STP Sahawali, Muzaffarnagar	2023	Muzaffar Nagar	22	21.18

102	15 MLD STP Kairana, Shamli, Muzaffarnagar	2024	Muzaffar Nagar	15	15
103	12 MLD STP Ayodhya	2014	Ayodhya	12	7
104	6 MLD STP Ramghat, Ayodhya	2023	Ayodhya	6	4
105	13.59 (6.8) MLD STP, Masani, Mathura	2007	Mathura	6.8	6.8
106	04 MLD STP Vrindavan Near Pagal Baba Mandir, Mathura	2007	Mathura	4	4
107	08 MLD STP Near 100 Bed Hospital Vrindavan, Manth road	2015	Mathura	8	8
108	14.5 MLD STP Trans-yamuna, Jamunapar, Mathura	2007	Mathura	14.5	14.5
109	30 MLD STP Masani Mathura	2020	Mathura	30	30
110	16 MLD STP Trans Yamuna, Laxmi Nagar, Mathura	2015	Mathura	16	15
111	2.76 MLD STP Goverdhan STP	2011	Mathura	2.76	0
112	33 MLD STP Sector-54, Noida	2011	Noida	33	13
113	25 MLD STP Sector-50, Noida	2015	Noida	25	14
114	35 MLD STP Sector-123, Noida	2011	Noida	35	17
115	50 MLD STP Sector-168, Noida	2015	Noida	50	17
116	34 MLD STP Sector -50 Noida	2012	Noida	34	31

117	54 MLD STP Sector- 54, Noida	2012	Noida	54	43
118	100 MLD STP Sector- 168, Noida	2023	Noida	100	61
119	80 MLD STP Sector- 123, Noida	2023	Noida	80	64
120	2.0 MLD STP Greater Noida Authority STP, Vill- Badalpur	2015	Greater Noida	2	2
121	15 MLD STP ECO tech -2	2018	Greater Noida	15	8
122	20 MLD STP ECO tech -3	2018	Greater Noida	20	14
123	137 MLD STP Kasana, GreaterNoida	2015	Greater Noida	137	95
124	0.805 MLD STP Ahara Road, Zone- A, Anoopshahar	2003	Bulandshahar	0.805	0.805
125	1.75 MLD STP Ahara Road, (Shivanand Ashram) Zone-B, Anoopshahar	2003	Bulandshahar	1.75	1.75
126	2.25 MLD STP Narora Atomic power Station Narora Township	2000	Bulandshahar	2.25	2.25
127	01 MLD STP Zone-B Anoopshahar	2016	Bulandshahar	1	1
128	1.5 MLD STP Anoopshahar Zone A (NGRBA)	2016	Bulandshahar	1.5	1.5
129	40 MLD STP Bulandshahar	2023	Bulandshahar	40	20
130	04 MLD STP , Narora (NGRBA)	2015	Bulandshahar	4	4

131	24 MLD STP, Bijnor	2018	Bijnor	24	23.5
132	58 MLD STP Moradabad	2018	Moradabad	58	24
133	20 MLD STP Moradabad	2017	Moradabad	20	14
134	14 MLD STP, Benzirpur	2016	Rampur	14	10
135	5 MLD STP , Rampur	2016	Rampur	5	4
136	15 MLD STP Pehrigaon	2015	Rampur	15	11
137	15 MLD STP, Kasganj	2022	Kasganj, Aligarh	15	9.6
138	24 MLD STP, Manpur, Etah	2023	Etah, Aligarh	24	16
139	45 MLD STP Laxmi Nagar, Aligarh	2023	Aligarh	45	18
140	8.95 MLD STP Bela, Pratapgarh	2023	Pratapgarh	8.95	7.2
141	5 MLD STP Palhipur, Sultanpur	2024	Sultanpur	5	1.4
142	2 MLD STP Miranpur, Sadar, Sultanpur	2024	Sultanpur	2	4.3
143	10 MLD STP Hathia Nala, Lolepur	2006	Sultanpur	10	7.1
144	18 MLD STP Raebareli	2023	Raebareli	18	4.8
145	35 MLD STP, Saraitalfi	2023	Bareilly	35	0
146	42 MLD STP, HarooNagla, Bareilly	2024	Bareilly	42	42
147	20 MLD STP Barinagla, Bareilly	2024	Bareilly	20	18
148	01 MLD STP, Girdaripur, Bareilly	2024	Bareilly	1	1
149	40 MLD STP, Shahjahanpur	2025	Shahjahanpur	40	10

150	15 MLD STP Unnao	2024	Unnao	15	13
151	21 MLD STP Mau Road, Ghazipur	2024	Ghazipur, Varanasi	21	12
152	33 MLD STP Ayodhya	2025	Ayodhya	33	0
153	15 MLD STP Baniyapur	2018	Kanpur Nagar	15	0
154	5 MLD STP Yamuna Expressway Industrial Development Authority (YIDA)	2023	Jewar (Gt. Noida)	5	0
155	20 MLD STP Ballia	2025	Ballia	20	0
156	25 MLD STP Moradabad	2025	Moradabad	25	0

Note :- The standards as per MoEF&CC Notification dated 13.10.2017, tit

For State Capital: pH-6.5-9.0; BOD - <20 mg/l; TSS- <50 mg/l & FC- <100

Other than State Capital: pH-6.5-9.0; BOD - <30 mg/l; TSS- <100 mg/l &]

Note:- As per the data received from Regional offices, UPPCB

Performance of Existing STPs in U.P. OCTOBER- 2025
Third Week

Technology / process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Rural (R)\Urban(U)\Other(O)	Date of Sampling	Sampling Method (Grab or Composite)	pH	BOD (mg/l)
WSP	UP Jal Nigam	R	24.10.2025	Grab	8.1	27
SBR	UP Jal Nigam	R	24.10.2025	Grab	7.8	9.2
SBR	UP Jal Nigam	R	24.10.2025	Grab	8	22
UASB	NPP	O	24.10.2025	Grab	7.9	24
ASP+ extended aeration	U.P. Jal Nigam	U	24.10.2025	Grab	7.8	9.6
SBR	Others	O	24.10.2025	Grab	7.7	22
UASB	U.P. Jal Nigam	U	24.10.2025	Grab	7.8	23
Oxidation Pond	U.P. Jal Nigam	U	24.10.2025	Grab	7.9	25
SBR	U.P. Jal Nigam	U	17.10.2025	Grab	7.67	26
SBR	U.P. Jal Nigam	U	17.10.2025	Grab	7.45	23
SBR	Nagar Nigam	O	14.10.2025	Grab	7.58	28.5
Oxidation Pond	Nagar Palika Parishad	O	28.10.2025	Grab	7.89	28.51

ASP	U.P. Jal Nigam	R	21.10.2025	Grab	7.77	22.5
UASB	U.P. Jal Nigam	R	21.10.2025	Grab	7.76	40.5
ASP	U.P. Jal Nigam	R	21.10.2025	Grab	7.79	21
UASB	U.P. Jal Nigam	R	21.10.2025	Grab	7.94	18
SBR	U.P. Jal Nigam	U	14.10.2025	Grab	7.4	24
SBR	U.P. Jal Nigam	R	21.10.2025	Grab	7.7	24
UASB	U.P. Jal Nigam	U	21.10.2025	Grab	7.93	42
SBR	U.P. Jal Nigam	R	21.10.2025	Grab	7.98	19.5
SBR	U.P. Jal Nigam	R	21.10.2025	Grab	7.91	21
HRBF	Ganga Pollution control unit, U.P. Jal Nigam	R	25.10.2025	Composite	7.86	24.8
HRBF	Ganga Pollution control unit, U.P. Jal Nigam	R	25.10.2025	Composite	7.9	24.2
HRBF	Ganga Pollution control unit, U.P. Jal Nigam	R	25.10.2025	Composite	7.8	23.7
UASB	Ganga Pollution control unit, U.P. Jal Nigam	R	18.10.2025	Composite	7.6	28.6
FAB	Ganga Pollution control unit, U.P. Jal Nigam	R	17.10.2025	Composite	6.98	26.9
SBR	Ganga Pollution control unit, U.P. Jal Nigam	U	17.10.2025	Composite	7.08	20.6
ASP	Ganga Pollution control unit, U.P. Jal Nigam	R	17.10.2025	Composite	6.94	27.8
FCR	U.P. Jal Nigam	R	17.10.2025	Composite	7.09	23

FCR	U.P. Jal Nigam	R	18.10.2025	Composite	7.37	24.2
FCR	U.P. Jal Nigam	R	18.10.2025		Not operati	
Anaerobic Anoxic Oxidation (A2O)	U.P. Jal Nigam	R	25.10.2025	Grab	7.43	14.4
ASP	U.P. Jal Nigam	U	16.10.2025	Grab	7.53	26.9
ASP	U.P. Jal Nigam	R	25.10.2025	Grab	7.47	28.4
ASP	U.P. Jal Nigam	U	16.10.2025	Grab	7.72	13.6
UASB	U.P. Jal Nigam	U	16.10.2025	Grab	7.61	12.2
ASP	BLW	O	25.10.2025	Grab	7.51	28.1
SBR	U.P. Jal Nigam	R	16.10.2025	-	Not operati	
A2O	U.P. Jal Nigam	R	25.10.2025	Grab	7.56	9.4
WSP	Nagarpalika	U	28.10.2025	Grab	7.58	8.2
UASB	U.P. Jal Nigam	R	28.10.2025	Grab	7.46	28.2
SBR	U.P. Jal Nigam	R	28.10.2025	Grab	7.52	8.6
SBR	U.P. Jal Nigam	R	28.10.2025	Grab	7.52	8.6
SBR	U.P. Jal Nigam	U	21.10.2025	Grab	7.7	7.5
SBR	U.P. Jal Nigam	U	21.10.2025	Grab	7.7	7.5

SBR	U.P. Jal Nigam	U	21.10.2025	Grab	7.6	7
SBR	U.P. Jal Nigam	U	21.10.2025	Grab	7.65	8
SBR	U.P. Jal Nigam	U	16.10.2025	-		
UASB	U.P. Jal Nigam	U	21.10.2025	Grab	7.5	26
SBR	Jal Kal	O	24.10.2025	Grab	7.25	17
SBR	U.P. Awas vikas Parishad	O	24.10.2025	Grab	7.33	15
UASB	U.P. Jal Nigam	U	24.10.2025	Grab	7.11	17
FAB	U.P. Jal Nigam	U	24.10.2025	Grab	7.33	18
MBBR	Nagar Nigam (Smart City)	O	24.10.2025	-	Not operati	
SBR	U.P. Jal Nigam	R	24.10.2025	Grab	7.32	11
SBR	U.P. Jal Nigam	U	24.10.2025	Grab	7.38	14
SBR	LDA	O	24.10.2025	-	Not operati	
UASB	U.P. Jal Nigam	U	25.10.2025	Grab	7.55	22
MBBR	U.P. Jal Nigam	U	24.10.2025	Grab	7.57	9

SBR	U.P. Jal Nigam	U	25.10.2025	Grab	7.58	9
SBR	GDA	O	24.10.2025	Grab	7.5	8
UASB followed by extended aeration	U.P. Jal Nigam (NGRBA)	R	24.10.2025	Grab	7.44	7
UASB followed by extended aeration	U.P. Jal Nigam (NGRBA)	R	24.10.2025	Grab	7.56	9
SBR	Nagar Nigam	O	25.10.2025	Grab	7.48	8
SBR	U.P. Jal Nigam	U	25.10.2025	Grab	7.56	9
UASB	U.P. Jal Nigam	U	25.10.2025	Grab	7.65	26
UASB	U.P. Jal Nigam	U	22.10.2025	Grab	7.4	18
MBBR	UPSIDA	O	24.10.2025	Grab	7.5	12
SBR	GDA	O	24.10.2025	Grab	7.4	8
SBR	U.P. Jal Nigam	U	24.10.2025	Grab	7.55	14
SBR	Nagar Nigam	O	25.10.2025	Grab	7.47	9

SBR	U.P. Jal Nigam	U	22.10.2025	Grab	7.5	16
SBR	Awas Vikas	O	25.10.2025	Grab	7.47	18
UASB	U.P. Jal Nigam	U	17.10.2025	Grab	7.84	24
WSP	U.P. Jal Nigam	U	17.10.2025	Grab	7.89	26
WSP	U.P. Jal Nigam	U	17.10.2025	Grab	7.88	28
UASB	U.P. Jal Nigam	U	17.10.2025	Grab	7.7	25
UASB	U.P. Jal Nigam	U	17.10.2025	Grab	7.9	23
UASB	U.P. Jal Nigam	U	17.10.2025	Grab	7.84	28
SBR	ADA	O	17.10.2025	Grab	7.69	27
UASB	U.P. Jal Nigam	U	17.10.2025	Grab	7.81	21
UASB	ADA	O	17.10.2025	Grab	7.58	27
ASP	MDA	O	16.10.2025	Grab	7.54	22
ASP	MDA	O	16.10.2025	Grab	7.55	14
ASP	MDA	O	16.10.2025	Grab	7.47	14
ASP	MDA	O	16.10.2025	Grab	7.39	18

ASP	MDA	O	16.10.2025	Grab	7.41	10
ASP	MDA	O	16.10.2025	Grab	7.47	10
ASP	MDA	O	16.10.2025	Grab	7.41	12
ASP	MDA	O	16.10.2025	Grab	7.48	15
UASB	MDA	O	16.10.2025	Grab	7.44	10
ASP	MDA	O	16.10.2025	Grab	7.46	14
ASP	MDA	O	16.10.2025	Grab	7.51	16
ASP	U.P. Jal Nigam	U	16.10.2025	Grab	7.37	9
SBR	MDA	O	16.10.2025	Grab	7.38	9
SBR	MDA	O	16.10.2025	Grab	7.53	17
SBR	U.P. Jal Nigam	R	13.10.2025	Grab	7.57	20
WSP	U.P. Jal Nigam	U	21.10.2025	Grab	7.4	24
SBR	U.P. Jal Nigam	R	21.10.2025	Composite	7.5	9
SBR	U.P. Jal Nigam	R	21.10.2025	Grab	7.5	8
SBR	U.P. Jal Nigam	R	21.10.2025	Grab	7.6	7

SBR	U.P. Jal Nigam	U	21.10.2025	Composite	7.6	9
UASB	U.P. Jal Nigam	U	21.10.2025	Grab	7.52	20
SBR	U.P. Jal Nigam	U	21.10.2025	Grab	7.62	18
WSP	U.P. Jal Nigam	R	25.10.2025	Grab	8	25
WSP	U.P. Jal Nigam	R	25.10.2025	Grab	7.8	27
UASB	U.P. Jal Nigam	U	25.10.2025	Grab	7.9	26
WSP	U.P. Jal Nigam	R	25.10.2025	Grab	8.2	48
SBR	U.P. Jal Nigam	R	25.10.2025	Grab	7.7	22
UASB	U.P. Jal Nigam	R	25.10.2025	Grab	7.9	27
WSP	Nagar Palika Parishad	O	25.10.2025	-	Not operati	
SBR	Noida Authority	O	17.10.2025	Composite	7.39	15.3
SBR	Noida Authority	O	17.10.2025	-	Not operati	
SBR	Noida Authority	O	17.10.2025	Composite	7.53	15.7
SBR	Noida Authority	O	17.10.2025	Composite	7.55	13.9
SBR	Noida Authority	O	17.10.2025	Composite	7.23	14.9

SBR	Noida Authority	O	17.10.2025	Composite	7.45	16.7
SBR	Noida Authority	O	17.10.2025	Composite	7.59	17.3
SBR	Noida Authority	O	17.10.2025	Composite	7.67	14.8
SBR	GNIDA	O	25.10.2025	Grab	7.37	12
SBR	GNIDA	O	25.10.2025	Grab	7.55	14
SBR	GNIDA	O	25.10.2025	Grab	7.4	16
SBR	GNIDA	O	25.10.2025	Grab	7.6	20
WSP	U.P. Jal Nigam	U	20.10.2025	Grab	7.65	24
WSP	U.P. Jal Nigam	U	20.10.2025	Grab	7.68	22
ASP	Narora Atomic power Station	O	20.10.2025	Grab	7.48	16
MBBR	U.P. Jal Nigam	R	20.10.2025	Grab	7.66	28
UASB	U.P. Jal Nigam	R	20.10.2025	Grab	8.88	26
SBR	U.P. Jal Nigam	U	20.10.2025	Grab	7.51	22
UASB	U.P. Jal Nigam	R	20.10.2025	Grab	7.74	26

UASB	U.P. Jal Nigam	U	25.10.2025	Grab	7.5	8
UASB	U.P. Jal Nigam	R	21.10.2025	Grab	7.59	6.4
SBR	MDA	O	21.10.2025	Grab	7.59	13
UASB	U.P. Jal Nigam	U	21.10.2025	Grab	7.82	20
SBR	U.P. Jal Nigam	U	21.10.2025	Grab	7.56	6.6
UASB	U.P. Jal Nigam	U	21.10.2025	Grab	7.68	24
SBR	U.P. Jal Nigam	R	24.10.2025	Grab	7.47	22
SBR	U.P. Jal Nigam	U	24.10.2025	Grab	7.22	14
SBR	U.P. Jal Nigam	U	24.10.2025	Grab	7.38	16
FAB	U.P. Jal Nigam	U	15.10.2025	Grab	7.95	24.0
SBR	U.P. Jal Nigam	R	16.10.2025	Grab	8.02	23.0
SBR	U.P. Jal Nigam	R	16.10.2025	Grab	8.05	26.0
Aerated Lagoon	U.P. Jal Nigam	R	16.10.2025	Grab	7.91	20.0
SBR	U.P. Jal Nigam	U	20.10.2025	Grab	7.94	8.0
ASP	Nagar Nigam	O	24.10.2025	-	Not operati	
SBR	U.P. Jal Nigam	R	24.10.2025	Grab	7.4	6
SBR	U.P. Jal Nigam	R	24.10.2025	Grab	7.2	6
SBR	U.P. Jal Nigam	R	24.10.2025	Grab	7.4	8
SBR	U.P. Jal Nigam	U	24.10.2025	Grab	7.4	6

SBR	U.P. Jal Nigam	R	17.10.2025	Grab	8.16	19
SBR	U.P. Jal Nigam	R	25.10.2025	Grab	7.65	6.3
SBR	UPJN (Rural)	R	21.10.2025	-		
SBR	UPJN (Urban)	U	14.10.2025	-		Not operati
SBR	UPJN (Rural)	R	25.10.2025	-		Not operati
SBR	UPJN (Urban)	U	16.10.2025	-		
SBR	UPJN(Rural)	R	21.10.2025	-		

led "Applicable Effluent Discharge Standards for STPs" are as follows:

0 MPN/100 ml

FC- <1000 MPN/100 ml

COD (mg/l)	TSS (mg/l)	TC (MPN/1 00ml)	FC (MPN/1 00ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
160	57	11000	920	Achieving
40	7	7000	680	Achieving
110	38	7900	830	Achieving
140	46	9400	810	Achieving
70	8	7000	610	Achieving
120	35	8400	910	Achieving
130	41	7900	780	Achieving
140	42	9400	910	Achieving
106.92	12	3400	930	Achieving
75.24	11	3400	920	Achieving
49.92	11	3400	930	Achieving
47.52	16	1800	680	Achieving

150	54	-	-	Achieving
190	64	-	-	Not Achieving
180	62	-	-	Achieving
160	56	-	-	Achieving
120	57	-	-	Achieving
120	46	-	-	Achieving
190	66	-	-	Not Achieving
160	50	-	-	Achieving
170	64	-	-	Achieving
60	58	-	-	Achieving
52	50	-	-	Achieving
48	35	-	-	Achieving
92	74	-	-	Achieving
64	60	-	-	Achieving
40	33	-	-	Achieving
80	68	-	-	Achieving
56	50	-	-	Achieving

72	52	-	-	Achieving
ional Due to Maintenance Work				
78	16	630	230	Achieving
158	84	630	230	Achieving
162	92	430	220	Achieving
42	16	430	220	Achieving
38	14	430	170	Achieving
178	90	250	130	Achieving
ional Due to Maintenance Work				
46	7	250	130	Achieving
46	18	430	220	Achieving
142	48	1100	790	Achieving
44	16	350	170	Achieving
44	16	350	170	Achieving
24	25	2100	910	Achieving
24	25	2100	910	Achieving

28	27	1700	780	Achieving
32	22	2000	930	Achieving
Under Trial Run				
188	45	720	660	Achieving
76	42	3900	920	Achieving
74	32	4000	610	Achieving
88	47	5400	940	Achieving
92	48	7000	930	Achieving
ional Due to Maintenance Work				
57	30	3200	610	Achieving
72	34	3900	780	Achieving
ional Due to Maintenance Work				
88	50	2400	780	Achieving
74	10	1600	920	Achieving

82	10	1700	680	Achieving
38	8	1600	280	Achieving
36	8	3400	610	Achieving
40	10	2100	400	Achieving
44	9	1400	790	Achieving
52	10	1600	540	Achieving
90	49	2200	790	Achieving
72	47	2100	780	Achieving
92	42	1600	540	Achieving
40	9	1600	350	Achieving
80	35	2100	830	Achieving
76	10	2700	680	Achieving

118	55	2200	450	Achieving
84	47	2000	610	Achieving
130	48	5800	910	Achieving
120	42	4800	680	Achieving
100	40	6300	810	Achieving
120	38	3400	930	Achieving
100	36	5800	910	Achieving
100	46	3400	930	Achieving
120	54	6300	810	Achieving
90	30	3100	680	Achieving
110	52	4800	680	Achieving
188	80	930	810	Achieving
88	44	830	610	Achieving
76	52	820	600	Achieving
136	58	930	810	Achieving

28	18	810	560	Achieving
24	20	810	560	Achieving
28	24	810	600	Achieving
92	50	830	680	Achieving
32	22	810	600	Achieving
72	40	920	610	Achieving
96	44	920	780	Achieving
28	10	820	600	Achieving
24	10	780	550	Achieving
132	56	930	820	Achieving
148	58	930	810	Achieving
88	40	1700	680	Achieving
28	18	-	-	Achieving
28	18	1300	110	Achieving
24	16	1300	170	Achieving

26	14	-	-	Achieving
98	65	4000	920	Achieving
86	52	2600	680	Achieving
224	76	3800	920	Achieving
240	92	3900	920	Achieving
216	76	3300	930	Achieving
384	164	13000	3300	Not Achieving
184	58	2700	930	Achieving
248	96	3400	930	Achieving
ional Due to Maintenance Work				
127.2	37	-	-	Achieving
ional Due to Maintenance Work				
128	35	-	-	Achieving
85.6	24	-	-	Achieving
110.4	34	-	-	Achieving

134.4	41	-	-	Achieving
139.2	45	-	-	Achieving
108	29	-	-	Achieving
66	22	1600	350	Achieving
48	20	1400	610	Achieving
62	25	2200	400	Achieving
78	36	3300	680	Achieving
96	43	1200	610	Achieving
84	49	1700	930	Achieving
76	46	920	540	Achieving
132	91	2000	680	Achieving
148	94	2200	680	Achieving
104	53	1500	840	Achieving
120	71	1600	920	Achieving

32	20	790	120	Achieving
68	6	920	61	Achieving
76	30	1300	780	Achieving
88	34	2100	930	Achieving
82	7	610	61	Achieving
72	32	1700	680	Achieving
96	78	1600	920	Achieving
44	69	1500	840	Achieving
84	87	2600	920	Achieving
48.00	30.0	780	230	Achieving
60.48	30.0	2300	930	Achieving
58.88	32.0	2000	680	Achieving
59.20	40.0	2100	920	Achieving
41.92	9.0	790	200	Achieving

ional Due to Maintenance Work

32	16	170	68	Achieving
40	15	220	79	Achieving
40	15	210	68	Achieving
32	7	170	68	Achieving

156	56	5400	2200	Not Achieving
36	7.2	470	170	Achieving
Under Trial Run				
ional Due to Maintenance Work				
ional Due to Maintenance Work				
Under Trial Run				
Under Trial Run				

Performance of

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Utilized Capacity (MLD)	Technology/ process STP based
1	10.445 MLD STP near Tixi Tempel (Karanpur)	2001	Etawah	10.445	8	WSP
2	21 MLD STP Etawah	2022	Etawah	21	20	SBR
3	13.5 MLD STP at Mauja Umrain	2013	Etawah	13.5	12.5	SBR
4	03 MLD STP Firozabad	2014	Firozabad	3	1.4	UASB
5	67 MLD STP Mohammadpur, Biharipur	2020	Firozabad	67	52	ASP+ extended aeration
6	1.65 MLD STP Saifai (Paramedicals)	2013	Etawah	1.65	0.9	SBR
7	23 MLD STP at Mauja Odenya, Padaria	2014	Mainpuri	23	17	UASB
8	1.5 MLD STP Saifai Village, Etawah	2006	Etawah	1.5	1.1	Oxidation Pond
9	26 MLD STP Jhansi Laxmi Taal	2021	Jhansi	26	22	SBR
9	26 MLD STP Jhansi Laxmi Taal	2021	Jhansi	26	4	SBR
10	26 MLD STP Smart City, Lahargird	2025	Jhansi	26	26	SBR

11	3.42 MLD STP Near Divyang kendra	2000	Chitrakoot	3.42	3.42	Oxidatio n Pond
12	42 MLD STP, Sajari Kanpur	2016-17	Kanpur Nagar	42	22	ASP
13	210 MLD STP, Bingawan Kanpur	2015-16	Kanpur Nagar	210	110	UASB
14	130 MLD STP Jajmau, Kanpur	1998-99	Kanpur Nagar	130	115	ASP
15	43 MLD STP Jajmau, Kanpur	2020	Kanpur Nagar	43	40	UASB
16	13 MLD STP Jalalpur, Amrapur, Kannauj	2017	Kanpur Dehat	13	12	SBR
17	30 MLD STP Pankha, Kanpur	2023	Kanpur Nagar	30	30	SBR
18	36 MLD STP Jajmau, Kanpur	9+27 MLD (1992) = 36 MLD (2024)	Kanpur Nagar	36	25	UASB
19	17.7 MLD STP Fatehgarh, Farrukhabad	2024	Kanpur Nagar	17.7	17.7	SBR
20	30 MLD STP Farrukhabad	2024	Kanpur Nagar	30	30	SBR
21	50 MLD STP Numayadahi	2013	Prayagraj	50	50	HRBF
22	10 MLD STP Ponghat	2013	Prayagraj	10	10	HRBF
23	25 MLD STP Kodra	2013	Prayagraj	25	25	HRBF
24	60 MLD STP Rajapur	2013	Prayagraj	60	60	UASB

25	29 MLD STP Salori-1	2007	Prayagraj	29	29	FAB
26	14 MLD STP Salori-2 Expansion	2016	Prayagraj	14	14	SBR
27	80 MLD STP Naini	2013	Prayagraj	80	80	ASP
28	42 MLD STP, Naini	2023	Prayagraj	42	36	FCR
29	14 MLD STP Phaphamau	2023	Prayagraj	14	14	FCR
30	16 MLD STP Jhunsi	2023	Prayagraj	16	0	FCR
31	10 MLD STP Ramnagar	2021	Varanasi	10	9.5	Anaerobic Anoxic Oxic (A2O)
32	80 MLD STP Dinapur	1994	Varanasi	80	68	ASP
33	9.8 MLD STP Bhagwanpur	1989	Varanasi	9.8	9.8	ASP
34	140 MLD STP Dinapur	2018	Varanasi	140	99	ASP
35	120 MLD STP Goithaha	2019	Varanasi	120	40	UASB
36	12 MLD BLW STP	1989	Varanasi	12	12	ASP
37	50 MLD STP Ramana	2021	Varanasi	50	50	SBR
38	30 MLD STP Pachhahatiya Jaunpur	2023	Jaunpur, Varanasi	30	30	A2O
39	07 MLD Vindyalchal Mirzapur	2022	Mirzapur	7	4.933	WSP
40	14 MLD STP Pakka Pokhra	1994	Mirzapur	14	13.22	UASB

41	8.5 MLD STP Pakka Pokhra, Mirzapur	2024	Mirzapur	8.5	4.15	SBR
42	8.5 MLD STP Bisunderpur, Mirzapur	2024	Mirzapur	8.5	7.6	SBR
43	15 MLD S.T.P. Jharkhandi, Maherwa ki Bari	2015	Gorakhpur	15	11.89	SBR
44	5 MLD S.T.P. Jharkhandi, Maherwa ki Bari	2023	Gorakhpur	5	4.5	SBR
45	30 MLD S.T.P. Opp. Manyavar Kanshiram Shahri Garib Awas Yojna, Deoria bypass Road	2015	Gorakhpur	30	19.83	SBR
46	10 MLD STP Gorakhpur	2024	Gorakhpur	10	10	SBR
47	8 MLD STP Azamgarh	2024	Azamgarh	8	0	SBR
48	38 MLD STP, Mahilpur Road	1998	Saharanpur	38	38	UASB
49	6.5 MLD STP Awas vikas Parishad STP	2018	Lucknow	6.5	6.5	SBR
50	37.5 MLD STP Awas vikas Parishad STP	2017	Lucknow	37.5	37.5	SBR
51	345 MLD STP, Bharwara	2011	Lucknow	345	345	UASB
53	56 MLD STP, Daulatganj	2003 & 2009	Lucknow	56 (42+14)	56	FAB
54	1.5 MLD STP Hathi Park, (Smart City)	2021	Lucknow	1.5	1.5	MBBR
55	39 MLD STP, Sajjadbagh, Daulatganj	2024	Lucknow	39	39	SBR
56	120 MLD STP near 1090 Chauraha	2025	Lucknow	120	80	SBR

57	19 MLD STP C.G. City, Lucknow	2023	Lucknow	19	0	SBR
58	56 MLD STP Trans Hindon (Indirapuram), Ghaziabad	2000	Ghaziabad	56	56	UASB
59	30 MLD STP, Sadullabad (Loni), Ghaziabad	2012	Ghaziabad	30	20	MBBR
60	74 MLD STP S.B.R., Indirapuram, Ghaziabad	2013	Ghaziabad	74	74	SBR
61	56 MLD STP S.B.R., Bapudham, Ghaziabad	2014	Ghaziabad	56	1.5	SBR
62	6 MLD STP Garh Zone, Garhmukeshwar Hapur	2011	Hapur / Garhmuktesw ar	6	4.62	UASB followed by extended aeration
63	3 MLD STP Brijghat Zone, Garhmukeshwar Hapur	2011	Hapur / Garhmuktesw ar	3	2.57	UASB followed by extended aeration
64	56 MLD STP , Indirapuram, (GDA), Ghaziabad	2012	Ghaziabad	56	20	SBR
65	56 MLD STP S.B.R., Dudahaida Vijay Nagar, Ghaziabad	2013	Ghaziabad	56	56	SBR
66	70 MLD STP U.A.S.B.R. Dudahaida Vijay Nagar, Ghaziabad	2000	Ghaziabad	70	70	UASB
67	3 MLD STP Pilkhaun	2015	Ghaziabad	3	2.57	UASB

68	5 MLD STP Trans Delhi Signature City (Tronica City), Loni	2019	Ghaziabad	5	3.81	MBBR
69	56 MLD STP S.B.R. Govindpuram, Ghaziabad	2014	Ghaziabad	56	14	SBR
70	20 MLD STP Modinagar	2023	Modinagar, Ghaziabad	20	7.8	SBR
71	56 MLD STP S.B.R., Morty, Ghaziabad	2018	Ghaziabad	56	27	SBR
72	30 MLD STP, Rampur Road, Hapur	2022	Hapur, Ghaziabad	30	8	SBR
73	21.5 MLD STP Siddharthvihar, Ghaziabad	2024	Ghaziabad	21.5	4.5	SBR
74	78 MLD STP Dhadhupura, Agra	2013	Agra	78	78	UASB
75	2.25 MLD STP Budi ka Nagla, Agra	2000	Agra	2.25	2.25	WSP
76	10 MLD STP Peelakhar, Agra	2000	Agra	10	10	WSP
77	12 MLD STP Devri Road, (Bhimnagri), Agra	2011	Agra	12	8	UASB
78	14 MLD STP Jaganpur, Sikandarpur, Agra	2011	Agra	14	14	UASB
79	40 MLD STP Sadarban, Bichhpuri, Agra	2013	Agra	40	28.5	UASB
80	36 MLD STP Sadawan (Bichpuri) New	2018	Agra	36	36	SBR
81	24 MLD STP Dhadhupura (New), Agra	2014	Agra	24	15	UASB

82	4.50 MLD STP Kalindi Vihar, Agra	2014	Agra	4.5	4.5	UASB
83	03 MLD STP Pandav Nagar, Meerut	2013	Meerut	3	2.7	ASP
84	07 MLD STP Pallavpuram-1, Meerut	2012	Meerut	7	6.5	ASP
85	11 MLD STP Pallavpuram-2, Meerut	2008	Meerut	11	7	ASP
86	06 MLD STP Rakshapuram, Meerut	2011	Meerut	6	4.4	ASP
87	10 MLD STP Lohiya Nagar, Meerut	2010	Meerut	10	2	ASP
88	15 MLD STP Shatabdinagar, Meerut	2010	Meerut	15	4.8	ASP
89	15 MLD STP Vedvyaspuri Meerut	2011	Meerut	15	4.5	ASP
90	06 MLD STP Shradhapuri-1, Meerut	2012	Meerut	6	5.5	ASP
91	06 MLD STP Sainik Vihar	2017	Meerut	6	5.95	UASB
92	5 MLD STP Modipuram Tiraha	2016	Meerut	5	4.9	ASP
93	07 MLD STP Sports Goods Complex, Meerut	2012	Meerut	7	4	ASP
94	72 MLD STP Garh road (Jagriti vihar) Kamalpur	2018	Meerut	72	72	ASP
95	10 MLD STP Ganga Nagar, Meerut	2011	Meerut	10	3.8	SBR
96	06 MLD STP Shradhapuri- Phase-2, Meerut	2012	Meerut	6	5.6	SBR

97	14 MLD STP Baghpat, Meerut	2021	Baghpat, Meerut	14	7.8	SBR
98	32.5 MLD STP (WSP) Nagar Palika Parishad, Kidwai nagar	2001	Muzaffar Nagar	32.5	32.5	WSP
99	32.5 MLD STP Near A2Z Garbage plant KidwaiNagar	2025	Muzaffar Nagar	32.5	18.48	SBR
100	10 MLD STP Budhana	2024	Muzaffar Nagar	10	7.32	SBR
101	22 MLD STP Sahawali, Muzaffarnagar	2023	Muzaffar Nagar	22	21.18	SBR
102	15 MLD STP Kairana, Shamli, Muzaffarnagar	2024	Muzaffar Nagar	15	15	SBR
103	12 MLD STP Ayodhya	2014	Ayodhya	12	7	UASB
104	6 MLD STP Ramghat, Ayodhya	2023	Ayodhya	6	4	SBR
105	13.59 (6.8) MLD STP, Masani, Mathura	2007	Mathura	6.8	6.8	WSP
106	04 MLD STP Vrindavan Near Pagal Baba Mandir, Mathura	2007	Mathura	4	4	WSP
107	08 MLD STP Near 100 Bed Hospital Vrindavan, Manth road	2015	Mathura	8	8	UASB
108	14.5 MLD STP Trans-yamuna, Jamunapar, Mathura	2007	Mathura	14.5	14.5	WSP
109	30 MLD STP Masani Mathura	2020	Mathura	30	30	SBR

110	16 MLD STP Trans Yamuna, Laxmi Nagar, Mathura	2015	Mathura	16	15	UASB
111	2.76 MLD STP Goverdhan STP	2011	Mathura	2.76	0	WSP
112	33 MLD STP Sector-54, Noida	2011	Noida	33	13	SBR
113	25 MLD STP Sector-50, Noida	2015	Noida	25	14	SBR
114	35 MLD STP Sector-123, Noida	2011	Noida	35	17	SBR
115	50 MLD STP Sector-168, Noida	2015	Noida	50	17	SBR
116	34 MLD STP Sector -50 Noida	2012	Noida	34	31	SBR
117	54 MLD STP Sector- 54, Noida	2012	Noida	54	43	SBR
118	100 MLD STP Sector- 168, Noida	2023	Noida	100	61	SBR
119	80 MLD STP Sector- 123, Noida	2023	Noida	80	64	SBR
120	2.0 MLD STP Greater Noida Authority STP, Vill- Badalpur	2015	Greater Noida	2	2	SBR
121	15 MLD STP ECO tech -2	2018	Greater Noida	15	8	SBR
122	20 MLD STP ECO tech -3	2018	Greater Noida	20	14	SBR
123	137 MLD STP Kasana, GreaterNoida	2015	Greater Noida	137	95	SBR
124	0.805 MLD STP Ahara Road, Zone-A, Anoopshahar	2003	Bulandshahar	0.805	0.805	WSP

125	1.75 MLD STP Ahara Road, (Shivanand Ashram) Zone-B, Anoopshahar	2003	Bulandshahar	1.75	1.75	WSP
126	2.25 MLD STP Narora Atomic power Station Narora Township	2000	Bulandshahar	2.25	2.25	ASP
127	01 MLD STP Zone-B Anoopshahar	2016	Bulandshahar	1	1	MBBR
128	1.5 MLD STP Anoopshahar Zone A (NGRBA)	2016	Bulandshahar	1.5	1.5	UASB
129	40 MLD STP Bulandshahar	2023	Bulandshahar	40	20	SBR
130	04 MLD STP , Narora (NGRBA)	2015	Bulandshahar	4	4	UASB
131	24 MLD STP, Bijnor	2018	Bijnor	24	23.5	UASB
132	58 MLD STP Moradabad	2018	Moradabad	58	24	UASB
133	20 MLD STP Moradabad	2017	Moradabad	20	14	SBR
134	14 MLD STP, Benzirpur	2016	Rampur	14	10	UASB
135	5 MLD STP , Rampur	2016	Rampur	5	4	SBR
136	15 MLD STP Pehrigaon	2015	Rampur	15	11	UASB
137	15 MLD STP, Kasganj	2022	Kasganj, Aligarh	15	9.6	SBR
138	24 MLD STP, Manpur, Etah	2023	Etah, Aligarh	24	16	SBR
139	45 MLD STP Laxmi Nagar, Aligarh	2023	Aligarh	45	18	SBR
140	8.95 MLD STP Bela, Pratapgarh	2023	Pratapgarh	8.95	7.2	FAB
141	5 MLD STP Palhipur, Sultanpur	2024	Sultanpur	5	1.4	SBR

142	2 MLD STP Miranpur, Sadar, Sultanpur	2024	Sultanpur	2	4.3	SBR
143	10 MLD STP Hathia Nala, Lolepur	2006	Sultanpur	10	7.1	Aerated Lagoon
144	18 MLD STP Raebareli	2023	Raebareli	18	4.8	SBR
145	35 MLD STP, Saraitalfi	2023	Bareilly	35	0	ASP
146	42 MLD STP, HarooNagla, Bareilly	2024	Bareilly	42	42	SBR
147	20 MLD STP Barinagla, Bareilly	2024	Bareilly	20	18	SBR
148	01 MLD STP, Girdaripur, Bareilly	2024	Bareilly	1	1	SBR
149	40 MLD STP, Shahjahanpur	2025	Shahjahanpur	40	10	SBR
150	15 MLD STP Unnao	2024	Unnao	15	13	SBR
151	21 MLD STP Mau Road, Ghazipur	2024	Ghazipur, Varanasi	21	12	SBR
152	33 MLD STP Ayodhya	2025	Ayodhya	33	0	SBR
153	15 MLD STP Baniyapur	2018	Kanpur Nagar	15	0	SBR
154	5 MLD STP Yamuna Expressway Industrial Development Authority (YIDA)	2023	Jewar (Gt. Noida)	5	0	SBR
155	20 MLD STP Ballia	2025	Ballia	20	0	SBR
156	25 MLD STP Moradabad	2025	Moradabad	25	0	SBR

Note :- The standards as per MoEF&CC Notification dated 13.10.2017, titled "Ap

For State Capital: pH-6.5-9.0; BOD - <20 mg/l; TSS- <50 mg/l & FC- <1000 MPN/l

Other than State Capital: pH-6.5-9.0; BOD - <30 mg/l; TSS- <100 mg/l & FC- <100

Note:- As per the data received from Regional offices, UPPCB

Existing STPs in U.P. OCTOBER- 2025
Last Week

Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Rural (R)\Urban(U)\Other(O)	Date of Sampling	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)
UP Jal Nigam	R	28.10.2025	Grab	7.8	28	160	47
UP Jal Nigam	R	28.10.2025	Grab	8	12	60	11
UP Jal Nigam	R	28.10.2025	-	Not operational Due to Mainten			
NPP	O	29.10.2025	Grab	7.9	21	110	39
U.P. Jal Nigam	U	29.10.2025	Grab	7.8	10.4	80	11
Others	O	28.10.2025	Grab	7.9	18	80	17
U.P. Jal Nigam	U	27.10.2025	Grab	7.7	26	160	45
U.P. Jal Nigam	U	28.10.2025	Grab	8.1	28	170	48
U.P. Jal Nigam	U	24.10.2025	Grab	7.36	27	51.48	13
U.P. Jal Nigam	U	24.10.2025	Grab	7.21	21	67.32	11
Nagar Nigam	O	25.10.2025	Grab	7.34	28	63.36	13

Nagar Palika Parishad	O	28.10.2025	Grab	7.89	28.51	47.52	16
U.P. Jal Nigam	R	28.10.2025	Grab	7.75	24	160	50
U.P. Jal Nigam	R	28.10.2025	Grab	7.73	60	200	58
U.P. Jal Nigam	R	28.10.2025	Grab	7.82	18	190	58
U.P. Jal Nigam	R	28.10.2025	Grab	7.98	19.5	170	54
U.P. Jal Nigam	U	28.10.2025	Grab	7.6	25.5	130	52
U.P. Jal Nigam	R	28.10.2025	Grab	7.74	22.5	130	42
U.P. Jal Nigam	U	28.10.2025	Grab	7.96	39	180	68
U.P. Jal Nigam	R	28.10.2025	Grab	7.99	21	150	56
U.P. Jal Nigam	R	28.10.2025	Grab	7.94	18	180	60
Ganga Pollution control unit, U.P. Jal Nigam	R	29.10.2025	Grab	7.38	24	60	50
Ganga Pollution control unit, U.P. Jal Nigam	R	29.10.2025	Grab	7.28	23.5	56	54
Ganga Pollution control unit, U.P. Jal Nigam	R	29.10.2025	Grab	7.06	23.4	52	45
Ganga Pollution control unit, U.P. Jal Nigam	R	29.10.2025	Grab	7.21	28.6	80	78

Ganga Pollution control unit, U.P. Jal Nigam	R	29.10.2025	Grab	7.16	26.6	68	66
Ganga Pollution control unit, U.P. Jal Nigam	U	29.10.2025	Grab	7.06	20.4	48	36
Ganga Pollution control unit, U.P. Jal Nigam	R	29.10.2025	Grab	7.02	26.8	64	75
U.P. Jal Nigam	R	29.10.2025	Grab	7.34	24.2	60	48
U.P. Jal Nigam	R	29.10.2025	Grab	7.39	24.5	76	56
U.P. Jal Nigam	R	29.10.2025	-	Not operational Due to Mainten			
U.P. Jal Nigam	R	25.10.2025	Grab	7.43	14.4	78	16
U.P. Jal Nigam	U	25.10.2025	Grab	7.62	24.2	142	88
U.P. Jal Nigam	R	25.10.2025	Grab	7.47	28.4	162	92
U.P. Jal Nigam	U	25.10.2025	Grab	7.68	12.8	40	14
U.P. Jal Nigam	U	25.10.2025	Grab	7.52	15.4	44	18
BLW	O	25.10.2025	Grab	7.51	28.1	178	90
U.P. Jal Nigam	R	25.10.2025	Grab	7.34	20.2	108	34
U.P. Jal Nigam	R	25.10.2025	Grab	7.56	9.4	46	7
Nagarpalika	U	28.10.2025	Grab	7.58	8.2	46	18
U.P. Jal Nigam	R	28.10.2025	Grab	7.46	28.2	142	48

U.P. Jal Nigam	R	28.10.2025	Grab	7.52	8.6	44	16
U.P. Jal Nigam	R	28.10.2025	Grab	7.62	8	40	18
U.P. Jal Nigam	U	28.10.2025	Grab	7.58	8.5	36	27
U.P. Jal Nigam	U	28.10.2025	Grab	7.58	8.5	36	27
U.P. Jal Nigam	U	28.10.2025	Grab	7.61	9	42	25
U.P. Jal Nigam	U	28.10.2025	Grab	7.64	8	40	26
U.P. Jal Nigam	U	25.10.2025	-	Under Trial Run			
U.P. Jal Nigam	U	28.10.2025	Grab	7.5	25	184	44
Jal Kal	O	31.10.2025	-	Not operational Due to Mainten			
U.P. Awas vikas Parishad	O	31.10.2025	Grab	7.5	13	68	33
U.P. Jal Nigam	U	31.10.2025	Grab	7.37	18	94	46
U.P. Jal Nigam	U	31.10.2025	Grab	7.49	16	85	47
Nagar Nigam (Smart City)	O	31.10.2025	-	Not operational Due to Mainten			
U.P. Jal Nigam	R	31.10.2025	Grab	7.65	12	59	38
U.P. Jal Nigam	U	31.10.2025	Grab	7.52	13	68	42

LDA	O	31.10.2025	-	Not operational Due to Mainten.			
U.P. Jal Nigam	U	30.10.2025	Grab	7.46	16	76	40
U.P. Jal Nigam	U	30.10.2025	Grab	7.48	8	62	9
U.P. Jal Nigam	U	30.10.2025	Grab	7.5	8	54	9
GDA	O	30.10.2025	Grab	7.53	7	28	9
U.P. Jal Nigam (NGRBA)	R	27.10.2025	Grab	7.52	8	42	9
U.P. Jal Nigam (NGRBA)	R	27.10.2025	Grab	7.47	8	42	9
Nagar Nigam	O	30.10.2025	Grab	7.6	7	38	8
U.P. Jal Nigam	U	30.10.2025	Grab	7.48	7	36	9
U.P. Jal Nigam	U	30.10.2025	Grab	7.68	18	80	42
U.P. Jal Nigam	U	27.10.2025	Grab	7.57	12	68	35

UPSIDA	O	30.10.2025	Grab	7.42	14	78	40
GDA	O	30.10.2025	Grab	7.45	9	48	10
U.P. Jal Nigam	U	29.10.2025	Grab	7.9	18	96	50
Nagar Nigam	O	30.10.2025	Grab	7.58	12	88	22
U.P. Jal Nigam	U	27.10.2025	Grab	7.44	20	120	50
Awas Vikas	O	30.10.2025	Grab	7.44	14	76	38
U.P. Jal Nigam	U	25.10.2025	Grab	7.88	26	110	46
U.P. Jal Nigam	U	25.10.2025	Grab	7.95	27	100	38
U.P. Jal Nigam	U	25.10.2025	Grab	7.92	26	120	42
U.P. Jal Nigam	U	25.10.2025	Grab	7.76	28	130	46
U.P. Jal Nigam	U	25.10.2025	Grab	7.91	28	140	40
U.P. Jal Nigam	U	25.10.2025	Grab	7.83	27	120	42
ADA	O	25.10.2025	Grab	7.84	28	140	64
U.P. Jal Nigam	U	25.10.2025	Grab	7.84	22	120	34

ADA	O	25.10.2025	-	Not operational Due to Mainten			
MDA	O	24.10.2025	Grab	7.52	20	160	92
MDA	O	24.10.2025	Grab	7.51	14	88	48
MDA	O	24.10.2025	Grab	7.44	15	80	45
MDA	O	24.10.2025	Grab	7.46	16	120	62
MDA	O	24.10.2025	Grab	7.39	8	20	20
MDA	O	24.10.2025	Grab	7.42	8	20	22
MDA	O	24.10.2025	Grab	7.38	10	24	26
MDA	O	24.10.2025	Grab	7.44	16	104	52
MDA	O	24.10.2025	Grab	7.38	12	24	24
MDA	O	24.10.2025	Grab	7.51	15	64	38
MDA	O	24.10.2025	Grab	7.51	14	88	48
U.P. Jal Nigam	U	31.10.2025	Grab	7.41	10	60	10
MDA	O	24.10.2025	Grab	7.41	8	18	8
MDA	O	24.10.2025	Grab	7.52	18	140	60

U.P. Jal Nigam	R	24.10.2025	Grab	7.52	18	164	80
U.P. Jal Nigam	U	28.10.2025	Composite	7.6	22	76	38
U.P. Jal Nigam	R	28.10.2025	Grab	7.5	6	24	16
U.P. Jal Nigam	R	28.10.2025	Composite	7.5	9	28	16
U.P. Jal Nigam	R	28.10.2025	Composite	7.4	8	26	14
U.P. Jal Nigam	U	28.10.2025	Grab	7.6	6	22	18
U.P. Jal Nigam	U	28.10.2025	Grab	7.33	18	90	58
U.P. Jal Nigam	U	28.1.02025	Grab	7.4	13	62	48
U.P. Jal Nigam	R	28.10.2025	Grab	8.1	27	240	88
U.P. Jal Nigam	R	28.10.2025	Grab	7.9	26	224	80
U.P. Jal Nigam	U	28.10.2025	Grab	7.8	27	232	84
U.P. Jal Nigam	R	29.10.2025	Grab	8	44	368	148
U.P. Jal Nigam	R	28.10.2025	Grab	7.8	24	200	66

U.P. Jal Nigam	R	29.10.2025	Grab	8	25	232	82
Nagar Palika Parishad	O	29.10.2025	-	Not operational Due to Mainten.			
Noida Authority	O	21.10.2025	Grab	7.45	12.3	85.6	25
Noida Authority	O	21.10.2025	-	Not operational Due to Mainten.			
Noida Authority	O	21.10.2025	Grab	7.51	12.5	96.4	27
Noida Authority	O	21.10.2025	Grab	7.29	10.7	84.8	22
Noida Authority	O	21.10.2025	Grab	7.34	11.6	80.8	21
Noida Authority	O	21.10.2025	Grab	7.51	10.9	80	17
Noida Authority	O	21.10.2025	Grab	7.69	13.7	108	31
Noida Authority	O	21.10.2025	Grab	7.59	11.1	81.6	26
GNIDA	O	27.10.2025	Grab	7.66	16	96	40
GNIDA	O	27.10.2025	Grab	7.62	12	80	30
GNIDA	O	27.10.2025	Grab	7.85	8	44	17
GNIDA	O	27.10.2025	Grab	7.55	10	56	25
U.P. Jal Nigam	U	27.10.2025	Grab	7.71	26	92	47

U.P. Jal Nigam	U	27.10.2025	Grab	7.64	26	96	52
Narora Atomic power Station	O	27.10.2025	Grab	7.51	20	88	41
U.P. Jal Nigam	R	27.10.2025	Grab	7.73	24	144	87
U.P. Jal Nigam	R	20.10.2025	Grab	8.88	26	148	94
U.P. Jal Nigam	U	27,10,2025	Grab	7.54	24	116	58
U.P. Jal Nigam	R	27.10.2025	Grab	7.67	22	112	65
U.P. Jal Nigam	U	31.10.2025	Grab	7.56	8	32	19
U.P. Jal Nigam	R	28.10.2025	G	7.61	6.6	76	8
MDA	O	28.10.2025	Grab	7.66	15	82	28
U.P. Jal Nigam	U	28.10.2025	Grab	7.92	21	82	30
U.P. Jal Nigam	U	28.10.2025	Grab	7.44	6.7	78	6
U.P. Jal Nigam	U	28.10.2025	Grab	7.52	22	80	34
U.P. Jal Nigam	R	28.10.2025	Grab	7.43	18	96	72
U.P. Jal Nigam	U	27.10.2025	Grab	7.63	12	52	38
U.P. Jal Nigam	U	28.10.2025	Grab	7.28	22	108	88
U.P. Jal Nigam	U	22.10.2025	Grab	7.90	26.0	50.56	34.0
U.P. Jal Nigam	R	23.10.2025	Grab	8.07	20.0	57.60	34.0

U.P. Jal Nigam	R	23.10.2025	Grab	8.09	22.0	56.00	36.0
U.P. Jal Nigam	R	23.10.2025	Grab	7.94	22.0	61.44	35.0
U.P. Jal Nigam	U	27.10.2025	Grab	7.99	9.0	40.00	7.0
Nagar Nigam	O	30.10.2025	-	Not operational Due to Mainten.			
U.P. Jal Nigam	R	30.10.2025	Grab	7.3	8	40	17
U.P. Jal Nigam	R	30.10.2025	Grab	7.6	6	36	18
U.P. Jal Nigam	R	30.10.2025	Grab	7.6	6	32	14
U.P. Jal Nigam	U	30.10.2025	Grab	7.6	8	40	8
U.P. Jal Nigam	R	29.10.2025	Grab	8.2	18.8	148	58
U.P. Jal Nigam	R	01.11.2025	Grab	7.52	8.9	46	8.2
UPJN (Rural)	R	28.10.2025	-	Under Trial Run			
UPJN (Urban)	U	28.10.2025	-	Not operational Due to Mainten.			
UPJN (Rural)	R	27.10.2025	-	Not operational Due to Mainten.			
UPJN (Urban)	U	25.10.2025	-	Under Trial Run			
UPJN(Rural)	R	28.10.2025	-	Under Trial Run			

Applicable Effluent Discharge Standards for STPs" are as follows:

100 ml

100 MPN/100 ml

TC (MPN/1 00ml)	FC (MPN/1 00ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
12000	930	Achieving
9400	810	Achieving
ance Work		
8400	830	Achieving
7900	680	Achieving
7900	780	Achieving
11000	920	Achieving
11000	920	Achieving
3400	920	Achieving
3400	910	Achieving
3400	910	Achieving

1800	680	Achieving
-	-	Achieving
-	-	Not Achieving
-	-	Achieving
-	-	Not Achieving
-	-	Achieving
-	-	Achieving
2100	780	Achieving
1400	610	Achieving
2000	610	Achieving
2600	930	Achieving

2400	920	Achieving
1700	680	Achieving
2100	920	Achieving
2000	680	Achieving
1700	610	Achieving
ance Work		
630	230	Achieving
430	220	Achieving
430	220	Achieving
390	220	Achieving
310	170	Achieving
250	130	Achieving
840	330	Achieving
250	130	Achieving
430	220	Achieving
1100	790	Achieving

350	170	Achieving
280	130	Achieving
2100	930	Achieving
2100	930	Achieving
1700	780	Achieving
2000	920	Achieving
660	210	Achieving
ance Work		
2600	780	Achieving
2000	920	Achieving
3500	940	Achieving
ance Work		
3400	680	Achieving
2200	700	Achieving

ance Work		
2200	790	Achieving
2100	780	Achieving
2000	610	Achieving
1600	220	Achieving
1700	400	Achieving
1700	400	Achieving
1600	540	Achieving
2200	400	Achieving
1600	540	Achieving
2000	610	Achieving

2500	830	Achieving
2200	400	Achieving
2100	610	Achieving
3500	790	Achieving
2500	830	Achieving
2700	680	Achieving
4600	920	Achieving
5800	910	Achieving
5800	910	Achieving
6300	810	Achieving
3800	910	Achieving
3400	930	Achieving
3100	680	Achieving
4800	680	Achieving

ance Work		
930	820	Achieving
830	680	Achieving
910	780	Achieving
920	680	Achieving
810	600	Achieving
780	550	Achieving
610	780	Achieving
920	780	Achieving
830	610	Achieving
910	680	Achieving
830	680	Achieving
780	600	Achieving
810	560	Achieving
930	780	Achieving

930	780	Achieving
-	-	Achieving
1300	140	Achieving
-	-	Achieving
-	-	Achieving
1700	210	Achieving
3500	700	Achieving
2100	780	Achieving
3900	930	Achieving
3300	930	Achieving
3400	930	Achieving
12000	3200	Not Achieving
3100	910	Achieving

3200	920	Achieving
ance Work		
1600	540	Achieving
ance Work		
1600	920	Achieving
1100	790	Achieving
1700	400	Achieving
1500	400	Achieving
1600	350	Achieving
1600	240	Achieving
1700	400	Achieving
2700	930	Achieving
2200	680	Achieving
2100	610	Achieving
920	540	Achieving

1600	920	Achieving
1100	400	Achieving
2200	680	Achieving
2200	680	Achieving
2100	920	Achieving
1500	840	Achieving
940	130	Achieving
680	61	Achieving
1700	680	Achieving
1700	680	Achieving
930	68	Achieving
2100	930	Achieving
1400	680	Achieving
1200	610	Achieving
4000	610	Achieving
700	240	Achieving
2100	920	Achieving

Performance of Existing								
Sl. No.	Name and Address of STP	Year of Commissioning	City/Town / District	Installed Capacity (MLD)	Utilized Capacity (MLD)	Technology/process STP based	Hotel/Ashram/ Authority / Local Urban body/other institutions responsible for O&M of STP	Rural (R)\Urban(U)\Other(O)
A	STPs Not Achieved							
	26 MLD STP Jhansi Laxmi Taal	2021	Jhansi	26	22	SBR	U.P. Jal Nigam	U
	210 MLD STP, Bingawan Kanpur	2015-16	Kanpur Nagar	210	110	UASB	U.P. Jal Nigam	R
	36 MLD STP Jajmau, Kanpur	9+27 MLD (1992) = 36 MLD (2024)	Kanpur Nagar	36	25	UASB	U.P. Jal Nigam	U
	14.5 MLD STP Trans-yamuna, Jamunapar, Mathura	2007	Mathura	14.5	14.5	WSP	U.P. Jal Nigam	R
B	STPs Not Achieved							
	210 MLD STP, Bingawan Kanpur	2015-16	Kanpur Nagar	210	110	UASB	U.P. Jal Nigam	R
	36 MLD STP Jajmau, Kanpur	9+27 MLD (1992) = 36 MLD (2024)	Kanpur Nagar	36	25	UASB	U.P. Jal Nigam	U

	30 MLD STP Farrukhabad	2024	Kanpur Nagar	30	30	SBR	U.P. Jal Nigam	R
	14.5 MLD STP Trans-yamuna, Jamunapar, Mathura	2007	Mathura	14.5	14.5	WSP	U.P. Jal Nigam	R
C	STPs Not Achieved							
	210 MLD STP, Bingawan Kanpur	2015-16	Kanpur Nagar	210	110	UASB	U.P. Jal Nigam	R
	36 MLD STP Jajmau, Kanpur	9+27 MLD (1992) = 36 MLD (2024)	Kanpur Nagar	36	25	UASB	U.P. Jal Nigam	U
	14.5 MLD STP Trans-yamuna, Jamunapar, Mathura	2007	Mathura	14.5	14.5	WSP	U.P. Jal Nigam	R
	15 MLD STP Unnao	2024	Unnao	15	13	SBR	U.P. Jal Nigam	R
D	STPs Not Achieved							
	210 MLD STP, Bingawan Kanpur	2015-16	Kanpur Nagar	210	110	UASB	U.P. Jal Nigam	R
	36 MLD STP Jajmau, Kanpur	9+27 MLD (1992) = 36 MLD (2024)	Kanpur Nagar	36	25	UASB	U.P. Jal Nigam	U
	14.5 MLD STP Trans-yamuna, Jamunapar, Mathura	2007	Mathura	14.5	14.5	WSP	U.P. Jal Nigam	R

Note :- The standards as per MoEF&CC Notification dated 13.10.2017, titled "App For State Capital: pH-6.5-9.0; BOD - <20 mg/l; TSS- <50 mg/l & FC- <1000 MPN/100 ml; Other than State Capital: pH-6.5-9.0; BOD - <30 mg/l; TSS- <100 mg/l & FC- <1000 MPN/100 ml"
Note:- As per the data received from Regional offices, UP PCB

1g STPs in U.P. October- 2025

Date of Sampling	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)
------------------	-------------------------------------	----	------------	------------	------------	----------------	----------------

Meeting the Standards (First Week)

03.10.2025	Grab	6.92	21	104.76	16	4100	1200
07.10.2025	Grab	7.69	36	170	68	81000	61000
07.10.2025	Grab	7.85	40.5	180	62	84000	63000
09.10.2025	Grab	8.4	40	416	174	11000	2700

Meeting the Standards (Second Week)

14.10.2025	Grab	7.7	39	180	64	-	-
14.10.2025	Grab	7.88	39	170	60	-	-

14.10.2025	Grab	7.85	42.5	160	58	-	-
14.10.2025	Composite	8.7	52	432	188	-	-

Meeting the Standards (Third Week)

21.10.2025	Grab	7.76	40.5	190	64	-	-
21.10.2025	Grab	7.93	42	190	66	-	-
25.10.2025	Grab	8.2	48	384	164	13000	3300
17.10.2025	Grab	8.16	19	156	56	5400	2200

Meeting the Standards (Last Week)

28.10.2025	Grab	7.73	60	200	58	-	-
28.10.2025	Grab	7.96	39	180	68	-	-
29.10.2025	Grab	8	44	368	148	12000	3200

Applicable Effluent Discharge Standards for STPs" are as follows:

00 ml

0 MPN/100 ml

Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
Not Achieving
Not Achieving
Not Achieving
Not Achieving
Not Achieving
Not Achieving

Performance of Existing STPs in							
Sl. No.	Name and Address of STP	Year of Commissioning	City/Town / District	Installed Capacity (MLD)	Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP
A	STPs Not Operation						
	16 MLD STP Jhunsi	2023	Prayagraj	16	0	FCR	U.P. Jal Nigam
	50 MLD STP Ramana	2021	Varanasi	50	50	SBR	U.P. Jal Nigam
	19 MLD STP C.G. City, Lucknow	2023	Lucknow	19	0	SBR	LDA
	6 MLD STP Ramghat, Ayodhya	2023	Ayodhya	6	4	SBR	U.P. Jal Nigam
	2.76 MLD STP Goverdhan STP	2011	Mathura	2.76	0	WSP	Nagar Palika Parishad
	35 MLD STP, Saraitalfi	2023	Bareilly	35	0	ASP	Nagar Nigam
	15 MLD STP Baniyapur	2018	Kanpur Nagar	15	0	SBR	UPJN (Urban)
	5 MLD STP Yamuna Expressway Industrial Development Authority (YIDA)	2023	Jewar (Gt. Noida)	5	0	SBR	UPJN (Rural)
B	STPs Not Operationa						
	16 MLD STP Jhunsi	2023	Prayagraj	16	0	FCR	U.P. Jal Nigam
	50 MLD STP Ramana	2021	Varanasi	50	50	SBR	U.P. Jal Nigam
	1.5 MLD STP Hathi Park, (Smart City)	2021	Lucknow	1.5	1.5	MBBR	Nagar Nigam (Smart City)

	19 MLD STP C.G. City, Lucknow	2023	Lucknow	19	0	SBR	LDA
	2.76 MLD STP Goverdhan STP	2011	Mathura	2.76	0	WSP	Nagar Palika Parishad
	25 MLD STP Sector-50, Noida	2015	Noida	25	14	SBR	Noida Authority
	35 MLD STP, Saraitalfi	2023	Bareilly	35	0	ASP	Nagar Nigam
	15 MLD STP Baniyapur	2018	Kanpur Nagar	15	0	SBR	UPJN (Urban)
	5 MLD STP Yamuna Expressway Industrial Development Authority (YIDA)	2023	Jewar (Gt. Noida)	5	0	SBR	UPJN (Rural)
C	STPs Not Operations						
	16 MLD STP Jhunsi	2023	Prayagraj	16	0	FCR	U.P. Jal Nigam
	50 MLD STP Ramana	2021	Varanasi	50	50	SBR	U.P. Jal Nigam
	1.5 MLD STP Hathi Park, (Smart City)	2021	Lucknow	1.5	1.5	MBBR	Nagar Nigam (Smart City)
	19 MLD STP C.G. City, Lucknow	2023	Lucknow	19	0	SBR	LDA
	2.76 MLD STP Goverdhan STP	2011	Mathura	2.76	0	WSP	Nagar Palika Parishad
	25 MLD STP Sector-50, Noida	2015	Noida	25	14	SBR	Noida Authority
	35 MLD STP, Saraitalfi	2023	Bareilly	35	0	ASP	Nagar Nigam
	15 MLD STP Baniyapur	2018	Kanpur Nagar	15	0	SBR	UPJN (Urban)

	5 MLD STP Yamuna Expressway Industrial Development Authority (YIDA)	2023	Jewar (Gt. Noida)	5	0	SBR	UPJN (Rural)
D	STPs Not Operation						
	13.5 MLD STP at Mauja Umrain	2013	Etawah	13.5	12.5	SBR	UP Jal Nigam
	16 MLD STP Jhunsi	2023	Prayagraj	16	0	FCR	U.P. Jal Nigam
	6.5 MLD STP Awas vikas Parishad STP	2018	Lucknow	6.5	6.5	SBR	Jal Kal
	1.5 MLD STP Hathi Park, (Smart City)	2021	Lucknow	1.5	1.5	MBBR	Nagar Nigam (Smart City)
	19 MLD STP C.G. City, Lucknow	2023	Lucknow	19	0	SBR	LDA
	4.50 MLD STP Kalindi Vihar, Agra	2014	Agra	4.5	4.5	UASB	ADA
	2.76 MLD STP Goverdhan STP	2011	Mathura	2.76	0	WSP	Nagar Palika Parishad
	25 MLD STP Sector-50, Noida	2015	Noida	25	14	SBR	Noida Authority
	35 MLD STP, Saraitalfi	2023	Bareilly	35	0	ASP	Nagar Nigam
	15 MLD STP Baniyapur	2018	Kanpur Nagar	15	0	SBR	UPJN (Urban)
	5 MLD STP Yamuna Expressway Industrial Development Authority (YIDA)	2023	Jewar (Gt. Noida)	5	0	SBR	UPJN (Rural)

Note :- The standards as per MoEF&CC Notification dated 13.10.2017, titled "A)

For State Capital: pH-6.5-9.0; BOD - <20 mg/l; TSS- <50 mg/l & FC- <1000 MPN.

Other than State Capital: pH-6.5-9.0; BOD - <30 mg/l; TSS- <100 mg/l & FC- <10

Note:- As per the data received from Regional offices, UPPCB

U.P. October- 2025

Rural (R)\Urban(U)\Other(O)	Date of Sampling	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)	Reason for being not-operational
-----------------------------	------------------	---	----------------------------------

al (First Week)

R	07.10.2025	-	Not operational Due to Maintenance Work
R	10.10.2025	-	Not operational Due to Maintenance Work
O	08.10.2025	-	Not operational Due to Maintenance Work
U	06.10.2025	-	Not Operational Due To Maintenance Work
O	09.10.2025	-	Not operational Due to Maintenance Work
O	8.10.2025	-	Not operational Due to Maintenance Work
U	01.10.2025	-	Not operational Due to Maintenance Work
R	09.10.2025	-	Not operational Due to Maintenance Work

l (Second Week)

R	14.10.2025	-	Not operational Due to Maintenance Work
R	10.10.2025	-	Not operational Due to Maintenance Work
O	15.10.2025	-	Not operational Due to Maintenance Work

O	15.10.2025	-	Not operational Due to Maintenance Work
O	14.10.2025	-	Not operational Due to Maintenance Work
O	13.10.2025	-	Not operational Due to Maintenance Work
O	14.10.2025	-	Not operational Due to Maintenance Work
U	07.10.2025	-	Not operational Due to Maintenance Work
R	14.10.2025	-	Not operational Due to Maintenance Work

al (Third Week)

R	18.10.2025		Not operational Due to Maintenance Work
R	16.10.2025	-	Not operational Due to Maintenance Work
O	24.10.2025	-	Not operational Due to Maintenance Work
O	24.10.2025	-	Not operational Due to Maintenance Work
O	25.10.2025	-	Not operational Due to Maintenance Work
O	17.10.2025	-	Not operational Due to Maintenance Work
O	24.10.2025	-	Not operational Due to Maintenance Work
U	14.10.2025	-	Not operational Due to Maintenance Work

R	25.10.2025	-	Not operational Due to Maintenance Work
al (Last Week)			
R	28.10.2025	-	Not operational Due to Maintenance Work
R	29.10.2025	-	Not operational Due to Maintenance Work
O	31.10.2025	-	Not operational Due to Maintenance Work
O	31.10.2025	-	Not operational Due to Maintenance Work
O	31.10.2025	-	Not operational Due to Maintenance Work
O	25.10.2025	-	Not operational Due to Maintenance Work
O	29.10.2025	-	Not operational Due to Maintenance Work
O	21.10.2025	-	Not operational Due to Maintenance Work
O	30.10.2025	-	Not operational Due to Maintenance Work
U	28.10.2025	-	Not operational Due to Maintenance Work
R	27.10.2025	-	Not operational Due to Maintenance Work

pplicable Effluent Discharge Standards for STPs" are as follows:

/100 ml

000 MPN/100 ml

Performance of Existing STPs in U.							
Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP
A	STPs Under Trial Run (First V						
1	8 MLD STP Azamgarh	2024	Azamgarh	8	0	SBR	U.P. Jal Nigam
2	33 MLD STP Ayodhya	2025	Ayodhya	33	0	SBR	UPJN (Rural)
3	20 MLD STP Ballia	2025	Ballia	20	0	SBR	UPJN (Urban)
4	25 MLD STP Moradabad	2025	Moradabad	25	0	SBR	UPJN(Rural)
B	STPs Under Trial Run (
1	8 MLD STP Azamgarh	2024	Azamgarh	8	0	SBR	U.P. Jal Nigam
2	33 MLD STP Ayodhya	2025	Ayodhya	33	0	SBR	UPJN (Rural)
3	20 MLD STP Ballia	2025	Ballia	20	0	SBR	UPJN (Urban)

4	25 MLD STP Moradabad	2025	Moradabad	25	0	SBR	UPJN(Rural)
C	STPs Under Trial Run (Third)						
1	8 MLD STP Azamgarh	2024	Azamgarh	8	0	SBR	U.P. Jal Nigam
2	33 MLD STP Ayodhya	2025	Ayodhya	33	0	SBR	UPJN (Rural)
3	20 MLD STP Ballia	2025	Ballia	20	0	SBR	UPJN (Urban)
4	25 MLD STP Moradabad	2025	Moradabad	25	0	SBR	UPJN(Rural)
D	STPs Under Trial Run						
1	8 MLD STP Azamgarh	2024	Azamgarh	8	0	SBR	U.P. Jal Nigam
2	33 MLD STP Ayodhya	2025	Ayodhya	33	0	SBR	UPJN (Rural)
3	20 MLD STP Ballia	2025	Ballia	20	0	SBR	UPJN (Urban)
4	25 MLD STP Moradabad	2025	Moradabad	25	0	SBR	UPJN(Rural)

Note :- The standards as per MoEF&CC Notification dated 13.10.2017, title are as follows:

For State Capital: pH-6.5-9.0; BOD - <20 mg/l; TSS- <50 mg/l & FC- <1000

Other than State Capital: pH-6.5-9.0; BOD - <30 mg/l; TSS- <100 mg/l & FC

Note:- As per the data received from Regional offices, UPPCB

P. October- 2025

Rural (R)\Urban(U)\ Other(O)	Date of Sampling	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)	Operational Status
Week)			
U	01.10.2025	-	Under Trial Run
R	06.10.2025	-	Under Trial Run
U	01.10.2025	-	Under Trial Run
R	02.10.2025	-	Under Trial Run
(Second Week)			
U	10.10.2025	-	Under Trial Run
R	13.10.2025	-	Under Trial Run
U	10.10.2025	-	Under Trial Run

R	14.10.2025	-	Under Trial Run
Week)			
U	16.10.2025	-	Under Trial Run
R	21.10.2025	-	Under Trial Run
U	16.10.2025	-	Under Trial Run
R	21.10.2025	-	Under Trial Run
1 (Last Week)			
U	25.10.2025	-	Under Trial Run
R	28.10.2025	-	Under Trial Run
U	25.10.2025	-	Under Trial Run
R	28.10.2025	-	Under Trial Run

d "Applicable Effluent Discharge Standards for STPs"

MPN/100 ml

↳ <1000 MPN/100 ml

Operational Status of Sewage Treatment Plants (STPs) in Uttar Pradesh								
S.No	Total Installed STPs	Month: November 2025	Operational STPs	STPs Achieving Norms	STPs Not Achieving Norms	STP Not in Operation	Under Trial Run	STPs where sampling was not carried out by the Regional Office, UPPCB.
1	155	First Week	140	134	6	9	3	3
		Second Week	140	136	4	10	3	2
		Third Week	139	136	3	10	3	3
		Last Week	137	130	7	10	3	5
Note :-								
The standards as per MoEF&CC Notification dated 13.10.2017, titled "Applicable Effluent Discharge Standards for STPs" are as follows:								
For State Capital: pH-6.5-9.0; BOD - <20 mg/l; TSS- <50 mg/l & FC- <1000 MPN/100 ml								
Other than State Capital: pH-6.5-9.0; BOD - <30 mg/l; TSS- <100 mg/l & FC- <1000 MPN/100 ml								

Performance of Existing STPs in U.P.																	
WEEKLY DATA OF STPs																	
November- 2025																	
Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)\Urban(U)\ Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
1	10.445 MLD STP near Tixi Tempel (Karanpur)	2001	Etawah	10.445	8	WSP	UP Jal Nigam	R	04.11.2025	Grab	8	26	140	47	11000	910	Achieving
									12.11.2025	Grab	7.8	24	130	45	8400	830	Achieving
									20.11.2025	Grab	8.1	23	110	40	7900	810	Achieving
									27.11.2025	Grab	7.8	21	120	44	9400	920	Achieving
									04.11.2025	Grab	8.2	9	70	9	8400	610	Achieving
2	21 MLD STP Etawah	2022	Etawah	21	20	SBR	UP Jal Nigam	R	12.11.2025	Grab	8	9.2	60	8	7000	560	Achieving
									20.11.2025	Grab	8.2	7.6	40	6	7000	600	Achieving
									27.11.2025	Grab	7.9	10.8	70	9	7900	780	Achieving
									04.11.2025	Grab	7.9	28	140	49	12000	930	Achieving
									12.11.2025	Grab	7.9	28	140	49	12000	930	Achieving
3	13.5 MLD STP at Mauja Umrain	2013	Etawah	13.5	12	SBR	UP Jal Nigam	R	12.11.2025	Sampling has not been carried out by the Regional Office							
									20.11.2025	Grab	7.9	22	120	41	9400	820	Achieving
									27.11.2025	Grab	8.1	26	150	47	11000	920	Achieving
									03.11.2025	Grab	7.9	25	130	44	9400	820	Achieving
									10.11.2025	Grab	8.2	26	150	45	11000	920	Achieving
4	03 MLD STP Firozabad	2014	Firozabad	3	1.4	UASB	NPP	O	18.11.2025	Grab	8	28	130	48	9400	910	Achieving
									27.11.2025	Grab	7.8	22	110	39	8400	830	Achieving
									03.11.2025	Grab	7.8	12	70	11	8400	680	Achieving
									10.11.2025	Grab	8	9.6	60	8	7000	610	Achieving
									18.11.2025	Grab	8.1	9.2	60	8	7000	610	Achieving
5	67 MLD STP Mohammadpur, Biharipur	2020	Firozabad	67	50	ASP+ extended aeration	U.P. Jal Nigam	U	26.11.2025	Grab	7.9	10.4	70	9	7900	680	Achieving
									04.11.2025	Grab	8.1	14	90	24	2900	680	Achieving
									12.11.2025	Grab	8.2	15	110	27	8400	810	Achieving
									20.11.2025	Grab	8.1	18	90	31	7900	810	Achieving
									27.11.2025	Grab	7.8	22	120	42	9400	910	Achieving
6	1.65 MLD STP Saifai (Paramedicals)	2013	Etawah	1.65	0.8	SBR	Others	O	03.11.2025	Grab	7.9	24	140	42	9400	830	Achieving
									10.11.2025	Grab	8.2	26	150	45	11000	920	Achieving
									17.11.2025	Grab	8	23	130	42	8400	820	Achieving
									26.11.2025	Grab	7.9	28	140	47	11000	930	Achieving
									04.11.2025	Grab	8	28	140	43	9400	920	Achieving
7	23 MLD STP at Mauja Odenya, Padaria	2014	Mainpuri	23	17	UASB	U.P. Jal Nigam	U	12.11.2025	Grab	7.9	27	160	48	8400	830	Achieving
									20.11.2025	Grab	7.8	24	140	46	11000	930	Achieving
									04.11.2025	Grab	8	28	140	43	9400	920	Achieving
									12.11.2025	Grab	7.9	27	160	48	8400	830	Achieving
									20.11.2025	Grab	7.8	24	140	46	11000	930	Achieving
8	1.5 MLD STP Saifai Village, Etawah	2006	Etawah	1.5	1.1	Oxidation Pond	U.P. Jal Nigam	U	27.11.2025	Grab	8	27	150	48	12000	1100	Not Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)\Urban(U)\ Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
16	13 MLD STP Jalalpur, Amrapur, Kannauj	2017	Kanpur Dehat	13	12	SBR	Nagar Palika Parishad	O	04.11.2025	Grab	7.33	24	110	48	-	-	Achieving
									11.11.2025	Grab	7.3	21	100	52	330	270	Achieving
									18.11.2025	Grab	7.3	19.5	110	54	310	230	Achieving
									25.11.2025	Grab	7.4	15	90	44	320	210	Achieving
17	30 MLD STP Pankha, Kanpur	2023	Kanpur Nagar	30	29	SBR	U.P. Jal Nigam	R	04.11.2025	Grab	7.4	21	140	40	-	-	Achieving
									11.11.2025	Grab	7.76	27	160	56	580	310	Achieving
									18.11.2025	Grab	7.58	25.5	150	48	490	330	Achieving
									25.11.2025	Grab	7.62	24	140	52	470	210	Achieving
18	36 (9+27) MLD STP Jajmau, Kanpur	1992 & 2024	Kanpur Nagar	36	25	UASB	U.P. Jal Nigam	U	04.11.2025	Grab	8.15	37.5	190	60	-	-	Not Achieving
									11.11.2025	Grab	8.09	42	170	64	82000	61000	Not Achieving
									18.11.2025	Grab	8.1	39	180	60	68000	45000	Not Achieving
									25.11.2025	Grab	8.13	45	190	68	63000	33000	Not Achieving
19	17.7 MLD STP Fatehgarh, Farrukhabad	2024	Kanpur Nagar	17.7	17	SBR	U.P. Jal Nigam	R	04.11.2025	Grab	7.99	19.5	160	46	-	-	Achieving
									11.11.2025	Grab	8.08	19.5	180	52	840	630	Achieving
									18.11.2025	Grab	8.09	24	160	54	820	610	Achieving
									25.11.2025	Grab	8.14	25.5	150	58	790	490	Achieving
20	30 MLD STP Farrukhabad	2024	Kanpur Nagar	30	30	SBR	U.P. Jal Nigam	R	04.11.2025	Grab	7.86	18	220	52	-	-	Achieving
									11.11.2025	Grab	8.14	22.5	230	56	920	680	Achieving
									18.11.2025	Grab	8.16	18	190	50	840	630	Achieving
									25.11.2025	Grab	8.18	21	200	62	700	330	Achieving
21	50 MLD STP Numayadahi	2013	Prayagraj	50	50	ASP +Bio Tower Technology	Ganga Pollution control unit, U.P. Jal Nigam	R	03.11.2025	Grab	7.49	25	72	60	2000	780	Achieving
									11.11.2025	Composite	7.84	25.6	78	65	2200	780	Achieving
									18.11.2025	Grab	7.73	25.2	76	60	2600	780	Achieving
									24.11.2025	Grab	7.77	26	80	66	2400	780	Achieving
22	10 MLD STP Ponghat	2013	Prayagraj	10	10	ASP +Bio Tower Technology	Ganga Pollution control unit, U.P. Jal Nigam	R	03.11.2025	Grab	7.55	22	52	46	1400	680	Achieving
									11.11.2025	Composite	7.93	23.2	56	48	1700	680	Achieving
									18.11.2025	Grab	7.78	22.6	52	44	1700	610	Achieving
									24.11.2025	Grab	7.63	22	52	48	1700	790	Achieving
23	25 MLD STP Kodra	2013	Prayagraj	25	25	ASP +Bio Tower Technology	Ganga Pollution control unit, U.P. Jal Nigam	R	03.11.2025	Grab	7.14	22.2	56	48	1700	700	Achieving
									11.11.2025	Composite	7.68	23.5	60	54	2000	680	Achieving
									18.11.2025	Grab	7.61	23	64	54	2100	680	Achieving
									24.11.2025	Grab	7.56	22.8	60	56	2200	780	Achieving
24	60 MLD STP Rajapur	2013	Prayagraj	60	60	UASB	Ganga Pollution control unit, U.P. Jal Nigam	R	04.11.2025	Grab	7.28	28	88	72	2200	930	Achieving
									11.11.2025	Composite	7.61	28.6	84	78	2600	930	Achieving
									19.11.2025	Grab	7.72	28.2	88	72	2700	930	Achieving
									24.11.2025	Grab	7.84	28.6	92	76	2600	930	Achieving
25	29 MLD STP Salori-1	2007	Prayagraj	29	28	FAB	Ganga Pollution control unit, U.P. Jal Nigam	R	04.11.2025	Grab	7.45	27	76	62	2100	920	Achieving
									11.11.2025	Composite	7.7	27.4	80	70	2700	930	Achieving
									19.11.2025	Grab	7.68	27	84	66	2600	920	Achieving
									24.11.2025	Grab	7.65	28.8	88	72	2600	920	Achieving
26	14 MLD STP Salori-2 Expansion	2016	Prayagraj	14	14	SBR	Ganga Pollution control unit, U.P. Jal Nigam	U	04.11.2025	Grab	7.18	19.6	44	30	1400	610	Achieving
									11.11.2025	Composite	7.58	20.4	40	38	1400	680	Achieving
									19.11.2025	Grab	7.49	18.8	36	32	1400	610	Achieving
									24.11.2025	Grab	7.71	19.4	48	39	1700	700	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)\Urban(U)\ Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
27	80 MLD STP Naini	2013	Prayagraj	80	80	ASP	Ganga Pollution control unit, U.P. Jal Nigam	R	03.11.2025	Grab	7.22	27.2	80	66	2000	920	Achieving
									10.11.2025	Composite	7.64	26.8	72	68	2100	920	Achieving
									18.11.2025	Grab	7.57	26.2	80	62	2200	930	Achieving
									24.11.2025	Grab	7.82	27.8	84	68	2400	920	Achieving
28	42 MLD STP, Naini	2023	Prayagraj	42	36	FCR	U.P. Jal Nigam	R	03.11.2025	Grab	7.58	23.8	64	52	2100	780	Achieving
									10.11.2025	Composite	7.67	23	60	58	2300	780	Achieving
									18.11.2025	Grab	7.56	23.8	68	56	2400	780	Achieving
									24.11.2025	Grab	7.52	23.8	76	64	2300	780	Achieving
29	14 MLD STP Phaphamau	2023	Prayagraj	14	14	FCR	U.P. Jal Nigam	R	03.11.2025	Grab	7.29	22.6	60	50	1400	700	Achieving
									11.11.2025	Composite	7.99	23.2	68	52	1700	700	Achieving
									18.11.2025	Grab	7.81	22.8	60	52	2000	680	Achieving
									24.11.2025	Grab	7.68	22.2	56	48	2000	680	Achieving
30	16 MLD STP Jhunsi	2023	Prayagraj	16	15	FCR	U.P. Jal Nigam	R	04.11.2025	Grab	7.62	24.6	68	58	1700	790	Achieving
									10.11.2025	Composite	7.9	24.9	72	60	2000	610	Achieving
									19.11.2025	Grab	7.76	24	72	58	2200	680	Achieving
									24.11.2025	Grab	7.74	24.4	68	62	2100	680	Achieving
31	10 MLD STP Ramnagar	2021	Varanasi	10	9	Anaerobic Anoxic Oxidation (A2O)	U.P. Jal Nigam	R	06.11.2025	Grab	7.32	38.2	198	88	35000	17000	Not Achieving
									12.11.2025	Grab	7.42	18.2	88	28	430	220	Achieving
									17.11.2025	Grab	7.46	12.4	64	16	350	140	Achieving
									29.11.2025	Grab	7.42	26.8	162	90	1700	1100	Not Achieving
32	80 MLD STP Dinapur	1994	Varanasi	80	68	ASP	U.P. Jal Nigam	U	06.11.2025	Grab	7.58	28.2	152	84	540	220	Achieving
									12.11.2025	Grab	7.57	24.2	142	78	350	130	Achieving
									17.11.2025	Grab	7.62	27.4	138	76	390	170	Achieving
									29.11.2025	Grab	7.48	28.2	134	84	1500	630	Achieving
33	9.8 MLD STP Bhagwanpur	1989	Varanasi	9.8	8	ASP	U.P. Jal Nigam	R	09.11.2025	Grab	7.38	24.9	134	82	350	130	Achieving
									12.11.2025	Grab	7.48	24.2	132	72	310	170	Achieving
									17.11.2025	Grab	7.41	26.2	148	78	380	170	Achieving
									29.11.2025	Grab	7.49	28.6	156	88	1600	940	Achieving
34	140 MLD STP Dinapur	2018	Varanasi	140	99	ASP	U.P. Jal Nigam	U	06.11.2025	Grab	7.71	15.4	40	10.2	250	130	Achieving
									12.11.2025	Grab	7.67	12.4	42	14	350	140	Achieving
									17.11.2025	Grab	7.69	14.2	48	12	380	170	Achieving
									29.11.2025	Grab	7.66	12.6	62	18	350	130	Achieving
35	120 MLD STP Goithaha	2019	Varanasi	120	40	UASB	U.P. Jal Nigam	U	06.11.2025	Grab	7.42	22.8	72	26	43000	17000	Not Achieving
									12.11.2025	Grab	7.61	14.4	52	18	350	130	Achieving
									17.11.2025	Grab	7.58	18.3	60	22	310	170	Achieving
									29.11.2025	Grab	7.59	16.7	58	20	540	220	Achieving
36	12 MLD BLW STP	1989	Varanasi	12	12	ASP	BLW	O	09.11.2025	Grab	7.56	27.2	164	84	350	140	Achieving
									12.11.2025	Grab	7.58	26.7	156	76	470	210	Achieving
									17.11.2025	Grab	7.53	24.8	188	88	540	220	Achieving
									29.11.2025	Grab	7.53	27.3	184	96	1500	700	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)\Urban(U)\ Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
37	50 MLD STP Ramana	2021	Varanasi	50	50	SBR	U.P. Jal Nigam	R	06.11.2025	Grab	7.38	40.4	176	62	28000	13000	Not Achieving
									12.11.2025	Grab	7.42	28.2	104	42	390	220	Achieving
									17.11.2025	Grab	7.49	24.2	68	18	430	170	Achieving
									29.11.2025	Grab	7.57	16.2	56	24	1400	790	Achieving
38	30 MLD STP Pachhahatiya Jaunpur	2023	Jaunpur, Varanasi	30	30	A2O	U.P. Jal Nigam	R	06.11.2025	Grab	7.62	8	38	6	390	220	Achieving
									11.11.2025	Grab	7.57	7.2	42	6.2	320	220	Achieving
									21.11.2025	Grab	7.64	8.8	44	7.4	310	130	Achieving
									29.11.2025	Grab	7.71	7.8	38	9	310	130	Achieving
39	07 MLD Vindyachal Mirzapur	2022	Mirzapur	7	5	WSP	Nagar Palika Parishad	O	04.11.2025	Grab	7.58	14.6	68	40	630	310	Achieving
									11.11.2025	Grab	7.51	16.2	72	46	470	260	Achieving
									19.11.2025	Grab	7.41	15.4	62	38	700	310	Achieving
									24.11.2025	Grab	7.36	22.6	88	52	940	490	Achieving
40	14 MLD STP Pakka Pokhra	1994	Mirzapur	14	13	UASB	U.P. Jal Nigam	R	04.11.2025	Grab	7.55	27.6	158	72	920	700	Achieving
									11.11.2025	Grab	7.52	31.8	174	82	2300	1300	Not Achieving
									19.11.2025	Grab	7.43	29.4	166	86	1200	630	Achieving
									24.11.2025	Grab	7.39	34.8	184	88	4700	2200	Not Achieving
41	8.5 MLD STP Pakka Pokhra, Mirzapur	2024	Mirzapur	8.5	4.25	SBR	U.P. Jal Nigam	R	04.11.2025	Grab	7.45	12.2	58	26	940	460	Achieving
									11.11.2025	Grab	7.51	15.3	62	32	840	430	Achieving
									19.11.2025	Grab	7.38	14.4	54	28	920	410	Achieving
									24.11.2025	Grab	7.34	24.8	72	48	1200	460	Achieving
42	8.5 MLD STP Bisunderpur, Mirzapur	2024	Mirzapur	8.5	7.6	SBR	U.P. Jal Nigam	R	04.11.2025	Grab	7.5	11.4	54	32	430	210	Achieving
									11.11.2025	Grab	7.48	16.6	64	36	920	480	Achieving
									19.11.2025	Grab	7.37	14.2	56	26	1600	540	Achieving
									24.11.2025	Grab	7.41	21.2	78	38	920	700	Achieving
43	15 MLD S.T.P. Jharkhandi, Maherwa ki Bari	2015	Gorakhpur	15	11.89	SBR	U.P. Jal Nigam	U	04.11.2025	Grab	7.32	9	32	22	2000	920	Achieving
									11.11.2025	Grab	7.52	8	34	28	2400	910	Achieving
									18.11.2025	Grab	7.69	7.5	28	27	1700	780	Achieving
									25.11.2025	Grab	7.52	8	32	30	2400	910	Achieving
44	5 MLD S.T.P. Jharkhandi, Maherwa ki Bari	2023	Gorakhpur	5	4	SBR	U.P. Jal Nigam	U	04.11.2025	Grab	7.32	9	32	22	2000	920	Achieving
									11.11.2025	Grab	7.52	8	34	28	2400	910	Achieving
									18.11.2025	Grab	7.69	7.5	28	27	1700	780	Achieving
									25.11.2025	Grab	7.52	8	32	30	2400	910	Achieving
45	30 MLD S.T.P. Opp. Manyavar Kanshiram Shabri Garib Awas	2015	Gorakhpur	30	20	SBR	U.P. Jal Nigam	U	04.11.2025	Grab	7.74	8.5	28	25	1700	780	Achieving
									11.11.2025	Grab	7.64	9.5	38	26	2100	820	Achieving
									18.11.2025	Grab	7.74	8.5	36	25	2400	910	Achieving
									25.11.2025	Grab	7.41	7	24	22	2100	930	Achieving
46	10 MLD STP Gorakhpur	2024	Gorakhpur	10	10	SBR	U.P. Jal Nigam	U	04.11.2025	Grab	7.96	7.5	24	27	2100	930	Achieving
									11.11.2025	Grab	7.61	7.5	40	22	2000	930	Achieving
									18.11.2025	Grab	7.59	8	32	22	2100	930	Achieving
									25.11.2025	Grab	7.64	7.5	28	25	1700	780	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)\Urban(U)\ Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
56	19 MLD STP C.G. City, Lucknow	2023	Lucknow	19	0	SBR	LDA	O	07.11.2025	Not Operational Due to Maintainance Works							
									10.11.2025								
									21.11.2025								
									24.11.2025								
57	56 MLD STP Trans Hindon (Indirapuram), Ghaziabad	2000	Ghaziabad	56	56	UASB	U.P. Jal Nigam	U	06.11.2025	Grab	7.4	20	72	42	1600	540	Achieving
									13.11.2025	Grab	7.52	16	66	35	2200	790	Achieving
									18.11.2025	Grab	7.5	14	60	30	2700	680	Achieving
									27.11.2025	Grab	7.54	16	74	32	1600	920	Achieving
									04.11.2025	Grab	7.45	8	62	9	2100	780	Achieving
58	30 MLD STP, Sadullabad (Loni), Ghaziabad	2012	Ghaziabad	30	20	MBBR	U.P. Jal Nigam	U	11.11.2025	Grab	7.65	9	68	10	1600	350	Achieving
									19.11.2025	Grab	7.6	8	52	9	2400	780	Achieving
									24.11.2025	Grab	7.57	9	60	10	1500	930	Achieving
									06.11.2025	Grab	7.54	8	60	9	2100	610	Achieving
									13.11.2025	Grab	7.49	9	62	10	2700	680	Achieving
59	74 MLD STP S.B.R., Indirapuram, Ghaziabad	2013	Ghaziabad	74	74	SBR	U.P. Jal Nigam	U	18.11.2025	Grab	7.34	8	54	9	2500	450	Achieving
									27.11.2025	Grab	7.5	9	58	10	1700	680	Achieving
									06.11.2025	Grab	7.45	9	34	10	2200	790	Achieving
									13.11.2025	Grab	7.4	8	26	9	1600	350	Achieving
									18.11.2025	Grab	7.26	7	24	9	2200	790	Achieving
60	56 MLD STP S.B.R., Bapudham, Ghaziabad	2014	Ghaziabad	56	1.5	SBR	GDA	O	27.11.2025	Grab	7.42	8	28	10	1600	220	Achieving
									03.11.2025	Grab	7.53	9	38	10	2400	780	Achieving
									10.11.2025	Grab	7.58	8	30	9	1600	540	Achieving
									17.11.2025	Grab	7.53	7	26	9	2200	400	Achieving
									26.11.2025	Grab	7.62	8	28	10	1600	280	Achieving
61	6 MLD STP Garh Zone, Garhmukteswar Hapur	2011	Hapur / Garhmukteswar	6	4.62	UASB followed by extended	U.P. Jal Nigam (NGRBA)	R	03.11.2025	Grab	7.48	8	34	10	1600	280	Achieving
									10.11.2025	Grab	7.64	7	26	9	1600	350	Achieving
									17.11.2025	Grab	7.48	8	32	10	1700	400	Achieving
									26.11.2025	Grab	7.44	6	24	8	1600	540	Achieving
									06.11.2025	Grab	7.56	9	48	10	1600	350	Achieving
62	3 MLD STP Brijghat Zone, Garhmukteswar Hapur	2011	Hapur / Garhmukteswar	3	2.5	UASB followed by extended	U.P. Jal Nigam (NGRBA)	R	13.11.2025	Grab	7.55	8	40	9	1600	350	Achieving
									18.11.2025	Grab	7.4	9	46	10	1600	540	Achieving
									27.11.2025	Grab	7.35	8	42	9	2500	400	Achieving
									07.11.2025	Grab	7.48	7	34	9	2500	780	Achieving
									13.11.2025	Grab	7.53	9	48	10	1600	540	Achieving
63	56 MLD STP S.B.R., Dudahaida Vijay Nagar, Ghaziabad	2013	Ghaziabad	56	56	SBR	U.P. Jal Nigam	U	18.11.2025	Grab	7.4	8	44	10	2200	790	Achieving
									27.11.2025	Grab	7.48	7	36	9	1600	540	Achieving
									07.11.2025	Grab	7.62	18	76	42	1600	920	Achieving
									13.11.2025	Grab	7.54	24	84	47	2200	450	Achieving
									18.11.2025	Grab	7.36	20	80	45	1600	540	Achieving
64	70 MLD STP U.A.S.B.R. Dudahaida Vijay Nagar, Ghaziabad	2000	Ghaziabad	70	70	UASB	U.P. Jal Nigam	U	27.11.2025	Grab	7.52	16	78	40	2200	400	Achieving
									03.11.2025	Grab	7.64	22	68	40	1600	540	Achieving
									10.11.2025	Grab	7.57	20	74	50	2000	610	Achieving
									17.11.2025	Grab	7.37	18	88	49	2700	830	Achieving
									26.11.2025	Grab	7.4	14	72	35	2100	680	Achieving
65	3 MLD STP Pilkhaun	2015	Ghaziabad	3	2.5	UASB	U.P. Jal Nigam	U	03.11.2025	Grab	7.64	22	68	40	1600	540	Achieving
									10.11.2025	Grab	7.57	20	74	50	2000	610	Achieving
									17.11.2025	Grab	7.37	18	88	49	2700	830	Achieving
									26.11.2025	Grab	7.4	14	72	35	2100	680	Achieving
									07.11.2025	Grab	7.62	18	76	42	1600	920	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town/ District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)\Urban(U)\ Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
67	5 MLD STP Trans Delhi Signature City (Tronica City),	2019	Ghaziabad	5	3.8	MBBR	UPSIDA	O	04.11.2025	Grab	7.63	14	80	35	2200	450	Achieving
									11.11.2025	Grab	7.49	10	74	30	1600	540	Achieving
									19.11.2025	Grab	7.44	12	78	34	2400	920	Achieving
									24.11.2025	Grab	7.56	16	82	40	1600	350	Achieving
68	56 MLD STP S.B.R. Govindpuram, Ghaziabad	2014	Ghaziabad	56	14	SBR	GDA	O	06.11.2025	Grab	7.45	8	36	9	1600	280	Achieving
									13.11.2025	Grab	7.64	7	32	8	1700	400	Achieving
									18.11.2025	Grab	7.55	8	38	9	2000	450	Achieving
									27.11.2025	Grab	7.53	9	44	10	1600	280	Achieving
69	20 MLD STP Modinagar	2023	Modinagar, Ghaziabad	20	7.8	SBR	Nagar Palika Parishad	O	04.11.2025	Grab	7.5	12	66	30	1600	920	Achieving
									11.11.2025	Grab	7.58	14	52	25	1600	540	Achieving
									19.11.2025	Grab	7.46	18	66	30	2800	790	Achieving
									24.11.2025	Grab	7.4	16	74	37	2100	680	Achieving
70	56 MLD STP S.B.R., Morty, Ghaziabad	2018	Ghaziabad	56	27	SBR	Nagar Nigam Ghaziabad	O	06.11.2025	Grab	7.42	8	68	12	1600	540	Achieving
									13.11.2025	Grab	7.5	10	74	15	1600	920	Achieving
									18.11.2025	Grab	7.55	14	82	20	2000	610	Achieving
									27.11.2025	Grab	7.46	9	66	10	2200	400	Achieving
71	30 MLD STP, Rampur Road, Hapur	2022	Hapur, Ghaziabad	30	8	SBR	Nagar Palika Parishad	O	03.11.2025	Grab	7.44	12	112	40	1700	680	Achieving
									10.11.2025	Grab	7.62	18	128	47	2100	400	Achieving
									17.11.2025	Grab	7.5	16	120	40	1400	610	Achieving
									26.11.2025	Grab	7.48	14	112	39	1700	930	Achieving
72	21.5 MLD STP Siddharthvihar, Ghaziabad	2024	Ghaziabad	21.5	4.5	SBR	Awaz Vikas	O	07.11.2025	Grab	7.63	12	92	35	2200	790	Achieving
									13.11.2025	Grab	7.66	10	88	32	1600	350	Achieving
									18.11.2025	Grab	7.49	12	76	30	1600	280	Achieving
									27.11.2025	Grab	7.6	14	80	35	2200	400	Achieving
73	78 MLD STP Dhadhupura, Agra	2013	Agra	78	78	UASB	U.P. Jal Nigam	U	01.11.2025	Grab	7.84	24	100	44	3400	930	Achieving
									07.11.2025	Grab	7.86	25	100	48	3400	930	Achieving
									15.11.2025	Grab	7.94	27	140	37	6300	810	Achieving
									22.11.2025	Grab	7.84	28	120	48	6300	810	Achieving
74	2.25 MLD STP Budi ka Nagla, Agra	2000	Agra	2.25	2.25	WSP	U.P. Jal Nigam	U	01.11.2025	Grab	7.91	27	140	37	6300	810	Achieving
									07.11.2025	Grab	7.9	28	100	42	4600	920	Achieving
									15.11.2025	Grab	7.88	25	100	43	6300	810	Achieving
									22.11.2025	Grab	7.91	27	120	32	6300	810	Achieving
75	10 MLD STP Peelakhar, Agra	2000	Agra	10	10	WSP	U.P. Jal Nigam	U	01.11.2025	Grab	7.86	28	120	36	3800	910	Achieving
									07.11.2025	Grab	7.89	27	120	46	6300	810	Achieving
									15.11.2025	Grab	7.85	26	110	46	5800	910	Achieving
									22.11.2025	Grab	7.86	28	140	34	5800	910	Achieving
76	12 MLD STP Devri Road, (Bhimnagri), Agra	2011	Agra	12	8	UASB	U.P. Jal Nigam	U	01.11.2025	Grab	7.8	26	100	38	3400	930	Achieving
									07.11.2025	Grab	7.91	27	140	40	4800	680	Achieving
									15.11.2025	Grab	7.89	25	120	48	3400	930	Achieving
									22.11.2025	Grab	7.82	27	120	36	3400	930	Achieving
77	14 MLD STP Jaganpur, Sikandarpur, Agra	2011	Agra	14	14	UASB	U.P. Jal Nigam	U	01.11.2025	Grab	7.88	25	120	36	5800	910	Achieving
									07.11.2025	Grab	7.87	25	120	45	3400	930	Achieving
									15.11.2025	Grab	7.89	24	140	44	4600	920	Achieving
									22.11.2025	Grab	7.87	28	110	38	4600	920	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)\Urban(U)\ Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)		
78	40 MLD STP Sadarban, Bichhpuri, Agra	2013	Agra	40	28	UASB	U.P. Jal Nigam	U	01.11.2025	Grab	7.9	27	140	40	3800	910	Achieving		
									04.11.2025	Grab	7.44	26	110	43	3400	930	Achieving		
									15.11.2025	Grab	7.83	28	100	38	3400	930	Achieving		
									22.11.2025	Grab	7.87	27	130	38	3400	930	Achieving		
79	36 MLD STP Sadarwan (Bichpuri) New	2018	Agra	36	36	SBR	Nagar Nigam	O	01.11.2025	Grab	7.48	28	160	63	4600	920	Achieving		
									04.11.2025	Grab	7.48	29	140	58	3800	910	Achieving		
									15.11.2025	Grab	7.63	28	120	68	4600	810	Achieving		
									22.11.2025	Grab	7.83	28	110	64	3800	910	Achieving		
80	24 MLD STP Dhadhupura (New), Agra	2014	Agra	24	15	UASB	U.P. Jal Nigam	U	01.11.2025	Grab	7.81	22	80	32	3100	680	Achieving		
									07.11.2025	Grab	7.89	23	100	38	3100	680	Achieving		
									15.11.2025	Grab	7.9	25	120	34	3800	910	Achieving		
									22.11.2025	Grab	7.88	29	100	36	5800	910	Achieving		
81	4.50 MLD STP Kalindi Vihar, Agra	2014	Agra	4.5	4.5	UASB	Nagar Nigam	O	01.11.2025	Not Operational Due to Maintainance Works									
									07.11.2025	Grab	7.56	28	140	65	6300	810	Achieving		
									15.11.2025	Not Operational Due to Maintainance Works									
									22.11.2025	Not Operational Due to Maintainance Works									
82	03 MLD STP Pandav Nagar, Meerut	2013	Meerut	3	2.7	ASP	MDA	O	06.11.2025	Grab	7.48	22	168	78	930	810	Achieving		
									12.11.2025	Grab	7.51	20	148	84	930	820	Achieving		
									20.11.2025	Grab	7.47	22	132	68	920	680	Achieving		
									27.11.2025	Grab	7.55	20	124	60	820	680	Achieving		
83	07 MLD STP Pallavpuram-1, Meerut	2012	Meerut	7	6.5	ASP	MDA	O	06.11.2025	Grab	7.47	15	88	46	920	780	Achieving		
									12.11.2025	Grab	7.37	17	116	57	810	560	Achieving		
									20.11.2025	Grab	7.55	16	96	50	910	610	Achieving		
									27.11.2025	Grab	7.46	15	88	44	810	610	Achieving		
84	11 MLD STP Pallavpuram-2, Meerut	2008	Meerut	11	7	ASP	MDA	O	06.11.2025	Grab	7.44	16	96	52	820	680	Achieving		
									12.11.2025	Grab	7.45	18	136	62	920	780	Achieving		
									20.11.2025	Grab	7.47	15	88	52	930	680	Achieving		
									27.11.2025	Grab	7.51	16	96	48	810	680	Achieving		
85	06 MLD STP Rakshapuram, Meerut	2011	Meerut	6	4.4	ASP	MDA	O	06.11.2025	Grab	7.56	18	132	62	930	780	Achieving		
									12.11.2025	Grab	7.47	16	112	68	830	680	Achieving		
									20.11.2025	Grab	7.56	18	104	60	930	780	Achieving		
									27.11.2025	Grab	7.48	17	112	56	830	780	Achieving		
86	10 MLD STP Lohiya Nagar, Meerut	2010	Meerut	10	2	ASP	MDA	O	06.11.2025	Grab	7.41	10	24	20	830	680	Achieving		
									12.11.2025	Grab	7.46	10	28	24	810	600	Achieving		
									20.11.2025	Grab	7.39	12	28	24	830	610	Achieving		
									27.11.2025	Grab	7.41	10	24	20	780	610	Achieving		
87	15 MLD STP Shatabdinagar, Meerut	2010	Meerut	15	4.8	ASP	MDA	O	06.11.2025	Grab	7.41	10	20	25	810	600	Achieving		
									12.11.2025	Grab	7.36	8	24	22	780	550	Achieving		
									20.11.2025	Grab	7.42	10	20	20	810	600	Achieving		
									27.11.2025	Grab	7.45	12	24	18	780	680	Achieving		

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)\Urban(U)\ Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
88	15 MLD STP Vedvyaspuri Meerut	2011	Meerut	15	4.5	ASP	MDA	O	06.11.2025	Grab	7.39	8	20	20	810	600	Achieving
									12.11.2025	Grab	7.38	12	68	24	810	610	Achieving
									20.11.2025	Grab	7.42	10	32	28	820	600	Achieving
									27.11.2025	Grab	7.39	10	28	24	830	600	Achieving
89	06 MLD STP Shradhapuri-1, Meerut	2012	Meerut	6	5.5	ASP	MDA	O	06.11.2025	Grab	7.51	17	112	48	830	610	Achieving
									12.11.2025	Grab	7.52	18	128	60	920	680	Achieving
									20.11.2025	Grab	7.44	16	112	48	910	680	Achieving
									27.11.2025	Grab	7.52	15	86	56	920	680	Achieving
90	06 MLD STP Sainik Vihar	2017	Meerut	6	5.9	UASB	MDA	O	06.11.2025	Grab	7.54	10	28	18	920	680	Achieving
									12.11.2025	Grab	7.43	14	48	26	820	600	Achieving
									20.11.2025	Grab	7.46	12	32	32	910	680	Achieving
									27.11.2025	Grab	7.44	10	28	26	830	810	Achieving
91	5 MLD STP Modipuram Tiraha	2016	Meerut	5	4.5	ASP	MDA	O	06.11.2025	Grab	7.56	16	72	50	830	610	Achieving
									12.11.2025	Grab	7.38	15	88	44	780	610	Achieving
									20.11.2025	Grab	7.42	14	60	34	830	610	Achieving
									27.11.2025	Grab	7.39	12	44	28	820	680	Achieving
92	07 MLD STP Sports Goods Complex, Meerut	2012	Meerut	7	4	ASP	MDA	O	06.11.2025	Grab	7.45	16	92	60	910	680	Achieving
									12.11.2025	Grab	7.41	16	100	52	810	600	Achieving
									20.11.2025	Grab	7.51	14	84	34	830	610	Achieving
									27.11.2025	Grab	7.42	12	40	30	810	780	Achieving
93	72 MLD STP Garh road (Jagriti vihar) Kamalpur	2018	Meerut	72	72	ASP	U.P. Jal Nigam	U	06.11.2025	Grab	7.38	10	24	8	910	680	Achieving
									12.11.2025	Grab	7.41	10	30	10	920	780	Achieving
									20.11.2025	Grab	7.38	12	36	14	830	610	Achieving
									27.11.2025	Grab	7.47	10	28	10	910	600	Achieving
94	10 MLD STP Ganga Nagar, Meerut	2011	Meerut	10	3.8	SBR	MDA	O	06.11.2025	Grab	7.44	9	20	8	780	550	Achieving
									12.11.2025	Grab	7.39	10	24	10	830	610	Achieving
									20.11.2025	Grab	7.41	8	20	8	810	600	Achieving
									27.11.2025	Grab	7.46	10	24	10	810	600	Achieving
95	06 MLD STP Shradhapuri-Phase-2, Meerut	2012	Meerut	6	5.6	SBR	MDA	O	06.11.2025	Grab	7.48	20	156	64	920	810	Achieving
									12.11.2025	Grab	7.44	14	96	70	820	600	Achieving
									20.11.2025	Grab	7.48	17	120	56	930	780	Achieving
									27.11.2025	Grab	7.47	18	124	60	820	780	Achieving
96	14 MLD STP Baghpat, Meerut	2021	Baghpat, Meerut	14	7.8	SBR	U.P. Jal Nigam	R	03.11.2025	Grab	7.52	20	180	82	920	680	Achieving
									10.11.2025	Grab	7.59	17	128	74	810	560	Achieving
									20.11.2025	Grab	7.62	18	140	64	930	780	Achieving
									27.11.2025	Grab	7.56	17	128	56	920	810	Achieving
97	32.5 MLD STP (WSP) Nagar Palika Parishad, Kidwai nagar	2001	Muzaffar Nagar	32.5	32.5	WSP	U.P. Jal Nigam	U	04.11.2025	Grab	7.7	20	64	48	2100	700	Achieving
									11.11.2025	Grab	7.5	24	88	40	1700	680	Achieving
									19.11.2025	Grab	7.4	26	96	44	2100	700	Achieving
									26.11.2025	Grab	7.5	24	88	44	2200	940	Achieving
98	32.5 MLD STP Near A2Z Garbage plant KidwaiNagar	2025	Muzaffar Nagar	32.5	18	SBR	U.P. Jal Nigam	R	04.11.2025	Grab	7.5	6	24	16	1400	110	Achieving
									11.11.2025	Grab	7.6	9	28	18	1100	140	Achieving
									19.11.2025	Grab	7.5	7	24	12	1400	110	Achieving
									26.11.2025	Grab	7.6	8	26	14	1300	110	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)\Urban(U)\ Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
99	10 MLD STP Budhana	2024	Muzaffar Nagar	10	7.32	SBR	U.P. Jal Nigam	R	04.11.2025	Grab	7.4	8	24	18	1700	140	Achieving
									11.11.2025	Grab	7.4	8	28	18	1300	110	Achieving
									19.11.2025	Grab	7.6	6	24	14	1300	170	Achieving
									26.11.2025	Grab	7.5	7	26	18	1100	140	Achieving
100	22 MLD STP Sahawali, Muzaffarnagar	2023	Muzaffar Nagar	22	21	SBR	U.P. Jal Nigam	R	04.11.2025	Grab	7.6	7	26	14	1100	130	Achieving
									11.11.2025	Grab	7.2	7	24	16	1300	170	Achieving
									19.11.2025	Grab	7.5	7	26	18	1300	210	Achieving
									26.11.2025	Grab	7.4	9	28	16	1400	110	Achieving
101	15 MLD STP Kairana, Shamli, Muzaffarnagar	2024	Muzaffar Nagar	15	15	SBR	U.P. Jal Nigam	U	04.11.2025	Grab	7.3	9	28	12	1300	170	Achieving
									11.11.2025	Grab	7.7	9	26	14	1400	210	Achieving
									19.11.2025	Grab	7.4	8	28	16	1400	170	Achieving
									26.11.2025	Grab	7.5	6	24	12	1300	130	Achieving
102	12 MLD STP Ayodhya	2014	Ayodhya	12	7	UASB	U.P. Jal Nigam	U	03.11.2025	Grab	7.3	25	124	70	4700	930	Achieving
									13.11.02025	Grab	7.41	18	102	64	3300	780	Achieving
									18.11.2025	Grab	7.46	22	114	62	3400	940	Achieving
									26.11.2025	Grab	7.4	15	78	56	2600	680	Achieving
103	6 MLD STP Ramghat, Ayodhya	2023	Ayodhya	6	4	SBR	U.P. Jal Nigam	U	03.11.20252	Grab	7.4	11	57	43	2200	700	Achieving
									13.11.02025	Grab	7.43	14	68	55	4000	610	Achieving
									18.11.2025	Grab	7.22	16	84	51	3200	780	Achieving
									26.11.2025	Grab	7.3	21	98	72	3900	920	Achieving
104	13.59 (6.8) MLD STP, Masani, Mathura	2007	Mathura	6.8	6.5	WSP	U.P. Jal Nigam	R	04.11.2025	Grab	7.9	24	232	84	3800	920	Achieving
									11.11.2025	Composite	7.7	23	216	72	-	-	Achieving
									19.11.2025	Grab	7.9	25	232	86	3900	930	Achieving
									28.11.2025	Grab	7.8	27	240	94	3800	920	Achieving
105	04 MLD STP Vrindavan Near Pagal Baba Mandir, Mathura	2007	Mathura	4	4	WSP	U.P. Jal Nigam	R	04.11.2025	Grab	7.7	24	208	70	3100	910	Achieving
									11.11.2025	Composite	7.8	25	232	82	-	-	Achieving
									19.11.2025	Grab	7.9	27	240	86	3400	930	Achieving
									28.11.2025	Grab	7.7	26	232	72	3200	920	Achieving
106	08 MLD STP Near 100 Bed Hospital Vrindavan, Manth	2015	Mathura	8	8	UASB	U.P. Jal Nigam	U	04.11.2025	Grab	7.6	25	216	78	3200	920	Achieving
									11.11.2025	Composite	7.5	22	192	70	-	-	Achieving
									18.11.2025	Grab	7.6	24	208	74	3300	930	Achieving
									28.11.2025	Grab	7.8	25	224	80	3400	930	Achieving
107	14.5 MLD STP Trans-yamuna, Jamunapar, Mathura	2007	Mathura	14.5	14.5	WSP	U.P. Jal Nigam	R	04.11.2025	Grab	8.3	50	384	160	17000	3300	Not Achieving
									11.11.2025	Composite	8.1	42	352	154	-	-	Not Achieving
									18.11.2025	Grab	7.9	44	384	162	14000	3100	Not Achieving
									28.11.2025	Grab	8.1	52	400	156	13000	3300	Not Achieving
108	30 MLD STP Masani Mathura	2020	Mathura	30	30	SBR	U.P. Jal Nigam	R	04.11.2025	Grab	7.6	23	192	60	2500	910	Achieving
									11.11.2025	Composite	7.5	21	184	48	-	-	Achieving
									19.11.2025	Grab	7.7	23	200	56	2700	930	Achieving
									28.11.2025	Grab	7.6	24	208	64	3100	910	Achieving
109	16 MLD STP Trans Yamuna, Laxmi Nagar, Mathura	2015	Mathura	16	15	UASB	U.P. Jal Nigam	R	04.11.2025	Grab	8.2	26	248	90	3400	930	Achieving
									11.11.2025	Composite	7.9	24	240	84	-	-	Achieving
									18.11.2025	Grab	7.8	27	248	88	3800	920	Achieving
									28.11.2025	Grab	7.9	24	216	68	3300	930	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)\Urban(U)\ Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
110	2.76 MLD STP Goverdhan STP	2011	Mathura	2.76	0	WSP	Nagar Palika Parishad	O	04.11.2025	Not Operational Due to Maintainance Works							
									11.11.2025								
									18.11.2025								
									28.11.2025								
111	33 MLD STP Sector-54, Noida	2011	Noida	33	13	SBR	Noida Authority	O	03.11.2025	Grab	7.35	12.7	94.4	23	1700	900	Achieving
									10.11.2025	Grab	7.51	11.09	89.6	24	2200	400	Achieving
									17.11.2025	Grab	7.41	10.3	88.8	29	1600	540	Achieving
									21.11.2025	Composite	7.3	18.8	129.6	56	-	-	Achieving
									24.11.2025	Grab	7.38	12.5	96	27	1600	920	Achieving
112	25 MLD STP Sector-50, Noida	2015	Noida	25	0	SBR	Noida Authority	O	03.11.2025	Not Operational Due to Maintainance Works							
									10.11.2025								
									17.11.2025								
									21.11.2025								
113	35 MLD STP Sector-123, Noida	2011	Noida	35	18	SBR	Noida Authority	O	03.11.2025	Grab	7.38	11.6	72	21	1700	680	Achieving
									10.11.2025	Grab	7.66	12.9	102.4	25	2700	610	Achieving
									17.11.2025	Grab	7.63	14.4	104	33	2200	680	Achieving
									21.11.2025	Composite	7.19	17.2	155.2	61	-	-	Achieving
									24.11.2025	Grab	7.41	14.2	109.6	29	1200	630	Achieving
114	50 MLD STP Sector-168, Noida	2015	Noida	50	19	SBR	Noida Authority	O	03.11.2025	Grab	7.53	13.5	99.2	25	1700	780	Achieving
									10.11.2025	Grab	7.61	13.5	109.6	19	1200	830	Achieving
									17.11.2025	Grab	7.39	13.1	64	27	2200	680	Achieving
									21.11.2025	Composite	7.59	17.2	136.8	49	-	-	Achieving
									24.11.2025	Grab	7.51	15.5	115.2	30	1600	220	Achieving
115	34 MLD STP Sector -50 Noida	2012	Noida	34	32	SBR	Noida Authority	O	03.11.2025	Grab	7.54	9.1	80	21	1400	680	Achieving
									10.11.2025	Grab	7.39	21.1	95.2	27	1700	450	Achieving
									17.11.2025	Grab	7.23	11.8	82.4	28	1200	610	Achieving
									21.11.2025	Composite	7.17	20.1	153.6	66	-	-	Achieving
									24.11.2025	Grab	7.31	11.3	80	24	1500	400	Achieving
116	54 MLD STP Sector- 54, Noida	2012	Noida	54	42	SBR	Noida Authority	O	03.11.2025	Grab	7.47	8.3	64	18	1600	540	Achieving
									10.11.2025	Grab	7.44	10.7	82.4	21	1600	350	Achieving
									17.11.2025	Grab	7.49	13.9	96.8	81	3400	930	Achieving
									21.11.2025	Composite	7.53	16.5	132.8	47	-	-	Achieving
									24.11.2025	Grab	7.38	10.7	848	22	1600	350	Not Achieving
117	100 MLD STP Sector- 168, Noida	2023	Noida	100	62	SBR	Noida Authority	O	03.11.2025	Grab	7.65	14.2	89.6	26	1700	780	Achieving
									10.11.2025	Grab	7.67	11.2	64	17	2200	790	Achieving
									17.11.2025	Grab	7.59	10.3	72	24	1600	350	Achieving
									21.11.2025	Composite	7.67	14.3	114.8	31	-	-	Achieving
									24.11.2025	Grab	7.5	9.6	56	17	1600	540	Achieving
118	80 MLD STP Sector- 123, Noida	2023	Noida	80	65	SBR	Noida Authority	O	03.11.2025	Grab	7.49	12.1	89.6	20	2500	920	Achieving
									10.11.2025	Grab	7.38	10.7	64.8	19	1600	540	Achieving
									17.11.2025	Grab	7.31	9.8	56	22	1400	200	Achieving
									21.11.2025	Composite	7.33	15.9	112.8	37	-	-	Achieving
									24.11.2025	Grab	7.39	11.2	68	19	2100	830	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)\Urban(U)\ Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)	
119	2.0 MLD STP Greater Noida Authority STP, Vill- Badalpur	2015	Greater Noida	2	2	SBR	GNIDA	O	06.11.2025	Grab	7.6	9	42	15	2100	680	Achieving	
									15.11.2025	Grab	7.56	10	38	19	1700	680	Achieving	
									22.11.2025	Grab	7.49	9	44	25	1600	540	Achieving	
									29.11.2025	Composite	7.45	12	96	40	1600	920	Achieving	
120	15 MLD STP ECO tech -2	2018	Greater Noida	15	8	SBR	GNIDA	O	06.11.2025	Grab	7.42	8	40	10	1600	540	Achieving	
									15.11.2025	Grab	7.64	9	36	15	1600	280	Achieving	
									22.11.2025	Grab	7.47	16	76	32	2200	400	Achieving	
									29.11.2025	Composite	7.42	14	66	35	2100	930	Achieving	
121	20 MLD STP ECO tech -3	2018	Greater Noida	20	12	SBR	GNIDA	O	06.11.2025	Grab	7.6	14	68	20	2200	400	Achieving	
									15.11.2025	Grab	7.55	12	42	20	2200	400	Achieving	
									22.11.2025	Grab	7.35	10	40	19	2100	680	Achieving	
									29.11.2025	Composite	7.66	10	26	12	1600	540	Achieving	
122	137 MLD STP Kasana, GreaterNoida	2015	Greater Noida	137	90	SBR	GNIDA	O	06.11.2025	Grab	7.48	8	34	12	1600	350	Achieving	
									15.11.2025	Grab	7.47	8	28	10	1600	220	Achieving	
									22.11.2025	Grab	7.5	12	54	27	1700	930	Achieving	
									29.11.2025	Composite	7.42	9	48	20	1400	400	Achieving	
123	0.805 MLD STP Ahara Road, Zone-A, Anoopshahar	2003	Bulandshahr	0.805	0.8	WSP	U.P. Jal Nigam	U	03.11.2025	Grab	7.76	20	96	45	1300	450	Achieving	
									10.11.2025	Grab	7.78	24	92	41	1200	610	Achieving	
									17.11.2025	Grab	7.65	22	104	49	1100	400	Achieving	
									24.11.2025	Grab	7.72	20	92	46	930	450	Achieving	
124	1.75 MLD STP Ahara Road, (Shivanand Ashram) Zone-B,	2003	Bulandshahr	1.75	1.75	WSP	U.P. Jal Nigam	U	03.11.2025	Grab	7.68	24	88	49	1700	680	Achieving	
									10.11.2025	Grab	7.72	22	84	43	1500	840	Achieving	
									17.11.2025	Grab	7.76	26	96	48	1400	680	Achieving	
									24.11.2025	Grab	7.69	22	88	49	920	540	Achieving	
125	2.25 MLD STP Narora Atomic power Station Narora Township	2000	Bulandshahr	2.25	2.25	ASP	Narora Atomic power Station	O	03.11.2025	Grab	7.45	18	104	64	920	540	Achieving	
									10.11.2025	Grab	7.53	16	112	73	540	240	Achieving	
									17.11.2025	Grab	7.48	18	96	65	540	240	Achieving	
									24.11.2025	Grab	7.43	16	92	61	540	240	Achieving	
126	01 MLD STP Zone-B Anoopshahar	2016	Bulandshahr	1	1	MBBR	Nagar Palika Parishad	O	03.11.2025	Grab	7.71	26	132	78	2200	780	Achieving	
									10.11.2025	Grab	7.68	24	124	89	2000	680	Achieving	
									17.11.2025	Grab	7.63	22	112	85	2000	680	Achieving	
									24.11.2025	Grab	7.67	26	120	73	1700	930	Achieving	
127	1.5 MLD STP Anoopshahar Zone A (NGRBA)	2016	Bulandshahr	1.5	0	UASB	Nagar Palika Parishad	O	03.11.2025	Grab	8.78	28	144	87	1600	920	Achieving	
									10.11.2025	Not Operational Due to Maintainnce Works								
									17.11.2025	Not Operational Due to Maintainnce Works								
									24.11.2025	Not Operational Due to Maintainnce Works								
128	40 MLD STP Bulandshahar	2023	Bulandshahr	40	20	SBR	Nagar Palika Parishad	O	03.11.2025	Grab	7.58	20	108	51	2000	680	Achieving	
									10.11.2025	Grab	7.61	18	108	64	2200	680	Achieving	
									17.11.2025	Grab	7.55	14	92	51	1500	840	Achieving	
									24.11.2025	Grab	7.57	18	84	41	1400	680	Achieving	
129	04 MLD STP , Narora (NGRBA)	2015	Bulandshahr	4	4	UASB	Nagar Palika Parishad	O	03.11.2025	Grab	7.74	24	124	68	2100	930	Achieving	
									10.11.2025	Grab	7.71	22	104	71	1600	920	Achieving	
									17.11.2025	Grab	7.78	26	116	75	1700	930	Achieving	
									24.11.2025	Grab	7.75	22	108	77	2600	920	Achieving	

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)\Urban(U)\ Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
141	2 MLD STP Miranpur, Sadar, Sultanpur	2024	Sultanpur	2	1.4	SBR	U.P. Jal Nigam	R	03.11.2025	Grab	8.08	24.0	56.00	36.0	2400	930	Achieving
									13.11.2025	Grab	8.14	23.0	52.80	39.0	2100	920	Achieving
									20.11.2025	Grab	8.13	24.0	56.00	41.0	2200	920	Achieving
									27.11.2025	Grab	8.17	21	51.2	36	2000	780	Achieving
142	10 MLD STP Hathia Nala, Lolepur	2006	Sultanpur	10	6.5	Aerated Lagoon	U.P. Jal Nigam	R	03.11.2025	Grab	8.02	20.0	60.80	37.0	2400	920	Achieving
									13.11.2025	Grab	8.07	22.0	59.20	39.0	2300	920	Achieving
									20.11.2025	Grab	8.05	25.0	56.00	35.0	2400	930	Achieving
									27.11.2025	Grab	8.01	22	54.4	38	2100	780	Achieving
143	18 MLD STP Raebareli	2023	Raebareli	18	5.0	SBR	Nagar Palika Parishad	O	04.11.2025	Grab	8.01	8.5	47.68	7.0	780	200	Achieving
									10.11.2025	Grab	8.05	8.0	48.00	7.5	790	210	Achieving
									17.11.2025	Grab	8.01	9.0	49.60	8.0	680	200	Achieving
									24.11.2025	Grab	8.06	8.5	49.28	7	780	210	Achieving
144	35 MLD STP, Saraitafi	2023	Bareilly	35	0	ASP	Nagar Nigam	O	04.11.2025	Not Operational Due to Maintainnace Works							
									11.11.2025								
									18.11.2025								
									26.11.2025								
145	42 MLD STP, HarooNagla, Bareilly	2024	Bareilly	42	42	SBR	U.P. Jal Nigam	R	04.11.2025	Grab	7.8	6	32	13	170	90	Achieving
									11.11.2025	Composite	7.5	8	36	15	210	94	Achieving
									18.11.2025	Grab	7.6	6	40	17	220	79	Achieving
									26.11.2025	Grab	7.4	8	44	14	170	68	Achieving
146	20 MLD STP Barinagla, Bareilly	2024	Bareilly	20	18	SBR	U.P. Jal Nigam	R	04.11.2025	Grab	7.4	8	40	15	220	94	Achieving
									11.11.2025	Composite	7.8	6	44	17	170	79	Achieving
									18.11.2025	Grab	7.3	8	36	14	210	90	Achieving
									26.11.2025	Grab	7.6	6	40	16	220	79	Achieving
147	01 MLD STP, Girdaripur, Bareilly	2024	Bareilly	1	1	SBR	U.P. Jal Nigam	R	04.11.2025	Grab	7.1	8	40	16	210	79	Achieving
									11.11.2025	Composite	7.6	8	36	17	220	90	Achieving
									18.11.2025	Grab	7.5	6	44	15	170	68	Achieving
									26.11.2025	Grab	7.9	8	32	13	210	94	Achieving
148	40 MLD STP, Shahjahanpur	2025	Shahjahanpur	40	10	SBR	U.P. Jal Nigam	U	04.11.2025	Grab	7.2	6	32	6	170	68	Achieving
									11.11.2025	Grab	7.6	8	40	9	220	90	Achieving
									18.11.2025	Composite	7.9	6	36	7	210	79	Achieving
									26.11.2025	Grab	7.4		44	8			
149	15 MLD STP Unnao	2024	Unnao	15	13	SBR	U.P. Jal Nigam	R		Sampling has not been carried out by the Regional Office,UppCB							
									11.11.2025	Grab	8.46	16.8	164	62.2	4100	930	Achieving
									20.11.2025	Grab	8.29	20.2	172	70.8	4900	780	Achieving
150	21 MLD STP Mau Road, Ghazipur	2024	Ghazipur, Varanasi	21	12	SBR	U.P. Jal Nigam	R	01.11.2025	Grab	7.52	7.9	40	6.2	470	210	Achieving
									04.11.2025	Grab	7.59	7.1	38	6.8	330	170	Achieving
									11.11.2025	Grab	7.48	8.4	44	7.4	310	130	Achieving
									21.11.2025	Grab	7.61	6.8	36	6.4	400	220	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)\Urban(U)\ Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
151	33 MLD STP Ayodhya	2025	Ayodhya	33	0	SBR	UPJN (Rural)	R	03.11.2025	Under Trial Run							
									13.11.02025	Under Trial Run							
									18.11.2025	Under Trial Run							
									26.11.2025	Under Trial Run							
152	15 MLD STP Baniyapur	2018	Kampur Nagar	15	0	SBR	UPJN (Urban)	U	04.11.2025	Not operational Due to Maintenance Work							
									11.11.2025								
									18.11.2025								
									25.11.2025								
153	5 MLD STP Yamuna Expressway Industrial	2023	Jewar (Gt. Noida)	5	0	SBR	UPJN (Rural)	R	06.11.2025	Not operational Due to Maintenance Work							
									15.11.2025								
									22.11.2025								
									29.11.2025								
154	20 MLD STP Ballia	2025	Ballia	20	0	SBR	UPJN (Urban)	U	14.11.2025	Under Trial Run							
155	25 MLD STP Moradabad	2025	Moradabad	25	0	SBR	UPJN(Rural)	R	04.11.2025	Under Trial Run							
									11.11.2025	Under Trial Run							
									18.11.2025	Under Trial Run							
									26.11.2025	Under Trial Run							

Note :- The standards as per MoEF&CC Notification dated 13.10.2017, titled "Applicable Effluent Discharge Standards for STPs" are as follows:
For State Capital: pH-6.5-9.0; BOD - <20 mg/l; TSS- <50 mg/l & FC- <1000 MPN/100 ml
Other than State Capital: pH-6.5-9.0; BOD - <30 mg/l; TSS- <100 mg/l & FC- <1000 MPN/100 ml
Note:- As per the data received from Regional offices, UPPCB

Performance of Existing STPs in U.P. (First Week)																	November- 2025	
Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)\Urban(U)\ Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)	
1	10.445 MLD STP near Tixi Tempel (Karanpur)	2001	Etawah	10.445	8	WSP	UP Jal Nigam	R	04.11.2025	Grab	8	26	140	47	11000	910	Achieving	
2	21 MLD STP Etawah	2022	Etawah	21	20	SBR	UP Jal Nigam	R	04.11.2025	Grab	8.2	9	70	9	8400	610	Achieving	
3	13.5 MLD STP at Mauja Umrain	2013	Etawah	13.5	12	SBR	UP Jal Nigam	R	04.11.2025	Grab	7.9	28	140	49	12000	930	Achieving	
4	03 MLD STP Firozabad	2014	Firozabad	3	1.4	UASB	NPP	O	03.11.2025	Grab	7.9	25	130	44	9400	820	Achieving	
5	67 MLD STP Mohammadpur, Biharipur	2020	Firozabad	67	50	ASP+ extended aeration	U.P. Jal Nigam	U	03.11.2025	Grab	7.8	12	70	11	8400	680	Achieving	
6	1.65 MLD STP Saifai (Paramedicals)	2013	Etawah	1.65	0.8	SBR	Others	O	04.11.2025	Grab	8.1	14	90	24	2900	680	Achieving	
7	23 MLD STP at Mauja Odenya, Padaria	2014	Mainpuri	23	17	UASB	U.P. Jal Nigam	U	03.11.2025	Grab	7.9	24	140	42	9400	830	Achieving	
8	1.5 MLD STP Saifai Village, Etawah	2006	Etawah	1.5	1.1	Oxidation Pond	U.P. Jal Nigam	U	04.11.2025	Grab	8	28	140	43	9400	920	Achieving	
9	26 (22+4) MLD STP Jhansi Laxmi Taal	2021	Jhansi	26	22	SBR	U.P. Jal Nigam	U	07.11.2025	Grab	7.21	20	246.96	14	2100	780	Achieving	
					4				07.11.2025	Grab	7.18	15	74.48	12	2000	680	Achieving	
10	26 MLD STP Smart City, Lahargird	2025	Jhansi	26	25	SBR	Nagar Nigam	O	04.11.2025	Grab	7.59	23.52	39.2	13	1600	540	Achieving	
11	3.42 MLD STP Near Divyang kendra	2000	Chitrakoot	3.42	0	Oxidation Pond	Nagar Palika Parishad	O	Based on the consensus of the Joint Committee chaired by the District Magistrate, Chitrakoot, during the meeting.									
12	42 MLD STP, Sajari Kanpur	2016-17	Kanpur Nagar	42	22	ASP	U.P. Jal Nigam	R	04.11.2025	Grab	7.79	18	180	58	-	-	Achieving	
13	210 MLD STP, Bingawan Kanpur	2015-16	Kanpur Nagar	210	110	UASB	U.P. Jal Nigam	R	04.11.2025	Grab	7.56	63	230	72	-	-	Not Achieving	
14	130 MLD STP Jajmau, Kanpur	1998-99	Kanpur Nagar	130	115	ASP	U.P. Jal Nigam	R	04.11.2025	Grab	7.84	19.5	170	52	-	-	Achieving	
15	43 MLD STP Jajmau, Kanpur	2020	Kanpur Nagar	43	40	UASB	U.P. Jal Nigam	R	04.11.2025	Grab	7.9	18	180	48	-	-	Achieving	
16	13 MLD STP Jalalpur, Amrapur, Kannauj	2017	Kanpur Dehat	13	12	SBR	Nagar Palika Parishad	O	04.11.2025	Grab	7.33	24	110	48	-	-	Achieving	
17	30 MLD STP Pankha, Kanpur	2023	Kanpur Nagar	30	29	SBR	U.P. Jal Nigam	R	04.11.2025	Grab	7.4	21	140	40	-	-	Achieving	
18	36 (9+27) MLD STP Jajmau, Kanpur	1992 & 2024	Kanpur Nagar	36	25	UASB	U.P. Jal Nigam	U	04.11.2025	Grab	8.15	37.5	190	60	-	-	Not Achieving	
19	17.7 MLD STP Fatehgarh, Farrukhabad	2024	Kanpur Nagar	17.7	17	SBR	U.P. Jal Nigam	R	04.11.2025	Grab	7.99	19.5	160	46	-	-	Achieving	
20	30 MLD STP Farrukhabad	2024	Kanpur Nagar	30	30	SBR	U.P. Jal Nigam	R	04.11.2025	Grab	7.86	18	220	52	-	-	Achieving	

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)Urban(U) Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
21	50 MLD STP Numayadahi	2013	Prayagraj	50	50	ASP +Bio Tower Technology	Ganga Pollution control unit, U.P. Jal Nigam	R	03.11.2025	Grab	7.49	25	72	60	2000	780	Achieving
22	10 MLD STP Ponghat	2013	Prayagraj	10	10	ASP +Bio Tower Technology	Ganga Pollution control unit, U.P. Jal Nigam	R	03.11.2025	Grab	7.55	22	52	46	1400	680	Achieving
23	25 MLD STP Kodra	2013	Prayagraj	25	25	ASP +Bio Tower Technology	Ganga Pollution control unit, U.P. Jal Nigam	R	03.11.2025	Grab	7.14	22.2	56	48	1700	700	Achieving
24	60 MLD STP Rajapur	2013	Prayagraj	60	60	UASB	Ganga Pollution control unit, U.P. Jal Nigam	R	04.11.2025	Grab	7.28	28	88	72	2200	930	Achieving
25	29 MLD STP Salori-1	2007	Prayagraj	29	28	FAB	Ganga Pollution control unit, U.P. Jal Nigam	R	04.11.2025	Grab	7.45	27	76	62	2100	920	Achieving
26	14 MLD STP Salori-2 Expansion	2016	Prayagraj	14	14	SBR	Ganga Pollution control unit, U.P. Jal Nigam	U	04.11.2025	Grab	7.18	19.6	44	30	1400	610	Achieving
27	80 MLD STP Naini	2013	Prayagraj	80	80	ASP	Ganga Pollution control unit, U.P. Jal Nigam	R	03.11.2025	Grab	7.22	27.2	80	66	2000	920	Achieving
28	42 MLD STP, Naini	2023	Prayagraj	42	36	FCR	U.P. Jal Nigam	R	03.11.2025	Grab	7.58	23.8	64	52	2100	780	Achieving
29	14 MLD STP Phaphamau	2023	Prayagraj	14	14	FCR	U.P. Jal Nigam	R	03.11.2025	Grab	7.29	22.6	60	50	1400	700	Achieving
30	16 MLD STP Jhunsi	2023	Prayagraj	16	15	FCR	U.P. Jal Nigam	R	04.11.2025	Grab	7.62	24.6	68	58	1700	790	Achieving
31	10 MLD STP Ramnagar	2021	Varanasi	10	9	Anaerobic Anoxic Oxidation (A2O)	U.P. Jal Nigam	R	06.11.2025	Grab	7.32	38.2	198	88	35000	17000	Not Achieving
32	80 MLD STP Dinapur	1994	Varanasi	80	68	ASP	U.P. Jal Nigam	U	06.11.2025	Grab	7.58	28.2	152	84	540	220	Achieving
33	9.8 MLD STP Bhagwanpur	1989	Varanasi	9.8	8	ASP	U.P. Jal Nigam	R	09.11.2025	Grab	7.38	24.9	134	82	350	130	Achieving
34	140 MLD STP Dinapur	2018	Varanasi	140	99	ASP	U.P. Jal Nigam	U	06.11.2025	Grab	7.71	15.4	40	10.2	250	130	Achieving
35	120 MLD STP Goithaha	2019	Varanasi	120	40	UASB	U.P. Jal Nigam	U	06.11.2025	Grab	7.42	22.8	72	26	43000	17000	Not Achieving
36	12 MLD BLW STP	1989	Varanasi	12	12	ASP	BLW	O	09.11.2025	Grab	7.56	27.2	164	84	350	140	Achieving
37	50 MLD STP Ramana	2021	Varanasi	50	50	SBR	U.P. Jal Nigam	R	06.11.2025	Grab	7.38	40.4	176	62	28000	13000	Not Achieving
38	30 MLD STP Pachhahatiya Jaunpur	2023	Jaunpur, Varanasi	30	30	A2O	U.P. Jal Nigam	R	06.11.2025	Grab	7.62	8	38	6	390	220	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)(Urban(U)) Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
39	07 MLD Vindyalchal Mirzapur	2022	Mirzapur	7	5	WSP	Nagar Palika Parishad	O	04.11.2025	Grab	7.58	14.6	68	40	630	310	Achieving
40	14 MLD STP Pakka Pokhra	1994	Mirzapur	14	13	UASB	U.P. Jal Nigam	R	04.11.2025	Grab	7.55	27.6	158	72	920	700	Achieving
41	8.5 MLD STP Pakka Pokhra, Mirzapur	2024	Mirzapur	8.5	4.25	SBR	U.P. Jal Nigam	R	04.11.2025	Grab	7.45	12.2	58	26	940	460	Achieving
42	8.5 MLD STP Bisunderpur, Mirzapur	2024	Mirzapur	8.5	4.6	SBR	U.P. Jal Nigam	R	04.11.2025	Grab	7.5	11.4	54	32	430	210	Achieving
43	15 MLD S.T.P. Jharkhandi, Maherwa ki Bari	2015	Gorakhpur	15	11.89	SBR	U.P. Jal Nigam	U	04.11.2025	Grab	7.32	9	32	22	2000	920	Achieving
44	5 MLD S.T.P. Jharkhandi, Maherwa ki Bari	2023	Gorakhpur	5	4	SBR	U.P. Jal Nigam	U	04.11.2025	Grab	7.32	9	32	22	2000	920	Achieving
45	30 MLD S.T.P. Opp. Manyavar Kanshiram Shahri Garib Awas Yojna, Deoria bypass Road	2015	Gorakhpur	30	20	SBR	U.P. Jal Nigam	U	04.11.2025	Grab	7.74	8.5	28	25	1700	780	Achieving
46	10 MLD STP Gorakhpur	2024	Gorakhpur	10	10	SBR	U.P. Jal Nigam	U	04.11.2025	Grab	7.96	7.5	24	27	2100	930	Achieving
47	8 MLD STP Azamgarh	2024	Azamgarh	8	5	SBR	Nagar Palika Parishad	O	04.11.2025	Sampling has not been carried out by the Regional Office,UPPCB							
48	38 MLD STP, Mahilpur Road	1998	Saharanpur	38	38	UASB	U.P. Jal Nigam	U	04.11.2025	Grab	7.3	24	174	40	420	210	Achieving
49	6.5 MLD STP Awas vikas Parishad STP	2018	Lucknow	6.5	0	SBR	Jal Kal Vibhag	O	04.11.2025	Not Operational Due to Maintainnace Works							
50	37.5 MLD STP Awas vikas Parishad STP	2017	Lucknow	37.5	37.5	SBR	U.P. Awas vikas Parishad	O	04.11.2025	Grab	7.5	11	58	35	2400	450	Achieving
51	345 MLD STP, Bharwara	2011	Lucknow	345	345	UASB	U.P. Jal Nigam	U	04.11.2025	Grab	7.59	17	110	48	5400	940	Achieving
52	56 (42+14) MLD STP, Daulatganj	2003	Lucknow	56	56	FAB	U.P. Jal Nigam	U	07.11.2025	Grab	7.43	18	102	47	4700	920	Achieving
53	1.5 MLD STP Hathi Park, (Smart City)	2021	Lucknow	1.5	0	MBBR	Nagar Nigam (Smart City)	O	07.11.2025	Not Operational Due to Maintainnace Works							
54	39 MLD STP, Sajjadbagh, Daulatganj	2024	Lucknow	39	39	SBR	U.P. Jal Nigam	R	07.11.2025	Grab	7.48	15	80	45	2600	610	Achieving
55	120 MLD STP near 1090 Chauraha	2025	Lucknow	120	80	SBR	U.P. Jal Nigam	U	07.11.2025	Grab	7.48	15	80	45	2600	610	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)\Urban(U)\ Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
56	19 MLD STP C.G. City, Lucknow	2023	Lucknow	19	0	SBR	LDA	O	07.11.2025	Not Operational Due to Maintenance Works							
57	56 MLD STP Trans Hindon (Indirapuram), Ghaziabad	2000	Ghaziabad	56	56	UASB	U.P. Jal Nigam	U	06.11.2025	Grab	7.4	20	72	42	1600	540	Achieving
58	30 MLD STP, Sadullabad (Loni), Ghaziabad	2012	Ghaziabad	30	20	MBBR	U.P. Jal Nigam	U	04.11.2025	Grab	7.45	8	62	9	2100	780	Achieving
59	74 MLD STP S.B.R., Indirapuram, Ghaziabad	2013	Ghaziabad	74	74	SBR	U.P. Jal Nigam	U	06.11.2025	Grab	7.54	8	60	9	2100	610	Achieving
60	56 MLD STP S.B.R., Bapudham, Ghaziabad	2014	Ghaziabad	56	1.5	SBR	GDA	O	06.11.2025	Grab	7.45	9	34	10	2200	790	Achieving
61	6 MLD STP Garh Zone, Garhmukteswar Hapur	2011	Hapur / Garhmukteswar	6	4.62	UASB followed by extended aeration	U.P. Jal Nigam (NGRBA)	R	03.11.2025	Grab	7.53	9	38	10	2400	780	Achieving
62	3 MLD STP Brijghat Zone, Garhmukteswar Hapur	2011	Hapur / Garhmukteswar	3	2.5	UASB followed by extended aeration	U.P. Jal Nigam (NGRBA)	R	03.11.2025	Grab	7.48	8	34	10	1600	280	Achieving
63	56 MLD STP, Indirapuram, (GDA), Ghaziabad	2012	Ghaziabad	56	20	SBR	Nagar Nigam	O	06.11.2025	Grab	7.56	9	48	10	1600	350	Achieving
64	56 MLD STP S.B.R., Dudahaida Vijay Nagar, Ghaziabad	2013	Ghaziabad	56	56	SBR	U.P. Jal Nigam	U	07.11.2025	Grab	7.48	7	34	9	2500	780	Achieving
65	70 MLD STP U.A.S.B.R. Dudahaida Vijay Nagar, Ghaziabad	2000	Ghaziabad	70	70	UASB	U.P. Jal Nigam	U	07.11.2025	Grab	7.62	18	76	42	1600	920	Achieving
66	3 MLD STP Pilkhaun	2015	Ghaziabad	3	2.5	UASB	U.P. Jal Nigam	U	03.11.2025	Grab	7.64	22	68	40	1600	540	Achieving
67	5 MLD STP Trans Delhi Signature City (Tronica City), Loni	2019	Ghaziabad	5	5	MBBR	UPSIDA	O	04.11.2025	Grab	7.63	14	80	35	2200	450	Achieving
68	56 MLD STP S.B.R. Govindpuram, Ghaziabad	2014	Ghaziabad	56	14	SBR	GDA	O	06.11.2025	Grab	7.45	8	36	9	1600	280	Achieving
69	20 MLD STP Modinagar	2023	Modinagar, Ghaziabad	20	7.8	SBR	Nagar Palika Parishad	O	04.11.2025	Grab	7.5	12	66	30	1600	920	Achieving
70	56 MLD STP S.B.R., Morty, Ghaziabad	2018	Ghaziabad	56	27	SBR	Nagar Nigam Ghaziabad	O	06.11.2025	Grab	7.42	8	68	12	1600	540	Achieving
71	30 MLD STP, Rampur Road, Hapur	2022	Hapur, Ghaziabad	30	8	SBR	Nagar Palika Parishad	O	03.11.2025	Grab	7.44	12	112	40	1700	680	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)\Urban(U)\ Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
72	21.5 MLD STP Siddharthvihar, Ghaziabad	2024	Ghaziabad	21.5	4.5	SBR	Awas Vikas	O	07.11.2025	Grab	7.63	12	92	35	2200	790	Achieving
73	78 MLD STP Dhadhpura, Agra	2013	Agra	78	78	UASB	U.P. Jal Nigam	U	01.11.2025	Grab	7.84	24	100	44	3400	930	Achieving
74	2.25 MLD STP Budi ka Nagla, Agra	2000	Agra	2.25	2.25	WSP	U.P. Jal Nigam	U	01.11.2025	Grab	7.91	27	140	37	6300	810	Achieving
75	10 MLD STP Peelakhar, Agra	2000	Agra	10	10	WSP	U.P. Jal Nigam	U	01.11.2025	Grab	7.86	28	120	36	3800	910	Achieving
76	12 MLD STP Devri Road, (Bhimnagri), Agra	2011	Agra	12	8	UASB	U.P. Jal Nigam	U	01.11.2025	Grab	7.8	26	100	38	3400	930	Achieving
77	14 MLD STP Jaganpur, Sikandarpur, Agra	2011	Agra	14	14	UASB	U.P. Jal Nigam	U	01.11.2025	Grab	7.88	25	120	36	5800	910	Achieving
78	40 MLD STP Sadarban, Bichhpuri, Agra	2013	Agra	40	28	UASB	U.P. Jal Nigam	U	01.11.2025	Grab	7.9	27	140	40	3800	910	Achieving
79	36 MLD STP Sadarwan (Bichpuri) New	2018	Agra	36	36	SBR	Nagar Nigam	O	01.11.2025	Grab	7.48	28	160	63	4600	920	Achieving
80	24 MLD STP Dhadhpura (New), Agra	2014	Agra	24	15	UASB	U.P. Jal Nigam	U	01.11.2025	Grab	7.81	22	80	32	3100	680	Achieving
81	4.50 MLD STP Kalindi Vihar, Agra	2014	Agra	4.5	4.5	UASB	Nagar Nigam	O	01.11.2025	Not Operational Due to Maintainance Works							
82	03 MLD STP Pandav Nagar, Meerut	2013	Meerut	3	2.7	ASP	MDA	O	06.11.2025	Grab	7.48	22	168	78	930	810	Achieving
83	07 MLD STP Pallavpuram-1, Meerut	2012	Meerut	7	6.5	ASP	MDA	O	06.11.2025	Grab	7.47	15	88	46	920	780	Achieving
84	11 MLD STP Pallavpuram-2, Meerut	2008	Meerut	11	7	ASP	MDA	O	06.11.2025	Grab	7.44	16	96	52	820	680	Achieving
85	06 MLD STP Rakshapuram, Meerut	2011	Meerut	6	4.4	ASP	MDA	O	06.11.2025	Grab	7.56	18	132	62	930	780	Achieving
86	10 MLD STP Lohiya Nagar, Meerut	2010	Meerut	10	2	ASP	MDA	O	06.11.2025	Grab	7.41	10	24	20	830	680	Achieving
87	15 MLD STP Shatabdinagar, Meerut	2010	Meerut	15	4.8	ASP	MDA	O	06.11.2025	Grab	7.41	10	20	25	810	600	Achieving
88	15 MLD STP Vedvyasपुरi Meerut	2011	Meerut	15	4.5	ASP	MDA	O	06.11.2025	Grab	7.39	8	20	20	810	600	Achieving
89	06 MLD STP Shradhapuri-1, Meerut	2012	Meerut	6	5.5	ASP	MDA	O	06.11.2025	Grab	7.51	17	112	48	830	610	Achieving
90	06 MLD STP Sainik Vihar	2017	Meerut	6	5.9	UASB	MDA	O	06.11.2025	Grab	7.54	10	28	18	920	680	Achieving
91	5 MLD STP Modipuram Tiraha	2016	Meerut	5	4.5	ASP	MDA	O	06.11.2025	Grab	7.56	16	72	50	830	610	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)Urban(U) Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
92	07 MLD STP Sports Goods Complex, Meerut	2012	Meerut	7	4	ASP	MDA	O	06.11.2025	Grab	7.45	16	92	60	910	680	Achieving
93	72 MLD STP Garh road (Jagriti vihar) Kamalpur	2018	Meerut	72	72	ASP	U.P. Jal Nigam	U	06.11.2025	Grab	7.38	10	24	8	910	680	Achieving
94	10 MLD STP Ganga Nagar, Meerut	2011	Meerut	10	3.8	SBR	MDA	O	06.11.2025	Grab	7.44	9	20	8	780	550	Achieving
95	06 MLD STP Shradhapuri- Phase-2, Meerut	2012	Meerut	6	5.6	SBR	MDA	O	06.11.2025	Grab	7.48	20	156	64	920	810	Achieving
96	14 MLD STP Baghat, Meerut	2021	Baghat, Meerut	14	7.8	SBR	U.P. Jal Nigam	R	03.11.2025	Grab	7.52	20	180	82	920	680	Achieving
97	32.5 MLD STP (WSP) Nagar Palika Parishad, Kidwai nagar	2001	Muzaffar Nagar	32.5	32.5	WSP	U.P. Jal Nigam	U	04.11.2025	Grab	7.7	20	64	48	2100	700	Achieving
98	32.5 MLD STP Near A2Z Garbage plant KidwaiNagar	2025	Muzaffar Nagar	32.5	18	SBR	U.P. Jal Nigam	R	04.11.2025	Grab	7.5	6	24	16	1400	110	Achieving
99	10 MLD STP Budhana	2024	Muzaffar Nagar	10	7.32	SBR	U.P. Jal Nigam	R	04.11.2025	Grab	7.4	8	24	18	1700	140	Achieving
100	22 MLD STP Sahawali, Muzaffarnagar	2023	Muzaffar Nagar	22	21	SBR	U.P. Jal Nigam	R	04.11.2025	Grab	7.6	7	26	14	1100	130	Achieving
101	15 MLD STP Kairana, Shamli, Muzaffarnagar	2024	Muzaffar Nagar	15	15	SBR	U.P. Jal Nigam	U	04.11.2025	Grab	7.3	9	28	12	1300	170	Achieving
102	12 MLD STP Ayodhya	2014	Ayodhya	12	7	UASB	U.P. Jal Nigam	U	03.11.2025	Grab	7.3	25	124	70	4700	930	Achieving
103	6 MLD STP Ramghat, Ayodhya	2023	Ayodhya	6	4	SBR	U.P. Jal Nigam	U	03.11.2025	Grab	7.4	11	57	43	2200	700	Achieving
104	13.59 (6.8) MLD STP, Masani, Mathura	2007	Mathura	6.8	6.5	WSP	U.P. Jal Nigam	R	04.11.2025	Grab	7.9	24	232	84	3800	920	Achieving
105	04 MLD STP Vrindavan Near Pagal Baba Mandir, Mathura	2007	Mathura	4	4	WSP	U.P. Jal Nigam	R	04.11.2025	Grab	7.7	24	208	70	3100	910	Achieving
106	08 MLD STP Near 100 Bed Hospital Vrindavan, Manth road	2015	Mathura	8	8	UASB	U.P. Jal Nigam	U	04.11.2025	Grab	7.6	25	216	78	3200	920	Achieving
107	14.5 MLD STP Transyamuna, Jamunapar, Mathura	2007	Mathura	14.5	14.5	WSP	U.P. Jal Nigam	R	04.11.2025	Grab	8.3	50	384	160	17000	3300	Not Achieving
108	30 MLD STP Masani Mathura	2020	Mathura	30	30	SBR	U.P. Jal Nigam	R	04.11.2025	Grab	7.6	23	192	60	2500	910	Achieving
109	16 MLD STP Trans Yamuna, Laxmi Nagar, Mathura	2015	Mathura	16	16	UASB	U.P. Jal Nigam	R	04.11.2025	Grab	8.2	26	248	90	3400	930	Achieving
110	2.76 MLD STP Goverdhan STP	2011	Mathura	2.76	0	WSP	Nagar Palika Parishad	O	04.11.2025	Not Operational Due to Maintainance Works							

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)\Urban(U)\Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
111	33 MLD STP Sector-54, Noida	2011	Noida	33	13	SBR	Noida Authority	O	03.11.2025	Grab	7.35	12.7	94.4	23	1700	900	Achieving
112	25 MLD STP Sector-50, Noida	2015	Noida	25	0	SBR	Noida Authority	O	03.11.2025	Not Operational Due to Maintainance Works							
113	35 MLD STP Sector-123, Noida	2011	Noida	35	18	SBR	Noida Authority	O	03.11.2025	Grab	7.38	11.6	72	21	1700	680	Achieving
114	50 MLD STP Sector-168, Noida	2015	Noida	50	19	SBR	Noida Authority	O	03.11.2025	Grab	7.53	13.5	99.2	25	1700	780	Achieving
115	34 MLD STP Sector -50 Noida	2012	Noida	34	32	SBR	Noida Authority	O	03.11.2025	Grab	7.54	9.1	80	21	1400	680	Achieving
116	54 MLD STP Sector- 54, Noida	2012	Noida	54	42	SBR	Noida Authority	O	03.11.2025	Grab	7.47	8.3	64	18	1600	540	Achieving
117	100 MLD STP Sector-168, Noida	2023	Noida	100	62	SBR	Noida Authority	O	03.11.2025	Grab	7.65	14.2	89.6	26	1700	780	Achieving
118	80 MLD STP Sector-123, Noida	2023	Noida	80	65	SBR	Noida Authority	O	03.11.2025	Grab	7.49	12.1	89.6	20	2500	920	Achieving
119	2.0 MLD STP Greater Noida Authority STP, Vill- Badalpur	2015	Greater Noida	2	2	SBR	GNIDA	O	06.11.2025	Grab	7.6	9	42	15	2100	680	Achieving
120	15 MLD STP ECO tech - 2	2018	Greater Noida	15	8	SBR	GNIDA	O	06.11.2025	Grab	7.42	8	40	10	1600	540	Achieving
121	20 MLD STP ECO tech - 3	2018	Greater Noida	20	12	SBR	GNIDA	O	06.11.2025	Grab	7.6	14	68	20	2200	400	Achieving
122	137 MLD STP Kasana, GreaterNoida	2015	Greater Noida	137	90	SBR	GNIDA	O	06.11.2025	Grab	7.48	8	34	12	1600	350	Achieving
123	0.805 MLD STP Ahara Road, Zone-A, Anoopshahar	2003	Bulandshahr	0.805	0.8	WSP	U.P. Jal Nigam	U	03.11.2025	Grab	7.76	20	96	45	1300	450	Achieving
124	1.75 MLD STP Ahara Road, (Shivanand Ashram) Zone-B, Anoopshahar	2003	Bulandshahr	1.75	1.75	WSP	U.P. Jal Nigam	U	03.11.2025	Grab	7.68	24	88	49	1700	680	Achieving
125	2.25 MLD STP Narora Atomic power Station Narora Township	2000	Bulandshahr	2.25	2.25	ASP	Narora Atomic Power Station	O	03.11.2025	Grab	7.45	18	104	64	920	540	Achieving
126	01 MLD STP Zone-B Anoopshahar	2016	Bulandshahr	1	1	MBBR	Nagar Palika Parishad	O	03.11.2025	Grab	7.71	26	132	78	2200	780	Achieving
127	1.5 MLD STP Anoopshahar Zone A (NGRBA)	2016	Bulandshahr	1.5	0	UASB	Nagar Palika Parishad	O	03.11.2025	Grab	8.78	28	144	87	1600	920	Achieving
128	40 MLD STP Bulandshahar	2023	Bulandshahr	40	20	SBR	Nagar Palika Parishad	O	03.11.2025	Grab	7.58	20	108	51	2000	680	Achieving
129	04 MLD STP , Narora (NGRBA)	2015	Bulandshahr	4	4	UASB	Nagar Palika Parishad	O	03.11.2025	Grab	7.74	24	124	68	2100	930	Achieving
130	24 MLD STP, Bijnor	2018	Bijnor	24	23.5	UASB	Nagar Palika Parishad	O	07.11.2025	Grab	7.53	12	48	26	1300	130	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)Urban(U) Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
131	58 MLD STP Moradabad	2018	Moradabad	58	24	UASB	U.P. Jal Nigam	R	04.11.2025	Grab	7.49	6.2	72	7	920	68	Achieving
132	20 MLD STP Moradabad	2017	Moradabad	20	0	SBR	MDA	O	04.11.2025	Grab	7.72	14	80	26	1200	680	Achieving
133	14 MLD STP, Benzirpur	2016	Rampur	14	10	UASB	U.P. Jal Nigam	U	04.11.2025	Grab	7.76	24	78	32	2000	920	Achieving
134	5 MLD STP, Rampur	2016	Rampur	5	4	SBR	U.P. Jal Nigam	U	04.11.2025	Grab	7.51	6.4	84	8	920	61	Achieving
135	15 MLD STP Pehrigan	2015	Rampur	15	11	UASB	U.P. Jal Nigam	U	04.11.2025	Grab	7.46	20	76	35	1400	780	Achieving
136	15 MLD STP, Kasganj	2022	Kasganj, Aligarh	15	9.6	SBR	U.P. Jal Nigam	R	04.11.2025	Grab	7.42	18.2	116	78	1400	610	Achieving
137	24 MLD STP, Manpur, Etah	2023	Etah, Aligarh	24	16	SBR	Nagar Palika Parishad	O	04.11.2025	Grab	7.48	12	64	48	2000	680	Achieving
138	45 MLD STP Laxmi Nagar, Aligarh	2023	Aligarh	45	18	SBR	Nagar Nigam	O	06.11.2025	Grab	7.37	24.2	196	86	2600	920	Achieving
139	8.95 MLD STP Bela, Pratapgarh	2023	Pratapgarh	8.95	7	FAB	Nagar Palika Parishad	O	04.11.2025	Grab	8.05	22	54.4	34	1200	780	Achieving
140	5 MLD STP Palthipur, Sultanpur	2024	Sultanpur	5	4.4	SBR	U.P. Jal Nigam	R	03.11.2025	Grab	8.07	22	59.2	34	2400	930	Achieving
141	2 MLD STP Miranpur, Sadar, Sultanpur	2024	Sultanpur	2	1.4	SBR	U.P. Jal Nigam	R	03.11.2025	Grab	8.08	24	56	36	2400	930	Achieving
142	10 MLD STP Hathia Nala, Lolepur	2006	Sultanpur	10	6.5	Aerated Lagoon	U.P. Jal Nigam	R	03.11.2025	Grab	8.02	20	60.8	37	2400	920	Achieving
143	18 MLD STP Raebareli	2023	Raebareli	18	5	SBR	Nagar Palika Parishad	O	04.11.2025	Grab	8.01	8.5	47.68	7	780	200	Achieving
144	35 MLD STP, Saraitalfi	2023	Bareilly	35	0	ASP	Nagar Nigam	O	04.11.2025	Not Operational Due to Maintainance Works							
145	42 MLD STP, HaroonNagla, Bareilly	2024	Bareilly	42	42	SBR	U.P. Jal Nigam	R	04.11.2025	Grab	7.8	6	32	13	170	90	Achieving
146	20 MLD STP Barinagla, Bareilly	2024	Bareilly	20	18	SBR	U.P. Jal Nigam	R	04.11.2025	Grab	7.4	8	40	15	220	94	Achieving
147	01 MLD STP, Girdaripur, Bareilly	2024	Bareilly	1	1	SBR	U.P. Jal Nigam	R	04.11.2025	Grab	7.1	8	40	16	210	79	Achieving
148	40 MLD STP, Shahjahanpur	2025	Shahjahanpur	40	10	SBR	U.P. Jal Nigam	U	04.11.2025	Grab	7.2	6	32	6	170	68	Achieving
149	15 MLD STP Unnao	2024	Unnao	15	13	SBR	U.P. Jal Nigam	R	04.11.2025	Sampling has not been carried out by the Regional Office,UPPCB.							
150	21 MLD STP Mau Road, Ghazipur	2024	Ghazipur, Varanasi	21	12	SBR	U.P. Jal Nigam	R	01.11.2025	Grab	7.52	7.9	40	6.2	470	210	Achieving
151	33 MLD STP Ayodhya	2025	Ayodhya	33	0	SBR	UPJN (Rural)	R	03.11.2025	Under Trial Run							

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)\Urban(U)\ Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
152	15 MLD STP Baniyapur	2018	Kanpur Nagar	15	0	SBR	UPJN (Urban)	U	04.11.2025	Not operational Due to Maintenance Work							
153	5 MLD STP Yamuna Expressway Industrial Development Authority (YIDA)	2023	Jewar (Gt. Noida)	5	0	SBR	UPJN (Rural)	R	06.11.2025	Not operational Due to Maintenance Work							
154	20 MLD STP Ballia	2025	Ballia	20	0	SBR	UPJN (Urban)	U		Under Trial Run							
155	25 MLD STP Moradabad	2025	Moradabad	25	0	SBR	UPJN(Rural)	R	04.11.2025	Under Trial Run							
<p>Note :- The standards as per MoEF&CC Notification dated 13.10.2017, titled "Applicable Effluent Discharge Standards for STPs" are as follows: For State Capital: pH-6.5-9.0; BOD - <20 mg/l; TSS- <50 mg/l & FC- <1000 MPN/100 ml Other than State Capital: pH-6.5-9.0; BOD - <30 mg/l; TSS- <100 mg/l & FC- <1000 MPN/100 ml Note:- As per the data received from Regional offices, UPPCB</p>																	

**Performance of Existing STPs in U.P.
(Second Week)**

November- 2025

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)Urban(U)\ Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
1	10.445 MLD STP near Tixi Tempel (Karanpur)	2001	Etawah	10.445	8	WSP	UP Jal Nigam	R	12.11.2025	Grab	7.8	24	130	45	8400	830	Achieving
2	21 MLD STP Etawah	2022	Etawah	21	20	SBR	UP Jal Nigam	R	12.11.2025	Grab	8	9.2	60	8	7000	560	Achieving
3	13.5 MLD STP at Mauja Umrain	2013	Etawah	13.5	12	SBR	UP Jal Nigam	R	12.11.2025	Sampling has not been carried out by the Regional Office							
4	03 MLD STP Firozabad	2014	Firozabad	3	1.4	UASB	NPP	O	10.11.2025	Grab	8.2	26	150	45	11000	920	Achieving
5	67 MLD STP Mohammadpur, Biharipur	2020	Firozabad	67	50	ASP+ extended aeration	U.P. Jal Nigam	U	10.11.2025	Grab	8	9.6	60	8	7000	610	Achieving
6	1.65 MLD STP Saifai (Paramedicals)	2013	Etawah	1.65	0.8	SBR	Others	O	12.11.2025	Grab	8.2	15	110	27	8400	810	Achieving
7	23 MLD STP at Mauja Odenya, Padaria	2014	Mainpuri	23	17	UASB	U.P. Jal Nigam	U	10.11.2025	Grab	8.2	26	150	45	11000	920	Achieving
8	1.5 MLD STP Saifai Village, Etawah	2006	Etawah	1.5	1.1	Oxidation Pond	U.P. Jal Nigam	U	12.11.2025	Grab	7.9	27	160	48	8400	830	Achieving
9	26 MLD STP Jhansi Laxmi Taal	2021	Jhansi	26	22	SBR	U.P. Jal Nigam	U	14.11.2025	Grab	7.4	25.6	42.68	13	1400	680	Achieving
					4	SBR	U.P. Jal Nigam	U	14.11.2025	Grab	7.31	23.28	38.8	12	1500	610	Achieving
10	26 MLD STP Smart City, Lahargird	2025	Jhansi	26	25	SBR	Nagar Nigam	O	12.11.2025	Composite	7.33	26	194	10	2100	780	Achieving
11	3.42 MLD STP Near Divyang kendra	2000	Chitrakoot	3.42	0	Oxidation Pond	Nagar Palika Parishad	O	Based on the consensus of the Joint Committee chaired by the District Magistrate, Chitrakoot, during the meeting held on 03.10.2025, this unit has been formally omitted from the STP category. Sampling has not been carried out by the Regional Office,UPPCB.								
12	42 MLD STP, Sajari Kanpur	2016-17	Kanpur Nagar	42	22	ASP	U.P. Jal Nigam	R	11.11.2025	Grab	7.88	24	170	58	260	170	Achieving
13	210 MLD STP, Bingawan Kanpur	2015-16	Kanpur Nagar	210	110	UASB	U.P. Jal Nigam	R	11.11.2025	Grab	7.89	45	210	68	91000	68000	Not Achieving
14	130 MLD STP Jajmau, Kanpur	1998-99	Kanpur Nagar	130	115	ASP	U.P. Jal Nigam	R	11.11.2025	Grab	7.92	24	180	56	1700	400	Achieving
15	43 MLD STP Jajmau, Kanpur	2020	Kanpur Nagar	43	40	UASB	U.P. Jal Nigam	R	11.11.2025	Grab	7.98	21	160	46	1700	400	Achieving
16	13 MLD STP Jalalpur, Amrapur, Kannauj	2017	Kanpur Dehat	13	12	SBR	Nagar Palika Parishad	O	11.11.2025	Grab	7.3	21	100	52	330	270	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)Urban(U)Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
17	30 MLD STP Pankha, Kanpur	2023	Kanpur Nagar	30	29	SBR	U.P. Jal Nigam	R	11.11.2025	Grab	7.76	27	160	56	580	310	Achieving
18	36 (9+27) MLD STP Jajmau, Kanpur	1992 & 2024)	Kanpur Nagar	36	25	UASB	U.P. Jal Nigam	U	11.11.2025	Grab	8.09	42	170	64	82000	61000	Not Achieving
19	17.7 MLD STP Fatehgarh, Farrukhabad	2024	Kanpur Nagar	17.7	17	SBR	U.P. Jal Nigam	R	11.11.2025	Grab	8.08	19.5	180	52	840	630	Achieving
20	30 MLD STP Farrukhabad	2024	Kanpur Nagar	30	30	SBR	U.P. Jal Nigam	R	11.11.2025	Grab	8.14	22.5	230	56	920	680	Achieving
21	50 MLD STP Numayadahi	2013	Prayagraj	50	50	ASP +Bio Tower Technology	Ganga Pollution control unit, U.P. Jal Nigam	R	11.11.2025	Composite	7.84	25.6	78	65	2200	780	Achieving
22	10 MLD STP Ponghat	2013	Prayagraj	10	10	ASP +Bio Tower Technology	Ganga Pollution control unit, U.P. Jal Nigam	R	11.11.2025	Composite	7.93	23.2	56	48	1700	680	Achieving
23	25 MLD STP Kodra	2013	Prayagraj	25	25	ASP +Bio Tower Technology	Ganga Pollution control unit, U.P. Jal Nigam	R	11.11.2025	Composite	7.68	23.5	60	54	2000	680	Achieving
24	60 MLD STP Rajapur	2013	Prayagraj	60	60	UASB	Ganga Pollution control unit, U.P. Jal Nigam	R	11.11.2025	Composite	7.61	28.6	84	78	2600	930	Achieving
25	29 MLD STP Salori-1	2007	Prayagraj	29	28	FAB	Ganga Pollution control unit, U.P. Jal Nigam	R	11.11.2025	Composite	7.7	27.4	80	70	2700	930	Achieving
26	14 MLD STP Salori-2 Expansion	2016	Prayagraj	14	14	SBR	Ganga Pollution control unit, U.P. Jal Nigam	U	11.11.2025	Composite	7.58	20.4	40	38	1400	680	Achieving
27	80 MLD STP Naini	2013	Prayagraj	80	80	ASP	Ganga Pollution control unit, U.P. Jal Nigam	R	10.11.2025	Composite	7.64	26.8	72	68	2100	920	Achieving
28	42 MLD STP, Naini	2023	Prayagraj	42	36	FCR	U.P. Jal Nigam	R	10.11.2025	Composite	7.67	23	60	58	2300	780	Achieving
29	14 MLD STP Phaphamau	2023	Prayagraj	14	14	FCR	U.P. Jal Nigam	R	11.11.2025	Composite	7.99	23.2	68	52	1700	700	Achieving
30	16 MLD STP Jhansi	2023	Prayagraj	16	15	FCR	U.P. Jal Nigam	R	10.11.2025	Composite	7.9	24.9	72	60	2000	610	Achieving
31	10 MLD STP Ramnagar	2021	Varanasi	10	9	Anaerobic Anoxic Oxid (A2O)	U.P. Jal Nigam	R	12.11.2025	Grab	7.42	18.2	88	28	430	220	Achieving
32	80 MLD STP Dinapur	1994	Varanasi	80	68	ASP	U.P. Jal Nigam	U	12.11.2025	Grab	7.57	24.2	142	78	350	130	Achieving
33	9.8 MLD STP Bhagwanpur	1989	Varanasi	9.8	8	ASP	U.P. Jal Nigam	R	12.11.2025	Grab	7.48	24.2	132	72	310	170	Achieving
34	140 MLD STP Dinapur	2018	Varanasi	140	99	ASP	U.P. Jal Nigam	U	12.11.2025	Grab	7.67	12.4	42	14	350	140	Achieving
35	120 MLD STP Gothaha	2019	Varanasi	120	40	UASB	U.P. Jal Nigam	U	12.11.2025	Grab	7.61	14.4	52	18	350	130	Achieving
36	12 MLD BLW STP	1989	Varanasi	12	12	ASP	BLW	O	12.11.2025	Grab	7.58	26.7	156	76	470	210	Achieving
37	50 MLD STP Ramana	2021	Varanasi	50	50	SBR	U.P. Jal Nigam	R	12.11.2025	Grab	7.42	28.2	104	42	390	220	Achieving
38	30 MLD STP Pachhahatiya Jaunpur	2023	Jaunpur, Varanasi	30	30	A2O	U.P. Jal Nigam	R	11.11.2025	Grab	7.57	7.2	42	6.2	320	220	Achieving
39	07 MLD Vindyachal Mirzapur	2022	Mirzapur	7	5	WSP	Nagar Palika Parisad	O	11.11.2025	Grab	7.51	16.2	72	46	470	260	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)Urban(U)Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
40	14 MLD STP Pakka Pokhra	1994	Mirzapur	14	13	UASB	U.P. Jal Nigam	R	11.11.2025	Grab	7.52	31.8	174	82	2300	1300	Not Achieving
41	8.5 MLD STP Pakka Pokhra, Mirzapur	2024	Mirzapur	8.5	4.25	SBR	U.P. Jal Nigam	R	11.11.2025	Grab	7.51	15.3	62	32	840	430	Achieving
42	8.5 MLD STP Bisunderpur, Mirzapur	2024	Mirzapur	8.5	4.6	SBR	U.P. Jal Nigam	R	11.11.2025	Grab	7.48	16.6	64	36	920	480	Achieving
43	15 MLD S.T.P. Jharkhandi, Maherwa ki Bari	2015	Gorakhpur	15	11.89	SBR	U.P. Jal Nigam	U	11.11.2025	Grab	7.52	8	34	28	2400	910	Achieving
44	5 MLD S.T.P. Jharkhandi, Maherwa ki Bari	2023	Gorakhpur	5	4	SBR	U.P. Jal Nigam	U	11.11.2025	Grab	7.52	8	34	28	2400	910	Achieving
45	30 MLD S.T.P. Opp. Manyavar Kanshiram Shahri Garib Awas Yojna, Deoria bypass Road	2015	Gorakhpur	30	20	SBR	U.P. Jal Nigam	U	11.11.2025	Grab	7.64	9.5	38	26	2100	820	Achieving
46	10 MLD STP Gorakhpur	2024	Gorakhpur	10	10	SBR	U.P. Jal Nigam	U	11.11.2025	Grab	7.61	7.5	40	22	2000	930	Achieving
47	8 MLD STP Azamgarh	2024	Azamgarh	8	5	SBR	Nagar Palika Parishad	O	14.11.2025	Grab	7.54	9.4	38.5	15.2	430	230	Achieving
48	38 MLD STP, Mahilpur Road	1998	Saharanpur	38	38	UASB	U.P. Jal Nigam	U	11.11.2025	Grab	7.4	26	188	45	720	660	Achieving
49	6.5 MLD STP Awasthi vikas Parishad STP	2018	Lucknow	6.5	0	SBR	Jal Kal Vibhag	O	11.11.2025	Not Operational Due to Maintainance Works							
50	37.5 MLD STP Awasthi vikas Parishad STP	2017	Lucknow	37.5	37.5	SBR	U.P. Awasthi vikas Parishad	O	10.11.2025	Grab	7.6	12	66	40	2600	680	Achieving
51	345 MLD STP, Bharwara	2011	Lucknow	345	345	UASB	U.P. Jal Nigam	U	10.11.2025	Grab	7.46	16	126	47	3300	930	Achieving
52	56 (42+14) MLD STP, Daulatganj	2003 & 2009	Lucknow	56	56	FAB	U.P. Jal Nigam	U	10.11.2025	Grab	7.47	17	108	44	4000	780	Achieving
53	1.5 MLD STP Hathi Park, (Smart City)	2021	Lucknow	1.5	0	MBBR	Nagar Nigam (Smart City)	O	10.11.2025	Not Operational Due to Maintainance Works							
54	39 MLD STP, Sajjadbagh, Daulatganj	2024	Lucknow	39	39	SBR	U.P. Jal Nigam	R	10.11.2025	Grab	7.52	13	74	42	5400	700	Achieving
55	120 MLD STP near 1090 Chauraha	2025	Lucknow	120	80	SBR	U.P. Jal Nigam	U	10.11.2025	Grab	7.64	16	84	44	2100	610	Achieving
56	19 MLD STP C.G. City, Lucknow	2023	Lucknow	19	0	SBR	LDA	O	10.11.2025	Not Operational Due to Maintainance Works							
57	56 MLD STP Trans Hindon (Indirapuram), Ghaziabad	2000	Ghaziabad	56	56	UASB	U.P. Jal Nigam	U	13.11.2025	Grab	7.52	16	66	35	2200	790	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)\Urban(U)\Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
58	30 MLD STP, Sadullabad (Loni), Ghaziabad	2012	Ghaziabad	30	20	MBBR	U.P. Jal Nigam	U	11.11.2025	Grab	7.65	9	68	10	1600	350	Achieving
59	74 MLD STP S.B.R., Indrapuram, Ghaziabad	2013	Ghaziabad	74	74	SBR	U.P. Jal Nigam	U	13.11.2025	Grab	7.49	9	62	10	2700	680	Achieving
60	56 MLD STP S.B.R., Bapudham, Ghaziabad	2014	Ghaziabad	56	1.5	SBR	GDA	O	13.11.2025	Grab	7.4	8	26	9	1600	350	Achieving
61	6 MLD STP Garh Zone, Garhmukteswar Hapur	2011	Hapur / Garhmukteswar	6	4.62	UASB followed by extended aeration	U.P. Jal Nigam (NGRBA)	R	10.11.2025	Grab	7.58	8	30	9	1600	540	Achieving
62	3 MLD STP Brijghat Zone, Garhmukteswar Hapur	2011	Hapur / Garhmukteswar	3	2.5	UASB followed by extended aeration	U.P. Jal Nigam (NGRBA)	R	10.11.2025	Grab	7.64	7	26	9	1600	350	Achieving
63	56 MLD STP, Indrapuram, (GDA), Ghaziabad	2012	Ghaziabad	56	20	SBR	Nagar Nigam	O	13.11.2025	Grab	7.55	8	40	9	1600	350	Achieving
64	56 MLD STP S.B.R., Dudahaida Vijay Nagar, Ghaziabad	2013	Ghaziabad	56	56	SBR	U.P. Jal Nigam	U	13.11.2025	Grab	7.53	9	48	10	1600	540	Achieving
65	70 MLD STP U.A.S.B.R. Dudahaida Vijay Nagar, Ghaziabad	2000	Ghaziabad	70	70	UASB	U.P. Jal Nigam	U	13.11.2025	Grab	7.54	24	84	47	2200	450	Achieving
66	3 MLD STP Pilkhaun	2015	Ghaziabad	3	2.5	UASB	U.P. Jal Nigam	U	10.11.2025	Grab	7.57	20	74	50	2000	610	Achieving
67	5 MLD STP Trans Delhi Signature City (Tronica City), Loni	2019	Ghaziabad	5	5	MBBR	UPSIDA	O	11.11.2025	Grab	7.49	10	74	30	1600	540	Achieving
68	56 MLD STP S.B.R. Govindpuram, Ghaziabad	2014	Ghaziabad	56	14	SBR	GDA	O	13.11.2025	Grab	7.64	7	32	8	1700	400	Achieving
69	20 MLD STP Modinagar	2023	Modinagar, Ghaziabad	20	7.8	SBR	Nagar Palika Parishad	O	11.11.2025	Grab	7.58	14	52	25	1600	540	Achieving
70	56 MLD STP S.B.R., Mority, Ghaziabad	2018	Ghaziabad	56	27	SBR	Nagar Nigam Ghaziabad	O	13.11.2025	Grab	7.5	10	74	15	1600	920	Achieving
71	30 MLD STP, Rampur Road, Hapur	2022	Hapur, Ghaziabad	30	8	SBR	Nagar Palika Parishad	O	10.11.2025	Grab	7.62	18	128	47	2100	400	Achieving
72	21.5 MLD STP Siddharthvihar, Ghaziabad	2024	Ghaziabad	21.5	4.5	SBR	Awass Vikas	O	13.11.2025	Grab	7.66	10	88	32	1600	350	Achieving
73	78 MLD STP Dhadhpura, Agra	2013	Agra	78	78	UASB	U.P. Jal Nigam	U	07.11.2025	Grab	7.86	25	100	48	3400	930	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)\Urban(U)\Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
74	2.25 MLD STP Budi ka Nagla, Agra	2000	Agra	2.25	2.25	WSP	U.P. Jal Nigam	U	07.11.2025	Grab	7.9	28	100	42	4600	920	Achieving
75	10 MLD STP Peelakhar, Agra	2000	Agra	10	10	WSP	U.P. Jal Nigam	U	07.11.2025	Grab	7.89	27	120	46	6300	810	Achieving
76	12 MLD STP Devri Road, (Bhimnagri), Agra	2011	Agra	12	8	UASB	U.P. Jal Nigam	U	07.11.2025	Grab	7.91	27	140	40	4800	680	Achieving
77	14 MLD STP Jaganpur, Sikandarpur, Agra	2011	Agra	14	14	UASB	U.P. Jal Nigam	U	07.11.2025	Grab	7.87	25	120	45	3400	930	Achieving
78	40 MLD STP Sadarban, Bichhpuri, Agra	2013	Agra	40	28	UASB	U.P. Jal Nigam	U	04.11.2025	Grab	7.44	26	110	43	3400	930	Achieving
79	36 MLD STP Sadarwan (Bichpuri) New	2018	Agra	36	36	SBR	ADA	O	04.11.2025	Grab	7.48	29	140	58	3800	910	Achieving
80	24 MLD STP Dhadhupura (New), Agra	2014	Agra	24	15	UASB	U.P. Jal Nigam	U	07.11.2025	Grab	7.89	23	100	38	3100	680	Achieving
81	4.50 MLD STP Kalindi Vihar, Agra	2014	Agra	4.5	4.5	UASB	Nagar Nigam Agra	O	07.11.2025	Grab	7.56	28	140	65	6300	810	Achieving
82	03 MLD STP Pandav Nagar, Meerut	2013	Meerut	3	2.7	ASP	MDA	O	12.11.2025	Grab	7.51	20	148	84	930	820	Achieving
83	07 MLD STP Pallavpuram-1, Meerut	2012	Meerut	7	6.5	ASP	MDA	O	12.11.2025	Grab	7.37	17	116	57	810	560	Achieving
84	11 MLD STP Pallavpuram-2, Meerut	2008	Meerut	11	7	ASP	MDA	O	12.11.2025	Grab	7.45	18	136	62	920	780	Achieving
85	06 MLD STP Rakshapuram, Meerut	2011	Meerut	6	4.4	ASP	MDA	O	12.11.2025	Grab	7.47	16	112	68	830	680	Achieving
86	10 MLD STP Lohiya Nagar, Meerut	2010	Meerut	10	2	ASP	MDA	O	12.11.2025	Grab	7.46	10	28	24	810	600	Achieving
87	15 MLD STP Shatabdinagar, Meerut	2010	Meerut	15	4.8	ASP	MDA	O	12.11.2025	Grab	7.36	8	24	22	780	550	Achieving
88	15 MLD STP Vedvyaspuri Meerut	2011	Meerut	15	4.5	ASP	MDA	O	12.11.2025	Grab	7.38	12	68	24	810	610	Achieving
89	06 MLD STP Shradhapuri-1, Meerut	2012	Meerut	6	5.5	ASP	MDA	O	12.11.2025	Grab	7.52	18	128	60	920	680	Achieving
90	06 MLD STP Sainik Vihar	2017	Meerut	6	5.9	UASB	MDA	O	12.11.2025	Grab	7.43	14	48	26	820	600	Achieving
91	5 MLD STP Modipuram Tiraha	2016	Meerut	5	4.5	ASP	MDA	O	12.11.2025	Grab	7.38	15	88	44	780	610	Achieving
92	07 MLD STP Sports Goods Complex, Meerut	2012	Meerut	7	4	ASP	MDA	O	12.11.2025	Grab	7.41	16	100	52	810	600	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)\Urban(U)\Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
93	72 MLD STP Garh road (Jagriti vihar) Kamalpur	2018	Meerut	72	72	ASP	U.P. Jal Nigam	U	12.11.2025	Grab	7.41	10	30	10	920	780	Achieving
94	10 MLD STP Ganga Nagar, Meerut	2011	Meerut	10	3.8	SBR	MDA	O	12.11.2025	Grab	7.39	10	24	10	830	610	Achieving
95	06 MLD STP Shradhapuri-Phase-2, Meerut	2012	Meerut	6	5.6	SBR	MDA	O	12.11.2025	Grab	7.44	14	96	70	820	600	Achieving
96	14 MLD STP Baghpat, Meerut	2021	Baghpat, Meerut	14	7.8	SBR	U.P. Jal Nigam	R	10.11.2025	Grab	7.59	17	128	74	810	560	Achieving
97	32.5 MLD STP (WSP) Nagar Palika Parishad, Kidwai nagar	2001	Muzaffar Nagar	32.5	32.5	WSP	U.P. Jal Nigam	U	11.11.2025	Grab	7.5	24	88	40	1700	680	Achieving
98	32.5 MLD STP Near A2Z Garbage plant KidwaiNagar	2025	Muzaffar Nagar	32.5	18	SBR	U.P. Jal Nigam	R	11.11.2025	Grab	7.6	9	28	18	1100	140	Achieving
99	10 MLD STP Budhana	2024	Muzaffar Nagar	10	7.32	SBR	U.P. Jal Nigam	R	11.11.2025	Grab	7.4	8	28	18	1300	110	Achieving
100	22 MLD STP Sahawali, Muzaffarnagar	2023	Muzaffar Nagar	22	21	SBR	U.P. Jal Nigam	R	11.11.2025	Grab	7.2	7	24	16	1300	170	Achieving
101	15 MLD STP Kairana, Shamli, Muzaffarnagar	2024	Muzaffar Nagar	15	15	SBR	U.P. Jal Nigam	U	11.11.2025	Grab	7.7	9	26	14	1400	210	Achieving
102	12 MLD STP Ayodhya	2014	Ayodhya	12	7	UASB	U.P. Jal Nigam	U	13.11.02025	Grab	7.41	18	102	64	3300	780	Achieving
103	6 MLD STP Ramghat, Ayodhya	2023	Ayodhya	6	4	SBR	U.P. Jal Nigam	U	13.11.02025	Grab	7.43	14	68	55	4000	610	Achieving
104	13.59 (6.8) MLD STP, Masani, Mathura	2007	Mathura	6.8	6.5	WSP	U.P. Jal Nigam	R	11.11.2025	Composite	7.7	23	216	72	-	-	Achieving
105	04 MLD STP Vrindavan Near Pagal Baba Mandir, Mathura	2007	Mathura	4	4	WSP	U.P. Jal Nigam	R	11.11.2025	Composite	7.8	25	232	82	-	-	Achieving
106	08 MLD STP Near 100 Bed Hospital Vrindavan, Manth road	2015	Mathura	8	8	UASB	U.P. Jal Nigam	U	11.11.2025	Composite	7.5	22	192	70	-	-	Achieving
107	14.5 MLD STP Trans-yamuna, Jamunapar, Mathura	2007	Mathura	14.5	14.5	WSP	U.P. Jal Nigam	R	11.11.2025	Composite	8.1	42	352	154	-	-	Not Achieving
108	30 MLD STP Masani Mathura	2020	Mathura	30	30	SBR	U.P. Jal Nigam	R	11.11.2025	Composite	7.5	21	184	48	-	-	Achieving
109	16 MLD STP Trans Yamuna, Laxmi Nagar, Mathura	2015	Mathura	16	16	UASB	U.P. Jal Nigam	R	11.11.2025	Composite	7.9	24	240	84	-	-	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)\Urban(U)\Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
110	2.76 MLD STP Goverdhan STP	2011	Mathura	2.76	0	WSP	Nagar Palika Parishad	O	11.11.2025	Not Operational Due to Maintainnace Works							
111	33 MLD STP Sector-54, Noida	2011	Noida	33	13	SBR	Noida Authority	O	10.11.2025	Grab	7.51	11.09	89.6	24	2200	400	Achieving
112	25 MLD STP Sector-50, Noida	2015	Noida	25	0	SBR	Noida Authority	O	10.11.2025	Not Operational Due to Maintainnace Works							
113	35 MLD STP Sector-123, Noida	2011	Noida	35	18	SBR	Noida Authority	O	10.11.2025	Grab	7.66	12.9	102.4	25	2700	610	Achieving
114	50 MLD STP Sector-168, Noida	2015	Noida	50	19	SBR	Noida Authority	O	10.11.2025	Grab	7.61	13.5	109.6	19	1200	830	Achieving
115	34 MLD STP Sector -50 Noida	2012	Noida	34	32	SBR	Noida Authority	O	10.11.2025	Grab	7.39	21.1	95.2	27	1700	450	Achieving
116	54 MLD STP Sector- 54, Noida	2012	Noida	54	42	SBR	Noida Authority	O	10.11.2025	Grab	7.44	10.7	82.4	21	1600	350	Achieving
117	100 MLD STP Sector- 168, Noida	2023	Noida	100	62	SBR	Noida Authority	O	10.11.2025	Grab	7.67	11.2	64	17	2200	790	Achieving
118	80 MLD STP Sector- 123, Noida	2023	Noida	80	65	SBR	Noida Authority	O	10.11.2025	Grab	7.38	10.7	64.8	19	1600	540	Achieving
119	2.0 MLD STP Greater Noida Authority STP, Vill- Badalpur	2015	Greater Noida	2	2	SBR	GNIDA	O	15.11.2025	Grab	7.56	10	38	19	1700	680	Achieving
120	15 MLD STP ECO tech -2	2018	Greater Noida	15	8	SBR	GNIDA	O	15.11.2025	Grab	7.64	9	36	15	1600	280	Achieving
121	20 MLD STP ECO tech -3	2018	Greater Noida	20	12	SBR	GNIDA	O	15.11.2025	Grab	7.55	12	42	20	2200	400	Achieving
122	137 MLD STP Kasana, GreaterNoida	2015	Greater Noida	137	90	SBR	GNIDA	O	15.11.2025	Grab	7.47	8	28	10	1600	220	Achieving
123	0.805 MLD STP Ahara Road, Zone-A, Anoopshahar	2003	Bulandshahar	0.805	0.8	WSP	U.P. Jal Nigam	U	10.11.2025	Grab	7.78	24	92	41	1200	610	Achieving
124	1.75 MLD STP Ahara Road, (Shivanand Ashram) Zone-B, Anoopshahar	2003	Bulandshahar	1.75	1.75	WSP	U.P. Jal Nigam	U	10.11.2025	Grab	7.72	22	84	43	1500	840	Achieving
125	2.25 MLD STP Narora Atomic power Station Narora Township	2000	Bulandshahar	2.25	2.25	ASP	Narora Atomic power Station	O	10.11.2025	Grab	7.53	16	112	73	540	240	Achieving
126	01 MLD STP Zone-B Anoopshahar	2016	Bulandshahar	1	1	MBBR	Nagar Palika Parishad	O	10.11.2025	Grab	7.68	24	124	89	2000	680	Achieving
127	1.5 MLD STP Anoopshahar Zone A (NGRBA)	2016	Bulandshahar	1.5	0	UASB	Nagar Palika Parishad	O	10.11.2025	Not Operational Due to Maintainnace Works							
128	40 MLD STP Bulandshahar	2023	Bulandshahar	40	20	SBR	Nagar Palika Parishad	O	10.11.2025	Grab	7.61	18	108	64	2200	680	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)\Urban(U)\Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
129	04 MLD STP , Narora (NGRBA)	2015	Bulandshahar	4	4	UASB	Nagar Palika Parishad	O	10.11.2025	Grab	7.71	22	104	71	1600	920	Achieving
130	24 MLD STP, Bijnor	2018	Bijnor	24	23.5	UASB	Nagar Palika Parishad	O	14.11.2025	Grab	7.64	8	32	21	1100	120	Achieving
131	58 MLD STP Moradabad	2018	Moradabad	58	24	UASB	U.P. Jal Nigam	R	11.11.2025	Grab	7.51	6.8	64	6	930	68	Achieving
132	20 MLD STP Moradabad	2017	Moradabad	20	0	SBR	MDA	O	11.11.2025	Not Operational Due to Maintainance Works							
133	14 MLD STP, Benzipur	2016	Rampur	14	10	UASB	U.P. Jal Nigam	U	11.11.2025	Grab	7.79	26	80	36	2100	930	Achieving
134	5 MLD STP , Rampur	2016	Rampur	5	4	SBR	U.P. Jal Nigam	U	11.11.2025	Grab	7.62	6.6	72	7	610	61	Achieving
135	15 MLD STP Pehrigan	2015	Rampur	15	11	UASB	U.P. Jal Nigam	U	11.11.2025	Grab	7.72	24	78	32	1400	680	Achieving
136	15 MLD STP, Kasganj	2022	Kasganj, Aligarh	15	9.6	SBR	U.P. Jal Nigam	R	11.11.2025	Grab	6.97	25.4	142.8	71	1600	920	Achieving
137	24 MLD STP, Manpur, Etah	2023	Etah, Aligarh	24	16	SBR	Nagar Palika Parishad	O	11.11.2025	Grab	7.53	12.8	46	42	2100	780	Achieving
138	45 MLD STP Laxmi Nagar, Aligarh	2023	Aligarh	45	18	SBR	Nagar Nigam	O	11.11.2025	Grab	7.28	24	106	58	2600	920	Achieving
139	8.95 MLD STP Bela, Pratapgarh	2023	Pratapgarh	8.95	7	FAB	Nagar Palika Parishad	O	12.11.2025	Grab	8.11	23	51.2	32	1100	680	Achieving
140	5 MLD STP Palhipur, Sultanpur	2024	Sultanpur	5	4.4	SBR	U.P. Jal Nigam	R	13.11.2025	Grab	8.1	21	56	37	2700	930	Achieving
141	2 MLD STP Miranpur, Sadar, Sultanpur	2024	Sultanpur	2	1.4	SBR	U.P. Jal Nigam	R	13.11.2025	Grab	8.14	23	52.8	39	2100	920	Achieving
142	10 MLD STP Hathia Nala, Lolepur	2006	Sultanpur	10	6.5	Aerated Lagoon	U.P. Jal Nigam	R	13.11.2025	Grab	8.07	22	59.2	39	2300	920	Achieving
143	18 MLD STP Raebareli	2023	Raebareli	18	5	SBR	Nagar Palika Parishad	O	10.11.2025	Grab	8.05	8	48	7.5	790	210	Achieving
144	35 MLD STP, Saraitalfi	2023	Bareilly	35	0	ASP	Nagar Nigam	O	11.11.2025	Not Operational Due to Maintainance Works							
145	42 MLD STP, HarooNagla, Bareilly	2024	Bareilly	42	42	SBR	U.P. Jal Nigam	R	11.11.2025	Composite	7.5	8	36	15	210	94	Achieving
146	20 MLD STP Barinagla, Bareilly	2024	Bareilly	20	18	SBR	U.P. Jal Nigam	R	11.11.2025	Composite	7.8	6	44	17	170	79	Achieving
147	01 MLD STP, Girdaripur,	2024	Bareilly	1	1	SBR	U.P. Jal Nigam	R	11.11.2025	Composite	7.6	8	36	17	220	90	Achieving
148	40 MLD STP, Shahjahanpur	2025	Shahjahanpur	40	10	SBR	U.P. Jal Nigam	U	11.11.2025	Grab	7.6	8	40	9	220	90	Achieving
149	15 MLD STP Unnao	2024	Unnao	15	13	SBR	U.P. Jal Nigam	R	11.11.2025	Grab	8.46	16.8	164	62.2	4100	930	Achieving
150	21 MLD STP Mau Road, Ghazipur	2024	Ghazipur, Varanasi	21	12	SBR	U.P. Jal Nigam	R	04.11.2025	Grab	7.59	7.1	38	6.8	330	170	Achieving
151	33 MLD STP Ayodhya	2025	Ayodhya	33	0	SBR	UPJN (Rural)	R	13.11.2025	Under Trial Run							

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)\Urban(U)\Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
152	15 MLD STP Baniyapur	2018	Kanpur Nagar	15	0	SBR	UPJN (Urban)	U	11.11.2025	Not operational Due to Maintenance Work							
153	5 MLD STP Yamuna Expressway Industrial Development Authority (YIDA)	2023	Jewar (Gt. Noida)	5	0	SBR	UPJN (Rural)	R	15.11.2025	Not operational Due to Maintenance Work							
154	20 MLD STP Ballia	2025	Ballia	20	0	SBR	UPJN (Urban)	U	14.11.2025	Under Trial Run							
155	25 MLD STP Moradabad	2025	Moradabad	25	0	SBR	UPJN(Rural)	R	11.11.2025	Under Trial Run							
<p>Note :- The standards as per MoEF&CC Notification dated 13.10.2017, titled "Applicable Effluent Discharge Standards for STPs" are as follows: For State Capital: pH-6.5-9.0; BOD - <20 mg/l; TSS- <50 mg/l & FC- <1000 MPN/100 ml Other than State Capital: pH-6.5-9.0; BOD - <30 mg/l; TSS- <100 mg/l & FC- <1000 MPN/100 ml Note:- As per the data received from Regional offices, UPPCB</p>																	

**Performance of Existing STPs in U.P.
(Third Week)**

November- 2025

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)Urban(U) Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
1	10.445 MLD STP near Tixi Tempel (Karanpur)	2001	Etawah	10.445	8	WSP	UP Jal Nigam	R	20.11.2025	Grab	8.1	23	110	40	7900	810	Achieving
2	21 MLD STP Etawah	2022	Etawah	21	20	SBR	UP Jal Nigam	R	20.11.2025	Grab	8.2	7.6	40	6	7000	600	Achieving
3	13.5 MLD STP at Mauja Umrain	2013	Etawah	13.5	12	SBR	UP Jal Nigam	R	20.11.2025	Grab	7.9	22	120	41	9400	820	Achieving
4	03 MLD STP Firozabad	2014	Firozabad	3	1.4	UASB	NPP	O	18.11.2025	Grab	8	28	130	48	9400	910	Achieving
5	67 MLD STP Mohammadpur, Biharipur	2020	Firozabad	67	50	ASP+ extended aeration	U.P. Jal Nigam	U	18.11.2025	Grab	8.1	9.2	60	8	7000	610	Achieving
6	1.65 MLD STP Saifai (Paramedicals)	2013	Etawah	1.65	0.8	SBR	Others	O	20.11.2025	Grab	8.1	18	90	31	7900	810	Achieving
7	23 MLD STP at Mauja Odenya, Padaria	2014	Mainpuri	23	17	UASB	U.P. Jal Nigam	U	17.11.2025	Grab	8	23	130	42	8400	820	Achieving
8	1.5 MLD STP Saifai Village, Etawah	2006	Etawah	1.5	1.1	Oxidation Pond	U.P. Jal Nigam	U	20.11.2025	Grab	7.8	24	140	46	11000	930	Achieving
9	26 MLD STP Jhansi Laxmi Taal	2021	Jhansi	26	22	SBR	U.P. Jal Nigam	U		Sampling has not been carried out by the Regional Office,UPPCB							
					4	SBR	U.P. Jal Nigam	U		Sampling has not been carried out by the Regional Office,UPPCB							
10	26 MLD STP Smart City, Lahargird	2025	Jhansi	26	25	SBR	Nagar Nigam	O	18.11.2025	Grab	7.42	16.29	27.16	9	3500	730	Achieving
11	3.42 MLD STP Near Divyang kendra	2000	Chitrakoot	3.42	0	Oxidation Pond	Nagar Palika Parishad	O	Based on the consensus of the Joint Committee chaired by the District Magistrate, Chitrakoot, during the meeting held on 03.10.2025, this unit has been formally omitted from the STP category. Sampling has not been carried out by the Regional Office,UPPCB.								
12	42 MLD STP, Sajari Kanpur	2016-17	Kanpur Nagar	42	22	ASP	U.P. Jal Nigam	R	18.11.2025	Grab	7.89	18	140	52	240	140	Achieving
13	210 MLD STP, Bingawan Kanpur	2015-16	Kanpur Nagar	210	110	UASB	U.P. Jal Nigam	R	18.11.2025	Grab	7.63	37.5	200	74	84000	63000	Not Achieving
14	130 MLD STP Jajmau, Kanpur	1998-99	Kanpur Nagar	130	115	ASP	U.P. Jal Nigam	R	18.11.2025	Grab	7.96	27	160	58	1100	780	Achieving
15	43 MLD STP Jajmau, Kanpur	2020	Kanpur Nagar	43	40	UASB	U.P. Jal Nigam	R	18.11.2025	Grab	7.88	22.5	140	52	1100	780	Achieving
16	13 MLD STP Jalalpur, Amrapur, Kannauj	2017	Kanpur Dehat	13	12	SBR	Nagar Palika Parishad	O	18.11.2025	Grab	7.3	19.5	110	54	310	230	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)/Urban(U)/Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
17	30 MLD STP Pankha, Kanpur	2023	Kanpur Nagar	30	29	SBR	U.P. Jal Nigam	R	18.11.2025	Grab	7.58	25.5	150	48	490	330	Achieving
18	36 (9+27) MLD STP Jajmau, Kanpur	1992 & 2024)	Kanpur Nagar	36	25	UASB	U.P. Jal Nigam	U	18.11.2025	Grab	8.1	39	180	60	68000	45000	Not Achieving
19	17.7 MLD STP Fatehgarh, Farrukhabad	2024	Kanpur Nagar	17.7	17	SBR	U.P. Jal Nigam	R	18.11.2025	Grab	8.09	24	160	54	820	610	Achieving
20	30 MLD STP Farrukhabad	2024	Kanpur Nagar	30	30	SBR	U.P. Jal Nigam	R	18.11.2025	Grab	8.16	18	190	50	840	630	Achieving
21	50 MLD STP Numayadahi	2013	Prayagraj	50	50	ASP+Bio Tower Technology	Ganga Pollution control unit, U.P. Jal Nigam	R	18.11.2025	Grab	7.73	25.2	76	60	2600	780	Achieving
22	10 MLD STP Ponghat	2013	Prayagraj	10	10	ASP+Bio Tower Technology	Ganga Pollution control unit, U.P. Jal Nigam	R	18.11.2025	Grab	7.78	22.6	52	44	1700	610	Achieving
23	25 MLD STP Kodra	2013	Prayagraj	25	25	ASP+Bio Tower Technology	Ganga Pollution control unit, U.P. Jal Nigam	R	18.11.2025	Grab	7.61	23	64	54	2100	680	Achieving
24	60 MLD STP Rajapur	2013	Prayagraj	60	60	UASB	Ganga Pollution control unit, U.P. Jal Nigam	R	19.11.2025	Grab	7.72	28.2	88	72	2700	930	Achieving
25	29 MLD STP Salori-1	2007	Prayagraj	29	28	FAB	Ganga Pollution control unit, U.P. Jal Nigam	R	19.11.2025	Grab	7.68	27	84	66	2600	920	Achieving
26	14 MLD STP Salori-2 Expansion	2016	Prayagraj	14	14	SBR	Ganga Pollution control unit, U.P. Jal Nigam	U	19.11.2025	Grab	7.49	18.8	36	32	1400	610	Achieving
27	80 MLD STP Naini	2013	Prayagraj	80	80	ASP	Ganga Pollution control unit, U.P. Jal Nigam	R	18.11.2025	Grab	7.57	26.2	80	62	2200	930	Achieving
28	42 MLD STP, Naini	2023	Prayagraj	42	36	FCR	U.P. Jal Nigam	R	18.11.2025	Grab	7.56	23.8	68	56	2400	780	Achieving
29	14 MLD STP Phaphamau	2023	Prayagraj	14	14	FCR	U.P. Jal Nigam	R	18.11.2025	Grab	7.81	22.8	60	52	2000	680	Achieving
30	16 MLD STP Jhunsi	2023	Prayagraj	16	15	FCR	U.P. Jal Nigam	R	19.11.2025	Grab	7.76	24	72	58	2200	680	Achieving
31	10 MLD STP Ramnagar	2021	Varanasi	10	9	Anaerobic Anoxic Oxidation (A2O)	U.P. Jal Nigam	R	17.11.2025	Grab	7.46	12.4	64	16	350	140	Achieving
32	80 MLD STP Dinapur	1994	Varanasi	80	68	ASP	U.P. Jal Nigam	U	17.11.2025	Grab	7.62	27.4	138	76	390	170	Achieving
33	9.8 MLD STP Bhagwanpur	1989	Varanasi	9.8	8	ASP	U.P. Jal Nigam	R	17.11.2025	Grab	7.41	26.2	148	78	380	170	Achieving
34	140 MLD STP Dinapur	2018	Varanasi	140	99	ASP	U.P. Jal Nigam	U	17.11.2025	Grab	7.69	14.2	48	12	380	170	Achieving
35	120 MLD STP Goithaha	2019	Varanasi	120	40	UASB	U.P. Jal Nigam	U	17.11.2025	Grab	7.58	18.3	60	22	310	170	Achieving
36	12 MLD BLW STP	1989	Varanasi	12	12	ASP	BLW	O	17.11.2025	Grab	7.53	24.8	188	88	540	220	Achieving
37	50 MLD STP Ramana	2021	Varanasi	50	50	SBR	U.P. Jal Nigam	R	17.11.2025	Grab	7.49	24.2	68	18	430	170	Achieving
38	30 MLD STP Pachhahatiya Jaunpur	2023	Jaunpur, Varanasi	30	30	A2O	U.P. Jal Nigam	R	21.11.2025	Grab	7.64	8.8	44	7.4	310	130	Achieving
39	07 MLD Vindiyachal Mirzapur	2022	Mirzapur	7	5	WSP	Nagar Palika Parisad	O	19.11.2025	Grab	7.41	15.4	62	38	700	310	Achieving
40	14 MLD STP Pakka Pokhra	1994	Mirzapur	14	13	UASB	U.P. Jal Nigam	R	19.11.2025	Grab	7.43	29.4	166	86	1200	630	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)/Urban(U)/Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
41	8.5 MLD STP Pakka Pokhra, Mirzapur	2024	Mirzapur	8.5	4.25	SBR	U.P. Jal Nigam	R	19.11.2025	Grab	7.38	14.4	54	28	920	410	Achieving
42	8.5 MLD STP Bisunderpur, Mirzapur	2024	Mirzapur	8.5	4.6	SBR	U.P. Jal Nigam	R	19.11.2025	Grab	7.37	14.2	56	26	1600	540	Achieving
43	15 MLD S.T.P. Jharkhandi, Maherwa ki Bari	2015	Gorakhpur	15	11.89	SBR	U.P. Jal Nigam	U	18.11.2025	Grab	7.69	7.5	28	27	1700	780	Achieving
44	5 MLD S.T.P. Jharkhandi, Maherwa ki Bari	2023	Gorakhpur	5	4	SBR	U.P. Jal Nigam	U	18.11.2025	Grab	7.69	7.5	28	27	1700	780	Achieving
45	30 MLD S.T.P. Opp. Manyavar Kanshiram Shahri Garib Awas Yojna, Deoria bypass Road	2015	Gorakhpur	30	20	SBR	U.P. Jal Nigam	U	18.11.2025	Grab	7.74	8.5	36	25	2400	910	Achieving
46	10 MLD STP Gorakhpur	2024	Gorakhpur	10	10	SBR	U.P. Jal Nigam	U	18.11.2025	Grab	7.59	8	32	22	2100	930	Achieving
47	8 MLD STP Azamgarh	2024	Azamgarh	8	5	SBR	Nagar Palika Parishad	O	18.11.2026	Sampling has not been carried out by the Regional Office,UPPCB							
48	38 MLD STP, Mahilpur Road	1998	Saharanpur	38	38	UASB	U.P. Jal Nigam	U	18.11.2025	Grab	7.5	25	176	44	660	320	Achieving
49	6.5 MLD STP Awas vikas Parishad STP	2018	Lucknow	6.5	0	SBR	Jal Kal Vibhag	O	21.11.2025	Not Operational Due to Maintainance Works							
50	37.5 MLD STP Awas vikas Parishad STP	2017	Lucknow	37.5	37.5	SBR	U.P. Awas vikas Parishad	O	21.11.2025	Grab	7.43	16	85	46	4900	780	Achieving
51	345 MLD STP, Bharwara	2011	Lucknow	345	345	UASB	U.P. Jal Nigam	U	21.11.2025	Grab	7.56	18	104	48	3900	920	Achieving
52	56 (42+14) MLD STP, Daulatganj	2003 & 2009	Lucknow	56	56	FAB	U.P. Jal Nigam	U	21.11.2025	Grab	7.45	18.4	112	45	7000	930	Achieving
53	1.5 MLD STP Hathi Park, (Smart City)	2021	Lucknow	1.5	0	MBBR	Nagar Nigam (Smart City)	O	21.11.2025	Not Operational Due to Maintainance Works							
54	39 MLD STP, Sajjadbagh, Daulatganj	2024	Lucknow	39	39	SBR	U.P. Jal Nigam	R	21.11.2025	Grab	7.45	12	65	40	2600	610	Achieving
55	120 MLD STP near 1090 Chauraha	2025	Lucknow	120	80	SBR	U.P. Jal Nigam	U	21.11.2025	Grab	7.38	13	68	42	5400	700	Achieving
56	19 MLD STP C.G. City, Lucknow	2023	Lucknow	19	0	SBR	LDA	O	21.11.2025	Not Operational Due to Maintainance Works							
57	56 MLD STP Trans Hindon (Indirapuram), Ghaziabad	2000	Ghaziabad	56	56	UASB	U.P. Jal Nigam	U	18.11.2025	Grab	7.5	14	60	30	2700	680	Achieving
58	30 MLD STP, Sadullabad (Loni), Ghaziabad	2012	Ghaziabad	30	20	MBBR	U.P. Jal Nigam	U	19.11.2025	Grab	7.6	8	52	9	2400	780	Achieving
59	74 MLD STP S.B.R., Indirapuram, Ghaziabad	2013	Ghaziabad	74	74	SBR	U.P. Jal Nigam	U	18.11.2025	Grab	7.34	8	54	9	2500	450	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)/Urban(U)/Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
60	56 MLD STP S.B.R., Bapudham, Ghaziabad	2014	Ghaziabad	56	1.5	SBR	GDA	O	18.11.2025	Grab	7.26	7	24	9	2200	790	Achieving
61	6 MLD STP Garh Zone, Garhmukeshwar Hapur	2011	Hapur / Garhmukteswar	6	4.62	UASB followed by extended aeration	U.P. Jal Nigam (NGRBA)	R	17.11.2025	Grab	7.53	7	26	9	2200	400	Achieving
62	3 MLD STP Brijghat Zone, Garhmukeshwar Hapur	2011	Hapur / Garhmukteswar	3	2.5	UASB followed by extended aeration	U.P. Jal Nigam (NGRBA)	R	17.11.2025	Grab	7.48	8	32	10	1700	400	Achieving
63	56 MLD STP , Indirapuram, (GDA), Ghaziabad	2012	Ghaziabad	56	20	SBR	Nagar Nigam	O	18.11.2025	Grab	7.4	9	46	10	1600	540	Achieving
64	56 MLD STP S.B.R., Dudahaida Vijay Nagar, Ghaziabad	2013	Ghaziabad	56	56	SBR	U.P. Jal Nigam	U	18.11.2025	Grab	7.4	8	44	10	2200	790	Achieving
65	70 MLD STP U.A.S.B.R. Dudahaida Vijay Nagar, Ghaziabad	2000	Ghaziabad	70	70	UASB	U.P. Jal Nigam	U	18.11.2025	Grab	7.36	20	80	45	1600	540	Achieving
66	3 MLD STP Pilkhaun	2015	Ghaziabad	3	2.5	UASB	U.P. Jal Nigam	U	17.11.2025	Grab	7.37	18	88	49	2700	830	Achieving
67	5 MLD STP Trans Delhi Signature City (Tronica City), Loni	2019	Ghaziabad	5	5	MBBR	UPSIDA	O	19.11.2025	Grab	7.44	12	78	34	2400	920	Achieving
68	56 MLD STP S.B.R. Govindpuram, Ghaziabad	2014	Ghaziabad	56	14	SBR	GDA	O	18.11.2025	Grab	7.55	8	38	9	2000	450	Achieving
69	20 MLD STP Modinagar	2023	Modinagar, Ghaziabad	20	7.8	SBR	Nagar Palika Parishad	O	19.11.2025	Grab	7.46	18	66	30	2800	790	Achieving
70	56 MLD STP S.B.R., Morty, Ghaziabad	2018	Ghaziabad	56	27	SBR	Nagar Nigam Ghaziabad	O	18.11.2025	Grab	7.55	14	82	20	2000	610	Achieving
71	30 MLD STP, Rampur Road, Hapur	2022	Hapur, Ghaziabad	30	8	SBR	Nagar Palika Parishad	O	17.11.2025	Grab	7.5	16	120	40	1400	610	Achieving
72	21.5 MLD STP Siddharthvihar, Ghaziabad	2024	Ghaziabad	21.5	4.5	SBR	Awass Vikas	O	18.11.2025	Grab	7.49	12	76	30	1600	280	Achieving
73	78 MLD STP Dhadhupura, Agra	2013	Agra	78	78	UASB	U.P. Jal Nigam	U	15.11.2025	Grab	7.94	27	140	37	6300	810	Achieving
74	2.25 MLD STP Budika Nagla, Agra	2000	Agra	2.25	2.25	WSP	U.P. Jal Nigam	U	15.11.2025	Grab	7.88	25	100	43	6300	810	Achieving
75	10 MLD STP Peelakhar, Agra	2000	Agra	10	10	WSP	U.P. Jal Nigam	U	15.11.2025	Grab	7.85	26	110	46	5800	910	Achieving
76	12 MLD STP Devri Road, (Bhimnagri), Agra	2011	Agra	12	8	UASB	U.P. Jal Nigam	U	15.11.2025	Grab	7.89	25	120	48	3400	930	Achieving
77	14 MLD STP Jaganpur, Sikandarpur, Agra	2011	Agra	14	14	UASB	U.P. Jal Nigam	U	15.11.2025	Grab	7.89	24	140	44	4600	920	Achieving
78	40 MLD STP Sadarban, Bichhpuri, Agra	2013	Agra	40	28	UASB	U.P. Jal Nigam	U	15.11.2025	Grab	7.83	28	100	38	3400	930	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)/Urban(U)/Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
79	36 MLD STP Sadarwan (Bichpuri) New	2018	Agra	36	36	SBR	ADA	O	15.11.2025	Grab	7.63	28	120	68	4600	810	Achieving
80	24 MLD STP Dhadhupura (New), Agra	2014	Agra	24	15	UASB	U.P. Jal Nigam	U	15.11.2025	Grab	7.9	25	120	34	3800	910	Achieving
81	4.50 MLD STP Kalindi Vihar, Agra	2014	Agra	4.5	4.5	UASB	Nagar Nigam Agra	O	15.11.2025	Not Operational Due to Maintainance Works							
82	03 MLD STP Pandav Nagar, Meerut	2013	Meerut	3	2.7	ASP	MDA	O	20.11.2025	Grab	7.47	22	132	68	920	680	Achieving
83	07 MLD STP Pallavpuram-1, Meerut	2012	Meerut	7	6.5	ASP	MDA	O	20.11.2025	Grab	7.55	16	96	50	910	610	Achieving
84	11 MLD STP Pallavpuram-2, Meerut	2008	Meerut	11	7	ASP	MDA	O	20.11.2025	Grab	7.47	15	88	52	930	680	Achieving
85	06 MLD STP Rakshapuram, Meerut	2011	Meerut	6	4.4	ASP	MDA	O	20.11.2025	Grab	7.56	18	104	60	930	780	Achieving
86	10 MLD STP Lohiya Nagar, Meerut	2010	Meerut	10	2	ASP	MDA	O	20.11.2025	Grab	7.39	12	28	24	830	610	Achieving
87	15 MLD STP Shatabdinagar, Meerut	2010	Meerut	15	4.8	ASP	MDA	O	20.11.2025	Grab	7.42	10	20	20	810	600	Achieving
88	15 MLD STP Vedyasपुरी Meerut	2011	Meerut	15	4.5	ASP	MDA	O	20.11.2025	Grab	7.42	10	32	28	820	600	Achieving
89	06 MLD STP Shradhapuri-1, Meerut	2012	Meerut	6	5.5	ASP	MDA	O	20.11.2025	Grab	7.44	16	112	48	910	680	Achieving
90	06 MLD STP Sainik Vihar	2017	Meerut	6	5.9	UASB	MDA	O	20.11.2025	Grab	7.46	12	32	32	910	680	Achieving
91	5 MLD STP Modipuram Tiraha	2016	Meerut	5	4.5	ASP	MDA	O	20.11.2025	Grab	7.42	14	60	34	830	610	Achieving
92	07 MLD STP Sports Goods Complex, Meerut	2012	Meerut	7	4	ASP	MDA	O	20.11.2025	Grab	7.51	14	84	34	830	610	Achieving
93	72 MLD STP Garh road (Jagriti vihar) Kamalpur	2018	Meerut	72	72	ASP	U.P. Jal Nigam	U	20.11.2025	Grab	7.38	12	36	14	830	610	Achieving
94	10 MLD STP Ganga Nagar, Meerut	2011	Meerut	10	3.8	SBR	MDA	O	20.11.2025	Grab	7.41	8	20	8	810	600	Achieving
95	06 MLD STP Shradhapuri- Phase-2, Meerut	2012	Meerut	6	5.6	SBR	MDA	O	20.11.2025	Grab	7.48	17	120	56	930	780	Achieving
96	14 MLD STP Baghpat, Meerut	2021	Baghpat, Meerut	14	7.8	SBR	U.P. Jal Nigam	R	20.11.2025	Grab	7.62	18	140	64	930	780	Achieving
97	32.5 MLD STP (WSP) Nagar Palika Parishad, Kidwai nagar	2001	Muzaffar Nagar	32.5	32.5	WSP	U.P. Jal Nigam	U	19.11.2025	Grab	7.4	26	96	44	2100	700	Achieving
98	32.5 MLD STP Near A2Z Garbage plant KidwaiNagar	2025	Muzaffar Nagar	32.5	18	SBR	U.P. Jal Nigam	R	19.11.2025	Grab	7.5	7	24	12	1400	110	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)/Urban(U)/Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
99	10 MLD STP Budhana	2024	Muzaffar Nagar	10	7.32	SBR	U.P. Jal Nigam	R	19.11.2025	Grab	7.6	6	24	14	1300	170	Achieving
100	22 MLD STP Sahawali, Muzaffarnagar	2023	Muzaffar Nagar	22	21	SBR	U.P. Jal Nigam	R	19.11.2025	Grab	7.5	7	26	18	1300	210	Achieving
101	15 MLD STP Kairana, Shamli, Muzaffarnagar	2024	Muzaffar Nagar	15	15	SBR	U.P. Jal Nigam	U	19.11.2025	Grab	7.4	8	28	16	1400	170	Achieving
102	12 MLD STP Ayodhya	2014	Ayodhya	12	7	UASB	U.P. Jal Nigam	U	18.11.2025	Grab	7.46	22	114	62	3400	940	Achieving
103	6 MLD STP Ramghat, Ayodhya	2023	Ayodhya	6	4	SBR	U.P. Jal Nigam	U	18.11.2025	Grab	7.22	16	84	51	3200	780	Achieving
104	13.59 (6.8) MLD STP, Masani, Mathura	2007	Mathura	6.8	6.5	WSP	U.P. Jal Nigam	R	19.11.2025	Grab	7.9	25	232	86	3900	930	Achieving
105	04 MLD STP Vrindavan Near Pagal Baba Mandir, Mathura	2007	Mathura	4	4	WSP	U.P. Jal Nigam	R	19.11.2025	Grab	7.9	27	240	86	3400	930	Achieving
106	08 MLD STP Near 100 Bed Hospital Vrindavan, Manth road	2015	Mathura	8	8	UASB	U.P. Jal Nigam	U	18.11.2025	Grab	7.6	24	208	74	3300	930	Achieving
107	14.5 MLD STP Transyamuna, Jamunapar, Mathura	2007	Mathura	14.5	14.5	WSP	U.P. Jal Nigam	R	18.11.2025	Grab	7.9	44	384	162	14000	3100	Not Achieving
108	30 MLD STP Masani Mathura	2020	Mathura	30	30	SBR	U.P. Jal Nigam	R	19.11.2025	Grab	7.7	23	200	56	2700	930	Achieving
109	16 MLD STP Trans Yamuna, Laxmi Nagar, Mathura	2015	Mathura	16	16	UASB	U.P. Jal Nigam	R	18.11.2025	Grab	7.8	27	248	88	3800	920	Achieving
110	2.76 MLD STP Goverdhan STP	2011	Mathura	2.76	0	WSP	Nagar Palika Parishad	O	18.11.2025	Not Operational Due to Maintainance Works							
111	33 MLD STP Sector-54, Noida	2011	Noida	33	13	SBR	Noida Authority	O	17.11.2025	Grab	7.41	10.3	88.8	29	1600	540	Achieving
112	25 MLD STP Sector-50, Noida	2015	Noida	25	0	SBR	Noida Authority	O	17.11.2025	Not Operational Due to Maintainance Works							
113	35 MLD STP Sector-123, Noida	2011	Noida	35	18	SBR	Noida Authority	O	17.11.2025	Grab	7.63	14.4	104	33	2200	680	Achieving
114	50 MLD STP Sector-168, Noida	2015	Noida	50	19	SBR	Noida Authority	O	17.11.2025	Grab	7.39	13.1	64	27	2200	680	Achieving
115	34 MLD STP Sector -50 Noida	2012	Noida	34	32	SBR	Noida Authority	O	17.11.2025	Grab	7.23	11.8	82.4	28	1200	610	Achieving
116	54 MLD STP Sector-54, Noida	2012	Noida	54	42	SBR	Noida Authority	O	17.11.2025	Grab	7.49	13.9	96.8	81	3400	930	Achieving
117	100 MLD STP Sector-168, Noida	2023	Noida	100	62	SBR	Noida Authority	O	17.11.2025	Grab	7.59	10.3	72	24	1600	350	Achieving
118	80 MLD STP Sector-123, Noida	2023	Noida	80	65	SBR	Noida Authority	O	17.11.2025	Grab	7.31	9.8	56	22	1400	200	Achieving
119	2.0 MLD STP Greater Noida Authority STP, Vill- Badalpur	2015	Greater Noida	2	2	SBR	GNIDA	O	22.11.2025	Grab	7.49	9	44	25	1600	540	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)/Urban(U)/Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
120	15 MLD STP ECO tech -2	2018	Greater Noida	15	8	SBR	GNIDA	O	22.11.2025	Grab	7.47	16	76	32	2200	400	Achieving
121	20 MLD STP ECO tech -3	2018	Greater Noida	20	12	SBR	GNIDA	O	22.11.2025	Grab	7.35	10	40	19	2100	680	Achieving
122	137 MLD STP Kasana, GreaterNoida	2015	Greater Noida	137	90	SBR	GNIDA	O	22.11.2025	Grab	7.5	12	54	27	1700	930	Achieving
123	0.805 MLD STP Ahara Road, Zone-A, Anoopshahar	2003	Bulandshahar	0.805	0.8	WSP	U.P. Jal Nigam	U	17.11.2025	Grab	7.65	22	104	49	1100	400	Achieving
124	1.75 MLD STP Ahara Road, (Shivanand Ashram) Zone-B, Anoopshahar	2003	Bulandshahar	1.75	1.75	WSP	U.P. Jal Nigam	U	17.11.2025	Grab	7.76	26	96	48	1400	680	Achieving
125	2.25 MLD STP Narora Atomic power Station Narora Township	2000	Bulandshahar	2.25	2.25	ASP	Narora Atomic power Station	O	17.11.2025	Grab	7.48	18	96	65	540	240	Achieving
126	01 MLD STP Zone-B Anoopshahar	2016	Bulandshahar	1	1	MBBR	Nagar Palika Parishad	O	17.11.2025	Grab	7.63	22	112	85	2000	680	Achieving
127	1.5 MLD STP Anoopshahar Zone A (NGRBA)	2016	Bulandshahar	1.5	0	UASB	Nagar Palika Parishad	O	17.11.2025	Not Operational Due to Maintainance Works							
128	40 MLD STP Bulandshahar	2023	Bulandshahar	40	20	SBR	Nagar Palika Parishad	O	17.11.2025	Grab	7.55	14	92	51	1500	840	Achieving
129	04 MLD STP , Narora (NGRBA)	2015	Bulandshahar	4	4	UASB	Nagar Palika Parishad	O	17.11.2025	Grab	7.78	26	116	75	1700	930	Achieving
130	24 MLD STP, Bijnor	2018	Bijnor	24	23.5	UASB	Nagar Palika Parishad	O	17.11.2025	Grab	7.72	10	40	23	940	120	Achieving
131	58 MLD STP Moradabad	2018	Moradabad	58	24	UASB	U.P. Jal Nigam	R	18.11.2025	Grab	7.53	6.4	62	7	680	61	Achieving
132	20 MLD STP Moradabad	2017	Moradabad	20	0	SBR	MDA	O	18.11.2025	Grab	7.63	12	78	28	1300	780	Achieving
133	14 MLD STP, Benzirpur	2016	Rampur	14	10	UASB	U.P. Jal Nigam	U	18.11.2025	Grab	7.81	22	76	34	1700	680	Achieving
134	5 MLD STP , Rampur	2016	Rampur	5	4	SBR	U.P. Jal Nigam	U	18.11.2025	Grab	7.56	6.2	80	6	930	68	Achieving
135	15 MLD STP Pehrigoan	2015	Rampur	15	11	UASB	U.P. Jal Nigam	U	18.11.2025	Grab	7.89	23	72	26	2100	930	Achieving
136	15 MLD STP, Kasganj	2022	Kasganj, Aligarh	15	9.6	SBR	U.P. Jal Nigam	R	17.11.2025	Grab	7.28	27.8	160	60	1200	610	Achieving
137	24 MLD STP, Manpur, Etah	2023	Etah, Aligarh	24	16	SBR	Nagar Palika Parishad	O	17.11.2025	Grab	7.31	24.6	142	58	2200	930	Achieving
138	45 MLD STP Laxmi Nagar, Aligarh	2023	Aligarh	45	18	SBR	Nagar Nigam	O	17.11.2025	Grab	7.08	28	176	72	3400	780	Achieving
139	8.95 MLD STP Bela, Pratapgarh	2023	Pratapgarh	8.95	7	FAB	Nagar Palika Parishad	O	19.11.2025	Grab	8.01	22	49.6	35	1300	610	Achieving
140	5 MLD STP Palhipur, Sultanpur	2024	Sultanpur	5	4.4	SBR	U.P. Jal Nigam	R	20.11.2025	Grab	8.13	24	59.2	39	2600	920	Achieving
141	2 MLD STP Miranpur, Sadar, Sultanpur	2024	Sultanpur	2	1.4	SBR	U.P. Jal Nigam	R	20.11.2025	Grab	8.13	24	56	41	2200	920	Achieving
142	10 MLD STP Hathia Nala, Lolepur	2006	Sultanpur	10	6.5	Aerated Lagoon	U.P. Jal Nigam	R	20.11.2025	Grab	8.05	25	56	35	2400	930	Achieving
143	18 MLD STP Raebareli	2023	Raebareli	18	5	SBR	Nagar Palika Parishad	O	17.11.2025	Grab	8.01	9	49.6	8	680	200	Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)Urban(U)Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
144	35 MLD STP, Saraitafi	2023	Bareilly	35	0	ASP	Nagar Nigam	O	18.11.2025	Not Operational Due to Maintenance Works							
145	42 MLD STP, HarooNagla, Bareilly	2024	Bareilly	42	42	SBR	U.P. Jal Nigam	R	18.11.2025	Grab	7.6	6	40	17	220	79	Achieving
146	20 MLD STP Barinagla, Bareilly	2024	Bareilly	20	18	SBR	U.P. Jal Nigam	R	18.11.2025	Grab	7.3	8	36	14	210	90	Achieving
147	01 MLD STP, Girdaripur, Bareilly	2024	Bareilly	1	1	SBR	U.P. Jal Nigam	R	18.11.2025	Grab	7.5	6	44	15	170	68	Achieving
148	40 MLD STP, Shahjahanpur	2025	Shahjahanpur	40	10	SBR	U.P. Jal Nigam	U	18.11.2025	Composite	7.9	6	36	7	210	79	Achieving
149	15 MLD STP Unnao	2024	Unnao	15	13	SBR	U.P. Jal Nigam	R	20.11.2025	Grab	8.29	20.2	172	70.8	4900	780	Achieving
150	21 MLD STP Mau Road, Ghazipur	2024	Ghazipur, Varanasi	21	12	SBR	U.P. Jal Nigam	R	11.11.2025	Grab	7.48	8.4	44	7.4	310	130	Achieving
151	33 MLD STP Ayodhya	2025	Ayodhya	33	0	SBR	UPJN (Rural)	R	18.11.2025	Under Trial Run							
152	15 MLD STP Baniyapur	2018	Kanpur Nagar	15	0	SBR	UPJN (Urban)	U	18.11.2025	Not operational Due to Maintenance Work							
153	5 MLD STP Yamuna Expressway Industrial Development Authority (YIDA)	2023	Jewar (Gt. Noida)	5	0	SBR	UPJN (Rural)	R	22.11.2025	Not operational Due to Maintenance Work							
154	20 MLD STP Ballia	2025	Ballia	20	0	SBR	UPJN (Urban)	U	22.11.2025	Under Trial Run							
155	25 MLD STP Moradabad	2025	Moradabad	25	0	SBR	UPJN(Rural)	R	18.11.2025	Under Trial Run							

Note :- The standards as per MoEF&CC Notification dated 13.10.2017, titled "Applicable Effluent Discharge Standards for STPs" are as follows:
For State Capital: pH-6.5-9.0; BOD - <20 mg/l; TSS- <50 mg/l & FC- <1000 MPN/100 ml
Other than State Capital: pH-6.5-9.0; BOD - <30 mg/l; TSS- <100 mg/l & FC- <1000 MPN/100 ml
Note:- As per the data received from Regional offices, UPPCB

**Performance of Existing STPs in U.P.
(Last Week)**

November- 2025

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Existing Category Rural (OR)\Urban(U)\Other(O)	Date of Sampling (X.11.2025)	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
123	0.805 MLD STP Ahara Road, Zone-A, Anoopshahar	2003	Bulandshahar	0.805	0.8	WSP	U.P. Jal Nigam	U	24.11.2025	Grab	7.72	20	92	46	930	450	Achieving
124	1.75 MLD STP Ahara Road, (Shivanand Ashram) Zone-B, Anoopshahar	2003	Bulandshahar	1.75	1.75	WSP	U.P. Jal Nigam	U	24.11.2025	Grab	7.69	22	88	49	920	540	Achieving
125	2.25 MLD STP Narora Atomic power Station Narora Township	2000	Bulandshahar	2.25	2.25	ASP	Narora Atomic power Station	O	24.11.2025	Grab	7.43	16	92	61	540	240	Achieving
126	01 MLD STP Zone-B Anoopshahar	2016	Bulandshahar	1	1	MBBR	Nagar Palika Parishad	O	24.11.2025	Grab	7.67	26	120	73	1700	930	Achieving
127	1.5 MLD STP Anoopshahar Zone A (NGRBA)	2016	Bulandshahar	1.5	0	UASB	Nagar Palika Parishad	O	24.11.2025	Not Operational Due to Maintainance Works							
128	40 MLD STP Bulandshahar	2023	Bulandshahar	40	20	SBR	Nagar Palika Parishad	O	24.11.2025	Grab	7.57	18	84	41	1400	680	Achieving
129	04 MLD STP , Narora (NGRBA)	2015	Bulandshahar	4	4	UASB	Nagar Palika Parishad	O	24.11.2025	Grab	7.75	22	108	77	2600	920	Achieving

Performance of Existing STPs in U.P.															November- 2025		
Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Rural (R)/Urban(U)/Other(O)	Date of Sampling	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
A																	
STPs Not Achieving the Standards (First Week)																	
1	210 MLD STP, Bingawan Kanpur	2015-16	Kanpur Nagar	210	110	UASB	U.P. Jal Nigam	R	04.11.2025	Grab	7.56	63	230	72	-	-	Not Achieving
2	36 (9+27) MLD STP Jajmau, Kanpur	1992 & 2024	Kanpur Nagar	36	25	UASB	U.P. Jal Nigam	U	04.11.2025	Grab	8.15	37.5	190	60	-	-	Not Achieving
3	10 MLD STP Ramnagar	2021	Varanasi	10	9	Anaerobic Anoxic Oxidation (A2O)	U.P. Jal Nigam	R	06.11.2025	Grab	7.32	38.2	198	88	35000	17000	Not Achieving
4	120 MLD STP Goithaha	2019	Varanasi	120	40	UASB	U.P. Jal Nigam	U	06.11.2025	Grab	7.42	22.8	72	26	43000	17000	Not Achieving
5	50 MLD STP Ramana	2021	Varanasi	50	50	SBR	U.P. Jal Nigam	R	06.11.2025	Grab	7.38	40.4	176	62	28000	13000	Not Achieving
6	14.5 MLD STP Trans-yamuna, Jamunapar, Mathura	2007	Mathura	14.5	14.5	WSP	U.P. Jal Nigam	R	04.11.2025	Grab	8.3	50	384	160	17000	3300	Not Achieving
B																	
STPs Not Achieving the Standards (Second Week)																	
1	210 MLD STP, Bingawan Kanpur	2015-16	Kanpur Nagar	210	110	UASB	U.P. Jal Nigam	R	11.11.2025	Grab	7.89	45	210	68	91000	68000	Not Achieving
2	36 (9+27) MLD STP Jajmau, Kanpur	1992 & 2024)	Kanpur Nagar	36	25	UASB	U.P. Jal Nigam	U	11.11.2025	Grab	8.09	42	170	64	82000	61000	Not Achieving
3	14 MLD STP Pakka Pokhra	1994	Mirzapur	14	13	UASB	U.P. Jal Nigam	R	11.11.2025	Grab	7.52	31.8	174	82	2300	1300	Not Achieving
4	14.5 MLD STP Trans-yamuna, Jamunapar, Mathura	2007	Mathura	14.5	14.5	WSP	U.P. Jal Nigam	R	11.11.2025	Composite	8.1	42	352	154	-	-	Not Achieving
C																	
STPs Not Achieving the Standards (Third Week)																	
1	210 MLD STP, Bingawan Kanpur	2015-16	Kanpur Nagar	210	110	UASB	U.P. Jal Nigam	R	18.11.2025	Grab	7.63	37.5	200	74	84000	63000	Not Achieving
2	36 (9+27) MLD STP Jajmau, Kanpur	1992 & 2024)	Kanpur Nagar	36	25	UASB	U.P. Jal Nigam	U	18.11.2025	Grab	8.1	39	180	60	68000	45000	Not Achieving

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Rural (R)/Urban(U)/Other(O)	Date of Sampling	Sampling Method (Grab or Composite)	pH	BOD (mg/l)	COD (mg/l)	TSS (mg/l)	TC (MPN/100ml)	FC (MPN/100ml)	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)
3	14.5 MLD STP Transyamuna, Jamunapar, Mathura	2007	Mathura	14.5	14.5	WSP	U.P. Jal Nigam	R	18.11.2025	Grab	7.9	44	384	162	14000	3100	Not Achieving
D	STPs Not Achieving the Standards (Last Week)																
1	1.5 MLD STP Saifai Village, Etawah	2006	Etawah	1.5	1.1	Oxidation Pond	U.P. Jal Nigam	U	27.11.2025	Grab	8	27	150	48	12000	1100	Not Achieving
2	10 MLD STP Ramnagar	2021	Varanasi	10	9	Anaerobic Anoxic Oxidation (A2O)	U.P. Jal Nigam	R	29.11.2025	Grab	7.42	26.8	162	90	1700	1100	Not Achieving
3	14 MLD STP Pakka Pokhra	1994	Mirzapur	14	13	UASB	U.P. Jal Nigam	R	24.11.2025	Grab	7.39	34.8	184	88	4700	2200	Not Achieving
4	210 MLD STP, Bingawan Kanpur	2015-16	Kanpur Nagar	210	110	UASB	U.P. Jal Nigam	R	25.11.2025	Grab	7.63	42	190	72	82000	61000	Not Achieving
5	36 (9+27) MLD STP Jajmau, Kanpur	1992 & 2024)	Kanpur Nagar	36	25	UASB	U.P. Jal Nigam	U	25.11.2025	Grab	8.13	45	190	68	63000	33000	Not Achieving
6	14.5 MLD STP Transyamuna, Jamunapar, Mathura	2007	Mathura	14.5	14.5	WSP	U.P. Jal Nigam	R	28.11.2025	Grab	8.1	52	400	156	13000	3300	Not Achieving
7	54 MLD STP Sector- 54, Noida	2012	Noida	54	42	SBR	Noida Authority	O	24.11.2025	Grab	7.38	10.7	848	22	1600	350	Not Achieving
<p>Note :- The standards as per MoEF&CC Notification dated 13.10.2017, titled "Applicable Effluent Discharge Standards for STPs" are as follows: For State Capital: pH-6.5-9.0; BOD - <20 mg/l; TSS- <50 mg/l & FC- <1000 MPN/100 ml Other than State Capital: pH-6.5-9.0; BOD - <30 mg/l; TSS- <100 mg/l & FC- <1000 MPN/100 ml Note:- As per the data received from Regional offices, UPPCB</p>																	

Performance of Existing STPs in U.P.							November- 2025			
Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Rural (R)\Urban(U)\Other(O)	Date of Sampling	Reason for being not-operational
A	STPs Not Operational (First Week)									
1	6.5 MLD STP Awas vikas Parishad STP	2018	Lucknow	6.5	0	SBR	Jal Kal Vibhag	O	04.11.2025	Not Operational Due to Maintainance Works
2	1.5 MLD STP Hathi Park, (Smart City)	2021	Lucknow	1.5	0	MBBR	Nagar Nigam (Smart City)	O	07.11.2025	Not Operational Due to Maintainance Works
3	19 MLD STP C.G. City, Lucknow	2023	Lucknow	19	0	SBR	LDA	O	07.11.2025	Not Operational Due to Maintainance Works
4	4.50 MLD STP Kalindi Vihar, Agra	2014	Agra	4.5	0	UASB	Nagar Nigam	O	01.11.2025	Not Operational Due to Maintainance Works
5	2.76 MLD STP Goverdhan STP	2011	Mathura	2.76	0	WSP	Nagar Palika Parishad	O	04.11.2025	Not Operational Due to Maintainance Works
6	25 MLD STP Sector-50, Noida	2015	Noida	25	0	SBR	Noida Authority	O	03.11.2025	Not Operational Due to Maintainance Works
7	35 MLD STP, Saraitalfi	2023	Bareilly	35	0	ASP	Nagar Nigam	O	04.11.2025	Not Operational Due to Maintainance Works
8	15 MLD STP Baniyapur	2018	Kanpur Nagar	15	0	SBR	UPJN (Urban)	U	04.11.2025	Not operational Due to Maintenance Work
9	5 MLD STP Yamuna Expressway Industrial Development Authority (YIDA)	2023	Jewar (Gt. Noida)	5	0	SBR	UPJN (Rural)	R	06.11.2025	Not operational Due to Maintenance Work
B	STPs Not Operational (Second Week)									
1	6.5 MLD STP Awas vikas Parishad STP	2018	Lucknow	6.5	0	SBR	Jal Kal Vibhag	O	11.11.2025	Not Operational Due to Maintainance Works
2	1.5 MLD STP Hathi Park, (Smart City)	2021	Lucknow	1.5	0	MBBR	Nagar Nigam (Smart City)	O	10.11.2025	Not Operational Due to Maintainance Works

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Rural (R)\Urban(U)\Other(O)	Date of Sampling	Reason for being not-operational
3	19 MLD STP C.G. City, Lucknow	2023	Lucknow	19	0	SBR	LDA	O	10.11.2025	Not Operational Due to Maintainance Works
4	2.76 MLD STP Goverdhan STP	2011	Mathura	2.76	0	WSP	Nagar Palika Parishad	O	11.11.2025	Not Operational Due to Maintainance Works
5	25 MLD STP Sector-50, Noida	2015	Noida	25	0	SBR	Noida Authority	O	10.11.2025	Not Operational Due to Maintainance Works
6	1.5 MLD STP Anoopshahar Zone A (NGRBA)	2016	Bulandshahar	1.5	0	UASB	Nagar Palika Parishad	O	10.11.2025	Not Operational Due to Maintainance Works
7	20 MLD STP Moradabad	2017	Moradabad	20	0	SBR	MDA	O	11.11.2025	Not Operational Due to Maintainance Works
8	35 MLD STP, Saraitalfi	2023	Bareilly	35	0	ASP	Nagar Nigam	O	11.11.2025	Not Operational Due to Maintainance Works
9	15 MLD STP Baniyapur	2018	Kanpur Nagar	15	0	SBR	UPJN (Urban)	U	11.11.2025	Not operational Due to Maintenance Work
10	5 MLD STP Yamuna Expressway Industrial Development Authority (YIDA)	2023	Jewar (Gt. Noida)	5	0	SBR	UPJN (Rural)	R	15.11.2025	Not operational Due to Maintenance Work
C	STPs Not Operational (Third Week)									
1	6.5 MLD STP Awas vikas Parishad STP	2018	Lucknow	6.5	0	SBR	Jal Kal Vibhag	O	21.11.2025	Not Operational Due to Maintainance Works
2	1.5 MLD STP Hathi Park, (Smart City)	2021	Lucknow	1.5	0	MBBR	Nagar Nigam (Smart City)	O	21.11.2025	Not Operational Due to Maintainance Works
3	19 MLD STP C.G. City, Lucknow	2023	Lucknow	19	0	SBR	LDA	O	21.11.2025	Not Operational Due to Maintainance Works

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Rural (R)\Urban(U)\Other(O)	Date of Sampling	Reason for being not-operational
4	4.50 MLD STP Kalindi Vihar, Agra	2014	Agra	4.5	0	UASB	Nagar Nigam Agra	O	15.11.2025	Not Operational Due to Maintainance Works
5	2.76 MLD STP Goverdhan STP	2011	Mathura	2.76	0	WSP	Nagar Palika Parishad	O	18.11.2025	Not Operational Due to Maintainance Works
6	25 MLD STP Sector-50, Noida	2015	Noida	25	0	SBR	Noida Authority	O	17.11.2025	Not Operational Due to Maintainance Works
7	1.5 MLD STP Anoopshahar Zone A (NGRBA)	2016	Bulandshahar	1.5	0	UASB	Nagar Palika Parishad	O	17.11.2025	Not Operational Due to Maintainance Works
8	35 MLD STP, Saraitalfi	2023	Bareilly	35	0	ASP	Nagar Nigam	O	18.11.2025	Not Operational Due to Maintainance Works
9	15 MLD STP Baniyapur	2018	Kanpur Nagar	15	0	SBR	UPJN (Urban)	U	18.11.2025	Not operational Due to Maintenance Work
10	5 MLD STP Yamuna Expressway Industrial Development Authority (YIDA)	2023	Jewar (Gt. Noida)	5	0	SBR	UPJN (Rural)	R	22.11.2025	Not operational Due to Maintenance Work
D	STPs Not Operational (Last Week)									
1	6.5 MLD STP Awas vikas Parishad STP	2018	Lucknow	6.5	0	SBR	Jal Kal Vibhag	O	24.11.2025	Not Operational Due to Maintainance Works
2	1.5 MLD STP Hathi Park, (Smart City)	2021	Lucknow	1.5	0	MBBR	Nagar Nigam (Smart City)	O	24.11.2025	Not Operational Due to Maintainance Works
3	19 MLD STP C.G. City, Lucknow	2023	Lucknow	19	0	SBR	LDA	O	24.11.2025	Not Operational Due to Maintainance Works
4	4.50 MLD STP Kalindi Vihar, Agra	2014	Agra	4.5	0	UASB	Nagar Nigam Agra	O	22.11.2025	Not Operational Due to Maintainance Works

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Rural (R)\Urban(U)\Other(O)	Date of Sampling	Reason for being not-operational
5	2.76 MLD STP Goverdhan STP	2011	Mathura	2.76	0	WSP	Nagar Palika Parishad	O	28.11.2025	Not Operational Due to Maintenance Works
6	25 MLD STP Sector-50, Noida	2015	Noida	25	0	SBR	Noida Authority	O	21.11.2025	Not Operational Due to Maintenance Works
7	1.5 MLD STP Anoopshahar Zone A (NGRBA)	2016	Bulandshahar	1.5	0	UASB	Nagar Palika Parishad	O	24.11.2025	Not operational Due to Maintenance Work
8	35 MLD STP, Saraitalfi	2023	Bareilly	35	0	ASP	Nagar Nigam	O	26.11.2025	Not operational Due to Maintenance Work
9	15 MLD STP Baniyapur	2018	Kanpur Nagar	15	0	SBR	UPJN (Urban)	U	25.11.2025	Not operational Due to Maintenance Work
10	5 MLD STP Yamuna Expressway Industrial Development Authority (YIDA)	2023	Jewar (Gt. Noida)	5	0	SBR	UPJN (Rural)	R	29.11.2025	Not operational Due to Maintenance Work

Note :- The standards as per MoEF&CC Notification dated 13.10.2017, titled "Applicable Effluent Discharge Standards for STPs" are as

For State Capital: pH-6.5-9.0; BOD - <20 mg/l; TSS- <50 mg/l & FC- <1000 MPN/100 ml

Other than State Capital: pH-6.5-9.0; BOD - <30 mg/l; TSS- <100 mg/l & FC- <1000 MPN/100 ml

Note:- As per the data received from Regional offices, UPPCB

Performance of Existing STPs in U.P. (STPs Under Trial Run)								November- 2025			
Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Rural (R)\Urban(U)\Other(O)	Date of Sampling	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)	Operational Status
A STPs Under Trial Run (First Week)											
1	33 MLD STP Ayodhya	2025	Ayodhya	33	0	SBR	UPJN (Rural)	R	03.11.2025	-	Under Trial Run
2	20 MLD STP Ballia	2025	Ballia	20	0	SBR	UPJN (Urban)	U	14.11.2025	-	Under Trial Run
3	25 MLD STP Moradabad	2025	Moradabad	25	0	SBR	UPJN(Rural)	R	04.11.2025	-	Under Trial Run
B STPs Under Trial Run (Second Week)											
1	33 MLD STP Ayodhya	2025	Ayodhya	33	0	SBR	UPJN (Rural)	R	13.11.2025	-	Under Trial Run
2	20 MLD STP Ballia	2025	Ballia	20	0	SBR	UPJN (Urban)	U	14.11.2025	-	Under Trial Run
3	25 MLD STP Moradabad	2025	Moradabad	25	0	SBR	UPJN(Rural)	R	11.11.2025	-	Under Trial Run
C STPs Under Trial Run (Third Week)											
1	33 MLD STP Ayodhya	2025	Ayodhya	33	0	SBR	UPJN (Rural)	R	18.11.2025	-	Under Trial Run
2	20 MLD STP Ballia	2025	Ballia	20	0	SBR	UPJN (Urban)	U	22.11.2025	-	Under Trial Run

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Rural (R)\Urban(U)\Other(O)	Date of Sampling	Achieving/ Not Achieving (As per MoEF&CC notification dated 13.10.2017)	Operational Status
3	25 MLD STP Moradabad	2025	Moradabad	25	0	SBR	UPJN(Rural)	R	18.11.2025	-	Under Trial Run
D	STPs Under Trial Run (Last Week)										
1	33 MLD STP Ayodhya	2025	Ayodhya	33	0	SBR	UPJN (Rural)	R	26.11.2025	-	Under Trial Run
2	20 MLD STP Ballia	2025	Ballia	20	0	SBR	UPJN (Urban)	U	29.11.2025	-	Under Trial Run
3	25 MLD STP Moradabad	2025	Moradabad	25	0	SBR	UPJN(Rural)	R	26.11.2025	-	Under Trial Run
<p>Note :- The standards as per MoEF&CC Notification dated 13.10.2017, titled "Applicable Effluent Discharge Standards for STPs" are as follows:</p> <p>For State Capital: pH-6.5-9.0; BOD - <20 mg/l; TSS- <50 mg/l & FC- <1000 MPN/100 ml</p> <p>Other than State Capital: pH-6.5-9.0; BOD - <30 mg/l; TSS- <100 mg/l & FC- <1000 MPN/100 ml</p> <p>Note:- As per the data received from Regional offices, UPPCB</p>											

Performance of Existing STPs in U.P.								November- 2025	
Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Rural (R)\Urban(U)\ Other(O)	Operational Status
A	STPs where sampling was not carried out by the Regional Office, UPPCB (First Week)								
1	8 MLD STP Azamgarh	2024	Azamgarh	8	5	SBR	Nagar Palika Parishad	O	Sampling has not been carried out by the Regional Office,UPPCB
2	3.42 MLD STP Near Divyang kendra	2000	Chitrakoot	3.42	0	Oxidation Pond	Nagar Palika Parishad	O	Sampling has not been carried out by the Regional Office,UPPCB.
3	15 MLD STP Unnao	2024	Unnao	15	13	SBR	U.P. Jal Nigam	R	Sampling has not been carried out by the Regional Office,UPPCB.
B	STPs where sampling was not carried out by the Regional Office, UPPCB (Second Week)								
1	13.5 MLD STP at Mauja Umrain	2013	Etawah	13.5	12	SBR	UP Jal Nigam	R	Sampling has not been carried out by the Regional Office
2	3.42 MLD STP Near Divyang kendra	2000	Chitrakoot	3.42	0	Oxidation Pond	Nagar Palika Parishad	O	Sampling has not been carried out by the Regional Office
C	STPs where sampling was not carried out by the Regional Office, UPPCB (Third Week)								
1	26 MLD STP Jhansi Laxmi Taal	2021	Jhansi	26	SBR	U.P. Jal Nigam	U	NA	Sampling has not been carried out by the Regional Office,UPPCB
2	3.42 MLD STP Near Divyang kendra	2000	Chitrakoot	3.42	0	Oxidation Pond	Nagar Palika Parishad	O	Sampling has not been carried out by the Regional Office,UPPCB
3	8 MLD STP Azamgarh	2024	Azamgarh	8	5	SBR	Nagar Palika Parishad	O	Sampling has not been carried out by the Regional Office,UPPCB
D	STPs where sampling was not carried out by the Regional Office, UPPCB (Last Week)								

Sl. No.	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Rural (R)\Urban(U)\ Other(O)	Operational Status
1	26 MLD STP Jhansi Laxmi Taal	2021	Jhansi	26	SBR	U.P. Jal Nigam	U	NA	Sampling has not been carried out by the Regional Office,UPPCB
2	26 MLD STP Smart City, Lahargird	2025	Jhansi	26	25	SBR	Nagar Nigam	O	Sampling has not been carried out by the Regional Office
3	3.42 MLD STP Near Divyang kendra	2000	Chitrakoot	3.42	0	Oxidation Pond	Nagar Palika Parishad	O	Sampling has not been carried out by the Regional Office,UPPCB
4	8 MLD STP Azamgarh	2024	Azamgarh	8	5	SBR	Nagar Palika Parishad	O	Sampling has not been carried out by the Regional Office,UPPCB
5	15 MLD STP Unnao	2024	Unnao	15	13	SBR	U.P. Jal Nigam	R	Sampling has not been carried out by the Regional Office,UPPCB

Frequency of STPs Not Achieving the Standards in U.P.								November- 2025	
Sl. No.	Period of the Month	Name and Address of STP	Year of Commissioning	City/ Town / District	Installed Capacity (MLD)	Average Utilized Capacity (MLD)	Technology/ process STP based	Hotel/ Ashram/ Authority/ Local Urban body/other institutions responsible for O&M of STP	Rural (R)\Urban(U)\ Other(O)
1	Failed to meet standards in all weekly samples.	36 (9+27) MLD STP Jajmau, Kanpur	1992 & 2024	Kanpur Nagar	36	25	UASB	U.P. Jal Nigam	U
		14.5 MLD STP Trans-yamuna, Jamunapar, Mathura	2007	Mathura	14.5	14.5	WSP	U.P. Jal Nigam	R
		210 MLD STP, Bingawan Kanpur	2015-16	Kanpur Nagar	210	110	UASB	U.P. Jal Nigam	R
2	Failed to meet standards in three weekly samples.								
3	Failed to meet standards in two weekly samples.	14 MLD STP Pakka Pokhra	1994	Mirzapur	14	13	UASB	U.P. Jal Nigam	R
		10 MLD STP Ramnagar	2021	Varanasi	10	9	Anaerobic Anoxic Oxidation (A2O)	U.P. Jal Nigam	R
4	Failed to meet standards in one weekly sample.	120 MLD STP Goithaha	2019	Varanasi	120	40	UASB	U.P. Jal Nigam	U
		50 MLD STP Ramana	2021	Varanasi	50	50	SBR	U.P. Jal Nigam	R
		54 MLD STP Sector- 54, Noida	2012	Noida	54	42	SBR	Noida Authority	O

एन०डब्लू०एम०पी० परियोजना के अन्तर्गत
उत्तर प्रदेश में प्रमुख नदियों एवं अन्य जल स्रोत की जलगुणता का विवरण
माह - नवम्बर 2025

क्रम सं.	क्षेत्रीय कार्यालय	जनपद	नदी	कोड सं०	नमूना एकत्रण बिन्दु	डी.डी. (मिगा/ली.)	बी.ओ.डी. (मिगा/ली.)	टोटल कोलीफॉर्म (एमपीएम/100 एम.एल.)	फिकैल कोलीफॉर्म (एमपीएम/100 एम.एल.)	श्रेणी (CATEGORY)
1	बिजनौर	बिजनौर	गंगा नदी	10150	एट मध्य गंगा बैराज, बिजनौर	9.20	1.30	940	330	C
2	मेरठ	मेरठ	गंगा नदी	5707	एट नांदुर-हरिस्तापुर ब्रिज	9.10	1.40	1000	680	C
3	बिजनौर	बिजनौर	गंगा नदी	5708	टिगरी गंगाघाट, टिगरी अमरोहा	8.90	1.40	1300	400	C
4	गाजियाबाद	हापुड़	गंगा नदी	10149	अपस्ट्रीम, ब्रिजघाट, गढ़मुक्तेशवर	10.40	1.60	430	350	B
5	गाजियाबाद	हापुड़	गंगा नदी	1062	गढ़मुक्तेशवर डाउन स्ट्रीम गंगा	10.20	1.80	920	540	C
6	बुलन्दशहर	बुलन्दशहर	गंगा नदी	2488	अपस्ट्रीम, अनूपशहर	8.60	1.40	1400	610	C
7	बुलन्दशहर	बुलन्दशहर	गंगा नदी	2489	डाउनस्ट्रीम, अनूपशहर	8.90	1.30	1600	920	C
8	बुलन्दशहर	बुलन्दशहर	गंगा नदी	1145	राजघाट डाउनस्ट्रीम, नरोरा	9.40	1.00	2200	680	C
9	बरेली	बदायूं	गंगा नदी	2490	कछलाघाट, बदायूं	8.80	1.10	330	260	B
10	कानपुर	फर्रुखाबाद	गंगा नदी	10151	एट फर्रुखाबाद (घटिया घाट)	8.80	2.80	3300	2700	C
11	कानपुर	कन्नौज	गंगा नदी	1063	अपस्ट्रीम, कन्नौज	8.60	3.00	3900	2600	C
12	कानपुर	कन्नौज	गंगा नदी	1066	डाउनस्ट्रीम, कन्नौज	8.50	3.20	4000	2700	D
13	कानपुर	कानपुर	गंगा नदी	5709	नानामऊ गंगा ब्रिज, लखनऊ-मोहान हसनगंज-रसूलाबाद मार्ग, करती अकबर सेना	8.40	3.30	4100	2100	D
14	कानपुर	कानपुर	गंगा नदी	1146	बितूर, कानपुर	8.50	3.20	4000	2700	D
15	कानपुर	कानपुर	गंगा नदी	1067	अपस्ट्रीम, कानपुर (शुक्लागंज)	8.40	3.30	6100	4000	D
16	कानपुर	कानपुर	गंगा नदी	10154	एट भैरव घाट (बाथिंग घाट)	8.30	3.40	5800	4300	D
17	कानपुर	कानपुर	गंगा नदी	10155	एट डी.एस. शुक्ला गंज	8.20	3.40	6800	4500	D
18	कानपुर	कानपुर	गंगा नदी	10156	एट गोला घाट (बाथिंग घाट)	8.00	3.50	5500	3700	D
19	कानपुर	कानपुर	गंगा नदी	10157	एट जाजमऊ ब्रिज (बाथिंग घाट)	8.10	3.50	4700	3300	D
20	कानपुर	कानपुर	गंगा नदी	1068	डाउनस्ट्रीम, कानपुर (जाना विलेज)	7.90	3.60	63000	31000	D
21	कानपुर	कानपुर	गंगा नदी	5710	पुराना राजापुर, राजापुर	8.30	3.30	3800	2600	D
22	प्रयागराज	फतेहपुर	गंगा नदी	5711	'पांडु नदी में मिलने के बाद मदेश्वर बाबा मंदिर, देवमई	8.70	2.70	3500	1700	C
23	रायबरेली	फतेहपुर	गंगा नदी	5712	माता गंगा ब्रिज एन०एच०-335, लालगंज रोड	8.80	2.40	2100	930	C
24	रायबरेली	रायबरेली	गंगा नदी	1147	डलमऊ, रायबरेली	8.50	2.50	2300	930	C
25	रायबरेली	प्रतापगढ़	गंगा नदी	2498	कालाकंकर	8.70	2.40	2300	1200	C
26	प्रयागराज	कोशाम्बी	गंगा नदी	2487	कड़ाघाट	8.20	2.40	2200	1100	C
27	रायबरेली	प्रतापगढ़	गंगा नदी	5713	एट गंगा ब्रिज, एन०एच०-19, धीमी	8.90	2.30	2200	1100	C
28	प्रयागराज	प्रयागराज	गंगा नदी	1046	अपस्ट्रीम, प्रयागराज (रसूलाबाद घाट)	8.10	2.50	2400	920	C
29	प्रयागराज	प्रयागराज	गंगा नदी	1049	डाउनस्ट्रीम, प्रयागराज (संगम)	7.80	2.70	3400	1400	C

(P. S. JRF)

(CA)

(S.A.)

1 (A.S.O)

(T.M. Lab)

339

क्रम सं.	क्षेत्रीय कार्यालय	जनपद	नदी	कोड सं०	नमूना एकत्रण बिन्दु	डी.डी. (मिग्रा/ली.)	बी.ओ.डी. (मिग्रा/ली.)	टोटल कोलीफार्म (एमपीएन/100 एम.एल.)	फीकैल कोलीफार्म (एमपीएन/100 एम.एल.)	श्रेणी (CATEGORY)
30	प्रयागराज	प्रयागराज	गंगा नदी	5714	तमसा नदी में मिलने से पूर्व, प्राचीन शिवालय दुमदुमा घाट	8.40	2.50	2000	1100	C
31	प्रयागराज	प्रयागराज	गंगा नदी	10158	तमसा नदी में मिलने के बाद, शिरसा, सोन बरसा	8.30	2.60	1700	920	C
32	सोनभद्र	मिर्जापुर	गंगा नदी	2485	अपस्ट्रीम, विंध्याचल, मिर्जापुर	7.90	2.40	1200	700	C
33	सोनभद्र	मिर्जापुर	गंगा नदी	2486	डाउनस्ट्रीम, मिर्जापुर	7.20	3.50	11000	4900	D
34	सोनभद्र	सोनभद्र	गंगा नदी	10153	एट चुनार पौनदून ब्रिज	7.80	3.20	8400	3300	D
35	वाराणसी	वाराणसी	गंगा नदी	1070	अपस्ट्रीम, वाराणसी	8.00	2.50	1400	790	C
36	वाराणसी	वाराणसी	गंगा नदी	1071	डाउनस्ट्रीम, वाराणसी	7.10	3.50	13000	7900	D
37	वाराणसी	वाराणसी	गंगा नदी	5715	गोमती नदी में मिलने के पूर्व बलुआ घाट ब्रिज	7.30	3.30	11000	7000	D
38	वाराणसी	गाजीपुर	गंगा नदी	10152	गोमती नदी में मिलने के बाद, भुसावल, सालदिया रोड, सैदपुर	7.50	3.20	8400	4900	D
39	वाराणसी	वाराणसी	गंगा नदी	5716	जमनिया गंगा ब्रिज जमनिया	7.80	3.00	7000	3300	D
40	वाराणसी	गाजीपुर	गंगा नदी	1073	डाउनस्ट्रीम, तारीघाट	7.00	3.60	15000	8400	D
41	आजमगढ़	बलिया	गंगा नदी	5717	डाउनस्ट्रीम बलिया एट बयासी बलिया ब्रिज	7.50	3.20	12000	6300	D
42	वाराणसी	वाराणसी	वरुणा नदी	2482	रामेश्वर, वाराणसी	7.80	2.70	1200	630	C
43	वाराणसी	वाराणसी	वरुणा नदी	2483	गंगा नदी में मिलने से पहले	1.40	17.80	46000	31000	E
44	मेरठ	मेरठ	काली (पूर्व)	2497	खरखोदा परिश्रित गढ़ रोड, ग्राम कोल	NIL	46.00	170000	130000	E
45	बुलन्दशहर	बुलन्दशहर	काली नदी (पूर्व)	1480	काली नदी, उर्ध्वप्रवाह (अपस्ट्रीम), बुलन्दशहर	NIL	50.00	4700000	3400000	E
46	कानपुर	कन्नौज	काली नदी	1065	काली नदी, कन्नौज (मेंहदी घाट)	6.80	4.00	-	-	D
47	मुजफ्फरनगर	मुजफ्फरनगर	काली नदी (पश्चिम)	1477	काली नदी, उर्ध्वप्रवाह, (अपस्ट्रीम) मुजफ्फरनगर	3.20	14.00	-	-	E
48	मुजफ्फरनगर	मुजफ्फरनगर	काली नदी (पश्चिम)	1478	काली नदी, अनुप्रवाह, (डाउनस्ट्रीम) मुजफ्फरनगर	NIL	34.00	-	-	E
49	कानपुर	फर्रुखाबाद	रामगंगा	1064	रामगंगा, फर्रुखाबाद	6.70	3.70	-	-	D
50	उन्नाव	उन्नाव	सई नदी	1361	बनी, उन्नाव	6.90	2.80	5400	2400	D
51	वाराणसी	जौनपुर	सई नदी	2484	जलालपुर, जौनपुर	8.00	2.60	2700	1300	C
52	सहारनपुर	सहारनपुर	हिण्डन नदी	10098	महेशपुर अपस्ट्रीम	Dry				
53	सहारनपुर	सहारनपुर	हिण्डन नदी	10099	महेशपुर डाउनस्ट्रीम	1.40	24.00	36000	24000	E
54	सहारनपुर	सहारनपुर	हिण्डन नदी	1357	डाउनस्ट्रीम, सहारनपुर	1.50	22.00	41000	33000	E
55	मेरठ	बागपत	हिण्डन नदी	2496	सरधना- बुधना रोड, ग्राम बपारसी	NIL	38.00	170000	140000	E
56	मेरठ	मेरठ	हिण्डन नदी	10100	बरनावा अपस्ट्रीम	NIL	34.00	150000	120000	E
57	मेरठ	मेरठ	हिण्डन नदी	10101	बरनावा डाउनस्ट्रीम	NIL	40.00	160000	100000	E
58	मेरठ	मेरठ	हिण्डन नदी	1483	हिण्डन नदी पुरा महादेव बलेनी, बागपत	NIL	48.00	210000	150000	E
59	गाजियाबाद	गाजियाबाद	हिण्डन नदी	10106	गाजियाबाद अपस्ट्रीम (करहेडा)	1.90	32.00	340000	270000	E

(SAR)

(CA)

(SA)

(A20)

(Ind. Lab)



क्रम सं.	क्षेत्रीय कार्यालय	जनपद	नदी	कोड सं०	340 नमूना एकत्रण बिन्दु	डी.ओ. (मिग्रा/ली.)	बी.ओ.डी. (मिग्रा/ली.)	टोटल कोलीफार्म (एमपीएन/100 एम.एल.)	फ्रीकैल कोलीफार्म (एमपीएन/100 एम.एल.)	श्रेणी (CATEGORY)
60	गाजियाबाद	गाजियाबाद	हिण्डन नदी	10102	मोहननगर अपस्ट्रीम (रोडब्रिज)	2.10	24.00	310000	210000	E
61	गाजियाबाद	गाजियाबाद	हिण्डन नदी	10103	मोहननगर डाउनस्ट्रीम (छिजारसी)	2.70	24.00	390000	210000	E
62	नोएडा	नोएडा	हिण्डन नदी	10104	नोएडा अपस्ट्रीम	3.60	18.00	390000	330000	E
63	गाजियाबाद	(नोएडा) गौतम बुद्ध नगर	हिण्डन नदी	1358	डाउनस्ट्रीम, कुलेसरा	NIL	62.00	5400000	3500000	E
64	नोएडा	नोएडा	हिण्डन नदी	10105	नोएडा डाउनस्ट्रीम	2.80	21.00	240000	120000	E
65	लखनऊ	सीतापुर	गोमती नदी	1350	अपस्ट्रीम, सीतापुर दधनामऊ घाट	9.80	2.30	1600	540	C
66	लखनऊ	सीतापुर	गोमती नदी	10083	नीमसार अपस्ट्रीम	9.70	2.30	1700	610	C
67	लखनऊ	सीतापुर	गोमती नदी	10084	नीमसार डाउनस्ट्रीम	9.40	2.50	2100	920	C
68	लखनऊ	सीतापुर	गोमती नदी	10085	भटपुर अपस्ट्रीम	9.30	2.60	2400	930	C
69	लखनऊ	सीतापुर	गोमती नदी	10086	भटपुर डाउनस्ट्रीम	8.80	2.90	3500	1700	C
70	लखनऊ	लखनऊ	गोमती नदी	10087	गऊघाट अपस्ट्रीम	8.00	3.40	4900	3300	D
71	लखनऊ	लखनऊ	गोमती नदी	10088	गऊघाट डाउनस्ट्रीम	7.60	3.60	5400	3500	D
72	लखनऊ	लखनऊ	गोमती नदी	10089	मोहन मेकिन अपस्ट्रीम	4.20	6.70	61000	40000	D
73	लखनऊ	लखनऊ	गोमती नदी	10090	मोहन मेकिन डाउनस्ट्रीम	3.80	7.20	68000	45000	E
74	लखनऊ	लखनऊ	गोमती नदी	1351	अपस्ट्रीम, लखनऊ	8.10	3.40	4900	3300	D
75	लखनऊ	लखनऊ	गोमती नदी	10091	पिपराघाट अपस्ट्रीम	2.40	9.40	110000	78000	E
76	लखनऊ	लखनऊ	गोमती नदी	10092	पिपराघाट डाउनस्ट्रीम	2.10	10.00	130000	79000	E
77	लखनऊ	लखनऊ	गोमती नदी	1352	डाउनस्ट्रीम लखनऊ	2.00	10.00	130000	79000	E
78	लखनऊ	बाराबंकी	गोमती नदी	10093	गंगागंज अपस्ट्रीम	3.70	7.60	70000	46000	E
79	लखनऊ	बाराबंकी	गोमती नदी	10094	गंगागंज डाउनस्ट्रीम	4.00	7.20	68000	45000	D
80	रायबरेली	सुलतानपुर	गोमती नदी	10095	सुलतानपुर अपस्ट्रीम	8.00	3.40	4600	2400	D
81	रायबरेली	सुलतानपुर	गोमती नदी	10096	सुलतानपुर डाउनस्ट्रीम	7.80	3.30	5400	2800	D
82	वाराणसी	जौनपुर	गोमती नदी	10097	जौनपुर अपस्ट्रीम	7.80	2.40	1500	700	C
83	वाराणसी	जौनपुर	गोमती नदी	1353	डाउनस्ट्रीम जौनपुर	7.40	3.10	5800	3100	D
84	वाराणसी	वाराणसी	गोमती नदी	1072	गोमती नदी गंगा में मिलने से पहले रजवारी, वाराणसी	7.60	2.90	4900	2300	C
85	रायबरेली	फैजाबाद	सरयू नदी	1354	सरयू एट अयोध्या	9.10	2.60	2400	1100	C
86	मथुरा	मथुरा	यमुना नदी	2493	शाहपुर, मथुरा	4.60	14.40	110000	46000	D
87	मथुरा	मथुरा	यमुना नदी	2495	केसीघाट, वृन्दावन	6.00	9.80	47000	20000	D
88	मथुरा	मथुरा	यमुना नदी	1123	अपस्ट्रीम मथुरा	6.40	10.40	58000	23000	D
89	मथुरा	मथुरा	यमुना नदी	2494	विश्रामघाट, मथुरा	5.80	11.60	79000	27000	D
90	मथुरा	मथुरा	यमुना नदी	1124	डाउनस्ट्रीम मथुरा	7.00	11.00	63000	22000	D
91	आगरा	आगरा	यमुना नदी	1125	अपस्ट्रीम आगरा (कैलाशघाट)	6.30	6.80	7900	1200	D
92	आगरा	आगरा	यमुना नदी	1126	डाउनस्ट्रीम आगरा (ताजमहल)	5.70	7.60	9400	2700	D
93	आगरा	आगरा	यमुना नदी	1498	बटेश्वर में यमुना नदी	6.70	7.20	11000	4100	D
94	फिरोजाबाद	इटावा	यमुना नदी	10082	एट उदी	7.50	12.80	11000	2400	D
95	फिरोजाबाद	इटावा	यमुना नदी	10081	इटावा डाउनस्ट्रीम	7.30	15.20	15000	3200	D
96	फिरोजाबाद	इटावा	यमुना नदी	1127	इटावा में यमुना नदी	7.20	14.40	14000	2700	D
97	फिरोजाबाद	इटावा	यमुना नदी	1499	चंबल, इटावा में संगम के पश्चात जूहीका में यमुना नदी	7.60	10.40	8400	1700	D
98	बांदा	हमीरपुर	यमुना नदी	2283	यमुना, हमीरपुर	7.45	3.30	700	370	D
99	प्रयागराज	प्रयागराज	यमुना नदी	1069	यमुना, प्रयागराज	8.40	2.50	2100	1200	C

(JRS)

(CA)

(S.A.)

3

(A.S.D.)

(Inv. Lab)



क्रम सं.	क्षेत्रीय कार्यालय	जनपद	नदी	कोड सं०	नमूना एकत्रण बिन्दु	डी.ओ. (मिगा/ली.)	बी.ओ.डी. (मिगा/ली.)	टोटल कोलीफार्म (एमपीएन/100 एम.एल.)	फ्रीकॉल कोलीफार्म (एमपीएन/100 एम.एल.)	श्रेणी (CATEGORY)
100	गोरखपुर	गोरखपुर	घाघरा नदी	2492	बडहलगंज, गोरखपुर	7.30	4.60	26000	14000	D
101	गोरखपुर	देवरिया	घाघरा नदी	1355	तुरतीपुर, देवरिया	7.40	4.20	22000	12000	D
102	गोरखपुर	गोरखपुर	राप्ती नदी	1363	डोमनगढ़, गोरखपुर	7.60	3.40	24000	12000	D
103	गोरखपुर	गोरखपुर	राप्ती नदी	2491	राजघाट, डाउनस्ट्रीम गोरखपुर	7.20	4.60	32000	20000	D
104	बांदा	हमीरपुर	बेतवा नदी	1356	बेतवा, हमीरपुर	7.26	2.80	700	360	C
105	मुजफ्फरनगर	मुजफ्फरनगर	बाण गंगा	2502	शुक ताल घाट	6.00	1.80	2200	940	C
106	मुजफ्फरनगर	मुजफ्फरनगर	रामसर साइट	5549	हैदरपुर वैटलैण्ड एरिया	6.30	1.60	1700	680	C
107	आगरा	आगरा	रामसर साइट	5514	सूर सरोवर पक्षी विहार (कीटम झील)	6.40	7.60	9400	2700	D
108	उन्नाव	हरदोई	रामसर साइट	5516	सान्डी बर्ड सेन्चुरी	6.00	3.80	17000	7900	D
109	फिरोजाबाद	मैनपुरी	रामसर साइट	5550	समन पक्षी विहार किशनी एट मैनपुरी	6.00	11.20	11000	3200	D
110	फिरोजाबाद	इटावा	रामसर साइट	5551	सरसई नवर झील	6.20	10.80	9400	2600	D
111	उन्नाव	उन्नाव	रामसर साइट	5515	नवाबगंज बर्ड सेन्चुरी	5.80	3.20	94000	46000	D
112	अयोध्या	गोंडा	रामसर साइट	5807	पार्वती आरंगा बर्ड सेन्चुरी	5.90	4.20	7900	2400	D
113	बस्ती	सन्त कबीर नगर	रामसर साइट	5552	बखिरा वाइल्ड लाइफ सेन्चुरी	6.74	5.40	220000	110000	D
114	झाँसी	झाँसी	तालाब	2500	माहिल तालाब, तहसील उरई, जालौन	6.80	3.30	2000	680	D
115	झाँसी	झाँसी	तालाब	2501	लक्ष्मी तालाब, झाँसी	6.14	4.10	3200	920	D
116	रायबरेली	रायबरेली	झील	2499	समसपुर झील, एट सलोन	7.00	3.40	7900	2600	D
117	गोरखपुर	गोरखपुर	रामगढ़ लेक	1364	रामगढ़ लेक, गोरखपुर	7.20	4.80	34000	26000	D
118	झाँसी	ललितपुर	गोविन्दसागर	1735	गोविन्द सागर	7.20	3.00	700	360	C
119	सोनभद्र	सोनभद्र	रिहन्दबाध	1359	अपस्ट्रीम रेनूकूट	8.50	1.70	350	170	B
120	सोनभद्र	सोनभद्र	रिहन्दबाध	1360	डाउनस्ट्रीम रेनूकूट	8.00	2.50	1300	790	C
121	गाजियाबाद	गाजियाबाद	वाटर ट्रीटमेंट	3050	वाटर वर्क्स, गाजियाबाद	10.20	NIL	NIL	NIL	A

(MRS)

(LA)

(S.A.)

(A.S.O)

(Inch Lab)



कायोलय
राज्य स्वच्छ गंगा मिशन-उत्तर प्रदेश ANNEXURE-3
नमामि गंगे तथा ग्रामीण जलापूर्ति विभाग, उ०प्र०
६-शाणाप्रताप मार्ग, उ०प्र० जल निगम मुख्यालय, हजरतगंज, लखनऊ।
Website <http://www.smcgup.org> /E-mail: ta@smcgup.org

पत्र संख्या- 913 / 0041 / SMCG-UP / 10 दिनांक : 23-12-2025

सेवा में,

संयुक्त सचिव,
नमामि गंगे तथा ग्रामीण जलापूर्ति अनुभाग-3,
उ०प्र० शासन।

विषय:-गणतंत्र दिवस समारोह "26 जनवरी, 2026" को गरिमापूर्ण ढंग से मनाये जाने के सम्बन्ध में।

महोदय,

कृपया उपरोक्त विषयक शासन के पत्र सं०-1254/76-3-2025-837/2009टी. सी.-1769449 दिनांक 17.12.2025 का संदर्भ ग्रहण करने का कष्ट करें, जिसके माध्यम से गणतंत्र दिवस समारोह "26 जनवरी, 2026" को गरिमापूर्ण ढंग से मनाये जाने के सम्बन्ध में विभाग में संचालित विभिन्न नीतियों, योजनाओं, कार्यक्रमों एवं उपलब्धियों की अद्यतन प्रगति रिपोर्ट उपलब्ध कराये जाने की अपेक्षा की गयी है।

उपरोक्तानुसार वांछित सूचना साफ्ट कॉपी में ईमेल-infobureau@upidgov.in पर तथा हार्ड कापी संलग्न कर आवश्यक कार्यवाही हेतु प्रेषित की जा रही है।
संलग्नक-उपरोक्तानुसार।

भवदीय,


(जोगिंदर सिंह)
परियोजना निदेशक

**राज्य स्वच्छ गंगा मिशन- उत्तर प्रदेश
नमामि गंगे कार्यक्रम**

विभाग की संचालित विभिन्न नीतियों, योजनाओं, कार्यक्रमों एवं उपलब्धियों की अद्यतन प्रगति रिपोर्ट।

1. राज्य में 74 सीवर शोधन की परियोजनायें स्वीकृत हुई हैं, जिनमें से 41 पूर्ण की जा चुकी हैं तथा शेष 22 पर कार्य प्रगति में है। 03 परियोजनाओं की निविदा प्रक्रिया पूर्ण कर कायदेशि निर्गत कर दिये गये हैं। 08 परियोजना के क्रियान्वयन हेतु वर्तमान में टेंडर की प्रक्रिया जारी है।
2. कुल 74 परियोजना हेतु स्वीकृत धनराशि रूपए 16177.12 करोड़ है।
3. उपरोक्त 74 परियोजनाओं के पूर्ण होने से 2288.30 MLD सीवेज शोधित हो सकेगा।
4. वर्तमान में राज्य में नमामि गंगे कार्यक्रम के अन्तर्गत 33 सीवेज ट्रीटमेंट प्लांट (22 प्रगतिशील परियोजनाओं में) निर्माणाधीन है जिनकी क्षमता 1030.10 MLD है। साथ ही 11 परियोजनाओं में 11 सीवेज ट्रीटमेंट प्लांट के कायदेशि निर्गत/निविदा प्रक्रिया के अधीन है, जिनकी कुल क्षमता 433.0 MLD है। वर्तमान में इनके आलावा 11 सीवेज परियोजनाओं की DPR नमामि गंगे कार्यक्रम के तहत विचाराधीन हैं जिनमें कुल 920.0 MLD क्षमता के 10 सीवेज ट्रीटमेंट प्लांट प्रस्तावित है।
5. नमामि गंगे कार्यक्रम के अन्तर्गत राज्य में अब तक कुल 41 परियोजनाओं में, 42 STP का निर्माण पूर्ण किया जा चुका है जिनकी कुल शोधन क्षमता 962 MLD है।
6. वर्तमान में राज्य में कुल 5500 MLD सीवेज उत्पन्न हो रहा है तथा कुल 152 सीवेज ट्रीटमेंट प्लांट जिनकी क्षमता 4651.60 MLD है, जल शोधन हेतु संचालित (ट्रायल रन में योजनाओं को शामिल करते हुए) हैं।
7. उ०प्र० में औद्योगिक उत्प्राह शोधन संबंधी 05 योजनाएं - कानपुर, उन्नाव, बन्धर, मथुरा तथा गोरखपुर में पूर्व में स्वीकृत हुई थी, जिसमें से मथुरा औद्योगिक क्षेत्र की परियोजना का कार्य पूर्व में पूर्ण हो चुका था। कानपुर (जाजमऊ टेनरी क्लस्टर) की परियोजना पूर्ण कर संचालित की गयी। बन्धर में कार्य प्रगति में है एवं 70 प्रतिशत कार्य पूर्ण हो चुका है। उन्नाव परियोजना के क्रियान्वयन हेतु अनुबन्ध गठन की कार्यवाही प्रगति पर है। गोरखपुर सी.ई.टी.पी. परियोजना हेतु संशोधित क्षमता हेतु डी.पी.आर. गठित कर एन.एम.सी.जी. को स्वीकृति हेतु प्रेषित किया जा चुका है।
8. उक्त के अतिरिक्त प्रयागराज में 07 घाटों (1. दशाश्वमेध घाट, 2. किला घाट, 3. नौकायन घाट, 4. ज्ञान गंगा आश्रम घाट, 5. सरस्वती घाट, 6. महेवा घाट, 7. रसूलाबाद घाट) का महाकुम्भ-2025 के पूर्व निर्माण कार्य पूर्ण कर लिया गया था। फतेहपुर (नागेश्वर धाम आश्रम घाट) तथा बलिया में घाट निर्माण का कार्य प्रगति पर है।
9. योजनाएं DBOT तथा HAM PPP मोड पर आधारित है। इन योजनाओं में 15 वर्ष के संचालन एवं रख रखाव की व्यवस्था की गयी है।

10. सीवर शोधन की परियोजना प्रयागराज (नैनी, फाफामऊ, झूसी), कन्नौज, नरोरा, गढ़ मुक्तेश्वर, अनूपशहर, कानपुर, बिठूर, अयोध्या, मथुरा-वृन्दावन, छाता (मथुरा), कोसीकला (मथुरा), वाराणसी, चुनार, फिरोजाबाद, मुरादाबाद, कासगंज, इटावा, शुक्लागंज-उन्नाव, सुल्तानपुर, जौनपुर, बागपत, मुजफ्फरनगर, बुडाना, लखनऊ, गाज़ीपुर, मिर्ज़ापुर, बरेली, कैराना, फर्रूखाबाद, मेरठ, देवबन्द (सहारनपुर), सहारनपुर, शामली, हापुड़, गोरखपुर, आगरा, गुलावटी (बुलंदशहर), पंडित दीन दयाल नगर (मुगलसराय-चन्दौली), भदोही, राम नगर, हाथरस, अलीगढ़, डलमऊ (रायबरेली), मानिकपुर (प्रतापगढ़), में क्रियान्वित की जा रही हैं या की गयी हैं।
11. इन परियोजनाओं का मुख्य उद्देश्य विभिन्न नालो द्वारा नदियों में प्रवाहित अपशिष्ट जल का शोधन कर नदियों में हो रहे प्रदूषण की रोकथाम करना है।
12. उपरोक्त के अतिरिक्त घाट, शवदाहगृह एवं कुंडो का निर्माण एवं पुनरुद्धार का कार्य भी किया जा रहा है।
13. इस क्रम में 80 घाटों एवं 15 शवदाहगृह का कार्य पूर्ण किया गया है।
14. वाराणसी में 26 नहाने वाले घाटों का पुनरुद्धार किया गया है।
15. वाराणसी में 08 कुंडो का पुनरुद्धार व सौन्द्रीयकरण का कार्य भी पूर्ण किया गया है।
16. वृन्दावन क्षेत्र में 09 कुंडो के पुनरुद्धार हेतु परियोजना तैयार कर NMCG को स्वीकृति हेतु प्रेषित है। स्वीकृति शीघ्र होने की संभावना है।
17. उत्तर प्रदेश राज्य के 25 शहरी निकाय RIVER CITY ALLIANCE प्लेटफार्म पर बोर्ड किये जा चुके हैं। इस सन्दर्भ में कानपुर एवं अयोध्या के URBAN RIVER MANGEMENT PLAN (URMP) NIUA एवं NMCG के सहयोग से तैयार कर लिया गया है। इससे पूर्व बरेली एवं मुरादाबाद का URMP NIUA द्वारा तैयार किया जा चुका था। इनके अतिरिक्त मिर्ज़ापुर, गोरखपुर, बिजनौर, मथुरा-वृन्दावन, शाहजहांपुर का URMP तैयार किये जाने हेतु इन नगर निकायों द्वारा कार्य प्रगति पर है। इस क्रम में प्रयागराज हेतु भी URMP+WaL के सिद्धांतों पर ड्राफ्ट योजना तैयार हो गयी है, जिसे शीघ्र ही अन्तिम रूप प्रदान कर दिया जायेगा।
18. उत्तर प्रदेश राज्य में गंगा नदी के बाढ़ क्षेत्र में राईपेरियन बफर क्षेत्र में निम्नानुसार वृक्षारोपण का कार्य सम्पन्न कराया गया है:-
 - a. उत्तर प्रदेश राज्य में कैम्पा के तहत 164.33 हेक्टेयर क्षेत्र में 8.9 लाख पौधों का रोपण किया गया तथा 17 गंगा नर्सरी स्थापित की गयी है।
 - b. नमामि गंगे कार्यक्रम के अन्तर्गत 8788.63 हेक्टेयर क्षेत्र में 49 लाख पौधरोपण कार्य किया गया।
 - c. विगत चार वर्षों में गंगा तट से 10 किमी⁰ क्षेत्र के अन्तर्गत वन विभाग द्वारा 2.26 करोड़ वृक्षारोपण का कार्य किया गया।
 - d. विगत चार वर्षों में गंगा जनपदों में वृक्षा रोपड़ अभियान के अन्तर्गत 31.84 करोड़ वृक्षारोपण का कार्य किया गया।

- e. कुल वृक्षारोपण (डी.पी.आर. के मुकाबले : 2016-17 से 2023-24 तक): 10431.96 हेक्टेयर - 57.90 लाख पौधे लगाये गये।
- f. गंगा नदी के किनारे 10 किमी० के अन्दर वन विभाग द्वारा बिन्दु सं० 18 a के अतिरिक्त 100 अन्य गंगा नर्सरी स्थापित की गयी है।
19. कुकरैत घड़ियाल एवं स्वच्छ जलीय कछुआ प्रजनन एवं पुनर्वास केंद्र लखनऊ का विस्तार, गंगा किनारे औषधीय पौधों की खेती एवं संरक्षण का कार्य, आद्रभूमि के संरक्षण एवं प्रबंधन का कार्य, गंगा झरो में वनीकरण, उत्तर प्रदेश प्रदूषण नियंत्रण बोर्ड की प्रयोगशालाओं का विस्तारीकरण के कार्य किये गये हैं।
20. नदी जल की गुणवत्ता की जाँच हेतु उत्तर प्रदेश प्रदूषण नियंत्रण बोर्ड द्वारा पूर्व निर्धारित 43 स्थानों पर प्रोटोकॉल के अनुसार समय समय पर नदी जल की जाँच की जाती है। जाँच हेतु मुख्यतः D.O, B.O.D, C.O.D, T.S.S, Faecal Coliform, Total Coliform, Phosphates, Nitrates and Sulphates की जाँच की जाती है। जाँच सम्बन्धी रिपोर्ट उत्तर प्रदेश प्रदूषण नियंत्रण बोर्ड के पोर्टल पर अपडेट की जाती है। नदियों के जल की गुणवत्ता में सुधार परिलक्षित हो रहा है जिसमें मुख्यतः D.O का बढ़ना तथा COD, BOD, TSS का घटना शामिल है। गंगा नदी पर फाफामऊ, प्रयागराज, बलुआघाट ब्रिज, मीरजापुर, गाजीपुर के डाउन स्ट्रीम पर (03 स्थानों) Real Time/Continuous Water Quality Monitoring Station सी.पी.सी.बी. द्वारा स्थापित किया गया। इसके अतिरिक्त गंगा एवं उसकी सहायक नदियों पर 30 प्र० राज्य में 12 अन्य स्थानों पर Real Time/Continuous Water Quality Monitoring Station सी.पी.सी.बी. द्वारा स्थापित है। 30 प्र० प्रदूषण नियंत्रण बोर्ड द्वारा गंगा एवं उसकी सहायक नदियों पर 14 और स्थानों पर Real Time/Continuous Water Quality Monitoring Station की स्थापना का प्रस्ताव है। 1294 on line Continuous Effluent Monitoring System (OCEMS), Grossly Polluting Industries पर स्थापित हैं। इन इकाइयों का निरीक्षण केन्द्रीय/राज्य प्रदूषण नियंत्रण बोर्ड एवं थर्ड पार्टी के माध्यम से निरन्तर किया जाता है।
21. नदी जल की गुणवत्ता में बड़ा सुधार परिलक्षित हो रहा है। गंगा नदी पर 41 स्थानों से माह जुलाई 2025 में NATIONAL WATER QUALITY MONITORING PROGRAM के तहत लिए गए सैम्पल्स की जाँच से उत्साह जनक नतीजे प्राप्त हुए हैं। गंगा जी में माह जुलाई 2025 में DO 9.40 पीपीएम से 7.3 पीपीएम के मध्य पाया गया है। साथ ही BOD भी जुलाई 2025 में अधिकतम 4.10 पीपीएम तथा न्यूनतम 1.2 पीपीएम तक प्राप्त हुई है। जिन 41 स्थानों से सैपल ग्रहण किये गए हैं वे स्थान हैं: बिजनौर, मेरठ, हापुड़, बुलंदशहर, बदायूं, फर्रुखाबाद, कन्नौज, कानपुर, रायबरेली, प्रतापगढ़, फतेहपुर, कौसाम्बी, प्रयागराज, मिर्जापुर, वाराणसी, गाजीपुर, बलिया।
22. शोधित जल को कीटाणु रहित करने हेतु क्लोरीन गैस का उपयोग किया जा रहा है। कुछ स्थानों पर अल्ट्रा वायलेट किरणों का भी उपयोग किया जा रहा है।

23. गंगा नदी के समीप कुल 275 आद्रभूमि चिन्हांकित की गयी हैं। इन 275 आद्रभूमि में से 231 आद्रभूमि हेतु Integrated Wetland Management Plan का निरूपण कार्य पूर्ण किया जा चुका है। इनमें से 93 आद्र भूमि रामगंगा के संगम से ऊपर, 106 आद्रभूमि रामगंगा संगम से लेकर गोमती संगम स्थल तक एवं 32 आद्रभूमि गोमती संगम से लेकर घाघरा संगम के मध्य विद्यमान हैं। वर्तमान में राज्य आद्र भूमि प्राधिकरण द्वारा गंगा किनारे स्थित उच्च प्राथमिकता के चिन्हित 39 आद्र भूमि को अधिसूचित किये जाने की प्रक्रिया प्रगति पर है। इन आद्र भूमियों के प्रबन्धन हेतु वैज्ञानिक आधार पर कार्ययोजना भी तैयार की जा रही है।
24. गंगा डॉलफिन के संरक्षण हेतु कार्यक्रम भी राज्य में वन विभाग द्वारा संचालित किया जा रहा है। राज्य में गंगा डॉलफिन के संख्या में उत्साहजनक बढ़ोतरी देखने को मिली है जो गंगा के निर्मल होने का भी जैविक प्रमाण है। वर्ष 2022 में वाइल्ड लाइफ इन्स्टीट्यूट ऑफ इण्डिया द्वारा किये गये सेन्सेस के अनुसार उत्तर प्रदेश राज्य में 2397 गंगा डॉल्फिन पायी गयी हैं, जो अन्य गंगा राज्यों के सापेक्ष सर्वाधिक है।
25. राज्य में 07 गंगा बायोडायवर्सिटी पार्क की भी स्थापना की जा रही है। इनमें (i) मोहनपुर बायोडायवर्सिटी पार्क-मिर्जापुर, (ii) रामघाट बायोडायवर्सिटी पार्क-बुलंदशहर, (iii) उझानी बायोडायवर्सिटी पार्क- बदायूं (iv) आलमगीर बायोडायवर्सिटी पार्क-हापुड़, (v) महात्मा विदुर बायोडायवर्सिटी पार्क-बिजनौर एवं (vi) कामाख्या भवानी बायोडायवर्सिटी पार्क-अयोध्या (vii) चिलबिला प्रतापगढ़ शामिल हैं।
26. नमामि गंगे द्वारा शोधित जल के पुनः उपयोग हेतु बढ़ावा दिया जा रहा है। शोधित जल का पुनः उपयोग ताप विद्युत ग्रहो में, रेलवे शेड में, सिंचाई हेतु, बागवानी हेतु, इत्यादि में प्रोत्साहित किया जा रहा है। शोधित जल का पुनः उपयोग हेतु एक राज्य नीति (State Policy) का आलेख तैयार कर लिया गया है, जिसे शासन की स्वीकृति हेतु अग्रसारित किया गया है।
27. राज्य में छोटी नदियों के कायाकल्प हेतु नमामि गंगे तथा ग्रामीण जलापूर्ति विभाग को राज्य सरकार द्वारा समन्वय हेतु नोडल विभाग नामित किया गया है। इन प्रयासों में राज्य में कई छोटी नदियां, जिसमें मुख्यतः काली ईस्ट (नागिन), गोमती, वरूणा, छोटी गण्डक, मनोरमा, गवाईन, कर्णावती, ससुरखदेरी, खाखोरी, तमसा, टेढ़ी, सुवांअ इत्यादि नदियों पर प्राथमिकता पर कार्य किया जा रहा है, साथ ही राज्य के समस्त जनपदों में एक नदी कायाकल्प हेतु चिन्हांकित कर कार्य को "एक जनपद एक नदी" (One District One River) की अवधारणा पर नदी पुनरोद्धार के उद्देश्य को प्राप्त किये जाने हेतु कार्य प्रगति पर है।
28. नमामि गंगे कार्यक्रम के अन्तर्गत विगत आठ वर्षों में किये गये प्रयासों से गंगा नदी के प्रदूषित खंड को प्राथमिकता खंड चार से हटा कर, प्राथमिकता खंड पांच में, कर दिया गया है। पूर्व में एक खंड प्राथमिकता खंड चार में कन्नौज से वाराणसी तक था, परन्तु अब प्राथमिकता खंड पांच में (i) फर्रुखाबाद से प्रयागराज एवं (ii) मिर्जापुर से गाज़ीपुर तक दो खंड निर्धारित किये गये हैं। प्राथमिकता

खंड चार में BOD की मात्रा 6-10 पीपीएम होती है एवं प्राथमिकता खंड पांच में BOD की मात्रा 3-6 पीपीएम होती है।

29. नमामि गंगे कार्यक्रम का राज्य में सफलतापूर्वक क्रियान्वयन किये जाने हेतु "जल" श्रेणी में "नदी पुनरोद्धार" के लिये वर्ष 2023-24 में "गोल्ड स्कॉच" पुरस्कार तथा महाकुम्भ 2025 के आयोजन के दौरान प्रयागराज पर गंगा एवं यमुना नदी की जल गुणवत्ता मानकों के अनुसार बनाये रखने हेतु किये गये अथक प्रयासों के लिये राज्य स्वच्छ गंगा मिशन-उ0प्र0 को वर्ष 2024-25 हेतु "प्लेटिनम स्कॉच" पुरस्कार प्रदत्त किया गया है।
30. जन जागरूकता अभियान के अन्तर्गत प्रदेश में गंगा बेसिन जिलों में लोगों तक गंगा संरक्षण का संदेश पहुंचाने हेतु स्वच्छता पखवाड़ा, गंगा स्वच्छता संकल्प दिवस, गंगा निरीक्षण अभियान, गंगा वृक्षारोपण सप्ताह, होम गार्ड के सहयोग से "नमामि गंगे" जागृति यात्रा, "स्वच्छता ही सेवा, "गंगा मंथन" प्रतियोगिता का आयोजन, गंगा सम्मेलन कार्यक्रम का आयोजन किया गया। प्रदेश भर में कई मुख्य मेलों जैसे माघ मेला, गढ़मुक्तेश्वर मेला, विन्ध्याचल मेला, रामनगरीया मेला व चित्रकूट मेलों में प्रदर्शनी का आयोजन किया गया।
- जिला गंगा समितियों द्वारा मासिक बैठकों का आयोजन किया जा रहा है। वित्तीय वर्ष अप्रैल, 2024 से मार्च, 2025 तक GDPMS पोर्टल पर 763/900 अपलोड किये जा चुके हैं। वित्तीय वर्ष 2025-26 (अप्रैल, मई व जून 2025) में 178/225 बैठकें आयोजित की गई हैं। वित्तीय वर्ष 2025-26 में कार्यवृत्त अपलोड करने का प्रतिशत- 82.22% हैं।
 - जिला गंगा समितियों द्वारा की गयी आई0ई0सी0 गतिविधियों के अन्तर्गत विभिन्न कार्यक्रमों का आयोजन जैसे:-अन्तराष्ट्रीय योगा दिवस कार्यक्रम, स्वच्छता ही सेवा अभियान (दिनांक 15 सितम्बर, 2024 से 02 अक्टूबर, 2024 तक), 4 नवम्बर, 2024 को गंगा उत्सव कार्यक्रम 75 जनपदों में आयोजित किया गया, मुख्यतः कानपुर व वाराणसी में मेगा इवेंट का आयोजन किया गया, मीरजापुर में नयनागढ़ महोत्सव का आयोजन श्रावस्ती में श्रावस्ती महोत्सव तथा स्वच्छता पखवाड़ा अभियान 16 मार्च से 31 मार्च 2025 का आयोजन किया गया। मिशन लाइफ कैम्पेन- 26 मई, 2024 से 05 जून, 2024 तक वाराणसी, बलिया, हापुड़ तथा अयोध्या में आयोजित।
 - राज्य स्वच्छ गंगा मिशन-उ0प्र0 द्वारा ग्रेटर नोएडा में International Trade Show में प्रतिभाग किया गया।
 - राज्य स्वच्छ गंगा मिशन-उ0प्र0 द्वारा जिला परियोजना अधिकारियों की 03 दिवसीय आवासीय कार्यशाला दिनांक 24 से 26 मार्च, 2025 को आयोजन किया गया।
 - राज्य स्वच्छ गंगा मिशन-उ0प्र0 द्वारा 22 मार्च, 2025 को विश्व जल दिवस का आयोजन किया गया।

- राज्य स्वच्छ गंगा मिशन-उ0प्र0 द्वारा 05 जनपदों के स्कूलों में जन-जागरूकता अभियान कराया गया।
- कुम्भ मेला के दौरान राज्य स्वच्छ गंगा मिशन द्वारा 50000 Sqft क्षेत्र को पेंट माई सिटी अभियान के अन्तर्गत पेंट किया गया है जिसमें गंगा अवतरण, गंगा आरती, मुख्य मंदिर, ऐतिहासिक गंगा जनपदों से जुड़ी इमारतें, गंगा किनारे निर्मित घाट, एस.टी.पी. जैवविविधता, गांगेय डल्फिन, कछुए, घड़ियाल तथा गांगेय जीव के अतिरिक्त स्वच्छता अभियान, क्या करें-क्या न करें के संदेश आदि सम्मिलित हैं।
- इसी के साथ महाकुम्भ में सम्मिलित होने वाले तीर्थार्थियों को गंगा तथा नमामि गंगे कार्यक्रम पर विस्तृत ज्ञानार्जन के लिए एक प्रदर्शनी भी लगाई गई। प्रदर्शनी का मुख्य आकर्षण बरेली, प्रयागराज, चुनार तथा बनारस के एस.टी.पी. मॉडल, दश्रामेघघाट का लघु रूप, डिजिटल गैलरी तथा द्वादश माघव परिक्रमा का विस्तृत वर्णन था। प्रदर्शनी में राज्य स्वच्छ गंगा मिशन-उ0प्र0 के अन्तर्गत प्रयागराज जिला गंगा समिति द्वारा नुक्कड़ नाटक, स्वच्छता अभियान तथा रैली आदि का भी आयोजन किया गया।
- इसी के साथ राज्य स्वच्छ गंगा मिशन द्वारा महाकुम्भ मेला के दौरान स्वच्छता निगरानी हेतु 1500 गंगा दूत नियुक्त किए गए थे, जो मेले में लगाए गए शौचालयों की स्वच्छता की निगरानी एप के माध्यम से की जा रही थी
- इलाहाबाद विश्वविद्यालय के प्राचीन इतिहास विभाग के सहयोग से राज्य स्वच्छ गंगा मिशन-उ0प्र0 द्वारा 02 दिवसीय राष्ट्रीय सेमिनार का आयोजन किया गया। सेमिनार में मुख्य अतिथि पद्म भूषण अनिल जोशी ने छोटी नदियों के पुनरूद्धार पर देशभर से आये 500 विद्यार्थियों का मार्गदर्शन किया। उनके अतिरिक्त रिवर मैन श्री रमाकान्त , आई0आई0टी0 कानपुर से श्री विनोद तारे तथा नाम संस्था के सी0ई0ओ0 गणेश थोरट सहित विभिन्न विभागों के वक्ताओं ने सार्थक चर्चा की।
- छोटी नदियों के पुनरूद्धार पर राज्य स्वच्छ गंगा मिशन द्वारा टाइम्स ऑफ इण्डिया ग्रुप के सहयोग से लखनऊ में रिवर डायलाग्स- नदी संवाद कार्यक्रम आयोजित किया गया, जिसमें जल पुरूष श्री राजेन्द्र सिंह नदी के पुनरूद्धार विषय पर विशेष चर्चा की। इस कार्यक्रम में अपर मुख्य सचिव श्री अनुराग श्रीवास्तव ने उत्तर प्रदेश में नदियों पुनरूद्धार हेतु किए जा रहे कार्यक्रम के बारे विस्तृत रूपरेखा प्रस्तुत की। इस कार्यक्रम का मीडिया के विभिन्न प्लेटफॉर्म पर व्यापक प्रचार प्रसार किया गया ताकि ने विशेष चर्चाएं आम जन मानस में नदी के प्रति संवेदना जागृत कर सके।
- प्रदेश में नमामि गंगे के प्रति जनजागरूकता हेतु रेडियों कैम्पेन तथा डिजिटल कैम्पेन भी चलाये गये।
- 75 जिला गंगा समितियों में एक पेड़ माँ के नाम कार्यक्रम आयोजित किये गए।

- 19 जिला गंगा समितियों द्वारा प्राकृतिक खेती की कार्यशालाएं आयोजित की गईं।
 - प्रदेश की सभी जिला गंगा समितियों द्वारा नदियों के किनारे वृहद पौधारोपण कराया गया, जिसकी कुल संख्या-21478525.00 (दो करोड़ चौदह लाख अठुत्तर हजार पांच सौ पच्चीस) है। पौधारोपण गंगा, यमुना, गोमती, सरयू, घाघरा, बेतवा, हिण्डन, पाण्डु, तमसा, रामगंगा, मंदाकिनी, राप्ती, आमी, बासुही, सई और वरूणा आदि नदियों के किनारे किया गया।
 - विश्व योग दिवस-2025 के अवसर पर गोमती के पांच घाटों क्रमशः 1. कुडिया घाट 2. मनकामेश्वर घाट, 3. झूलाल पार्क घाट, 4. छठ घाट तथा 5. गऊघाट पर 60 दिनों तक योग कार्यक्रम संचालित किया गया, जिसमें स्थानीय लोगों के सहयोग से घाट की सफाई कार्यक्रम भी 60 दिनों तक लगातार चलाया गया। इसे बी०बी०यू०, डी.जी.सी. लखनऊ तथा जी.टी.एफ. के सहयोग से संचालित किया गया। 21 जून को विश्व योग दिवस के अवसर पर कुडिया घाट पर समापन समारोह आयोजित किया गया, जिसमें 450 की संख्या में स्थानीय लोगों ने प्रतिभाग किया। इसके अतिरिक्त स्कूलों, विद्यालयों तथा कालेजों में गोमती की स्वच्छता को लेकर जागरूकता अभियान नियमित रूप से चलाए जा रहे हैं।
31. राज्य में गंगा एवं उसकी सहायक नदियों की निर्मलता एवं अविरलता को सुनिश्चित करने हेतु जन जन को नदियों से जोड़ने के प्रयास में "अर्थ गंगा" की अवधारणा को राज्य के विभिन्न विभागों के साथ समन्वय कर मूर्त रूप प्रदान किया जा रहा है। इनमें से मुख्यतः (i) कृषि विभाग द्वारा प्राकृतिक कृषि को बढ़ावा; (ii) पर्यटन विभाग द्वारा नदी पर्यटन को बढ़ावा देने हेतु पर्यटन केन्द्रों का विकास एवं वहां पर उपलब्ध सुविधाओं का विस्तार एवं सुधार; (iii) वन विभाग द्वारा नदियों किनारे वृक्षारोपण, (iv) शहरी निकायों द्वारा नदी केंद्रित विकास को प्राथमिकता; (v) उद्यान एवं बागवानी विभाग द्वारा फलदार वृक्षों के रोपण हेतु प्रोत्साहन; (vi) ग्रामीण विभाग द्वारा मनरेगा के अंतरगत छोटी नदियों का कायाकल्प, (vii) पंचायती राज द्वारा ग्रामीण स्वच्छता को बढ़ावा देना; (viii) मत्स्य पालन द्वारा नदियों में मत्स्य जीव को बढ़ाने हेतु प्रयास, (ix) शिक्षा विभाग द्वारा नदियों के प्रति छात्रों को जागरूक करने हेतु पाठ्यक्रम में बदलाव (x) संस्कृति विभाग द्वारा हेरिटेज को सहेजना एवं नदी से जुड़े उत्सवों को अधिक प्रचलित करने के प्रयास शामिल हैं।